



This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at <http://books.google.com/>

✓


~~452 h 10~~



1879

~~CEC. 11~~

VET. CELT. III B. 51



ach

THE GENEALOGIES, TRIBES, AND CUSTOMS

OF

HY-FLACHRACH,

COMMONLY CALLED

O'DOWDA'S COUNTRY.

NOW FIRST PUBLISHED

FROM THE BOOK OF LECAN, IN THE LIBRARY OF THE ROYAL IRISH ACADEMY, AND FROM THE
GENEALOGICAL MANUSCRIPT OF DUALD MAC FIBBIS, IN THE LIBRARY OF LORD RODEN,

WITH A TRANSLATION AND NOTES,

AND A MAP OF HY-FLACHRACH,


By JOHN O'DONOVAN.

DUBLIN:

FOR THE IRISH ARCHÆOLOGICAL SOCIETY.

MDCCCXLIV.

THIS COPY WAS PRINTED FOR
JAMES HAMILTON, ESQ. (*Taita & Co.*)
MEMBER OF THE SOCIETY.



DUBLIN:
PRINTED AT THE UNIVERSITY PRESS,
BY M. H. GILL.

IRISH ARCHÆOLOGICAL SOCIETY.

FOUNDED MDCCCXL.

Patron :

HIS ROYAL HIGHNESS THE PRINCE ALBERT.

President :

HIS GRACE THE DUKE OF LEINSTER.

Council :

Elected July 10, 1844.

THE MARQUIS OF KILDARE, M. R. I. A.

THE EARL OF LEITRIM, M. R. I. A.

THE VISCOUNT ADARE, M. P., M. R. I. A.

REV. RICHARD BUTLER, A. B., M. R. I. A.

JOHN SMITH FURLONG, Esq., Q. C., *Treasurer.*

JAMES HARDIMAN, Esq., M. R. I. A.

CAPTAIN LARCOM, R. E., M. R. I. A.

JAMES MAC CULLAGH, Esq., LL. D., M. R. I. A.

GEORGE PETRIE, Esq., R. H. A., V. P. R. I. A.

AQUILLA SMITH, M. D., M. R. I. A.

JOSEPH HUBAND SMITH, Esq., A. M., M. R. I. A.

REV. J. H. TODD, D. D., V. P. R. I. A., *Secretary.*

✓

~~452 k 10~~




1879

~~6605.11~~

VET. CELT. III B. 51





✓

~~452 h 10~~

7879

~~605 h~~

VET. CELT. III B. 51



He commenced his genealogical compilation in the College of St. Nicholas, at Galway, in the year 1650, and seems to have been adding to it and correcting and amending it till the year 1664, when he inserted the curious entry about the ancient celebrity of the Hy-Fiachrach race, which will be found at full length in this volume, p. 316–321.

Of this work and its author the venerable Charles O'Connor, of Belanagare, writes the following notice in his Preface to "*Ogygia Vindicated*, pp. ix, x :"

"DUALD MAC FIRBIS closed the line of the hereditary antiquaries of *Lecan*, in *Tirfiacra*, on the *Moy*, a family whose law reports and historical collections have derived great credit to their country (many of which lye now dispersed in *England* and *France*). This last of the *Firbisses* was unfortunately murdered at *Dunflin*, in the county of *Sligo*, A. D. 1670, and by his death our antiquities received an irreparable blow. His historical, topographical, and genealogical collections (written by his own hand) are now in the possession of a worthy nobleman, the Earl of *RODEN*, who added this to the other collections of *Irish* history made by his father, our late Lord Chancellor *JOCelyn*. Of that work *Mac Firbis* intended a second draught (as he intimates) with amendments and corrections, but whether he executed his design we cannot learn. As the work stands it is valuable, by preserving the descents and pointing out the possessions of our *Irish* families of latter times, very accurately ; but it is particularly valuable, by rescuing from oblivion the names of districts and tribes in *Ireland*, antecedently to the second century ; since which, the *Scots* have gradually imposed new names of their own, as they were enabled, from time to time, to expel the old *Belgic* inhabitants. It is a most curious chart of antient topography, and vastly preferable to that given by the *Alexandrian Geographer Ptolemy*, who must know [have known] but little of *Ireland*, wherein the *Romans* never made a descent.

"The last years of *Firbis's* life were employed in drawing up a glossary for the explanation of our old law terms, the great desideratum of the present age. Of the fate of this last performance we know nothing, but we may well suppose it lost, as the author lived without a single patron, in days unfavourable to the arts of which he was master."

In 1666 he drew up an abstract of his larger work, containing
some

some additional pedigrees; of this abridgement there is a good copy in the Library of the Marquis of Drogheda, and another in the collection of Messrs. Hodges and Smith, but the Editor has never seen the original. In this tract Mac Firbis mentions his having been acquainted with Irish chieftains who governed their septs according to the words of Fithel^c and the Royal Precepts—(Oo leanar do briaṛnaib Fíthil agur do'n Teagasg Rioghda); and he also speaks of several Irish Brehons then or lately in existence, and of one in particular who was his own relative and acquaintance. He informs us himself, in the Preface to his larger genealogical work, that he wrote a copious Glossary of the Brehon Laws (which is referred to by O'Connor in the extract above given), and an account of Irish writers, but neither of these works is now known to the Editor, except a fragment or rough draft of the former, which is preserved in the Library of Trinity College, Dublin. If the Earl of Roden has either of them in his Library, his Lordship might render an essential service to Irish literature, by depositing it in some public Library, or permitting it to be copied, as he has already very kindly done with respect to Mac Firbis's larger genealogical work. The Glossary would most undoubtedly save the translator of the old Irish Brehon laws much time and labour, although we may hope that their meaning is still recoverable by the aid of the copious glosses which accompany them in most of the copies.

From Harris's edition of Ware's Bishops^d we learn that Mac Firbis,

a

^c Fithel was chief Brehon of Ireland in the reign of Cormac Mac Art, who became monarch of Ireland in the middle of the third century. Some law tracts ascribed to him are still extant. The *Teagasg Rioghda*, or Royal Precepts, are said to have been written by King Cormac himself, in his old age, for the instruction of

his son Cairbrè Liffeachair. Many copies of the *Teagasg Rioghda* are still preserved, and translated specimens of it were published by the Editor in the Dublin Penny Journal, 1832, 1833, pp. 213, 231.

^d Archbishops of Tuam, under John De Burgo, who died 1450.

a short time before his death, had been employed by Sir James Ware to collect and translate Irish documents for him. Harris writes :

“One John was consecrated about the close of the year 1441 (Sir James Ware declares he could not discover when he died, and adds, that some called him John De Burgo, but that he could not answer for the truth of that name). But both these particulars are cleared up, and his immediate successor named by Dudley Firbisse, an Amanuensis whom Sir James Ware employed in his house to translate and collect for him from the Irish MSS., one of whose pieces begins thus :

“‘This translation began by Dudley Firbisse, in the House of Sir James Ware, in Castle-street, Dublin, 6th November, 1666,’—which was twenty-four days before the death of the said Knight. The Annals, or Translation, which he left behind him begin in the year 1443, and end in 1468. I suppose the death of his patron put a stop to his further progress. Not knowing from whence he translated these Annals, wherever I have occasion to quote them I mention them under the name of Annals of Dudley Firbisse.”

He also translated, during the short time he was employed by Sir James Ware, the Registry of Clonmacnoise, which translation is now preserved in the British Museum, No. LI. of the Clarendon collection. We learn from Charles O’Conor of Belanagare, in his Preface to “Ogygia Vindicated,” p. viii, that he was the Irish instructor of Roderic O’Flaherty, the author of “Ogygia” and “Ogygia Vindicated,” and it would appear from a list of tracts of Brehon laws which he furnished to Dr. Lynch, the author of *Cambrensis Eversus*, that he was intimate with that distinguished scholar*, but towards the latter end of his life he seems to have been in great distress, and we are informed by Charles O’Conor, in the passage already quoted, that he met a tragical death at Dunfin, in the county of Sligo, in the year 1670!

On the fate and general character of this remarkable man the
same

* See *Cambrensis Eversus*, pp. 157, 158, 159.

same writer speaks as follows in his "Dissertations on the History of Ireland," Dublin, 1766, pp. 124, 125.—(See also first edit., Dublin, 1753, p. 155):

"Duaid Mac Firbis, the most eminent antiquarian of the latter times, was possessed of a considerable number of the *Brethe Nimhe*. He alone could explain them, as he alone, without patronage or assistance, entered into the depths of this part of Scottish learning, so extremely obscure to us of the present age. When we mention Mac Firbis we are equally grieved and ashamed; his neglected abilities ignominious to his ungrateful country! his end tragical! his loss irreparable!"

The learned Roderic O'Flaherty, the pupil of Mac Firbis, thus speaks of his learned tutor, in the *Ogygia*, p. 233:

"Scoticis literis quinque accidunt, in quorum singulis ab aliarum gentium literis discrepant; nimirum, Nomen, Ordo, Numerus, Character et Potestas. Et quia *imperiti literarum in chartâ, aliave ulla materia ad memoriam pingendarum* harum rerum ignarus incautè effutiit Bollandus, de materiâ aliquid præfabor. Ea ante pergamænæ usum tabulæ erant e betulla arbore complanatæ, quas *Oraion et Taibhle Fileadh*, i. Tabulas Philosophicas dicebant. Ex his aliquas inter antiquitatum monumenta apud se superfuisse, ut et diversas characterum formulas, quas ter quinquagenas a Fenisii usque ætate numero, et *CRAOBH-OGHAM*, i. virgeos characteres nomine recenset, non ita pridem ad me scripsit Duaidus Firbissius rei antiquariæ Hibernorum unicum, dum vixit, columnen, et extinctus, detrimentum."

Some particulars of the history of Duaid Mac Firbis have been given in a small periodical called "The True Comet," and other obscure publications in Dublin, in which it is stated that his remains were interred at the old church of Kilglass, near the castle of Lecan, and that a stone there, measuring six feet in length by three in width, exhibits on its head end, a device, representing a chisel, which was probably intended as the crest of the Mac Firbis family, and containing an Irish inscription, which states that Duaid Mac Firbis died in the eightieth year of his age, and that he had spent thirty years
of

of his life in the castle of Lecan compiling the History of Ireland. But the Editor is sorry to be compelled to say, that no such inscription exists, nor ever existed at Kilglass. From a recent examination of Kilglass and an investigation of the local tradition connected with Duaid Mac Firbis, and particularly from a copy of the real inscription and crest on the stone above alluded to, made by Dr. James Vippler O'Dowda, it appears that this stone,—exhibiting a *chisel*, as the country people call it,—under which, they say, many of the Mac Firbises lie interred, contains not an *Irish* inscription, but an *English* one, in the raised letter, to the memory of George Wood of Lacken, Esq.; and that what the country people take to be a representation of a naked child holding a chisel, is the crest of the family of Wood, namely, “a naked savage with a club resting on his shoulder.” The inscription is now much defaced, and a great part of it illegible, but there never was any reason for supposing it to mark the tomb of the Mac Firbises except its exhibiting the name Lacken.

The Editor has to acknowledge the great assistance he has received from his friends in illustrating and editing the present volume. He is particularly indebted to James Hardiman, Esq., author of the History of Galway, and to Dr. James Vippler O'Dowda, the son and heir of the O'Dowda of Bunnyconnellan, for the use of many documents indispensably necessary to the illustration of the pedigrees of the O'Dowdas and other families of the Hy-Fiachrach race; and he has further to acknowledge his obligations to Dr. Todd of Trinity College, Mr. Petrie, and Mr. E. Curry, for much valuable assistance in translating and editing this work, which has been attended with much delay and difficulty, as it relates to a portion of Irish history and topography hitherto unexplored.

J. O'D.

GEINEALACH

GEINEALACH UA bh-FLACHRACH.

ΓΕΙΝΕΑΛΑΧ ΥΑ ΒΗ-ΦΙΑΧΡΑΧ.

ΟΙ ΦΙΑΪΡΑΪ, ΜΙC ΕΑΪΑΪ ΜΥΙΓΜΕΑΔΟΙΝ, [Ι. ΥΙ ΦΙΑΪΡΑΪ
ΜΥΑΙΔΕ, (Ι Β-ΤΑΜΑΙΒ-ΝΕ ΑΝΙΥ, 1666,) ΥΙ ΑΜΑΛΓΑΙΒ
ΙΟΡΡΥΙΡ, ΦΙΡ ΧΕΑΡΑ, ΥΙ ΦΙΑΪΡΑΪ ΑΙΘΝΕ, Β'Α Ν-ΓΟΙΡΤΕΑΡ
ΑΝΟΙΡ CΕΝΕΑΛ ΓΥΑΙΡΕ, CΕΝΕΑΛ ΑΘΒΑ ΝΑ Η-ΕΪΤΓΕ, CΟΙΛ
ΥΑ Β-ΦΙΑΪΡΑΪ, ΜΑΙΛΛΕ ΛΕ ΤΙΡΙΒ ΕΙΛΕ ΝΑΪ ΑΙΝΝΙΓΤΕΑΡ
ΒΟ ΙΒ ΦΙΑΪΡΑΪ ΑΝΙΥ].

COIG

The initial letters SI have been copied from the Book of Kells, fol. 97.

^a *Eochaidh Muighmheadhoin*.—He was King of Connaught, and was raised to the throne of Ireland in the year 358.—See O'Flaherty's *Ogygia*, Part III. c. 79.

^b *These are the*.—This passage, enclosed in brackets, is taken from Duaid Mac Firbis's smaller Genealogical compilation, made in 1666, of which a good copy is preserved in the Marquis of Drogheda's Library, and another in the collection of Messrs. Hodges and Smith, Dublin. His larger work was commenced in the

college of St. Nicholas, in Galway, in the year 1645.

^c *Hy-Fiachrach*, of the *Muaidh*, i. e. the inhabitants of Tir Fhiachrach, now Tire-ragh, on the east side of the River Moy, in the county of Sligo. The reader is to take notice that ΦιαΪραχ, which occurs so often throughout this volume, is the genitive form of ΦιαΪρα, a man's name. The River Moy is famous in ancient Irish history (see *Life of St. Cormac*, by Colgan), and now remarkable for its salmon fishery. It is called *Moda* by Adamnan (*Vita Columbæ*, Lib. 1, c. 6), *Moadus* by Giraldus Cambrensis,

GENEALOGY OF THE HY-FIACHRACH.

THE RACE OF FIACHRA, SON OF EOCHAIDH MUIGH-MHEADHOIN^a.—[These are the^b Hy-Fiachrach of the Muaidh^c (where we are this day, 1666), the Hy-Amhalgaidh of Iorrus^d, the men of Ceara^e, the Hy-Fiachrach Aidhne^f, now called Cineal Guaire^g, Cineal Aodha na h-Echtghe^h, Coill Ua bh-Fiachrachⁱ, together with other territories not considered as of the Hy-Fiachrach at the present day].

Fiachra,

Muadins by Colgan, and Moyus by Ware, and at present *Muaidh*, in Irish, by the natives. It rises in the barony of Leyny, in the county of Sligo, flows, by a circuitous course, through the barony of Gallen, in Mayo, and, passing through Foxford and Ballina, discharges itself into the bay of Killala, forming for some miles the boundary between the counties of Mayo and Sligo.

^a *The Hy-Amhalgaidh of Iorrus*, i. e. the descendants of Amhalgaidh, who dwelt in the present barony of Erris, in the north-

west of the county of Mayo.

^e *The Men of Ceara*, i. e. the inhabitants of the barony of Cara, in the county of Mayo.

^f *Hy-Fiachrach Aidhne*, i. e. the inhabitants of the diocese of Kilmacduagh, which comprises the entire of the territory anciently called *Aidhne*.—See Map of the Tract on Hy-Many.

^g *Cineal Guaire*, i. e. the descendants of the celebrated Guaire Aidhne, King of Connaught, in the seventh century.

^h *Cineal Aodha, na h-Echtghe*.—This

Coig mec Fiacraic, mec Eataic Muirneadoin, .i. Eapc Cúilbuidé, o d-táid pír Cheapa (ar aipe ad beapta Eapc Cúilbuidé dhe, uair nír buide an t-ór ar na bhuindead inár a folc. Agus po ba mór críóc a cloinne go rugrad clann dhriam i n-eric a n-atar uaidib). Agus bneapal, díobad a clann; agus Conaire, a quo Seacnall naom.

Amalgaid, mac Fiacraic, umorpo, ar uaid Uí Amalgaid la Muaid, ocur Uí becon. Amalgaid, umorpo, clann mór lair, .i. Feolim, Eocaid dá maig, .i. Máig Muirirge ingene Lioigan, agus Maig Muide, no Muaidé, agus Eunda, agus Conall, agus Congur, agus Eogan, agus Cormac, agus Corrbud. Oóc mec andorin Tperi, ingene Natpaoic, .i. depbpeatair Congura, mic Natpaoic, ríig Mumán.

Feolimio, mac Amalgaid, dia d-tá Ceneul Feolimio la h-Uib Amalgaid, .i. Uí Ceallacáin, Uí Caicmao, Mec Coinín, Uí Mum-neacáin,

was the tribe name of the O'Shaughnessys of Gort Inse Guaire, in the south-west of the county of Galway, who were called *na h-Echtghe*, because their country comprised a portion of the mountainous district of Sliabh Echtghe, now called Slieve Aughty, and sometimes corruptly Slieve Baughta.

ⁱ *Coill Ua bh-Fiachrach*. — This name, which is anglicised Killovveragh, is still well known in the county of Galway, and applied to the north-western portion of the barony of Kiltartan. It appears by an inquisition taken at Galway in 1608, that "Killovveragh, O'Heyne's contry, being estimated only as forty-five quarters of land, doth consist of 8640 acres, which maketh [in reality] three skore and twelve quarters."—See Map prefixed to the tract

on Hy-Many, for the situation of this territory.

ⁱⁱ *Five sons*.—Only four of the sons of Fiachra are here named. His fifth son was Dathi, who became monarch of Ireland, and is mentioned p. 17.

^j *Eric*, i. e. mulct, fine, or reparation.

^k *Sechnall the Saint*. — The pedigree of St. Sechnall, or Secundinus, the son of Darerca, the sister of St. Patrick, is given differently by Colgan.

^l *The Uí Amhalgaidh, on the Muaidh*, i. e. the inhabitants of the present barony of Tirawley, which is bounded on the east by the River Muaidh, now the Moy.

^m *The plain of Muirisc, daughter of Lioigan*, that is, the plain called after Muirisc, the daughter of Lioigan, for some account of whom see Dinnsenchus, Lib. Lecan, fol.

Fiachra, son of Eochaidh Muighmheadhoin, had five sons^h; namely, Earc Culbhuidhe from whom are *descended* the men of Ceara. (He was called Earc Culbhuidhe, because the smelted gold was not yellower than his hair. The territory of his descendants was great until the descendants of *his brother* Brian took it from them as *eric*^l for their father). Breasal, whose race became extinct; and Conaire, from whom *sprung* Sechnall^k, the Saint.

From Amhalgaidh, the *fourth* son of Fiachra, are sprung the Hy-Amhalgaidh on the Muaidh^l, and the Hy-Becon. This Amhalgaidh had a large family, namely, Fedhlim; Eochaidh of the two plains, i. e. of the plain of Muirisc, daughter of Liogan^m, and of the plain of Muidh, or Muaidh^a; Eunda; Conall; Aongus; Eoghan; Cormac; and Corrdubh. These were the eight sons of Tresí, the daughter of Nadfraoch, and sister of Aongus, son of Nadfraoch, king of Munster^o.

From Fedhlim, the son of Amhalgaidh, are *descended* the Cineal Fedhlimidh, in Hy-Amhalgaidh; that is, *the families of* O'Ceallachain^p, O'Caithniadh^q, Mac Coinin^r, O'Muimhneachain^s, Mag-Fhionain,

247. It is the name of a narrow piece of level land stretching from the foot of Croaghpatrick, in the county of Mayo, to the margin of Clew Bay. From the monastery of Muirisc in this place the barony of Murreak, anciently called Upper Umhall, was named in 1585.

^a *The plain of Muidh or Muaidh*, i. e. the plain through which the River Moy flows. It does not appear to have been the name of any distinct principality or territory, but a natural appellation given to the region traversed by this river.

^o *Aengus, son of Nadfraoch, King of Munster*, was slain in the battle of Cell

Osnata, in the plain of Magh Fea, now Kellistown, in the barony of Forth and county of Carlow, in the year 439.

^p *O'Ceallachain*, now O'Callaghan; but O'Callaghan of Erris is not to be confounded with O'Callaghan of Munster, who is of a different race and a far more distinguished family.

^q *O'Caithniadh*.—There is not one of this name in Erris at present, and it is believed that the family is extinct.

^r *Mac Coinin*.—This name still exists, but is variously anglicised Cunnion, Cunniam, Canning, &c.

^s *O'Muimhneachain*.—This name is still

neacáin, Me^g Fhionnain, Uí Gearad^hain, Uí Conboirne. Ceneal Feblimí^o rín la h-Iorpur.

Aon^gur, mac Amal^gaid, dia d-tá Cineul n-Aongura, la h-Uib Amal^gaid, .i. Uí Muir^gaid^oig, tair^gis an Lagáin, agur ar do cloinn Aongura po bai Diúcaill dára^gta^g á Síe bu^gda ingene dhui^ob^g Der^g; agur ar do cloinn Aongura lu^gct Dúna rinne, .i. Uí Cuin^o, agur Me^g O^oráin, agur Uí Com^oán, agur Uí Duib^gear^ga, agur Uí be^gar^ga, agur Uí b^gli^gge, agur Uí Duan^gma, nó Duan^gma^gig; agur ar do cloinn Aongura Uí Radubán Gleanna an Cairn, .i. Raduban, mac Muir^gaid^oig, mic Eata^gc, mic Aongura, mic Amal^gaid.

Do cloinn Aongura be^og Mac Conle^gtreac, ó Uor Letreac, .i. Cule^gtreac, mac Aoba, mic Muir^gaid^oig, mic Eata^gc, mic Aongura; agur ar do lb Muir^gaid^oig Uí Fhionnacáin na Fionn^gcáil^gne. Ar do lb Muir^gaid^oig, umor^gpo, po f^gar^gaib Cormac naom^g ion g-cea^gtra, agur ra^gc n-ur^gla^gb^gra, agur bua^go n-aileam^gna, agur ion com^ga^gir^gle, agur ceannur rí^oda agur com^ga^gir^gce la h-Uib Amal^gaid; agur ear^gra^go rí^gg Ua n-Amal^gaid do'n fíor bur deac d' lb Muir^gaid^oig.

Eocáid

numerous in Erris, but anglicised Minahan, or Mynahan. See notes to the Topographical Poem of Giolla Iosa Mor Mac Firbis, towards the end of this volume.

^t *Mag Fhionain*, now always anglicised Gannon.

^u *O'Gearadhain*, now Gearan, but the name is scarce in Erris.

^v *O'Conboirne*, now always anglicised Burns, but the name is more common on the east side of the Moy than in Erris.

^w *O'Muireadhaigh*, now Murray.

^x *Lagan*, a district in the north of the barony of Tirawley, in the county of Mayo, for the extent of which see notes to Gilla

Iosa Mor Mac Firbis's poem.

^y *The hill of Budh*.—This was the name of a celebrated hill not far from Rathcroghan, in the county of Roscommon. There is another hill of the name near the town of Strabane, in Tyrone. Bodhbh Dearg was a Tuatha De Danann chieftain, and the son of Daghdha, monarch of Ireland.

^z *Dun Finne*, now Dunfeeny, or Dunfinny, the name of an old church and parish in the north of the barony of Tirawley, and county of Mayo, about nine miles north-west from Killalla. The old church of this parish was built within the earthen fort, or *dun*, from which the place

nain^t, O'Gearadhain^u, O'Conboirne^v. These are the Cineal Fedhlimidh of Iorrus.

From Aongus, the son of Amhalgaidh, are *descended* the Cineal Aongusa, in Hy-Amhalgaidh; namely, the O'Muireadhaighs^w, chieftains of the Lagan^x; and of the descendants of *this* Aongus was Diucaill the Fierce, of the hill of Budh^y, daughter of Bodhbh Dearg; and of the descendants of Aongus are the people of Dun Finne^z; namely, *the families of* O'Cuinn, Mag Odhrain, O'Comhdhan, O'Duibhlearga, O'Bearga, O'Blighe, O'Duanma, or Duanmaigh; and of the race of Aongus is *the family of* O'Radubhan of Gleann an chairn^a, *who descend from* Radubhan, son of Muireadhach, son of Eochaidh, son of Aongus, son of Amhalgaidh.

Of the race of Aongus also is *the family of* Mac Conleireach, of Lios Leitreach^b, *who descend from* Culetreach, son of Aodh, son of Muireadhach, son of Eochaidh, son of Aongus; and of the Hy-Muireadhaigh is *the family of* O'Fionnacains^c, of Fionnchalamh^d. It was to *these* Hy-Muireadhaigh that St. Cormac^e left prosperity of cattle and the gift of eloquence, success of fosterage, the gift of good counsel, and the headship of peace and protection among the Hy-Amhalgaidh; and the battle dress of the King of Hy-Amhalgaidh was given to the best man of the Hy-Muireadhaigh.

Eochaidh

originally received its name.

^a *Gleann an chairn*, now Baile an ghleanna, or Glynn, a townland in the parish of Dunfeeny. The family names here mentioned are all obsolete at present in the barony of Tirawley.

^b *Lios Leitreach*.—This was the name of a fort in the townland of Ballykinlettragh, in the parish of Kilfian, in the barony of Tirawley. The name Mac Conleireach is now obsolete.

^c *O'Fionnacain*, now Finnagan, but the name, though common in other parts of Ireland, is scarce in this district.

^d *Fionnchalamh*, now obsolete. — See Notes farther on, and Index.

^e *St. Cormac*.—For some account of this saint's visit to Tirawley, see his life as translated by Colgan, *Acta Sanctorum*, p. 752, and also the Irish life preserved in the Book of Lecan, from a copy of which Colgan made his Latin version.

Eócaíð dá mág, mac Amalgaid, mac do Fiacra Fionn, ó d-táid Uí Fhiacra Fhinn la h-Uib Amalgaid, .i. Ua Congaile o Cill acáid duib, agus Uí Catúrtaí o Cill acáid duib beor.

Eogan, Cormac ocus Corrbuib, ní h-airnítear a g-clann ma ro págaid.

Eunna Cnom, mac Amalgaid, o d-táid Uí Eunna Chnuim la h-Uib Amalgaidh.

Conall, mac Amalgaid, o d-táid Uí Conuill Danle, co n-a g-com-
fogur. Mec Trepi rin.

Seact mec la h-Earca, ingen Eacac, níg Laignean, bean ele do Amalgaid, .i. Feargur, Cormac Ceann-foda, Colom, Seudna, Eócaíð, Aoldoban, agus Emeac, ó d-táid Uí Emeacáin. Feargur, mac Amalgaid, umorro, da mac lair, .i. Conaing, ocus Muirtheadó, .i. níg Ua n-Amalgaid. Conaing, umorro, ar uada atáid Uí Airítheadóis, .i. luét Chaille Conaill a tuais, .i. o Thráig Murbhaig go Fearraio Trepi, áit ar báitead Trepi, ingean Nodpaoic, bean Amalgaid, mic Fiacraic. Airiad ro cinneada an Chaille, .i. Uí Derg, agus Uí Aoda Airí ó n-Aoda, agus Uí Maoilconaire, agus Uí Flannabha, agus Uí Tegea. Agus ar do clonn Conaing, mic Feargura, Cumann Foda, dia d-ta Ceall Cumaoim, la Caille Conaing.

Muirtheadó

^c *Cill Achaidh duibh*, called Cill Ardubh in other authorities. The place is now called Killarduff, and is a townland containing the ruins of an ancient church, situated in the parish of Dunfeeny, in the barony of Tirawley, and about a mile below the village of Ballycastle.

^d *Dael*, now the Deel, a river which rises to the south of the townland of Glendavualagh, in the parish of Crossmolina, in the barony of Tirawley, and

flowing through the centre of the parish, and through the little town of Crossmolina, discharges itself into Lough Con, at its northern extremity. Our author, in his pedigree of the family of Walsh, describes this river as flowing by the country of the Clann Robert, in Tirawley.

^e *Traigh Murbhaigh*.—This, as our author informs us elsewhere, was the ancient name of the strand called Traigh Ceall in his own time. This strand is situated at

Eochaidh of the two plains, the son of Amhalgaidh, had a son Fiachra Fionn, from whom are *descended* the Hy-Fiachrach Finn, in Hy-Amhalgaidh, viz., *the families of* O'Congaile of Cill achaidh duibh^f, and O'Cathasaigh of Cill achaidh duibh also.

The descendants of Eoghan, Cormac, and Corrdubh, if they left any, are not mentioned.

From Eunda Crom, son of Amhalgaidh, are the Hy-Eunda Cruim among the Hy-Amhalgaidh.

From Conall, son of Amhalgaidh, are *descended* the Hy-Conaill, of the River Dael^g, with their correlatives. These were the sons of Tresí.

Earca, daughter of Eochaidh, King of Leinster, another wife of Amhalgaidh, had seven sons; namely, Fergus; Cormac Ceannfoda; Colom; Seudna; Eochaidh; Aoldobhar; and Emeach, from whom *are sprung the family of* O'h-Emeachain. Fergus, son of Amhalgaidh, had two sons, namely, Conaing and Muireadhach, King of Hy-Amhalgaidh. From Conaing are *sprung* the Hy-Airmeadhaigh, *who are* the inhabitants of Caille Conaill, in the north, that is *the tract extending* from Traigh Murbhaigh^h to Fearsad Tresíⁱ, where Tresí, the daughter of Nad-fraoch, and wife of Amhalgaidh, son of Fiachra, was drowned. These are the tribes of Caille, viz., *the families of* O'Derg; O'h-Aodha, of Ard O'n-Aodha^j; O'Maoilconaire; O'Flannabhra; and O'Tegha. And of the race of this Conaing, the son of Fergus, was Cumain Foda, from whom Cill Cumaoín^k in Caille Conaing *has derived its name*.

The

the village of Rathlacken, near Killala, in the barony of Tirawley. The Roman Catholic chapel of Lacken stands at its western extremity.

ⁱ *Fearsad Tresí*, i. e. the passage or *trajectus* of Tresí. It is now, and has been for centuries, called Fearsad Raith Bhrain, i. e. the passage or *trajectus* of Rafran. It lies just under the abbey of Rafran, in the

parish of Killala, and barony of Tirawley. There are two round stones on each side of the fearsad, or channel, to point out its position.

^j *Ard O'n-Aodha*, i. e. *altitudo nepotum Aidi*.—This name is now forgotten in the country.

^k *Cill Cumaoín*, more correctly called Cill Chuimin in the Book of Lecan, and

Muirneabóc, mac Feargura, iṛé a clann, .i. tpioḁa céud an dhac, agur Gleanda Nemtinde, agur letpioḁa céud na breudḁa. Ar iad ro fineaboiḡ duḁcúra an dhac, .i. O'Laḁtna, taoipioḁ an da dhac agur an Ghleanna, agur ar dḁb Uí Dubagáin, agur Clann Fhirbiriḡ, .i. fileabḁ Ua n-Amalḡaib agur Cloinne Fiaḁpáḁ (Laḁtna Mac Fhirbiriḡ aḁep Leabap balḁ Shemuir Mic Fhirbiriḡ), Uí Maoilruaib ó Arḁ-acáḁ, agur Uí Cuimín Leapa Cuimín la Muab.

Ar iad ro fineabḁ na breudḁa, .i. O'Tóḡḁa taoipioḁ na breudḁa, agur Ua Glaimín, agur Ua Luacáib, agur Ua ḡilin. Ar do ḡiol Muirneaboiḡ, mic Feargura, Ua Feargura la h-lapḁar Connacht.

Clann Muirinne (ingene Dubḁaiḡ, riḡ Ua Maine), mna ele do Amalḡaib, .i. Cairbre, dḁa d-ta Tḡearḡan Oipḁ Lóca Con; Aonḡur

elsewhere by our Author. The name is now anglicised Kilcummin, and is that of a parish in the barony of Tirawley, about four miles and a half north of Killala, on the west side of Killala Bay. The ancient church of this parish is one of great antiquity, built of very large stones in the primitive Irish style. At this church was preserved some years since a flat stone called Leac Chuimin, to which the peasantry resorted for many superstitious purposes, but it was removed by Dr. Lyons, now parish priest of Kilmore-Erria, who caused it to be built up in the wall of the new Roman Catholic Cathedral, at Ballina, for "certain weighty reasons."

This pedigree of St. Cumin is not given by the O'Clerys in their Genealogies of the Irish Saints.

¹ *Cantred of Bac*, is still well known in the country by the name of the Two Backs, and lies between Lough Con and the River Moy, in the barony of Tirawley; for a more definite description of which see Notes to the Topographical Poem of Gilla Iosa Mor Mac Firis further on.

^m *Gleann Nemhthinne*, now anglicised Glen Nephin, for the extent of which see Notes to Gilla Iosa Mor Mac Firis's Topographical Poem.

ⁿ *The half cantred of Breudach*.—This territory was nearly co-extensive with the parish of Moygawnagh, in the west of the barony of Tirawley.

^o *O'Lachtna*, now always O'Lachtnain in Irish, and anglicised Loughnane and Loftus. Dr. Martin Loftus, formerly professor of the Irish language in the College

The following are the descendants of Muireadhach, the son of Fergus, namely, *the inhabitants of* the cantred of Bac¹, and of Gleann Nemhthinne^m, and of the half cantred of Breudachⁿ. These are the hereditary tribes of Bac, viz., O'Lachtna^o, chief of the two Bacs and of the Glenn^p, and of them are *the families of* O'Dubhagain, and the Clann Firisigh, the poets of Hy-Amhalgaidh and of Hy-Fiachrach;—(the Leabhar Balbh^q of James Mac Firis, says, *that* Lachtna was Mac Firis^r);—O'Maoilruaidh^s; of Ard achaidh^t, and O'Cuimin, of Lios Cuimin^u on the Muaidh.

These are the families of Breudach, viz., O'Toghdha^v, chief of Breudach, O'Glaimin^w, O'Luachaibh^x, and O'Gilin^y. Of the race of *this* Muireadhach, the son of Fergus, is the family of O'Learghusa^z, of the west of Connaught.

The sons of Muirenn (daughter of Dubhthach, King of Hy-Many), another wife of Amhalgaidh, were the following, viz., Cairbre, from whom

of Maynooth, is of this family.

^p *Of the Glenn*, i. e. of Glen Nephin.

^q *The Leabhar Balbh*, i. e. the Dumb Book. This book, which is now unknown, would appear to have been called the *Dumb*, because it chronicled events which many of the chieftains in power did not wish to be known. But of this more distinctly hereafter.

^r *Lachtna was Mac Firis*, that is, the Lachtna, after whom the family of O'Lachtna was called, was of the Mac Firis tribe.

^s *O'Maoilruaidh*, now Mulroy, but the name is not in the district.

Ard achaidh, now Ardagh, a parish in the barony of Tirawley, about two miles and three quarters west south west of the

town of Ballina.

^u *Lios Chuimin*, i. e. Cuimin's fort. The name is now unknown, though it is highly probable that the fort remains.

^v *O'Toghdha*.—This name is now unknown in the district.

^w *O'Glaimin*, now obsolete.

^x *O'Luachaibh*, is written O'Luachaim in the Book of Lecan, but the *m* is evidently intended to be pronounced as if aspirated. The name is now obsolete.

^y *O'Gilin*.—This name not extant in the district, though common in other parts of Ireland.

^z *O'Learghusa*.—This name is now anglicised, correctly enough, Larissy, and is found in various parts of Ireland.

gus Fionn mac Amalgaid, dia d-táid Uí Gaibéacáin, Uí Fhlainn, agus Uí Maoilfhiona, plaice Calraige Muige h-Eleas; Duibion-
bráct mac Amalgaid, ó d-taid Muinirí Fotaig, Muinirí Culaicán,
agus Muinirí Duinncean; Cu-coingeit mac Amalgaid, ó d-tad
Muinirí Thomaltair; Concábar mac Amalgaid, ó d-tad Muin-
irí Ubain co n-a g-comfoigrib.

Cormac Ceann-rada, Colom, agus Seudna, agus Aoldobair, ní
h-oirdeiric a g-clann.

Fiacra mac Amalgaid, ó d-taid 1 beccan 1 Míde.

becon,

mac Comain,
mic Seanairg,
mic Aoda,
mic Fiacraic,

mic Amalgaid, rig Chonnaict,
mic Fiacraic,
mic Eatac Muigmeadoin, rig
Eirionn.

CENEUL AIRMHEADHAIGH AND SO.

Duibiondaic,

mac Airmeadoig,
mic Daoibain,
mic Fiacraic,
mic Conaing,

mic Feargura,
mic Amalgaid,
mic Fiacraic.

CENEUL

^a *St. Tighearnan, of Oireadh Locha Con*,
i. e. St. Tiernan, the patron of the church
or abbey of Errew, on Lough Con. A
celebrated relic of this saint, called *Miar*
Uigeapnám, i. e. St. Tiernan's dish, is
still preserved at Rappa Castle, in the ba-
rony of Tirawley. In the Book of Lecan,
fol. 46, the pedigree of this St. Tighearnan,
or Tiernan, is given as follows:—Tighearnan,
son of Ninnidh, son of Cairpri, son
of Amhalgaidh, son of Fiachra, son of

Eochaidh, monarch of Ireland; so that he
must have flourished in the latter end of
the fifth century.

^b *O'Gaibhtheachain*.—This name is now
correctly anglicised Gaughan, and is still
common in the district.

^c *O'Flainn*, now O'Flynn.

^d *O'Maoilfhiona*.—There is scarcely one
of this name now in Tirawley, though
they were formerly very powerful. The
little town of Crossmolina, in Irish called

whom sprung St. Tighearnan, of Oireadh Locha Con^a; Aongus Fionn Mac Amhalgaidh, from whom are *the families of* O'Gaibhtheachain^b, O'Flainn^c, and O'Maoilfhiona^d, chiefs of Calraighe Muighe h-Eleag^e; Duibhindracht Mac Amhalgaidh, from whom are the Muintir Fothaigh^f, Muintir Culachan, and Muintir Duinncean; Cucoingelt Mac Amhalgaidh, from whom are the Muintir Tomaltaigh; and Conchobhar Mac Amhalgaidh, from whom are the Muintir Ubain, with their correlatives.

The descendants of Cormac Ceannfada, *i. e. of the long head*, Colom, Seudna, and Aoldobhar, are not illustrious.

From Fiachra, the son of Amhalgaidh, are *descended* the Hy-Becon of Meath, *thus* :

Becon,	
son of Coman,	son of Amhalgaidh, King of Con-
son of Seanach,	naught,
son of Aodh,	son of Fiachra,
son of Fiachra,	son of Eochaidh Muighmheadh-
	oin, King of Ireland.

CINEAL AIRMHEADHAIGH HERE.

Duiniondach,	
son of Airmeadhach,	son of Fergus,
son of Baodan,	son of Amhalgaidh,
son of Fiachra,	son of Fiachra.
son of Conaing,	

THE

Croí Uí Mhaoilfhiona, *i. e.* O'Molina's Cross, took its name from them.

^a *Calraighe Muighe h-Eleag.*—This territory was nearly co-extensive with the parish of Crossmolina, in the barony of

Tirawley. See Notes to the Topographical Poem of Giolla Iosa Mor Mac Fírbia.

^f *Muintir Fothaigh, &c. &c.*—These, which were probably tribe names, are now unknown in Tirawley.

CENEUL N-EUNDA, MIC AMHALGAIÖH.

Maolbrigde,
 mac Cnairgiolla,
 mic Tomaltaiḡ,
 mic Reachtabra,
 mic Cloēra,
 mic Duiblača,
 mic Diarmada,
 mic Tigearnan,

[Reachtabra,
 mac Aelobair,
 mic Laitcino,
 mic Fuilm,
 mic Oima,

Fearḡur, aḡur Aongur,
 . dá Mac Chonaill,
 mic Fionain,
 mic Conaill,
 mic Fearaboiḡ,

mic Eric,
 mic Maine,
 mic Conaill,
 mic Eunda,
 mic Amalgaiö,
 mic Fiacrač.

mic Rora,
 mic Feiblimiḡ,
 mic Amalgaiö,
 mic Fiacra.]

mic Cormaic,
 mic Aongura,
 mic Amalgaiö,
 mic Fiacrač.

GENEALACH FEAR CEARA.

Cucotaiḡ,
 mac Maonaiḡ Cheara,
 mic Duncada,
 mic Floinn Róöba,
 mic Maoibóin,
 mic Failbe,
 mic Maolurna,

mic Fearaboiḡ,
 mic Rora Doiméiḡ,
 mic Maine Muinbrič,
 mic Eric Culbuide,
 mic Fiacrach Folcračaiḡ,
 mic Eatač Muigheaboin.

[Donbcačaiḡ,

^s *Reachtabhra*.—This line is supplied from the Book of Leacan, fol. 79, page a,

col. a. It does not belong to the heading Cineal Eunda.

THE CINEAL EUNDA, SON OF AMHALGAIDH.

Maolbrighde,	
son of Cnaimhghiollan,	son of Erc,
son of Tomaltach,	son of Maine,
son of Reachtabhra,	son of Conall,
son of Clothra,	son of Eunda,
son of Dubhlacha,	son of Amhalgaidh,
son of Diarmaid,	son of Fiachra.
son of Tighearnan,	

[Reachtabhra ^s ,	
son of Aeldobhar,	son of Ros,
son of Laitcenn,	son of Feidhlimidh,
son of Fuilim,	son of Amhalgaidh,
son of Dima,	son of Fiachra].

Fergus ^b and Aongus,	
two sons of Conall,	son of Cormac,
son of Fionan,	son of Aongus,
son of Conall,	son of Amhalgaidh,
son of Fearadhach,	son of Fiachra.

GENEALOGY OF THE MEN OF CEARA.

Cucothaigh,	
son of Maonach, of Ceara,	son of Fearadhach,
son of Dunchadh,	son of Ros Doimthigh,
son of Flann Rodhba, i. e. <i>Flann</i>	son of Maine Muinbreac,
<i>of the River Robe,</i>	son of Earc Culbhuidhe,
son of Maolduin,	son of Fiachra Foltsnathach,
son of Failbhe,	son of Eochaidh Muighmheadhoin.
son of Maolumha,	

Donncathaigh,

^b *Fergus*.—This line is given by our Author without any heading ; for it does not belong to Cineal Eunda, under which he places it.

[Donncaṡaigh,
mac Maílumai,
mic Fearadaigh,
mic Rora Doimṡigiu,

mic Maine Muinbricc,
mic Eirc Culbuidi.]

Cuig mec lap an Coincṡaigh rṡn, .i. Tighearnaṡ, ó d-táid Uí
Tighearnaigh, .i. Ríoga Ceara; Uaṡmarán, ó d-táid Uí Uaṡma-
ráin; Níall, a quo Mec Nell; Uada, ó d-táid Uí Uadach; agur
Fagarṡaṡ, ó d-táid Uí Fagarṡaigh, amail arperc:

Cuigear mac fa mór roḡan,
Níall, ir Uada, ir Uaṡmaran,
Fagarṡaṡ ro bṡir beárnaigh,
Lám eabharṡaṡ Tighearnaigh.

[Cuan, ó d-táid Clann Cuan,
mac Eacaṡ,
mic Floinn,
mic Fearadaigh,

mic Rora Doimṡigh,
mic Maine Muinbricc,
mic Eirc Culbuidi.]

SÍOL DATHI SÍOSANA.

Dati, mac Fiaṡraṡ, ríḡ Eireann, Alban, breatan, agur go Sliab
n-Ealpa, uair ar é do ḡab taréir Nell an ríḡe; .un. m-bliadna
rícead do iríḡe n-Eireann.

Ité

ⁱ *Donncaithaigh*. — This line is supplied from the Book of Lecan, fol. 79, page a, col. b.

^j *O'Tighearnaigh*, now anglicised Tierney, without the O'.

^k *Kings of Ceara*, i.e. chiefs of the territory of Ceara, now the barony of Cara, in the present county of Mayo.

^l *O'Uathmharaín*, now obsolete.

^m *Mac Neill*. — Duaid Mac Fírbis spells this name *Mac Nell*, but the Editor does not think it necessary to follow him, in this innovation, in the translation, as he has the authority of the Book of Lecan for making Néill the genitive form of Níall in almost every instance; but the original text of Duaid Mac Fírbis shall not be altered in any instance, al-

[Donncathaigh ¹ ,	
Son of Maelumhai,	Son of Maine Muinbrec,
Son of Fearadhach,	Son of Erc Culbhuidhi].
Son of Ros Doimdigiu,	

This Cucuthaigh had five sons, namely, Tighearnach, from whom is *the family of O'Tighearnaigh*¹, Kings of Ceara^k, Uathmharan, from whom is *the family of O'h-Uathmharain*¹; Niall, a quo *the family of Mac Neill*^m; Uada, from whom is *the family of O'h-Uadach*; and Faghartach, from whom is *the family of O'Faghartaigh*, as *the poet* said:

“ Five sons of great prosperity,
Niall and Uada, and Uathmharan,
Faghartach, who forced the gap,
And Tighearnach of the bounteous hand.”

[Cuan ⁿ , from whom are <i>descended</i> the Clann Cuain, was,	
Son of Eochaidh,	Son of Ros Doimtheach,
Son of Flann,	Son of Maine Muinbreac,
Son of Fearadhach,	Son of Earc Culbhuidhe.]

THE RACE OF DATHI, DOWN HERE.

Dathi, son of Fiachra, was King of Erin, Alba, Britain, and as far as the mountain of the Alps; for he succeeded Niall^o in the government, and reigned twenty seven years as King of Erin.

The

though it has been deemed necessary to preserve a uniform orthography of the names of men and places in the translation throughout. This family is now extinct.

ⁿ [Cuan.—This pedigree of Cuan, enclosed in brackets, is supplied from a copy of Mac Firbis's smaller work, compiled in 1666, in the collection of Messrs. Hodges and Smith, p. 173. For the situation of

the tribe called Clann Chuain see Notes to Giolla Iosa Mor Mac Firbis's poem.

^o *Succeeded Niall*. — Dathi succeeded his uncle Niall of the Nine Hostages in the year 405, according to O'Flaherty and the Irish Annalists, and was the last of the line of the Pagan kings of Ireland.—See additional remarks on this subject in the Addenda to this volume.

lé and ro na cata do cúir ag cornam Éiriond i n-biaig Nell, mic Eatac, .i. cat Áta Talmaide, cat bodaiḡe, cat Raḡa Cruacón, cat Muḡe h-Ailbe, agur cata iomda i n-Albain, agur Cat Muḡe Cincain, agur Cat Spata.

Luid Dáti iar rin go b-earpaib Éreann ler dár muir n-Icht docum Leata go m-baoi ag Sleb Ealpa do díogail Nell Naor-ḡiallaig. Ari rin aimir po ḡabarḡair Formenur (no Parmenur) ri Traigia a Shlab Ealpa ar d-toideact do ar tecead a riḡe agur ar ḡrád Dé go ríce Shlab Ealpa i n-aileire. Do rinead ler tor catrac, agur rearḡa traigib a aird, do fódair ocur do cloair, agur aon traigib deug uadrom go foille, agur po
baoi

^p *Ath Talmaide*.—This place is now unknown, at least to the Editor.

^q *Bodaiḡe*.—Unknown.

^r *Rath Cruachan*, now Rath Croghan, near Belanagare, in the county of Roscommon.

^s *Magh Ailbhe*.—This, which is Latinised *Campus Albus*, was the ancient name of an extensive plain in Leinster, extending from Slewmary, in the Queen's County, in an eastern direction, and comprising portions of the barony of Idrone, in the county of Carlow, and of the baronies of Kilkea and Moone, in the county of Kildare. Bealach Mughna, now Ballaghmoone, to the north of Carlow, is described in all the Irish authorities as in Magh Ailbhe. Ussher, in his *Primordia*, pp. 936, 937, thus describes this plain, on the authority of an ancient Life of St. Munnu:—"Campus ad ripam fluvii quem Ptolemeus Birgum, nos Barrow vocamus, non procul a monte Margeo posi-

tus." In a curious ancient poem, describing the monuments of Leinster, it is called the finest plain in Ireland.

^t *Magh Circan*, now unknown.

^u *Strath*.—There are many places of this name, signifying *holm*, or *strath*, in Ireland and Scotland, but the situation of the site of this battle is not defined.

^v *Muir n-Icht*.—This is the name by which the ancient Irish writers always call the British sea which divides England from France, and some have supposed it to be derived from the Iccian harbour, which Cæsar states that he sailed by to Britain. However this be, there can be no doubt what sea the Muir n-Icht is, from the many references to it in old Irish MSS.; Ussher, *Primordia*, p. 823, says, "Est autem mare Icht (ut ex Albei etiam et Declani Vitis didicimus) illud quod Galliam et Britanniam interfuit."

^w *Leatha*.—Duald Mac Firbis, in his

The following were the battles which he fought in defence of Erin after *the death of Niall*, the son of Eochaidh, viz., the battle of Ath Talmaide^p, the battle of Bodaighe^q, the battle of Rath Cruachan^r, and the battle of Magh Ailbhe^s; and many battles in Alba i.e. *Scotland*; the battle of Magh Circaín^t, and the battle of Srath^u.

Dathi went afterwards with the men of Erin across Muir n-Icht^v towards Leatha^w, until he reached the Alps^x, to revenge *the death of Niall of the Nine Hostages*^y. This was the time that Formenius (or Parmenius), King of Thrace^z, took up his residence in the Alps, having fled from his kingdom and retired thither for the love of God as a pilgrim. He erected there a circular tower of sods and stones sixty feet in height^a, and he lived in the middle of the tower, eleven

annotations on the Life of St. Patrick, says, that Leatha was the ancient Irish name of Italy; but Mr. Patrick Lynch, in his Life of Saint Patrick, page 77, says, that it was the Hibernicised form of Letavia, a name by which a part, and sometimes the whole, of Armoric Gaul was called by the writers of the middle ages; and he has been followed by Lanigan and others. See Addenda to this volume, where the subject will be further discussed.

^x *The Alps*.—*Sliabh Ealpa* is the name by which the ancient Irish writers designate the Alps.

^y *To revenge, &c.*—This would appear to be a mistake, for the monarch Niall of the Nine Hostages was not slain by a foreigner, but, according to all the authorities, by Eochaidh, son of Enna Ceinseallach, King of Leinster, who discharged a poi-

soned arrow at him on the banks of the Loire. But it may have happened that Eochaidh remained abroad, and that Dathi went to Gaul in pursuit of him. See Addenda to this volume.

^z *Formenius, &c.*—He is called *Formenius* in *Leabhar na h-Uidhri*, fol. 35, p. *b*, col. *a*. No account of this king is to be found in any foreign writer, as far as the Editor has been able to discover. Keating calls him Parmenius, a holy hermit, and O'Flaherty, in Ogygia, Part III. c. 87, p. 416, calls him "quidam Eremita S. Firminus" who, according to the Book of Lecan (fol. 302, *b*), was a king; but he does not call him King of Thrace.

^a *A circular tower, &c.*—*Top caépac*. O'Flaherty, in Ogygia (loco cit.), translates this *turris*, and describes it as seventeen cubits high. Keating calls it a *ouip-éach*, or hermit's cell.

baoi ríom i meadhon an tuir, agus ní faiceadh leir dhéne na roillirí and.

Tainis tra Dathi gur an top. Ar de ad bearta Dathi fíor, .i. ar daité a gabaltair agus a lamais, uair dá m-bé cead ag a diubhrasad no aincead oirra é, ar daité a lamais, conad uime rin no lean Dathi fair, agus Feradac a ainm ac dul roirid, agus toir no bairid Dathi fair. O do condaccatur muinir an rí an top uaidh, tangadar dia togar, agus no rgaroirid é, agus nó airgríod. Agus no airí Formenius an gaoit éirge, do togarbair Dia in n-olum tenead go n-deacaid mile cemionn ó'n top fódubis do rígne, agus no guibearbair do'n rí, do Dathi, co ná bia a plaitear ní buí rí ina rin; agus no guibearbair Dia fíor co ná buí oiriderc a leat ná a líge. Ní raibe tra íarom do ríogal ag an rí Dathi, acit airiad no bar ag taitmead an tuir, an tan tainis raigead gealain do ním éirge go b-fuar bair obann, aon uair de.

Mur

^b *Eleven feet from the light.*—The reading in *Leabhar na h-Uidhri* is, *ocur oen traig oec uao-rom co ríor*. From this it would appear that the diameter of the top, including the thickness of the wall, was twenty-two feet.

^c *Expertness.*—This derivation of the name of King Dathi is also given in *Leabhar na h-Uidhri*, fol. 35, p. b, col. a, but in the margin, and in a hand somewhat more modern than the original. Keating too gives the same derivation of the name, explaining *daité* by the modern word *capa*, expert, active, dexterous.

^d *Feradach.*—Keating also says that Fearadhach was his first name, and he calls *Dathi* his *forainm*, i. e. his cognomen.

^e *In a blaze of fire.*—The reading is nearly

the same in *Leabhar na h-Uidhri*, fol. 35, p. b, col. a. *Ruc tra Dia uaidh Formenius, i n-aolum teneo, mile cemenno ó'n tur*. This reading *i n-aolum teneo*, means that Formenius's body was converted into a blaze of fire, and in this subtle form removed from the tower, and from the impious assault of King Dathi and his Pagan plunderers. But in *n-olum teneo*, as the text is given by our author, means that his body was raised up in, i. e. within a mass of flame, which is a more correct idea, and seems to have been derived by the original writer from the fiery chariot of Elias.

^f *And he prayed, &c.*—The original runs in *Leabhar na h-Uidhri* (loco cit.) as follows:—*Ocur no guio Formenius in com-*

eleven feet from the light^b, and he saw not a ray of the sun or other light.

Dathi came to the tower. (He was called Dathi from his expertness^c [baite] at invading and shooting, for if there were one hundred *persons* shooting, i. e. *discharging arrows or javelins* at him, he would be protected against them by the activity of his hands in guarding, wherefore the name of Dathi clung unto him. Feradhach^d was his name when he went to the east, and it was on his expedition in the east he was called Dathi). When the king's (i. e. *Dathi's*) people saw the tower, they went to demolish it, and they tore it down and plundered it. Formenius felt the wind coming to him, and God raised him up in a blaze of fire^e one thousand paces from the tower of sods which he had built, and he prayed for King Dathi that his reign might continue no longer; and he also prayed God that his monument or tomb might not be remarkable. The life of Dathi endured no longer than until he had the tower destroyed, when there came a flash of lightning from heaven which struck him dead on the spot^f.

When

oio na bio flaitiur Dathi ní baó ría
inna rin, ocu po guio ná baó apóaic a
ligi. Ní ra bí epa oo paegal oc ono
píg aét aipet po báp oc eaiémeé na cat-
pac, in ean eanic paiget zelán oo nim
éucí co fuair báp.

"And Formenius prayed God that the reign of Dathi might endure no longer, and he also prayed that his monument might not be remarkable. The king enjoyed life only while he was destroying the tower, when a flash of lightning came from heaven upon him, so that he died."

Keating gives the story of the death of

Dathi as follows:—Do gab Dathi, mac
Fiaépac, mic Eóada Muigmeaðoin, oo
ríol Eipeamóin, píozaét Eipeann epí
bliaðna píceao. Fial, ingean Eacach,
ó ráióteap Cpuacán Féile, an céo bean
bí aige. An oapa bean, Eiréne, ingean
Opach, máéair Oilolla Muile. An
teap bean íomoppo, bí aige o'á n-gairéí
Ruab, ingean Aipicé Uicé-leacáin, mic
Fipconga, máéair Fiaépací Ealgaré,
agur ír o'á bpeíé fuair báp. Aip
ílióct an Dathi rí a tá O'Seacnapaig,
O'Duðoa, agur O'h-Eiðin. Fearaðac
pa céao ainm oileap oo, agur ír uime oo

Mur do éinneadap rir Éireann rin, do éuirriod Sborgc re
lapad i m-beol an rí, ionnur go raolfead gac aon go m-be' n-a
beataid, agur gur ob í a anail do be' ag teact tap a beul. A
deirid eoluid gur ob í an raigeat rin d'ar marbad Niall Naoi-
giallaid, do deonaid Dia do Formenur do cur, 'n a fíotbac, gur ob
oi do marbad Daí.

Do éuaid ona Formenur mile cémeno o'n t-Sliab rin ríor, conad
and ro an i n-áitrep oile.

Tabar tra Amalgaid, mac Daí, ceandur fear n-Éireann, agur
adnaid a atair ler ar iomcar, gur ro bhir naoi g-cata rir for-
mur, agur dech g-cata for éir, agur ré marb, amuil do éairpen-
dir a múintir pen corp an rí, ro muigeat rómpa fóir na pluagaid
teagaid riu. Até and ro amana na g-cat ro meaduid roime,
.i. cat Corpar, cat Cinge, no cat Cime, cat Colaim, cat Faile,
cat Mircail, cat Lunduin, cat Coirce, cat Moile, cat Drenur,
agur

gairé Daí de ar éapact do gabad a
airm air; ionann iomorro daí agur
tapa, agur do lean an foraim rin de.
Agur ir amlaid do marbad Daí, .i.
roigean teinide do éuicim i n-a mul-
lac ó neam, air m-beid do ag déanadh
concuir air an t-Fraingc; agur rílán
le Sliab Ealpa do marbad é, tré díog-
alcar Dé, mar gur h-airgeat leir dúir-
éac díreabair naomha, d'ar t'aimm
Parmenur, le r' malluigeat é; agur
iar n-a marbad amlaid rin, tugadap a
muintir a corp leó a n-Éirinn gur
h-aolacat a Roilg na Ríog a g-Crua-
cham é.

Thus translated by Dr. Lynch, the au-
thor of Cambrensis Eversus, in his Latin

translation of Keating's History of Ire-
land:

"Post Niellum Anno Domini 405 ex-
tinctum, Nepos ejus, ex fratre Fiachro,
Dathius Rex salutatur, et in ea dignitate
viginti tres annos perstitit, ter matrimo-
nio junctus, primum Feilæ Echachi filiæ,
a qua Cruachan Fheile traxit denomina-
tionem; Deinde Ethnæ, Orachi filiæ, Olilli
Molti matri; demum Ruadhæ, Arti Ucht-
leahoni, id est, Latipectoris, filiæ, quæ
Fiachum Elghodium pariens interiit. Ab
hoc Dathio genus suum O'Sachnesi,
O'Douhda, et O'Hein deducunt. Propri-
um ejus nomen Faradhachus, agnomen
Dathius erat, hoc ideo ipsi addito, quod
arma sibi quàm celerimè induere solitus

When the men of Erin perceived this, they put a lighted Sbongc [*Spongia?*] in the king's mouth, in order that all might suppose that he was living, and that it was his breath that was coming out of his mouth. But the learned say that it was the same arrow with which Niall of the Nine Hostages was slain, that God permitted Formenius to discharge from his bow that by it Dathi might be killed².

Formenius then went one thousand paces down from that mountain, and there dwelt in another habitation³.

Amhalgaidh, the son of Dathi¹, then took the command of the men of Erin, and he carried¹ the dead body of his father with him, and he gained nine battles by sea, and ten battles by land by means of the corpse: *for* when his people exhibited the body of the king, they used to rout the forces that opposed them. These are the names of the battles thus gained *by land*, viz., the battle of Corpar, the battle of Cinge, or Cime, the battle of Colom, the battle of Faile, the battle of Miscal, the battle of Lundunn, the battle of Coirte, the battle of Moile, the

fuerať, vox enim *daithi* celeritatem significat. Hic Galliam infestavit armis, et non procul ab Alpium finibus tum verſabatur, cum tactus de cœlo animam efflavit, Divino Numine poenas ab illo reſpoſcente, illati Parmenio cuidam viro memorabili ſanctimoniâ prædito, detrimenti, qui ſcœleſtum caput ob ſe violatum dirâ impræcatione defixerat. Sed cadaver a ſuis in Hiberniam aſportatum in Regum ſepulchro apud Cruachanum terræ mandatum eſt."

² *The learned say, &c.*—This paſſage, which differs ſo materially from the previous ſtory, is not given in Leabhar na h-Uidhri, but it is in the Book of Lecan, and in another MS. in the Library of

Trinity College, Dublin, H. 3, 17.

³ *Formenius then went, &c.*—This paſſage is in Leabhar na h-Uidhri, but in a more modern hand *inter lineas*.

¹ *Amhalgaidh, the ſon of Dathi.*—Leabhar na h-Uidhri has the following obſervation interlined here:—*Da Amalgaro po bá-ear anó, .i. Amalgaro, mac Fiaçpac, ocuť Amalgaro, mac Naçi, i. e.* "there were two Amhalgaidhs, viz., Amhalgaidh, the ſon of Fiaçhra, and Amhalgaidh, the ſon of Nathi." From the former the preſent barony of Tir-Amhalgaidh, now Angliciſed Tirawley, has derived its name.

¹ *He carried, &c.*—*Acnaig a acap leip.*—Leabhar na h-Uidhri. *Acnaig* is an ancient verb ſignifying *cug*, i. e. he brought.

agur caé ßernuir. Iy iad rin tra na caéa no muirioctar ré Daéi tpe n-a éopp do éairpeunad do na pluagaid agur ré marb.

Tugad trá corp Dhaéi go h-Erinn, go no h-aónaicead é i Releg na Riog i g-Cruacáin, i b-fail a rabattar. mionnairé ril Eremóin do umóir. Marb, umorro, Amalgaid, mac Daéi, iy na Derib breag, do gaoib éró na n-árd-gon fuair iy na caéaid rin. Conad i m-breagaid, no i m-breag-maid, acáid a élan agur a éneul, .i. Ceneul m-beccon.

Dungal, Planngur, Tuatal, agur Tomaltac, ar iad rin an ceatpar d'a aor gada tug leo corp an nio Daéi. [Tugad corp Dhaéi go Cruacáin, gur h-aónaicead e i Relg na Riog i g-Cruacáin, i b-fail a rabadar mionnairé Síol Ereamóin do umóir, aic a b-fuil gur anu an chairrte dearg mur liag or a lige 'n-a leact, laim re Rait Cruacáin gur anora 1666]. Go b-fuil for lár Aonaid na Cruacáin, amail no foillrig Torra Egear ag dearbaid adlaice mionnairé ril Ereamóin d' éaraid Erend :

Celir [ar] caé a Chruacá éroidearg, caom-nio Erend, Daéi, mac Baidac rial-ri ar muir, ar tpe, teargurtar caé cora nio iath no ort; ar caé m cel. Celir 7c.

Do Thorina Egear do foillrigead rin tpe fúigeact ar g-cup ailgeara

^k *These are the names, &c.*—The names of these battles, with some slight difference of orthography, are given in *Leabhar na h-Uidhri*, but in the margin, and in a hand somewhat more modern than the original text of the book.

^l *Dungal, &c.*—The names of these servants who carried home the body of Dathi are also given in *Leabhar na h-Uidhri*.

^m *Cairrthe dhearg.*—This passage enclosed in brackets is taken from our author's smaller work, compiled in 1666. The

Cairrthe dhearg is still to be seen at *Roilig na Riogh*, near *Rathcroghan*. It is a pillar stone of red grit, about nine feet in height, on a small mound, now called *Cnocan na g-corp*, about 200 paces to the north of the Pagan cemetery called *Roilig na Riogh*; but tradition at present has no recollection of its marking the sepulchre of Dathi, so that the imprecation of *Formenius* seems to have had its effect, when he prayed that his monument might not be honourable or conspicuous. No authority has been

the battle of Grenius, and the battle of Fermir^k. These were the battles gained by Dathi by exhibiting his dead body to the hosts.

The body of Dathi was carried to Erin, and interred in Releg na Riogh *the cemetery of the kings*, at Cruachan, where the kings of the race of Heremon were, for the most part, interred; and Amhalgaidh, the son of Dathi, died in Deisi Breagh of the venom of the deep wounds which he received in the above mentioned battles, and his tribe and progeny are in Bregia, or Breaghmhagh, i. e. the Cineal Becon.

Dungal', Flannghus, Tuathal, and Tomaltach were the four servants of trust who carried with them the body of the king. [The body of Dathi was brought to Cruachan, where the kings of the race of Heremon were, for the most part, interred, where, to this day, 1666, the cairrthe dhearg^m, *red pillar stone*, remains as a monument over his grave, near Rath Cruachan.] That the body of Dathi is interred in the middle of Aonach na Cruachna is attested by Torna Eigeas, in his poem pointing out the burial place of the kings of the race of Heremon to the men of Erin.

"Thou hast concealed from all, O Cruacha Croidhearg, the fair king of Erin, Dathi, son of Fiachra, a generous king by sea and land; all have been informed that he was killed in royal land; from all I will not conceal it. Thou hast, &c."

This was revealed to Torna Eigeas through poetical inspirationⁿ,
after

discovered for making this red pillar stone the monument of this monarch, except the smaller work, compiled in 1666, by Duaid Mac Firbis. Whether he had any written authority for the fact, it is now, perhaps, impossible to determine, but the Editor is of opinion that he had no authority for it but the tradition of the country, which was, no doubt, in his time very

vivid. The Editor saw this stone in the year 1837, when it was standing on the small mound already mentioned; but it has since been thrown down by the cattle, and is now lying prostrate, to the disgrace of the neighbouring gentry; the O'Conors, it must be hoped, will restore it.

ⁿ *Poetical inspiration*.—It was the belief in Ireland in Pagan times that a poet's

ailgeara u' fearaib' Eireann fain, im a fíor c'áit ar h-adhnaicead
Daí, mac Fiacraic, ní Eireann. Cona ann do nígne Torna Egear
an rítlearg fa aga dearbaid fín, agus po éan na panna fa :

Ata fuo-ra ní fionn b-fear b-Páil,

Daí, mac Fiacraic, fear ghaib,

A Chruaca, no céir fín

Ar Ghalluib, ar Ghaoidhealuib.

Ata fuo Dungalac dian,

Tug na gell tar muir aniar,

Ata fuo, foillrig a n-daí,

Cono, Tuatal, ir Tomaltaic.

Tní mec Eataic Feblig fíno,

Ataib do múr, mar maoidim,

Ata Eocaid Aineam faon

Ar na marbaid do mor-Mhaol.

Ata Eocaid Febleac plait

Fúo, agus Deirbre deac-mait,

Agus

mind was capable of being rendered prophetic by the aid of certain charms or incantations called *Imbas for Osnæ*, and *Teinm Loeghdha*; for some account of which see Battle of Magh Rath, pp. 46, 47, Note ^b. Torna Eigeas is said to have been chief poet of Ireland, and the tutor of the monarch Niall of the Nine Hostages, who was slain in the year 406.

^a *Rithlearg*.—*Retairic*, in *Leabhar na h-Uidhri*. It is the name of a kind of metrical prose put into the mouths of Druids and poets while under the influence of the *Teinm Loeghdha*.

^b *Man of dignity*.—In the Book of Leacan the reading is *feapgarib*, i. e. the fierce

or angry, and in *Leabhar na h-Uidhri* it is *mo aig*, i. e. of valour. These differences are traceable to the carelessness of transcribers, and sometimes to the obliterated state of the original MSS. from which the copies were made; for when the original was effaced or defective in some words the transcribers often filled up the blanks according to their own judgment.

^c *Who brought the hostages, &c.*—In the copy of this poem in *Leabhar na h-Uidhri* this line reads, *cuc in níg oap muir na rian*, i. e. who brought the king over the sea of roads, and this is obviously the true reading.

^d *Reveal their appearance*.—In *Leabhar*

after he had been requested by the men of Erin to discover where Dathi, son of Fiachra, king of Erin, was interred; so that it was on this occasion Torna Eigeas composed this rithlearg° *above given* to prove it; and he composed *also* the following quatrains:

“ Under thee lies the fair king of the men of Fail,
Dathi, son of Fiachra, man of dignity^p;
O Cruacha, thou hast concealed this
From the strangers, from the Gaels.

Under thee is Dungalach the vehement,
Who brought the hostages^q over the boisterous sea;
Under thee are, reveal their appearance^r,
Conn, Tuathal, and Tomaltach.

The three sons of Eochaidh Feidhleach^s, the fair,
Are in thy mound, as I boast,
As *also* is Eochaidh Aireamh^t feeble,
Having been slain by the great Maol.

The prince Eochaidh Feidhleach is
Beneath thee, and Derbhre^u of goodly aspect,

And

na h-Uidhri, full of the peace, of well-known prosperity.

^p *The three sons of Eochaidh Feidhleach.*—Eochaidh Feidhleach was monarch of Ireland, according to O’Flaherty’s Chronology, A. M. 3922, and had three sons, Breas, Nar, and Lothar, and six daughters, Mughain, Eile, Meadhbh, Deirbhre, Clothra, and Eithne, who are all much celebrated in Irish romance.

^t *Eochaidh Aireamh.*—He was brother of Eochaidh Feidhleach, and succeeded him as monarch of Ireland, A. M. 3934, according to O’Flaherty’s Chronology; (Ogygia,

Part III. c. 44, p. 271), who states that he was killed by lightning at Fremoinn, a hill in Teffia, in Westmeath (now Frawin Hill, to the north of Mullingar); but, according to Keating, he was slain at the same place, by a warrior called Siodhmall, which perhaps should be written Sidhmaol, as in this very ancient poem the slayer of this monarch is called the great *Maol*.

^u *Derbhre* is written *Ónebm* in Leabhar na h-Uidhri, and incorrectly called Deirdria by O’Flaherty (Ogyg. p. 267). She was one of the six daughters of the monarch Eochaidh Feidhleach.—See Note ^s.

Αἰγυρ Κλοῦρα, νι cem αἰργ,
 Αἰγυρ Μεαδδ, αἰγυρ Μυρεαργ.
 Ερε, Φοδλα, αἰγυρ δανδα,
 Τρι h-όγ-μῖνα αἰνε, ἀμῖρα,
 Αἰαῖο ἰ γ-Γρυαῖαῖν na γ-clann,
 Τρι ριοῖνα Τουατ De Danann.
 Τρι mec Cearmada a Sit Τρυμ,
 Αἰγυρ Λύγαῖο α Λιατρυμ,
 Clann Αοδα, μῖc an Ταῖδα,
 Αἰγυρ Μιῖοιρ μόν-ῶλμα.
 Αἰα ρόο lig na λυῖοε
 Cobtae Caol ἰρ Ugoine,
 Αἰγυρ δαδδῶαδ, ρem go ρατ,
 δραῖταιρ do Ugoine uallae.
 Clann Ρεδλῖμῖο Ρεῖτῖταιρ ράιν,

17

^v *Clothra*.—She was another of the daughters of Eochaidh Feidhleach, and gave name to the island of Inis Clothrann, in Lough Ree, an expansion of the Shannon between Athlone and Lanesborough.

^w *Meadhbh*, Latinized Mauda by O'Flaherty, and pronounced Meave. She was another daughter of Eochaidh Feidhleach, and a most celebrated character in Pagan Irish history, who is still vividly remembered in the traditions of the country.

^x *Muireasg*.—She was a daughter of Hugony Mor, monarch of Ireland, A. M. 3619. Book of Lecan, fol. 16, b, b.

^y *Eire, Fodhla, and Banba, &c.*—According to all the accounts of the Tuatha De Dananns, these were the three Queens of the Tuatha De Dananns at the arrival

of the Milesian or Scotie colony from Spain.—See Keating's History of Ireland, where almost all the bardic accounts of them are collected.

^z *The three sons of Cearmad*.—These were the three Tuatha De Danann kings who ruled Ireland at the period of the arrival of the Milesian or Scotie colony. They were the husbands of the three queens above mentioned.

^a *Sith Truim*, or Sith druim.—This, according to Keating, was the ancient name of the rock of Cashel.

^b *Lughaidh*, i. e. Lughaidh Lamhfhada, or Lughaidh the Long-handed, king of the Tuatha De Dananns, a character much celebrated in ancient Irish stories (see Ogygia, Part III. c. 13), and still the hero

And Clothra^r, no small honour *to thee*,
And Meadhbh^w, and Muireasg^r.

Eire, Fodhla, and Banba^r,
Three beauteous, famous young women,
Are in Cruachan of clans,
Three queens of the Tuatha De Dananns.

The three sons of Cearmad^r of Sith Truim^a,
And Lughaidh^b of Liatruim^c,
The sons of Aodh, son of the Daghdha^d,
And Midir^e, the great *and* brave.

Beneath thy stone are lying
Cobhthach Caol^f and Ugaine^g,
And Badhbhchadh of prosperous career,
Brother of the haughty Ugaine.

The sons of the noble Feidhlimidh Reachtmhar^h,

And

of many traditions.

^c *Liatruim*.—This was one of the ancient names of Tara Hill, in Meath.—See Dinnseanchus and O'Flaherty's *Ogygia*, Part III. c. 55.

^d *Daghdha*.—He was King of the Tuatha De Dananns for forty years, and is much celebrated in Irish stories.

^e *Midir*.—He was the son of Daghdha, and is much celebrated in Irish stories as Midir of Bri Leith, a hill near Ardagh, in the present county of Longford, where it was believed his spirit continued to reside long after his death. There is a very curious romance about this personage in *Leabhar na h-Uidhri*, which preserves one of the oldest poems in the Irish language.

^f *Cobhthach Caol*.—He is generally called Cobhthach Caol m-Breagh, i. e. Cobhthach the Slender, of Bregia. He was the son of Ugaine, or Hugony the Great, and monarch of Ireland in the year of the World 3665.

^g *Ugaine*.—He was a celebrated monarch of Ireland of the Scotie or Milesian colony, and ascended the throne in the year of the World 3619, according to O'Flaherty's *Chronology*.

^h *Feidhlimidh Reachtmhar*, or Felim the Lawgiver. He was monarch of Ireland early in the second century. For some account of him see Keating's *History of Ireland*, O'Flaherty's *Ogygia*, p. 306, and Colgan's *Trias Thaum.* p. 447.

17 clano Chuino 17 in 8-combail,
 Aét Art 17 Cormac na 8-caé;
 Deapb gur celir a Chpuaca.
 An naom, an togaril a mûir,
 A dubairt fûir 1 n-a pûin,
 A lîge an laoiç-ri ana
 Na bað oipðerc a Chpuaca.

Ατα.

Οατι,

¹ *The descendants of Conn*, i. e. Conn of the Hundred Battles, who became monarch of Ireland in the year of our Lord, 177.—See Keating and O'Flaherty's *Ogygia*, Part III. c. 60, p. 313.

² *Art*.—He was the son of Conn of the Hundred Battles, and monarch of Ireland in the early part of the third century. It is stated in *Leabhar na h-Uidhri* that this monarch was converted to Christianity and interred at Trevet in Meath.

³ *Cormac*.—He was the son of Art, and is generally styled O'Cuinn, as being the grandson of Conn of the Hundred Battles. He was one of the most celebrated of the Irish monarchs, and, according to *Leabhar na h-Uidhri*, embraced the Christian faith to the great annoyance of his druids, and was interred at Ros na riogh (now Rosnaree, near Slane, in the county of East Meath). Keating adds that St. Columbkille afterwards came to this place, and said three masses over the grave of his royal ancestor.

⁴ *The saint after the destruction of his walls*.—In *Leabhar na h-Uidhri* the last line of this quatrain reads better thus:

Ni bað apðerc, a Chpuaco. This quatrain is evidently misplaced, for it relates to Formenius the Eremite and the monarch Dathi. It should be introduced after the first quatrain; but as it is given last in all the copies, even in *Leabhar na h-Uidhri*, a manuscript of the twelfth century, the Editor does not feel himself at liberty to alter its position. Keating, in his *History of Ireland* (reign of Cormac O'Cuinn), quotes a considerable portion of this poem, which shall be here given, that the reader may have the advantage of Dr. Lynch's Latin translation of it.

Οά pñom-poiliz, iomorra, oo bi a n-Eirinn a nalloo, a n-aipir na Págan-taéta, 1 n-a-cuipéi upñór pñoz Eipeann, map ata ðpuz na ðóinne, agur Roiliz na pñoz, láim pe Cpuacain. 17 follur gur ð'ionao aðlaicé oo pñozab Eipeann ðpuz na ðóinne ar an reançar éuar; agur 17 deapb gur ð'ionao coicéann aðlaicé oo pñozab Eipeann Roiliz na pñoz, a 8-Cpuacain, oo pñir Thórna Eigeap 'ran laoið po pñor am' ðiað:

Ατα pút-ρα pñz pñonn Fáil,
 Οατι mac Píacnac pparguio;

And the descendants of Conn¹ are in the assembly,
(Excepting Art¹ and Cormac^k of battles);

It is certain that thou hast concealed them, O Cruacha.

The saint [i. e. *Formenius*], after the destruction of his walls¹,
Said to him [i. e. to *Dathi*], with prophetic spirit,

‘May not this hero’s monument

Be conspicuous;’ O Cruacha!

Under,” &c.

Dathi

Α Chpuaca, no ceilir roin
Ar Dhallanb, ar Dhaodaloib.
Αα fút, Dungalac oian,
Tug na geill cap muih aniar;
Αα fút, foillirig a n-bat,
Conn, Tuatál ir Tomaltac.
Tri mic Eacac Feidiligh finn
Ααίο fáo’ múr, map maoidim;
Αα Eocaió Aipeaní faon,
Iar n-a mapbaó le móh Mhaol.
Αα Eocaió Féidleac plaité
Fút, ir Deirdirigh deag-maité,
Aghur Cloépa, ní céim agh,
Aghur Meaóh, aghur Muraigh.
Eipe, Fóola aghur Danba,
Tri h-óg-mná áilne, aipha,
Ααίο a g-Cpuacain na g-clann,
Triar ban oo Thuatáib De Danann.
Tri mic Cearmasa á Sítoruim,
Aghur Luigaió á Liairuih
Clann Aoóa, mic an Daóda,
Aghur Míoir móh-éalma.
Αα fóó lig ’n-a luide
Coóeac Caol ir Uguine,
Aghur Daódbacó, réim go paré,
Aghur Ollam apo, uallac.
Thus translated by Lynch, the author

of Cambrensis Eversus :

“ Duo quondam præcipuæ notæ sepulchra in Hiberniâ extitere, dum ei adhuc Paganismi tenebræ offunderentur, in quibus plerique Hiberniæ reges terræ mandabantur, Bruigum, scilicet, prope Boinum amnem, et Cæmeterium Regum prope Cruachanum : in illo Teamoriæ reges sepeliri soliti sunt. Hoc autem omnibus Hiberniæ Regibus inhumandis vulgò prostitutum fuisse Turnus Egius fidem his carminibus facit :

“ O Cruachana, tua super tellure recondis
Indigenarum oculis peregrinorumque remotum
Insignem heroem, candentemque ora Dahihum,
Progenitum Fiachro Regem glacialis Iernæ,
Et Dungalachum præstantem viribus, hostis
Trans mare qui prædas duxit, formaque decoros
Tumultach, Conum, Tuathalum tres et Eochi
Feidalochi nivei natos, sub colle repostos,
Quos cognosco, tuo, quibus est adjunctus Eochus
Araimus dextrâ Mormoli cæsus, Eochus
Præterea Fedlach, necnon Derbrecha decora
Clothraque, Mebha simul cum Murca cedit honori
Non modico, Cruachana, tibi resista, sepulchro.
Tu quoque condis Eram, Follam Banbamque venustâ
Oris conspicuas specie, tres natio misit
Quæ Tuadedonan, Carmodi et pignora trina,
Qui coluit villam Sithrum ac ossa Lugadi,

Daí, umorpo, ceíre mec píceab aige, .i. Oilíoll Molt, Rí Epeann, agus Alban, fear do éabairg an dhomna fá éirí gan éat; agus Fiacra Ealgaic, ó d-taio Uí Fiacraic Muaidé, agus il-ceneula ele; Eocáio breac ó d-taio Uí Eachuio Muaidé agus Uí Fhiacraic Aíone; agus Eocáio meand, agus Fiacra mac Daí ar é po baio i n-gellíne ag Niall Naogíallac, agus ar uaída Uí Fhiacha, no Fhiacraic, Cuile Fabaí, i Míde. Eapc, Corc, Onbecc, beccon, Mac Uair, Aongus Lam-paia, Catál, Paolchu, o d-taio Uí Paolcon; Dungal, Conrac, Neapa, Amalgaid mac Daí, ó d-taio Cineul m-beccon, i m-breagaid beor, no i m-breagmuid. [beirer beor genelaic Cloinne Fírbirig gur an Amalgaid rin.] blacab no blacab, Cugamna, ó d-taio Mec Congamna, la Cineul Fein; agus Aod ó d-taio Uí Aoda la boirno.

Oilíoll Molt, mac Daí, mac doirén Ceallac, atair Eogan beul, agus Oilealla Ionbando, dá rig Chonnacht.

Eogan beul, umorpo, da mac lair, .i. Ceallac, ar a n-dearbad an martra móir, .i. a ceatra combaltaia fén d'a marbad a fill i n-Aro

Qui Liatrim coluit: necnon quos gignit Aidus Progenitus Dagao, cum bellatore Midro, Cobthachum Tenuem tegis Ugonemque sub herba, Heroesque alios Badbachum, copia rerum Cui fult, Ollamumque animis ingentibus altum."

^m *Twenty-four sons*.—It is strange, however, that only twenty are given by name.

ⁿ *Oilíoll Molt*.—He succeeded Laoghaire, the son of Niall, and was monarch of Ireland for twenty years, and died A. D. 483.

^o *The Borumean tribute*.—This was a very exorbitant mulct on the people of Leinster, said to have been first imposed by the monarch Tuathal Teachtmhar, A. D. 144. It was paid with great reluctance till

the latter part of the reign of Finnachta Fleadhach, and was the cause of much bloodshed, as the Lagenians seldom consented to the payment without a battle. It was finally remitted in the year 693, by Finnachta, at the request of St. Moling, to the great annoyance of the magnates of the Hy-Niall race. The monarch Brian, the ancestor of the O'Briens of Thomond, afterwards renewed this impost, for which he received his well known appellation of Brian Borumha. A historical tract on the Origin and History of the Borumean Tribute is preparing for publication by the Irish Archæological Society.

Dathi had twenty-four sons^m, namely, Oilioll Moltⁿ, King of Erin and Alba, and a man who exacted the Borumean tribute^o thrice without a battle; Fiachra Ealgach, from whom the Hy-Fiachrach of the Moy, and various other tribes are *descended*; Eochaidh Breac, from whom are *sprung* the Hy-Eachach of the Moy, and the Hy-Fiachrach Aidhne; Eochaidh Meann; Fiachra Mac Dathi, who was detained as a hostage by Niall of the Nine Hostages, and from whom the Hy-Fiacha, or Hy-Fiachrach, of Cuil Fabhair^p, in Meath, are descended; Earc; Corc; Onbecc; Becon; Mac Uais; Aongus the Long-handed; Cathal; Faolchu, from whom are the Ui Faolchon; Dunghal; Conrach; Neara; Amhalgaidh Mac Dathi, from whom are the Cineal m-Becon, in Bregia, or Breagh-mhuigh^q. [The pedigree of the Clann-Firbis^r is also traced to this Amhalgaidh.] Blachadh, or Bladhcadh; Cugamhna, from whom are the Mac Congamhnas, in Cineal Fechin^s; and Aodh, from whom are *sprung* the Hy-Aodha, in Boirinn^t.

Oilioll Molt, the son of Dathi, had a son Ceallach, the father of Eoghan Beul, and of Oilioll Ionbhanda, two kings of Connaught^u.

Eoghan Beul had two sons, namely, Ceallach, on whom the atrocious murder was committed, that is, his own four foster-brothers killed him treacherously at Ard an fhenneadha, at the instigation of Guaire

^p *Cuil Fabhair*.—This place was near Fore, in the county of Westmeath.

^q *Breagh-mhuigh*, a rich plain comprising the greater portion of the present county of East Meath.

^r [*The pedigree of the Clann Firbis*.—This passage is supplied from Duaid Mac Firbis's smaller work compiled in the year 1666.

^s *Cineal Fechin*, a territory in the south

IRISH ARCH. SOC. 12.

of the present county of Galway, comprising a considerable portion of the barony of Leitrim.—See Map in the Tract on Hy-Many.

^t *Boirinn*, now Burren, a rocky barony in the north-west of the county of Clare.

^u *Kings of Connaught*.—For the periods at which these kings reigned, see list of the Kings of Connaught towards the end of this volume.

n-*Arb* an *Fhenneaða*, *tré* *puráil* *Thuarie*, *míc* *Colmain*, *tre* *formad* *im* *ceann* *na* *rige*, *agur* *Cucoinzelc*, *mac* *Eogain*, *an* *mac* *ele*, *ar* *é* *por* *marb* *combaltaða* *Ceallai*, *trér* *an* *íon* *gail*, .i. *Maolcróin*, *Maolreanaig*, *Maolbalua*, *agur* *Mac* (*no* *Maol*) *Deoruid*. *No*, *ar* *é* *a* *riagad* *do* *ronad* *ag* *Sal* *Srotha* *derg*, *frir* *a* *n-abarétar* *Muaib*, *agur* *ar* *uaðaið* *atá* *Arb* *na* *riag* *ar* *an* *cului* *g* *óir* *Muaib*, *agur* *Arb* *na* *Maol* *aínn* *na* *culca*, *i* *n-ar* *h-að* *laicead* *iad*, *leat* *éall* *do'n* *c-rruid*.

CLANN EOCHAIÐH DHRIC, MÍC DATHI, AND SO SIS.

Eoðaið *breac*, *mac* *Dati*, *ceéne* *mec* *ler*, .i. *Laogairie*, *breéte*, *Ailgile*, *agur* *Eogán* *Aíðne*.

breéte, *mac* *Eacac* *bric*, *clann* *lair*, .i. *Muolparitce*, *ó* *o-táio* *Uí* *Maolaiçen*; *bróduð*, *ó* *o-táio* *Uí* *bróduib*; *breanaíno* *ó* *o-táio* *Uí* *Maolbrenuinn*, *agur* *Uí* *Chreacáin*. *Ar* *do* *cloinn* *breunuino*, *míc* *breéte*, *na* *tri* *Uí* *Suanai*, .i. *Fídmuine*, *Fíðairle*, *agur* *Fíðgura*, *no* *Fíðgur*, *tri* *mec*

Fíðbadois,

* *Sal Srotha Derg*, an ancient name of the River Moy.

" *Ard na riagh*, now Ardnarea, a village on the east side of the River Moy, in the barony of Tireragh and county of Sligo. This village, which may be now considered as a suburb to the town of Ballina, is connected with it by a bridge over the River Moy; but the locality originally called *Ard na riagh*, i. e. the hill of executions, immediately adjoins the village to the south, and is now generally called the Castle Hill, from a castle which formerly stood upon it.

* *Ard na Maol*, i. e. height or hill of the *Maols*, i. e. where the four youths whose names began with the word *Maol* were interred. For a more circumstantial account of the execution and interment of the four *Maols*, see Dinnseanchus in the Book of Lecan, fol. 246. The monument raised over these youths is still in existence, and situated on a hill on the west side of the River Moy, nearly opposite the hill of *Ard na riagh*, in the parish of Kilmore-Moy and barony of Tirawley, a short distance to the south of the town of Ballina. It is a remarkable Cromlech supported by

Guaire *Aidhne*, son of Colman, through envy about the sovereignty; and Cuchongelt Mac Eoghain, the other son, was he who slew the foster-brothers of Ceallach in revenge for their fratricide; they were Maolcroin, Maolseanaigh, Maoldalua, and Mac (or Maol) deoraidh. Or, *according to others*, these were hanged at *the river of* Sal Srotha Derg^r, which is called the Muaidh, and it was from them the hill over the Muaidh was called Ard na riogh^w; and Ard na Maol^x is the name of the hill on the other side of the stream, where they were interred.

THE DESCENDANTS OF EOCHADH BREAC, THE SON OF DATHI, DOWN HERE.

Eochaidh Breac, the son of Dathi, had four sons, namely, Laogh-aire, Brethe, Ailghile, and Eoghan Aidhne.

Brethe, the son of Eochaidh Breac, had issue, viz., Maolfaithe, from whom are the *family of* O'Maoilaichen^r; Brodubh, from whom are the *family of* O'Broduibh^s; Breanainn, from whom are the *family of* O'Maoilbreanainn^a, and the *family of* O'Creachain^b. Of the descendants of Breanainn, the son of Brethe, were the three O'Suanaighs, namely, Fidhmuine, Fiodhairle, and Fidhgusa, or Fiodhgus; *who were* the three sons of

Fiodhbhadach,

three pillar stones, and fixed as level as a horizontal dial. It is now popularly called the Table of the Giants by the natives when speaking English, and *Cloch an togbhála*, i. e. the raised stone, in Irish. This is the only Cromlech in Ireland which can be satisfactorily connected with history. In the Dinnseanchus this monument is called Leacht na Maol, and said to occupy a *lofty situation*, which, coupled with the description of its situation on the other

side of the Moy opposite Ard na riagh, leaves no doubt of its identity.

^r *O'Maoilaichen*, now unknown.

^s *O'Broduibh*, not known.

^a *O'Maoilbreanainn*, now always anglicised Mulrenin; the name is numerous in many parts of the province of Connaught.

^b *O'Creachain* is probably the name now anglicised Creaghan and Greahan.

Ḥiob̄b̄ab̄oiḡ,	
mīc Conb̄uiliḡ,	mīc ḡp̄enuinn,
mīc Com̄ain,	mīc ḡp̄ete,
mīc Suan̄aiḡ,	mīc Eac̄ac̄ ḡp̄ic,
mīc C̄p̄eac̄ain Mūaib̄e,	mīc Dāti, p̄iḡ Ēp̄eann.
mīc ḡp̄uib̄e,	

Ḥeap̄am̄la, ingean Dioma Duib̄, mīc Diap̄m̄ba, mīc Sean̄aiḡ,
mīc Laoḡair̄e, mīc Eac̄ac̄ ḡp̄ic, mīc Dāti, mātaip̄ na ḡ-ḡp̄i Ua
Suan̄aiḡ. Aḡup̄ ap̄ í mātaip̄ Aōb̄ain Chluana Eoc̄aille, 'ra
Chop̄ann, aḡup̄ ap̄ í mātaip̄ Dīclēte Uí Th̄p̄iallaḡ p̄a h̄-áit̄p̄eb̄ p̄il
í ḡ-ḡp̄ic̄ Ciap̄p̄aiḡe Lūac̄p̄a, aḡup̄ ap̄ í mātaip̄ Colm̄ain, mīc Eac̄ac̄,
p̄il í Sean̄bōtāc̄, í n-l̄b̄ Cen̄p̄ioluiḡ. Con̄ib̄ iad̄ p̄in naom̄ Ua n-Eac̄-
ach Mūaib̄e. Ap̄ p̄h̄ioc̄t̄ Eac̄ac̄ ḡp̄ic, mīc Dāti, at̄a Colman aḡup̄
Aōb̄ain. Naom̄ im̄opp̄o p̄il Eac̄ac̄ ḡp̄ic, .i.

Colman,	
mac̄ Dūac̄, ó ḡ-ḡá Ceall M̄h̄ic	mīc Ḥoib̄nenn,
Dūac̄,	mīc Con̄aill,
mīc Ain̄m̄p̄eac̄,	mīc Eoḡain Aib̄ne,
mīc Con̄aill,	mīc Eac̄ac̄ ḡp̄ic,
mīc Cob̄taḡ,	mīc Dāti.

Aḡup̄ na ḡp̄i Uí Suan̄aiḡ at̄e an̄b̄ p̄o a n-ḡab̄ála, .i. Ḥīomuine í
Rat̄uin, Ḥīb̄air̄le í ḡ-Cionu ḡ-Sáile, aḡup̄ Ḥīōḡup̄ í n-Ḥlar̄-ḡap̄p̄uiḡ.
Ap̄

^c *The Three O'Suanaighi*.—These were three saints of some celebrity in Irish history.

^d *Cluain Eochaille*, now Cloonoghill, in a parish of the same name, barony of Corran and county of Sligo.

^e *Sean bhothach*, called Sean boithe Sine in the Annals of the Four Masters, ad ann. 601, now Templeshanbo, i. e. the church of *Sean boithe*; it is situated at the foot of

Mount Leinster, in the barony of Scarawalsh and county of Wexford. The country anciently called Hy-Cinsellaigh comprised the entire of the present county of Wexford, and parts of those of Carlow and Wicklow.

^f *Ceall mhic Duach*, i. e. the church of the son of Duach, now Kilmacduagh, in the barony of Kiltartan, in the south-west of the county of Galway.

^g *Rathain*, generally called Rathain Uí

Fiodhbhadach,	
son of Cuduiligh,	son of Brenainn,
son of Coman,	son of Brethe,
son of Suanach,	son of Eochaidh Breac,
son of Creachan of the Moy,	son of Dathi, King of Erin.
son of Bruidhe,	

Fearamhla, the daughter of Dioma Dubh, son of Diarmaid, son of Seanach, son of Laoghaire, son of Eochaidh Breac, son of Dathi, was the mother of the three O'Suanaighs^c. She was also the mother of Aodhan, of Cluain Eochaille^d, in Corann, and of St. Dichlethe O'Triallaigh, whose habitation is in the country of Ciarraighe Luachra. And she was the mother of St. Colman, the son of Eochaidh, who is, i. e. *lies interred* at Sean bhothach^e, in Hy-Censiolaigh; and these are the saints of the Hy-Eathach, of the Moy. Of the race of Eochaidh Breac, son of Dathi, are the Saints Colman and Aodhan. The following are the saints of the race of Eochaidh Breac, viz.:

Colman,	
son of Duach, from whom Ceall	son of Goibhnenn,
mhic Duach ^f ,	son of Conall,
son of Ainmire,	son of Eoghain Aidhne,
son of Conall,	son of Eochaidh,
son of Cobhthach,	son of Dathi.

Also the three O'Suanaighs, *already mentioned*, who were established at the following places, viz., Fidhmuine, at Rathain^g; Fidhairle, at Cionn Saile^h; and Fiodhgus, at Glas-charraigⁱ.

It

Shuanaigh in the Irish Annals, now Rahen, in the barony of Ballycowan and King's County, and about five miles to the west of the town of Tullamore. There are remains of two very ancient churches at this place, of which a minute description is given in Mr. Petrie's Essay on the Round

Towers of Ireland. The death of Fidhmuine, who is called anchorite of Rathain, is recorded in the Annals of the Four Masters at the year 750.

^h *Cionn Saile*, now Kinsale, a well-known town in the south of the county of Cork.

ⁱ *Glascharraig*, i. e. the green rock, now

Ar e umorro Dúclete Ua Triallaiḡ, d'á n-ḡoirítear Triallac, po euloið ó Thir Amalḡaið ḡo Dúiriorc Uí Triallaiḡ, ar bhrú Caráin Ciarraiḡe; aḡur ar air do ronað an miorbhuile mór; dia raiðe aḡ triall imítecta ó macaibha mátar for eaçtra d'iarraið in Chomdeað, ḡur ḡabadar é, aḡur ḡur cuibriḡriod aḡ cor ḡlair iaroinn eoir a ceann aḡur a cora, aḡur do cuireað eoçair an ḡlair ir in fairrḡe. Aḡur ḡabar bpadán an eoçair ina beol, ḡur fluiḡ í. Eulair Triallac for an eachtra i ḡ-curaç ḡan coðail, .i. ḡan cpoicinn, ar an fairrḡe timcioll Epeann riar, aḡur an ḡlar eoir a ceann aḡur a cora, ḡo ráiniḡ ar bhu Ciarraiḡe Luacra, aḡur bpadan na h-eoçrac i ḡ-comdeact an cleiriḡ, ḡur ḡaib porc (tre furtaç n-De), i n-Dúiriorc Uí Triallaiḡ, ar bhrú Caráin Ciarraiḡe, co na feadar a braitreca ná a chineað ca leat do cuaið.

Do cuaið iarann Ua Suanaig aḡur Aoðan do iarraið míc a matar, uair nír feadar a uiol na a uiac, ḡo b-fuarriod é aḡ an Dúiriorc, aḡur a ḡlar fair, eoir a ceann aḡur a cora, aḡur re d'á dúcleç ar na cleircib bádar d'á iarraið. Nír çian dóib ann ḡo b-pacattar larḡaire cuca, .i. fear na h-airrebe, aḡur riabaiḡir riar na cleircib, aḡur do rona umaloið uiob, uair do airin ḡur do muiur

Glascarrick, a well-known place on the coast near Gorey, in the north-east of the county of Wexford; but no tradition of the saint is now preserved there. Fidhairle Ua Suanaigh is called of Rathain by Tighernach and the Four Masters, but they differ about the year of his death, the former placing it in the year 763, which is no doubt the true year, and the latter in 758.

¹ *Disert Uí Triallaigh, on the brink of the Casan Ciarraighe.*—This place is still

well known, and is the name of an old church near the south bank of the River Feal, to the west of Listowell, in the barony of Clanmaurice, and county of Kerry. The name Casan Ciarraighe, i. e. *the path of Kerry* (it being the high road into the country), anglicised Cashen River, is now applied to that part of the River Feal extending from the point where it receives the River Brick to the sea; but it is highly probable that the appellation of Casan Ciarraighe was originally applied to

It was Dichlethe O'Triallaigh, commonly called Triallach, that absconded from Tir Amhalgaidh, and went to Disert Ui Triallagh', on the brink of the *river* Casan Ciarraighe; and it was upon him the *following* great miracle was performed. One time, as he attempted to go away from the sons of his mother on an expedition to seek for God, they took him and fettered him, placing a lock of iron between his head and feet; and the key of the lock was cast into the sea, and a salmon took it in its mouth and swallowed it. Triallach *soon after* stole away on his expedition, and put to sea in a currach *which was not covered* with leather, and went round Ireland westwards, with the fetter between his head and feet, until he arrived on the coast of Ciarraighe Luachra^k, whither the salmon which had swallowed the key accompanied him, and by the assistance of God he landed there at Disert Ui Triallaigh, on the brink of *the river* Casan Ciarraighe, so that neither his brothers nor tribe knew in what direction he had gone.

O'Suanaigh and Aodhan afterwards went in search of their mother's son, and they knew not his fate or destiny until they found him at the Disert with his lock on between his head and feet, and he hiding himself from those clerics who were in search of him. They were not long there when they saw a fisherman^l coming towards them, the man to whom the habitation belonged, who bade the clerics welcome, and made obeisance to them, for he perceived that they

were

the river as far as it is navigable for a currach, or ancient Irish leather boat; and the fact that this church of Disert is described as on the margin of the *Casan* is no weak corroboration of this opinion.

^k *Ciarraighe Luachra* was the ancient name of a territory comprising the greater part of the present county of Kerry, as appears from O'Heerin's Topographical

poem, and many other authorities.

^l *Fisherman*. — Salmon's still much abound in this river; and when the Editor visited the church of Disert Triallaigh, in the summer of the year 1841, he was ferried across the river to the church, which is on the south side, by a fisherman, in a fishing cot, or small flat-bottomed boat.

muinicip De dóib, agus gur ob ag iarraidh an naoimh baol na n-ghlar báttur por an eacra ran, agus aoberc Triallac na cléirig do iarpuigad go maic, uair oleagaid aigib a riar. Ted iarum an t-iarfgaire do cup a lín dóib, go n-deberc Ua Suanaig rir, do geabta lán do lín, .i. bradán gacá mozuill ad líon, agus ná eug leat acé ár n-baictin, .i. bradán gac rir. Do pine an t-iarfgaire amlaid, agus do pad bradán do gac cléneac díob, agus rrit an eocair an muid an bradán eug do Thriallac, gur h-ordaid an glar di; agus atá an cuibric ran 'n a miond mionbairleac, agus Glaran Ua Triallaigh a comaimm.

Ar aine raitear Diclete Ua Triallaigh, .i. ar an g-clé do pona ar pén ag eulód ó a bráitrib, agus i d-tig an iarfgaire. Ar aine a deapair Triallac rir, ó'n triall do pona ar fairrige do aindéoin a bráitreaic.

Ailgile, mac Eataic boric, dia d-táid Muinicip Ailgeanain, no Ailgile, agus dia m-baol an fáid oirdere, .i. Cu-temin mac Ailgile.

Cuboirne, umorpo, an cuigead mac Eataic boric, ar uada, ríde atáid Muinicip Moáin Chille h-Átrac, .i. maor na Croiri Átrac.

GENEALACH

^m *Glavan O' Triallaigh.*—The Editor could find no account or tradition of this relic in the neighbourhood of the old church of Disert Triallaigh, so that it has probably been for some time lost, or carried away from the locality.

ⁿ *Triallach.*—If this be true it looks very strange that *Ua*, or *O'* should be prefixed to this name. It is probably a mistake, for, if true, it would go to prove that Triallach was the name of his grand-

father, and not of himself. No account of this Triallach has been as yet found in any other authority. His name is not entered in any of the Irish calendars, nor is his festival day now remembered at his church of Dysart, in Kerry.

^o *The celebrated prophet Cutemhen.*—In the Book of Lecan, fol. 80, page a, col. 1, he is called Cutemnen. The Editor has not yet been able to find any other notice of this Cutemhen or his prophecies.

were of the people of God, i. e. *ecclesiastics*, and that they had set out on their journey to search for the saint who was bound by the fetter. Triallach ordered that the clerics should be well entertained, "that strangers were entitled to attention." The fisherman then went to set his net for them, and O'Suanaigh said to him, "thou wilt take the full of thy net, that is a salmon in each mesh, but do not bring with thee more than a sufficiency for us, that is, a salmon for each man." The fisherman did accordingly, and he presented a salmon to each cleric; and the key was found in the belly of the salmon given to Triallach, and the lock was opened with it. That fetter is now a miraculous relic, and known by the name of Glasano Triallaigh^m, i. e. *Triallach's little lock or fetter*.

Triallach was called Diclethe, from the cleth, *or concealment*, which he made of himself in escaping from his brothers, and in the house of the fisherman. And he was called Triallachⁿ from the triall, *or voyage*, which he made on the sea in despite of his brothers.

From Ailghile, son of Eochaidh Breac, are *descended* Muintir Ailgheanain, or Ailghile, and of whom was the celebrated prophet Cutemen^o Mac Ailghile.

From Cuboirne, the fifth son of Eochaidh, are descended Muintir Mochain^p, of Cill Athracht^q, i. e. the keepers of the Cross of St. Athracht.

PEDIGREE

^p *Muintir Mochain*, now anglicised Mohan or Moghan, and the name is still common in the north of the county of Roscommon. The O'Clerys give also the pedigree of Domhnall O'Mochain, abbot of Boyle, who died in the year 1441; it runs thus:—"Domhnall, abbot of Boyle, son of Diarmaid, son of Muirgheas, son of Simon, son of Nichol, son of Domhnall, son of Donnchadh, son of Muircheartach."

IRISH ARCH. SOC. 12.

^q *Cill Athracht*, i. e. the church of St. Athracht, now Killaraght, a parish in the barony of Coolavin, in the county of Sligo. Athracht was cotemporary with St. Patrick, from whom she is said to have received the veil in the year 470. Her holy well in this parish is still held in the highest veneration, and visited by pilgrims, but the Editor has not been able to determine whether her cross is still

G

GENEALACH UA MOCHAIN.

Ḑreagóir Aipó-eaproc Thuama,

mac Siomoin,

mic Niacóil,

mic Domnuill,

mic Donncaid,

mic Muirceartaigh,

mic Muirceadaigh,

mic Fionn,

mic Meanman,

mic Donncaid,

mic Aiteartaigh,

mic Muirceartaigh,

mic Muircuid,

mic Močan a quo Uí Močan,

mic Aongusa,

mic Treartaigh,

mic Tighearnaigh,

mic Taidg,

mic Ailgeanaigh,

mic Concabair,

mic Floinn,

mic Caecil,

mic Con-boirne,

mic Eacac boric,

mic Daici rig Eireann.

No gomaó mac d' Eoghan Aidne, mac Eocaid boric, Cuboirne, ó d-taid Uí Močan; agur ar fíor rín.

Cland Laoğaire, mic Eacac boric, .i. Muinir Muircean Gleanna Maoilbúin la h-Eidneigh, agur Muinir Muircean ele la h-Umall, agur ar aon aicme iad apáon iar n-ğaol ġenealaigh, .i.

Maoilbúin,

in existence. The present head of the Mac Dermotts, who styles himself the prince of Coolavin, incorrectly, his real title being the chief of Moylurg, holds this saint in such veneration that he has given her name to one of his daughters.

* *Gregory, Archbishop of Tuam.*—Gregory O'Moghan was promoted to the see of Tuam in the year 1385, but deprived in 1386. His death is recorded in the Annals of the Four Masters at the year 1392, in

these words:—“A. D. 1392. Gregory O'Mochain, Archbishop of Tuam, a pious and charitable man, died.”—See also Ware's Bishops. The O'Clerys carry the pedigree three generations later, thus:—Maghnus and Diarmaid, sons of John, son of Gregory, son of Simon, &c., so that it would appear that this bishop had been married before he received holy orders.

* *Gleann Maoilduin, at the Eidhneach.*—The situation of this valley is unknown to

PEDIGREE OF O'MOCHAIN.

Gregory, Archbishop of Tuam ^r ,	
son of Simon,	son of Mochan, a quo the O'Mo-
son of Nicholas,	chains,
son of Domhnall,	son of Aongus,
son of Donnchadh,	son of Treasach,
son of Muirheartach,	son of Tighearnach,
son of Muireadhach,	son of Tadhg,
son of Finn,	son of Ailgheanach,
son of Meanman,	son of Conchobhar,
son of Donnchadh,	son of Flann,
son of Aitheasach,	son of Cathal,
son of Muirheartach,	son of Cuboirne,
son of Murchadh,	son of Eochaidh Breac,
	son of Dathi, King of Ireland.

Others say that the Cuboirne from whom the O'Mochains are descended, was son to Eoghan Aidhne, the son of Eochaidh Breac; and this is true.

The descendants of Laoghaire, son of Eochaidh Breac, are the Muintir Muiren, of Gleann Maoilduin, at the Eidhneach^r, and another family called Muintir Muiren, in Umhall^r, and they are both the same family with respect to their descent, viz. :

Maoilduin,

the Editor. But it is highly probable that it was the ancient name of the valley through which the River Inny, in the west of the barony of Tirawley, flows.

^r *Umhall*.—This territory, which is very celebrated in ancient Irish history, and of which, since the establishment of surnames in Ireland, in the tenth century, the

O'Malleys have been hereditary lords or toparchs, comprised the present baronies of Burrishoole and Murrisk, verging on the Atlantic, in the west of the present county of Mayo. Sir Samuel O'Malley is believed to be the present senior representative of the chiefs of Umhall.

Maolbúin,	
mac Muirén, a quo Uí Muirén	mic Maolbúin, o páitear
i n-Uíall,	Seann Maolbúin,
mic Diarmada,	mic Criomhainn,
mic Seanaig,	mic Dioma,
mic Laoгаire,	mic Diarmada,
mic Eacac bric,	mic Seanaig,
Agur Maol-briгde,	mic Laoгаire,
mac Muirén,	mic Eacac bric.
Cuimin,	
mac Dioma,	mic Seanaig,
mic Diarmada,	mic Laoгаire, &c.

Ара ísol íl i г-Cill Cuimin, .i. Uí Cuimin; agur ní h-é an Cuimin íin íor beannaig an baile ar túr, ac

Cuimin Foba,	
mac Conaing (no Conall),	mic Amalgaid,
mic Fearгura,	mic Fiacrac.

An tan ío h-aḡnac Cuimin, mac Dioma, ar ann ío h-aḡnaicead ír in Ulaib móir íó coraib Uí Suanaig, agur ír íaḡ a ísol íl ír in Cill o íin anuaí.

Ua

^u *Cill Cuimin*, now Kilcummin, a very ancient church which gave its name to a parish in the barony of Tirawley, and county of Mayo, lying on the western side of the Bay of Killala. The name O'Cui-min is now anglicised Comyn, or Cummins.

^v *In the church, &c.* — This passage is very obscure and unsatisfactory, as it does not inform us which of the three saints

who bore the surname of O'Suanaigh is referred to; and as we are given elsewhere to understand that one of these brothers was at Rathain, another at Cionn Saile, and the third at Glas-charraig, it is not easy to comprehend what is meant by this passage at all. The probability, however, is, that one of these brothers returned to his native country in his old age, and was interred at Cill Cuimin, and that his tomb

Maolduin,	
son of Muiren, a quo Ui Muiren	son of Maolduin, from whom is
in Umhal,	called Gleann Maoilduin,
son of Diarmaid,	son of Criomhthann,
son of Seanach,	son of Dioma,
son of Laoghaire,	son of Diarmaid,
son of Eochaidh Breac,	son of Seanach,
and Maolbrighde,	son of Laoghaire,
son of Muiren,	son of Eochaidh Breac.

Cuimin,	
son of Dioma,	son of Seanach,
son of Diarmaid,	son of Laoghaire, &c.

Whose descendants are at Cill Cuimin^u, that is the *family of* O'Cuimin. But he is not the *Saint* Cuimin by whom the place was first blest ; for he was

Cuimin Foda,	
son of Conaing or Conall,	son of Amhalgaidh,
son of Fergus,	son of Fiachra.

When Cuimin, the son of Dioma, was buried he was interred in the large uluidh, *or altar-tomb*, at the feet of O'Suanaigh, and it is his descendants that have been *as comharbas* in the church^v ever since.

O'Dorchaidhe

was well known there for ages after. The old church of St. Cuimin Fada is one of extreme antiquity, and there are several old tombstones in the churchyard, but none at present bearing the name of O'Suanaigh, nor is the Uluidh mhor, or great cairn or tomb, in which was interred	Cuimin, the ancestor of the family of O ^u Cuimin, who were comharbas, airchin-nechs, or wardens of this church, now identifiable or traceable. For the meaning of the word Uluidh see Battle of Magh Ráth, p. 298, Note °, where it is shown that uluib is still a living word.
---	--

Ua Dorcaíde, agus Ua Goirmiallaigh (dá tsaoiríoch Partraiḡe), do éiloinn Laoḡaire, mic Eacac b'ric, no Muaidé. Ad iomda na Partraiḡe. Fec Shioct d'hríam, mic Eacach Muigmeadhoin, cuille díob.

O Dorcaíde tsaoiríoch Partraiḡe, mar ad beir Mac Fírberigh (Giolla Iosa Mór), in b'liadainn rí do aoir Chriost 1417. Fec leatanaic ród.

Maid do éorain fonn na b'fear
O Dorcaíde ar ár d'aigneas,
Críoch Partraiḡe na ḡ-call ḡ-cuir,
Le crann alt-buidé i n-íomḡuin.

Dorchaidé,	
mac Olucaigh,	mic Laoḡaire,
mic Dioma Cróin,	mic Eocnó b'ric,
mic Diarmada,	mic Daéi.
mic Seanaigh,	

UI DORCHAIDHE ḡAILLMHE.

Seamur Riabach, agus Domnigh,	
mec Nioclair,	mic Tomair,
mic Seamuir Riabach,	mic b'haiteir Riabach, an céo
mic Nioclair,	feair d' íb Dorcaíde táinig ḡo
mic Concabair,	ḡailim, do r'ép lueta ḡail-
mic Pádraigh,	mé pén.

Mairtin,

^w *O'Dorchaidhe*.—This name is still common in the county of Mayo, and anglicised Dorcey, Darcey, and sometimes even D'Arcy.

^x *O'Goirmiallaigh*, now Gormley, but this family is to be distinguished from that of O'Gairmleadhaigh, or O'Gormley of the province of Ulster, who are of a different

race, and a far more distinguished family.

^y *Partraighe*, now anglicised Partry. For the situation and exact extent of this territory, which still retains its ancient name, see notes to the Topographical Poem of Giolla Iosa Mor Mac Fírbis, which will be given further on.

^z *Well has he defended*.—The language

O'Dorchaidhe^w and O'Goirmiallaigh^x (the two chiefs of Partraighe^y) are of the race of Laoghaire, the son of Eochaidh Breac (or *Eochaidh* of the Moy). There are many Partraighes.—See the Genealogies of the Race of Brian, son of Eochaidh Muighmheadhoin for more of them.

O'Dorchaidhe was chief of Partraighe according to Mac Firis (Giolla Iosa Mor), in the year of Christ 1417.—See page further on.

Well has he defended^{*} the land of the men,
O'Dorchaidhe of the high mind,
The country of Partraighe of fine hazel trees,
With a yellow-knotted *spear*-shaft in the battle.

Dorchaidhe,
Son of Dluthach,
Son of Dioma Cron,
Son of Diarmaid,
Son of Seanach,

Son of Laoghaire,
Son of Eochaidh Breac,
Son of Dathi.

O'DORCHADHE OF GAILLIMH^a.

James Riabhach, and Dominic,
Sons of Nicholas,
Son of James Riabhach,
Son of Nicholas,
Son of Conchobhar,
Son of Patrick,
Son of Thomas,

Son of Walter Riabhach, the first
man of the *family* of O'Dor-
chaidhe who came to Gaillimh,
according to the people of
Gaillimh themselves.

Martin,

of this quatrain is very much transposed ;
the natural order would be the following :

Well has O'Dorchaidhe of the lofty mind
Defended that land of heroes
The country of Partraighe of fine hazel trees,
With a yellow-knotted spear-shaft in the battle.

^a *O'Dorchaidhe of Gaillimh*, i. e. the
O'Dorceys or Darcys, of Galway. This
family have taken the name and arms of
the D'Arcys, and are now considered an
offset of the D'Arcys of Meath ; but this
is a perversion of history which the Editor

Μαίρτιν,
 mac Ρίρδερσ,
 mic Μαίρτιν,
 Μαίρτιν,
 mac Seamuir Ο'Γ,

feels himself called upon to notice and correct. It is clear from Mac Firbis, who wrote in the College of St. Nicholas, at Galway, in 1645, while the celebrated lawyer Patrick Darcy was living, that they then considered themselves to be of the ancient Irish race, though they were not able to supply him with more than eight generations of their pedigree (and there can be little doubt that these were supplied by Patrick the lawyer), viz., from James Riabhach, the head of the family in Mac Firbis's time, up to Walter Riabhach, the first of the family who, "according to the people of Galway themselves," settled in the town of Galway. In the last edition of Lodge's *Peerage* was published a pedigree, patched up by one of the family, who very ingeniously engrafted this family on that of the D'Arcys of Meath, and accounts, by a bold assertion, which is not proved, and which cannot be true, for the manner in which they obtained possession of the estate of O'Dorcey of Partry, in the county of Mayo. This pedigree, which is most ingeniously put together, deduces the descent of the Darcys of Galway from Sir John D'Arcy, who was Chief Justice of Ireland in 1323. But that the reader may clearly see where the forgery begins, this

mic Seumuir Riabaiḡ,
 mic Niocolair.

mic Seamuir Riabaiḡ.

Προηγουμεν,

fabricated line is here annexed :

1. Sir John D'Arcy, Chief Justice of Ireland in 1323.
2. William, born 1330.
3. John.
4. William.
5. John.
6. Nicholas, captain of horse, who married Jane, daughter and heir of O'Dorcey, of Partry.
7. Thomas.
8. Conyers.
9. Nicholas.
10. James Riveagh I., of Galway, who died in 1603.
11. Nicholas.
11. Patrick, the lawyer.
12. James Riveagh II.

This forgery could never, in all probability, have been detected, were it not that the honest and laborious Mac Firbis had committed the real descent of the Darcys of Galway to writing, before the family attempted to conceal their Milesian origin. It is curious to observe in this memoir, published in Lodge's *Peerage*, a perfect agreement with the line given by Mac Firbis up to Conchobhar (the grandfather of James Riabhach the elder), which the fabricator anglicises Conyers; but here the forgery commences, for this Conyers was the son of a Patrick O'Dorcey, not of a Thomas D'Arcy, as the fabricator would have us believe. The name Thomas, however, is given by Mac Firbis in the next genera-

Martin,
son of Richard,
son of Martin,

Matthew,
son of James Og,

son of James Riabhach,
son of Nicholas.

son of James Riabhach.

Francis,

tion, and it is evident that both had the same Thomas in view; but instead of making this Thomas the son of Walter Riabhach, the first of the family who settled in the town of Galway, as Mac Firbis was informed by the family themselves in 1645, the fabricator makes him the son of a Nicholas Darcy, captain of horse (and uncle of Sir William D'Arcy, of Platten, in the county of Meath), who, "being stationed in the county of Mayo, married Jane, daughter and heir to O'Duraghy" [O'Dorcey], "of Partry, in that county, who brought him the large estate of that family." Where is his authority to prove this marriage, or that O'Duraghy had large estates in Partry at the time in which he makes this Capt. Nicholas flourish? Here he undoubtedly engrafts the pedigree on a false stem, and then easily mounts up to Sir John D'Arcy, Chief Justice of Ireland, by the true generations of the Meath family. This was a poor shift to erect a respectability for a family who were already respectable enough by allowing them their true descent. The wish to be considered English also prevailed among the Kirwans of Galway, but the Editor never heard that they went so far as to fabricate a pedigree to that effect; he has been told, how-

ever, that the late Major Kirwan, of Dalgan, was constantly in the habit of stating that his own name was originally Whitecombe, of which *Cíop Bán* was but an Irish translation; the name Kirwan is, however, in Irish *O'Ciapouéan*, not *Cíop Bán*, but the family was never of any celebrity in Ireland until they made fortunes in Galway as merchants and shopkeepers. Not so, however, the O'Dorceys, they were chiefs of the territory of Partry in the year 1417, when *Giolla Iosa Mor Mac Firbis* wrote his topographical poem.

Should it be objected that the Christian names occurring in the line of pedigree given by Mac Firbis are English, such as Nicholas, Walter, James, &c., and that these names suggest a strong argument in favour of the fabricator of the pedigree published in Lodge's Peerage; to such objection may be replied, that English names are also found among other families of undoubted Irish origin, which names were derived from their intermarriages with English families; that this surname was O'Dorcey in Mac Firbis's time, not D'Arcy, and that the Christian-name Nicholl was in use among the O'Dorceys, of Partry, as early as the year 1306.—See Mageoghegan's Translation of the Annals

Ῥρηνριαρ,
mac Antóin,

mic Seamuir Riabaiḡ.

Αινδριu αγυρ Ῥαδραιḡ an fear dligiḡ, dá mhac ele d'on
τ-Seumuir Riabac ar pine.

Λαοḡαιpe βεορ dno, ar dia cloinn Uib Eacac Muaidē co n-a
ḡ-compoigrīb, αγυρ Uι Maoilḡaḡmaiρ, comarbadā Cille h-Ealaiḡ,
ι d-Τιρ, no ι n-lb Eacac Muaidē, dia m-bádar na react n-eaprhoḡ
naomēta, Mo-Cele Ua Maoilḡaḡmaiρ, dia d-táio Mec Cele Cille
h-Ealaiḡ, αγυρ po ba dfoḡ pór Aongyρ Eappoc, Muirēadoc Eap-
poc, Aod Eappoc, Ainmteac Eappoc, Maolán Eappoc, αγυρ
Flann, .i. an fear léigēinn, .i. Eappoc diada do Chloinn Chéle.

Ar do cloinn Λαοḡaipe, ι n-lb Eacach Muaidē, Uι Criaḡdēen,
Uι Leanáin αγυρ Uι Flaiteile, no Laiteile.

Cpoc Ua n-Eacac Muaidē, .i. ó Ror Sepce ḡo Fionḡcaluim,
αγυρ ḡo Fearraio Tpepi. Ar aipe ad beapap Ror Sepce piρ, .i.
Sepc, ingean Cairbpe, mic Amalḡaiḡ, do beannaḡ an baile, αγυρ an
poc

of Clonmacnoise, at the year 1306.—See also the pedigree of O'Mochain above, in p. 42, from which it appears that the names Gregory, Simon, and Nichol, were in use among that family even in the fourteenth century.

^a *Patrick the lawyer*.—This was the celebrated lawyer Patrick Darcy, of Galway: he was the second son of James Riabhach the elder, was born in Galway in the year 1598, died in Dublin in 1668, and was interred in the abbey of Kilconnell, in the county of Galway. For some notices of this remarkable man the reader is referred to Ware's Writers and Hardiman's His-

tory of Galway, p. 11, &c.

^b *The Hy-Eachach, of the Moy*.—The situation of this tribe will be pointed out more distinctly in the Notes to the Topographical Poem of Giolla Iosa Mor Mac Firbis.

^c *O'Maoilḡahmhair*.—This name still exists in the district, but is anglicised Milford, which is calculated to disguise the Irish origin of the family.

^d *Cill Ealaidh*, now Killala, in Tirawley.

^e *Mac Celes, of Cill Ealaidh*.—This is probably the family now called Mac Hale.

^f *Clann Cele*.—These seven bishops of the Clann Cele are not given in Ware's

Francis,
son of Anthony, son of James Riabhach.

Andrew, and Patrick the lawyer^a, two other sons of James Riabhach, the elder.

Of the race of Laoghair also are the Hy-Eachach of the Moy^b, with their correlatives, and the *family of O'Maoilfaghmhair*^c, comharbas of Cill Ealaidh^d, in Tir Eachach, or Hy-Eachach of the Moy, of whom were these seven holy bishops, viz., Mo Cele O'Maoilfaghmhair, from whom are *descended* the Mac Celes, of Cill Ealaidh^e; Aongus the Bishop, Muireadhach the Bishop, Aodh the Bishop, Ainmtheach the Bishop, Maolan the Bishop, and Flann the Lecturer, i. e. a pious Bishop of the Clann Cele^f.

Of the race of Laoghair, in Hy-Eachach, of the Moy, are the O'Criadhchens^g, the O'Leanains^h, and the O'Flaitilesⁱ, or O'Laitiles.

The country of Hy-Eachach, of the Moy, extends from Ros Serce^j to Fionnchaluim, and to Fearsad Tresí. Ros Serce is so called from Searc, the daughter of Cairbre, son of Amhalgaidh, who blessed the village and the wood which is at the mouth of the River Moy.

list of the bishops of Killala, nor has the Editor been able to find any notices of them in the Irish Annals. The earliest notice of the see of Killala collected by the Four Masters is at the year 1235. At the year 1257 they record the death of Maelpatrick Mac Cele, archinneach or herenach of Killala, and this is the earliest notice of the name of Mac Cele to be found in their work.

^g *O'Criadhchen*. — This is probably the name now anglicised Crean, which is still numerous and respectable in the county of Mayo.

^h *O'Leanain*, now Lennon.

ⁱ *O'Flaitile*, now anglicised Flatly and Flatilly; and in some parts of Ireland it has assumed the strange form of Flattery!

^j *Ros Serce*, now called Rosserk, a townland containing the ruins of a small but very beautiful abbey, in the parish of Ballysokeery, and barony of Tirawley, about four miles due north of Ballina. The abbey is about five centuries old, and there is no portion of the original church of the Virgin Searc now to be seen.

por a tá ag bun na Muaidhe. ban-naom miorbhuileac an t-Seapc rin, agus ar oi do rinead an pegleup, agus an duirteaac ril ag an por (no ir in por), roin, i Rorepc.

CLAND EOGHAIN AIDHNE, MIC EACACH DRIC.

Eogan Aidne, mac Eacac dric, mic Daci, ar aipe a deaptau Eogan Aidne rpor, uair ar in Aidne po h-oilead e ag Oguib deaptau, an treap cineul po baol in Aidne, uair tri cineula po badar in Aidne pe n-Uib Phiacrac, .i. Ciarrpaigne, Oga deaptau, agus Traopaigne Dubroir, agus Caonpaigne Airb Aidne. Oig deaptau, umorro, a Cric Ealla do lodar, agus do ril Eogain Taidlig iad, agus po gab-rad tuairgearc Aidne, agus ar iad po n-alt Eogan Aidne, mac Eacac dric, agus ar de ba h-Eogan Aidne. Oig deaptau beor po n-alt Eogan beul, mac Ceallaign, mic Oiholla Muile, mic Daci, agus ar iad pa ceud oipeact do ag gabail riige Conbacht. Traopaigne ono ar do cloinn Seanainn, mic Deala doib. Caonpaigne ono do clannaib Cuinn doib. Eogan Aidne

^k *Duirtheach*.—This word, which very frequently occurs in the Irish lives of the primitive Irish saints, is generally applied to a small oratory or a hermit's cell.—See *Fleadh Duin na n-Gedh*, p. 16, Note ⁿ, for a fuller explanation of it.

^l *Aidhne*.—This territory was co-extensive with the diocese of Kilmacduagh, forming the south-west portion of the county of Galway. It was bounded on the north by O'Flaherty's country, on the east by Moenmoy, on the south and south-west by the territory of Cineal Fearmaic, in Thomond, and on the west by Burren and the Bay of Galway.—See Map prefixed to the tract on Hy-Many.

^m *Dubh-ros*, i. e. the black promontory,

now Duros, or Dooross, near the little town of Kinvara, in the barony of Kiltartan, and county of Galway. The word Ros, when topographically applied, has two distinct meanings, namely; 1, a point of land extending into the sea, or a large lake; and, 2, a wood. Its diminutive form *porán* or *parán* is still used in the spoken Irish to denote a shrubbery or underwood.

ⁿ *The country of Ealla*.—This is still the name of a well known district and now a barony, in the county of Cork, and takes its name from the River *Ealla*, or *Alloe*, which flows through it. The name is always anglicised Duhallow from the Irish *Dúeall* *Ealla*, i. e. the district or country of *Ealla*.

Moy. This Searc was a miraculous female saint, and it was for her the church and duirtheach^t, which are at that Ros (or in that Ros), at Roserc, were erected.

OF THE DESCENDANTS OF EOGHAN AIDHNE, THE SON OF EOCHAI DH BREAC.

Eoghan Aidhne, son of Eochaidh Breac, who was son of Dathi, was called Eoghan Aidhne, because it was in *the territory of Aidhne*¹ he was fostered by the *tribe called Oga Beathra*, the third tribe who then inhabited Aidhne, for there were three tribes in Aidhne before the Hy-Fiachrach, namely, the Ciarraighe, Oga Beathra, the Tradraighe, of Dubh-ros^m, and the Caonraighe, of Ard Aidhne. The Oig Beathra came from the country of Eallaⁿ, and were of the race of Eoghan Taidhleach^o; they took possession of the northern part of Aidhne, and it was they that fostered Eoghan Aidhne, the son of Eochaidh Breac, for which he was called Eoghan Aidhne. The Oig Beathra also fostered Eoghan Beul, the son of Ceallach, son of Olioll Molt, son of Dathi, and they were his first faction when he was assuming the government of Connaught. The Tradraighe are of the race of Geanann, the son of Deala^p, and the Caenraighe are of the race of Conn^q. Eoghan Aidhne was the foster-son

^o *Eoghan Taidhleach*, i. e. Eoghan the splendid. He was otherwise called Mogha Nuadhat, and was the father of Olioll Olum, and the ancestor of the most distinguished families of Munster. He was contemporary with Conn of the Hundred Battles, whom he compelled to divide Ireland with him into two equal parts.

^p *Race of Geanann, son of Deala*.—He was a Firbolgic King of Connaught, and ruled, according to Keating and the ancient MS. accounts of this colony, over the district extending from the Luimneach,

or Lower Shannon, to the River Droghaiois, now the River Drowis, the boundary between Connaught and Ulster. There was another tribe of the name Tradraighe seated in the territory of Tradry, or Tradree, in the barony of Bunratty, and county of Clare.

^q *Race of Conn*, i. e. of Conn of the Hundred Battles, monarch of Ireland. There was another tribe of the name Caenraighe seated along the Shannon, on the south side, who gave name to the barony of Caenraighe, now Kenry, in the county of Limerick.

Αἰὼνε umoppo balta na n-aicmeaða ροιν, agur Oga m-beatra (mar a dubhamar), do corann crisoc Αἰὼνε do fen agur d'a cloinn 'n-a diaig.

Eogan Αἰὼνε cetpe mec ler, .i. Conall, Cormac, Seudna, agur Seacnurac, .i. Ceanngamna, agur ar ρir a deapetai Seanac Ceanngamna, agur ar uada Ceneul Cindgamna, .i. Uí Duibghiolla taoirig Cinél Cinngamna, agur ar do Cineul Cindgamna Sarnait, mgean Aoda Gabal-pada, mac Seanais, mic Eogain Αἰὼνε, mic Eacac bpic.

Conall, mac Eógain Αἰὼνε, ar uada Ceneul n-Guaire, .i.

Aod agur colman da

mac Cobetaig,
mic Toibnenn,
mic Conaill,

mic Eogain Αἰὼνε,
mic Eacada bpic,
mic Daeti, ρig Epeann.

Aod, mac Cóbetaig umoppo, ar uada Ceneul Aoda, .i. O' Seac-naruis, agur O' Caetail, dá ρig Ceneoil Aoda. Colmán ar uada Cenel n-Guaire.

Seudna, mac Eogain Αἰὼνε, ar a clano, .i. Ceneul Seudna.

Cormac mac Eogain ar uadha Ceneul Cearnaig.

Ceteapnac,

¹ *O'Duibhghiolla*. — This name is now obsolete in the territory of Aidhne, or lurks under some disguised form.

² *St. Sarnait*. — This is evidently the female saint now corruptly called St. Sourney, to whom there are wells dedicated in the district of Aidhne, and whose church still stands in ruins on the great island of Aran, in the bay of Galway. There is no mention of this Sarnait in the Book of Lecan.

³ *Aodh, son of Cobhthach*. — If this be true, O'Shaughnessy does not descend from Guaire Aidhne, King of Connaught, which was the boast of the Irish poets of the three last centuries, for Guaire was the son of Colman, the brother of the Aodh, who is here stated to have been the ancestor of O'Shaughnessy. Notwithstanding this statement, our author himself, in giving the pedigree of Sir Diarmaid O'Shaughnessy, deduces his descent not from Aodh, but

ter-son of these tribes, and it was the Oga Beathra (as we have already stated) that maintained the territory of Aidhne for him and his descendants after him.

Eoghan Aidhne had four sons, namely, Conall, Cormac, Seudna, and Seachnasach, who was called Ceanngamhna and Seanach Ceanngamhna, and from him are descended the Cineal Cinngamhna, i. e. the family of O'Duibhghiolla', chiefs of Cineal Cinngamhna. Of this tribe of Cineal Cinngamhna was *Saint Sarnait'*, the daughter of Aodh Gabhalfhada, son of Seanach, son of Eoghan Aidhne, son of Eochaidh Breac.

From Conall, son of Eoghan Aidhne are sprung the Cineal Guaire, thus :

Aodh and Colman,	
two sons of Cobhthach,	son of Eoghan Aidhne,
son of Goibhnenn,	son of Eochaidh Breac,
son of Conall,	son of Dathi, King of Ireland.

From Aodh, son of Cobhthach', are sprung the Cineal Aodha, i. e. O'Seachnasaigh and O'Cathail, two kings of Cineal Aodha; and from Colman are the Cineal Guaire.

Seudna, son of Eoghan Aidhne, was the progenitor of the Cineal Seudna.

From Cormac, Son of Eoghan [*Aidhne*], are the Cineal Cearnaigh.

from his brother Colman, through Guaire, King of Connaught, but it is highly probable that O'Shaughnessy is of the race of Aodh, as he is always mentioned in the Irish Annals as chief of the Cineal Aodha. In the Book of Lecan, the genealogical MS. of the O'Clerys, and in all the copies of Keating, the pedigree of O'Shaughnessy is de-

The
duced from Guaire Aidhne. This error seems to have arisen from mistaking Aodh, son of Cobhthach, the real ancestor of the Cineal Aodha, for Aodh, the grandson of Guaire Aidhne. This subject will be further considered in the pedigree of O'Shaughnessy, at the end of this volume.

Ceteapnac, mac Cuaiçe, dia d-tá Ceneul Cuaiçe, mac Crioim-
tairn Caoin, mic Eogain Phuiliḡ, mic Aoda Gabal-ḡaba.

ua cathail, za ceneul aodha.

Catal,

mac Ogain,
mic ḡracain,
mic Cionaoḡa,
mic Toppa,
mic Concabair,
mic Comurḡaiḡ,

mic bece,
mic Aoda,
mic Cobḡaiḡ,
mic ḡoibnenn,
mic Conaill,
mic Eogain Aione.

Cian,

mac Concabair,
mic Ubain,
mic Ogain,

mic ḡruacain, no ḡracain,
mic Cionaoḡa.

ḡenealach ui sheachnusaigh.

Sir Diarmaid (mairear anoir, 1666),	
mac Sir Ruaidriḡ, .i. ḡiolla	mic Uilliam,
duib O' Seachnusaigh d'an deap-	mic ḡiolla na naom,
bráite Daei agur Uilliam,	mic Ruaidriḡ,
mac Diarmada O' Seachnusaigh,	mic ḡiolla na naom,
mic an ḡhiolla duib,	mic Raḡnaill,
mic Diarmada,	mic Sealbaigh, no ḡailbige,
mic Uilliam,	mic Seachnusaigh, ó b-fuilio Uí
mic Seain,	Seachnusaigh,
mic Eogain,	mic Donncaid,

mic

^u *Bec, son of Aodh, son of Cobhthach.*— correct, as it agrees with what is stated
This descent of O'Cathail, now Cahill, is about the descent of the Cineal Aodha, of

The Cineal Cuaiche are sprung from Cethernach, son of Cuach, son of Criomhthann Caoin, son of Eoghan Fuileach, son of Aodh Gabhalfhada.

O'CATHAIL, IN CINEAL AODHA.

Cathal,	
son of Ogan,	son of Bec,
son of Bracan,	son of Aodh,
son of Cionaoth,	son of Cobhthach*,
son of Torpa,	son of Goibhnenn,
son of Conchobhar,	son of Conall,
son of Comuscach,	son of Eoghan Aidhne.
Cian,	
son of Conchobhar,	son of Bruachan, or Bracan,
son of Uban,	son of Cionaoth.
son of Ogan,	

PEDIGREE OF O'SEACHNASEAIGH.

Sir Diarmaid (now living, 1666),	
son of Sir Ruaidhri, i. e. Giolla	son of Eoghan,
dubh O'Seachnasaigh, whose	son of William,
brothers were Dathi and Wil-	son of Giolla na naomh,
liam,	son of Ruaidhri,
son of Diarmaid O'Seachnasaigh,	son of Giolla na naomh,
son of Giolla dubh,	son of Ragnall,
son of Diarmaid,	son of Sealbhach or Gailbhighe*,
son of William,	son of Seachnasach, from whom
son of John,	the <i>family</i> of O'Seachnasaigh,

son

whom he was a branch. One of this family was chief of the Hy-Fiachrach Aidhne in the year 1147.—See Annals of the Four Masters at that year.

* *Gailbhighe*.—His real name was Gealbhuide. He was slain in the battle of Ardee, in the year 1159, according to the Annals of the Four Masters.

mic Conmaighe (no Conmuighe),	mic bhoioin, no bhoiaoin Lebeirg,
mic Feargaile,	mic Muircáid,
mic Maoilciarain,	mic Aoda,
mic Cairine, no Cair,	[mic Airtgail,
mic Murgáile,	mic Guaire Aídhne,
mic Maoilcuile,	mic Colmain],
mic Simle (no Sioġmuile, no	mic Cobcáig,
Sioġmuine, no Sioctmuine),	mic Ğoibnenn,
mic Noibile (no Nocba no Ogba),	mic Conaill,
mic Cana (no Eagna no Aġna),	mic Eogain Aídhne,
mic Nadreudna,	mic Eocac bpic,
mic Ğarbbain (no Ğabrain),	mic Daeti, piġ Epeann,
mic Soġain (no Tobain no To-	mic Fiacrac,
baig, no Toġba),	mic Eocada Muigmeaboin, piġ
mic bpanain (no bponain),	Epeann.

ĜENEALACH MUINTIRE SĜANDOLAIN.

Eogán,	
mac Airt buide,	mic Taidġ,
mic bhoiaoin Ğairb,	mic Aoda,
mic Maġnura,	mic Toirdealbairġ,
mic Concabair,	mic Aoda,
mic Muirġeara,	mic Concabair,

mic

* *Colman, son of Cobthach.* — This line of pedigree contradicts what is already stated, namely, that O'Shaughnessy is of the Cinal Aodha, and descended from Aodh, son of Cobhthach, not from his brother Colman, the father of Guaire Aidhne, and the ancestor of the Cinal Guaire. It is, therefore, highly probable,

if not absolutely certain, that the three generations here enclosed in brackets were thrown in by the modern genealogists to make it appear that O'Shaughnessy was the senior representative of Guaire Aidhne, King of Connaught, so celebrated by the Irish bards as the very personification of hospitality (for the name Guaire Aidhne

son of Donnchadh,	son of Bran, or Brian Lethdherg,
son of Cumaighne, or Cumaighe,	son of Murchadh,
son of Feargal,	son of Aodh,
son of Maolciarain,	[son of Artghal,
son of Caisin, or Cas,	son of Guaire Aidhne,
son of Murgal,	son of Colman*],
son of Maoltuile,	son of Cobhthach,
son of Simil (or Sioghmal, or Sioghmuine, or Siothmuine),	son of Goibhnenn,
son of Nobile (or Nocba, or Ogba),	son of Conall,
son of Cana (or Eagna, or Aghna),	son of Eoghan Aidhne,
son of Nadseudna,	son of Eochaidh Breac,
son of Garbhan (or Gabhran),	son of Dathi, King of Ireland,
son of Soghan (or Toban, or Tobach, or Toghbha),	son of Fiachra,
son of Branan (or Bronan),	son of Eochaidh Muighmheadh- oin, King of Ireland.

PEDIGREE OF MUINTER SCANNLAIN*.

Eoghan,	
son of Art Buidhe,	son of Tadhg,
son of Brian Garbh,	son of Aodh,
son of Maghnus,	son of Toirdhealbhach,
son of Conchobhar,	son of Aodh,
son of Muirgheas.	son of Conchobhar,

son

and generosity are nearly synonymous terms with the Irish bards). It will, however, appear from the descent of the Cinel Aodha above given, p. 55, that O'Shaughnessy is not of the race of Guaire.—See this subject further discussed, in the Pedi-

gree of O'Shaughnessy, in the Addenda at the end of this volume.

* *Muintir Scannlain*, now anglicised Scanlan. This family sunk at an early period, under the O'Shaughnessys and O'Heynes.

mic Giolla na n-eac,
mic Aoda,
mic Sganlain Oig,
mic Ceallaiḡ,
mic Giolla beapuiḡ,
mic Domnaill,
mic Aoda,
mic Sganlain,

mic Fearḡail,
mic Maoilciarain,
mic Cairine,
mic Muirḡile,
mic Maoilcuile,
mic Timile,
mic Noibile ut rappa.

Ṭri mec Seanaiḡ Cinnḡamḡna, .i. Aod Ḥabal-ḡada, aḡur Aod baillbeḡḡ, aḡur Fearaodac, ó o-táio na cairiḡ, .i. Uí Duibḡiolla co n-a b-pineadaiḡ, dá'r labḡar beaḡan ceana ioinne ro.

[Ḥuairi, mac Colmain, mic Cobḡaiḡ, mic Ḥuibneḡ, mic Conaill, mic Eogain Aigri, mic Eacac bḡic, mic Dathi, ṫri meic lair, .i. Arṫḡal, aḡur Aed, aḡur Nap. Mac do'n Aed rin Fearḡal; da
mac

¹ *Guaire, the son of Colman.*—This passage, treating of the descendants of Guaire Aidhne, and here enclosed in brackets, is taken from the Book of Lecan, fol. 80, p. b, col. 3.

That O'Shaughnessy is not of the Cinel Guaire, or race of Guaire, is further corroborated by the Topographical Poem of O'Dugan, in which he mentions Mac Giolla Ceallaigh [Kilkelly] O'Heidhin [O'Heyne], and O'Clery, as of the race of Guaire, but O'Shaughnessy and O'Cathail he mentions as of the Cineal Aodha. The following are his words :

Ḭpuiḡeam le h-Aiḡne na n-each,
Ḥe a n-uairle 'r le n-eineach,
Ḥeanom a pḡḡa naḡ ḡann
Ḥeanom ḡe riol na raop-clann.

Ḥuaiḡeam Aiḡne ar feiḡm ḡan acḡ,
Fáḡḡam pineada Connaḡḡ,
Ḥiono-páioim a maiḡe amaḡ,
Ionpáíḡeam flaiḡe O' b-Fiaḡnac.

Clann Mhic Giolla Cheallaiḡ aiḡ,
Uí Eioin na n-eac reanḡ-blaíḡ,
Ḭíon a n-uaille ar a n-armaiḡ,
Ḭo riol Ḥuairḡe ḡlan-aḡraiḡ.

Maíḡ an feiḡoiḡ 'r ar pleadac,
Ua cléiriḡ 'r o'a n-ḡeinealac.
Ar Chinel Chinḡamḡna ḡloin,
Uí Duibḡiolla ir o'a n-ouḡoiḡ,
Ṭarḡa a o-ṫraiḡ 'r a o-tuile
O' Maḡna ar cláir Caonpuiḡe.

Dá pḡḡ Ceneoil Aoda ann,
O' Seacḡaraiḡ ná reachnam

son of Giolla na n-each,
 son of Aodh,
 son of Scannlan Og,
 son of Ceallach,
 son of Giolla-Bearaigh,
 son of Domhnall,
 son of Aodh,
 son of Scannlan,

son of Feargal,
 son of Maoilciarain,
 son of Caisin,
 son of Muirgeal,
 son of Maoiltuile,
 son of Timile,
 son of Nobile, ut suprâ.

Seanach Ceann Gamhna, had three sons, namely, Aodh Gabhal-fhada, Baill-derg, and Fearadhach, from whom are the chieftains, namely, the O'Duibhghiollas, with their correlatives, of whom I have already briefly spoken.

[Guaire, the son of Colman', son of Cobhthach, son of Goibhnenn, son of Conall, son of Eoghan Aidhne, son of Eochaidh Breac, son of Dathi, had three sons, viz., Artgal, Aedh, and Nar. This Aedh had

a

Ar oib O'Caith na g-cliair
 Min a acaio 'r a uir-rliaib.

" Let us approach Aidhne of steeds,
 Their nobility and hospitality ;
 Let us follow their kings who are not few,
 Let us touch upon the race of the nobles.

Let us treat of Aidhne, it is a duty without con-
 dition ;

Let us leave the tribes of Connaught ;
 Let us sweetly sing their chieftains out ;
 Let us celebrate the chiefs of Hy-Fiachrach.

The race of the noble Mac Giolla Ceallaigh,
 The O'Heynes of the slender-sleek steeds,
 The defence of whose pride depends on their arms
 Of the race of the fair-browed Guaire.

Good is the hero and hospitable
 O'Clery, who is of their lineage.
 Over the fair Cinel Cinnghamhna

Rules O'Duibhghiolla, in whom it is hereditary,
 Profitable their strand and flood ;
 O'Maghna is over the plain of Caenraighe.

Two kings of Cinel Aodha there are,
 O'Shaughnessy, whom I will not shun ;
 Of them is O'Cathail of learned men :
 Smooth his fields and his fertile mountain."

In this extract from O'Dugan's poem an obvious distinction is made between the race of Guaire, and the tribe called Cinel Aodha, of whom O'Shaughnessy was the chief, so that if he was of the race of King Guaire Aidhne, as all the modern writers have asserted, he was not of the Cinel Aodha, for we have seen above, p. 55, that they descended from Aodh, son of Cobhthach, not from Aodh, the grandson of King Guaire.

mac la Perygal, .i. Cormac, agur Enba, a quo Cinel Enba. Dibaid Cormac aet aen ingen, .i. Rignach, mátaip Colmain, mic Duach, ó cá Ceall meic Duach.

Nár, mac Thuairi, rindreir cloinni Thuairne, a quo Cinel Thuairne; Ar a uairli rin ainmnigter uad Cinel n-Thuairi reach na macaib ele, .i. Aed agur Arégal. En mac la Nár, .i. Cobéach; mac do'n Chobéach rin Flann, a quo Cinel n-Thuairne. O'Magna tairic Chinel n-Thuairi agur Chaenraidi, cor gab Mac Gilla Cheallais h-í iarbaid, iar n-díth a dúcéair. O'Quibgilla tairpech Cinel Chind gamna. Mac Gilla Cheallais tairpech Cinel n-Thuairne; O Cathan tairpech Cinel Ianna agur ip d'á dúcéuraib ó Močan agur ó h-oirpétais agur h-í Marcačan. Cinel Aeda meic Thuairi ann rin.

Mag Phiaéra tairpé Oigí bethra, agur a dúchuraig ó Caemagan, agur ó Dubagan, agur Mes Phlannagan].

Maolpábaill da mac laip, .i. Cugaola agur Maolcúlairb átaip Giolla na naom agur Flaitébeartuig, átaip Giolla Iora, Congaola (o d-taid Mec Congaola) Muireadóig agur Ghiolla Phupra.

Giolla na naom, mac Congaola aon mac laip, .i. Aod, átaip Ghiolla na naom agur Ghiolla Cheallais átaip Aoda (niri raici Maol

**O'Maghna*.—This is probably the name now anglicised Mooney, of which there are some respectable families in Westmeath.

^a *Mac Giolla Ceallaigh*, now sometimes anglicised Kilkelly, and sometimes Killikelly, and the name is still very respectable in the county of Galway.

^b *O'Cathan*, now Kane; but this family is to be distinguished from the O'Cathains or Kanes, of the county of Derry, who are

of the race of Eoghan, son of Niall of the Nine Hostages.

^c *O'Mochan*, now Mohan.

^d *O'h-Oirechtaigh*, now Heraghty, and some have corrupted the name to Geraghty, which is the name of a family of different descent and more celebrity in Irish history.

^e *O'Marcachain*.—This name is still numerous in the county of Clare, where it is anglicised Markham, and sometimes

a son Fergal; Fergal had two sons, viz., Cormac, and Enda a quo Cinel Enda. The issue of Cormac became extinct except one daughter, Righnach, the mother of St. Colman Mac Duach, a quo Ceall mic Duach, i. e. *Kilmacduagh*.

Nar, the son of Guaire, was the eldest of his sons, a quo Cinel Guaire. The Cinel Guaire are called after him for his nobleness beyond the other sons, Aedh and Artgal. Nar had one son, namely, Cobhthach; Cobhthach had a son Flann, a quo Cinel Guaire. O'Maghna² was chief of the Cinel Guaire and of the Caenraighe until Mac Giolla Ceallaigh^a deprived him of his patrimonial inheritance. O'Duibhghiolla is the chief of Cinel Cinngamhna; Mac Gilla Cheallaigh is chief of Cinel Guaire; O'Cathan^b is chief of Cinel Ianna, and of his followers are O'Mochan^c, O'h-Oirechtaigh^d, and the O'Marcachans^e. So far the Cinel Guaire.

Mag Fhiachra^f is the chief of Oig Bethra, and his retainers are O'Caemhagan^g, O'Dubhagan^h, and the Mag Flannagansⁱ].

Maolfabhaill had two sons, namely, Maolchulaird and Cugaola, the father of Giolla na naomh and Flaithbheartach, who was the father of Giolla Iosa, and Cugaola, from whom is the family of Mac Conghaola^j, as also of Muireadhach and Giolla Fursa.

Giolla na naomh, the son of Cugaola, had one son, namely, Aodh, the father of Giolla na naomh and Giolla Ceallaigh, who was the father

translated Ryder, because the Irish word *mapcaic* signifies a horseman.

^f *Mag Fhiachra*.—This name is still to be found in Aidhne, anglicised M'Keighry, and by some metamorphosed to Keary, and even Carey.

^g *O'Caemhagan*, unknown to the Editor. It would be anglicised Kevigan.

^h *O'Dubhagan*, now Dugan and Duggan, but this family is to be distinguished from the O'Dubhagains of Hy-Many.

ⁱ *Mag Flannagan*, unknown to the Editor.

^j *Mac Conghaola*, now probably Conneely.

Maol na m-bó) Ḡhiolla na naomh agur Chonḡaola. Maol na m-bó
aon mac ler, .i. Aod.

ḡENEALACH UI EḡHIN.

Eoḡan, agur Muirḡeartaḡ, ḡa	
mac Donnḡuib,	mic Eḡin,
mic Aodḡ,	mic Cleirḡ,
mic Eoḡain,	mic Ceudḡdoiḡ,
mic Ḡhiolla na naomh,	mic Cumarḡaiḡ,
mic Ḡhiolla Ceallaiḡ,	mic Catmoḡa,
mic Aodḡ,	mic Torpa,
mic Ḡhiolla na naomh na poḡla,	mic Fearḡaile,
mic Conḡaola,	mic Arḡaile,
mic Maoilpaḡuill,	mic ḡuaire Aḡone.
mic Floinn,	
Aod buḡde,	
mac Muirḡeartaḡ,	mic Aodḡ,
mic Donnḡuib,	mic Eoḡain, ḡc.

O'N LAIḡHḡIAḡAN.

Eoḡan,	
mac Aodḡ buḡde,	mic Eoḡain,
mic Aodḡ,	mic Eḡoinn,
	mic

* *O'Hedhin*, now O'Heyne and Hynes. It is curious that Mac Firbis dropped the *i* in the first syllable of Eḡin, for in their own country it is pronounced diphthongally like the German *ei* or the English *eye*; but this was to conform with his own system of orthography alluded to in the Preface to this volume. The pedigree

of this family shall be fully discussed in the Addenda to this volume. The O'Clerys give the line as follows:—Muircheartach and Eoghan, two sons of Donnchadh, son of Aedh, son of John, son of Eoghan, son of Giolla na naomh, son of Giolla Ceallaigh, son of Aedh, son of Conchobhar, son of Flann, son of Giolla na naomh, son of

father of Aodh (who was usually called Maol na m-bo), and also of Giolla na naomh and Cugaola. Maol na m-bo had one son, namely Aodh.

PEDIGREE OF O'H-EDHIN^k.

Eoghan and Muirheartach,	
two sons of Donnchadh,	son of Flann,
son of Aodh,	son of Edhin,
son of Eoghan,	son of Clereach,
son of Giolla na naomh,	son of Ceadadhach,
son of Giolla Cheallaigh,	son of Cumascach,
son of Aodh,	son of Cathmogha,
son of Giolla na naomh of the	son of Torpa,
plunder,	son of Feargal,
son of Cugaola,	son of Artghal,
son of Maolfabhuaill,	son of Guaire Aidhne.

Aodh Buidhe [O'h-Edhin],	
son of Muirheartach,	son of Aodh,
son of Donnchadh,	son of Eoghan, &c.

THE FAMILY OF LAIGHDIAGAN¹.

Eoghan [O'h-Edhin],	
son of Aodh Buidhe,	son of Eoghan,
son of Aodh,	son of Edmond,

SON

Aidhin from whom the surname, son of Cugaola, son of Giolla Cheallaigh, son of Comaltan, son of Maolceararda, or Flann, son of Maolfabhuaill, son of Cleireach, from whom are the O'Clerys, son of Ceadadhach, &c., as in Mac Firthis.

¹ *Laighdiagan*, now anglicised Lydican : it is the name of a townland containing the ruins of an old castle, situated in the parish of Ardrahan, about four miles south-east of the little town of Kinvara, in the barony of Kiltartan, and county of Galway.

mic Floinn,
mic Concabair,

mic ðriain,
mic Aoda buide.

Concabair Cron,
mac Floinn,
mic Concabair Chroin tanairde Uí Eðin.

Eogan Mantac,
mac Toirdealbais,
mic Eogain,
mic Emoinn,
mic Floinn,

mic Concabair,
mic ðriain,
mic Aoda buide.

Eumonn, airchinneac Chille Mhec Duac,
mac Ruaidri,
mic Eógain,
mic Ruaidri,
mic Floinn,
mic Concabair,
mic ðriain,
mic Aoda buide peamprate.

DUN EOGHAIN.

Aod Meirgeac,
mac ðriain,
mic Aoda buide,
mic ðriain na caoraisgeacta,

mic Aoda buide,
mic Floinn.

A DUN SUAIRE.

Aod buide,
mac Floinn,
mic Floinn,

mic Floinn buide.

O'N

^m *Eoghan Mantach*, i. e. Owen the toothless. It appears by an order of the Council of Connaught, dated Dublin, 13th May, 1586, that Owen Mantach O'Hein, of Lydegane, in the barony of Kiltaraght [now

Kiltartan], in the county of Galway, was the chief of his name.—See Pedigree of O'Heyne in the Addenda to this volume.

ⁿ *Airchinneach, of Cill Mhic Duach*, i. e. herenach of the lands belonging to

son of Flann,
son of Conchobhar,

son of Brian,
son of Aodh Buidhe, &c.

Conchobhar Cron,
son of Flann,
son of Conchobhar Cron, Tanist of O'h-Edhin.

Eoghan Mantach^m,
son of Toirdhealbhach,
son of Eoghan,
son of Edmond,
son of Flann,

son of Conchobhar,
son of Brian,
son of Aodh Buidhe.

Edmond, airchinneach of Cill Mhic Duach^a,
son of Ruaidhri,
son of Eoghan,
son of Ruaidhri,
son of Flann,

son of Conchobhar,
son of Brian,
son of Aodh Buidhe aforesaid.

THE FAMILY OF DUN EOGHAIN^o.

Aodh Meirgeach,
son of Brian,
son of Aodh Buidhe,
son of Brian na caoraoigheachta,

son of Aodh Buidhe,
son of Flann.

THE FAMILY OF DUN GUAIRE^p.

Aodh Buidhe,
son of Flann,
son of Flann,

son of Flann Buidhe.

O'Heyne's Monastery, at Kilmacduagh.

^o*Dun Eoghain*, now Dunowen, the name of a townland containing the ruins of a fort in which stood a castle in the parish and barony of Kiltartan.

THE
^p *Dun Guaire*, i. e. Guaire's fort, or fortified residence, now Dungorey, a castle in good preservation, situated immediately to the east of the little seaport town of Kinvara, in the barony of Kiltartan. This

O'N LUACHARNUIGH.

Θεραπευτὴς ἀγύρῃ ὄριαν, δά
μας Πλοῖνν,
μικρὰ Συνέταξι,
μικρὰ ὄριαν καὶ Καθημερινή,

μικρὰ Αἰδοῦσα ὀρίαν,
μικρὰ Πλοῖνν.

ḡeneazach mec ḡiozza cheazzaiḡh.

Ἰολλα Cheallaiḡ,
 mac Comaltáin, a quo Uí Co-
 maltáin,
 mic Maoiléalairb,
 mic Maoilpabaill,
 mic Floinn,
 mic Eðin, ó d-táð Uí Eðin,
 mic Cléirigh, a quo Uí Cléirigh,
 mic Ceudagairḡ, a quo Uí Ceu-
 dagairḡ,
 mic Cumargairḡ,
 mic Caetmogá, a quo Uí Caet-
 mogá,
 mic Torpa, γc.

ԴԵՆԵԱՆԱՅԻՆ ՄԵԼԻՑ ԴԻՕՆԱ ՇԵԱՆՆԱԴԻՆ.

Ḑiolla na naom,
 mac Ḑiolla Cheallaiḡ,
 mic Aebha,

mic Concobair,
 mic Floinn,

mic

castle was erected on the site of the palace of Guaire Aidhne, King of Connaught, the ancestor of the O'Heynes, who erected this and several other castles in its vicinity. It is stated in Lewis's Topographical Dictionary that "the castle of Doon belonged to Flann Killikelly, but that about the reign of Henry VIII. Rory More Darag O'Shaughnessy took it from him, totally demolished it, and erected one near its site, which he named Doongorey." But

this is a vague tradition not supported by any historical authority, as will be shown in the pedigree of O'Heyne at the end of this volume.

^a *Luacharnach*, i. e. *rushy land*, now Lougharnagh, a townland in the district of Coill O'bh-Fiachrach, in the barony of Kiltartan.

¹ *Mac Giolla Cheallaigh*, now anglicised Kilkelly and Killikelly. The chief seat of this family was the castle of Cloghbally-

THE FAMILY OF LUACHARNACH¹.

Gerald and Brian,	
two sons of Flann,	son of Aodh Buidhe,
son of Conchobhar,	son of Flann.
son of Brian na caoraoigheachta,	

PEDIGREE OF MAC GIOLLA CHEALLAIGH¹.

Giolla Cheallaigh,	
son of Comaltan, from whom are	son of Ceudadhachh, a quo Ui
the O'Comaltains,	Ceudaghaigh,
son of Maolchulaird,	son of Cumasgach,
son of Maolfhabhaill,	son of Cathmogh, a quo the
son of Flann,	O'Cathmoghas,
son of Edhin, a quo the O'h-Edhins,	son of Torpa, &c.
son of Clereach, a quo the O'Cle-	
rights,	

[PEDIGREE OF MAC GIOLLA CHEALLAIGH¹.

Giolla na naomh,	
son of Giolla Cheallaigh,	son of Conchobhar,
son of Aedh,	son of Flann,

SON

more, still standing in ruins in the parish of Kileenavarra, barony of Dunkellin, and county of Galway.

¹ *Mac Giolla Cheallaigh*. — This line of Mac Giolla Cheallaigh's pedigree is inserted from the genealogical MS. in the handwriting of Peregrine O'Clery, now preserved in the Library of the Royal Irish Academy; it comes down seven genera-

tions later than the line given by Mac Firbis. In the same MS. is given another line of pedigree of this family, which cannot be considered correct, but it is added here that nothing relating to this family may be omitted. "Flann, son of Murchadh, son of Giolla Cheallaigh, from whom is Mac Giolla Cheallaigh, son of Aodh Cleireach, from whom are descended the Clann Clery of

mic Giolla na naom,
 mic Congaela,
 mic Giolla Cheallaiḡ, ó raiceap
 an plonbad,
 mic Comalcain,
 mic Floinn, .i. Maelceapapb,
 mic Maoilpabaill,
 mic Cleiriḡ ó táct Uí Cleiriḡ,

Flann,
 mac Lonáin,
 mic Connmaig,
 mic Caiéniað,
 mic Aóða,

Arctgal,
 mac Plaiténiað,
 mic Fearḡail,

mic Cedaðaiḡ,
 mic Cumurḡaiḡ,
 mic Caémaḡa,
 mic Torpéa,
 mic Fearḡaile,
 mic Arctgaile,
 mic ḡuaire Aíðne].

mic Torpa,
 mic Fearḡaile,
 mic Arctgaile,
 mic ḡuaire Aíðne.

mic Arctgail,
 mic ḡuaire Aíðne.

[O por portamlaiḡ tra gabálcup ḡall (.i. búrcaiḡ do ísol
 Uilliam quonquer), por an plioct rin Eachðac bpic, mic Dathi,
 mic

Breifny-O'Reilly, being of the tribe of Diarmaid Ruadh,—from whom is called O'Ruaidhin,—son of Aedh, son of Colman, son of Cobhthach, son of Gaibhnenn, son of Conall, son of Eoghan, son of Eochaidh Breac, son of Dathi, son of Fiachra, son of Eochaidh Muighmheadhoin."

'*Flann, son of Lonan*.—He was a celebrated poet of Connaught, and flourished towards the close of the ninth century. He is styled the Virgil of the Race of Scots by the Four Masters at the year

918.—See O'Reilly's Irish Writers, pp. 58, 59.

" [*When the English invasion, &c.*—All this matter enclosed in brackets, down to the end of the pedigree of the O'Clerys, has been inserted from Peregrine O'Clery's genealogical MS. now deposited in the Library of the Royal Irish Academy. Mac Firbis has omitted this family altogether, but, as it appears from the authentic Irish Annals that they had supplied many distinguished chiefs to the territory

son of Giolla na naomh,	O'Clerys,
son of Cugaela,	son of Ceadadhach,
son of Giolla Cheallaigh, from	son of Cumasgach,
whom the surname is called,	son of Cathmogh,
son of Comaltan,	son of Torptha,
son of Flann, i. e. Maelcearard,	son of Feargal,
son of Maelfabhaill,	son of Artgal,
son of Cleireach, from whom the	son of Guaire Aidhne].

Flann,	
son of Lonan ^t ,	son of Torpa,
son of Conmach,	son of Feargal,
son of Caithniadh,	son of Artgal,
son of Aodh,	son of Guaire Aidhne.

Artgal,	
son of Flaithniadh,	son of Artgal,
son of Feargal,	son of Guaire Aidhne.

[When the English invasion" [*recte* invaders], namely, the Burkes of the race of William the Conqueror^v, prevailed over the race of

of Hy-Fiachrach Aidhne, the Editor, deeming it a pity that they should not have their place among the families of the race of Guaire Aidhne here treated of, has taken the liberty to lay before the reader the account which this family have written of themselves. And as a branch of them became poets and historians to the chiefs of Tirconnell, their genealogical compilation is as much entitled to respect and historical credence as that of Mac Firis, or any other Irish compiler of their time.

^v *William the Conqueror*.—This is not William the Conqueror of England, but William Fitz Adelm De Burgo, who is generally styled the Conqueror by Irish writers, because he conquered the province of Connaught. This celebrated man, the ancestor of all the Burkes of Ireland, died in the year 1204, according to the Annals of Clonmacnoise and the Four Masters, in both which his character is described in such words as show that he was no greater favourite with the Irish, than with

mic Fíachrach, no fódlaib, agus no h-eirpreidic araill díob ino aile chríochanb, .i. Mac Giolla Cheallan̄ co h-Iorppur Iapthair, agus díong d'Uib Cléirig h-i Tír Amalgaða mic Fíachrach, agus díeam aile do'n Mhumain, co non aitéreabrac h-i comfoguḡ Chille Canoin̄, agus apoile díób go díreipne Uí Raḡallan̄, dia n-garap Clann Cléirig. Do raot dno, iar d-eríoll, fear eagnaib do Uib Cléirigh á Tír Amalgaib mic Fíachrach go Cenel ḡ-Conaill mic

his own countryman, Giraldus Cambrensis, who in his *Hibernia Expugnata* (lib. ii. c. 16, Camden's Edition, p. 793), draws his character in very black colours. The Irish writers of the seventeenth century, however, attempted to break down the testimony of Giraldus, and of the older native writers, but with little success, as they have not been able to find any one good trait in his character on record. Connell Ma-geoghagan, who was probably related to the Burkes, has the following very curious note on the horrid account of his death in the Annals of Clonmacnoise: "These and many other reproachfull words my author layeth down in the old book, which I was loath to translate, because they were uttered by him for the disgrace of so worthy and noble a man as William Burk was, and left out other his reproachfull words, which he (as I conceive) rather declared of an evil will, which he did bear towards the said William, then any other just cause."

Duald Mac Firbis also attempts, in his pedigree of the Earl of Clanrickard, to defend the character of Fitz Adelm by stating that Giraldus was prejudiced against

him; and it must be admitted on comparing the character which Giraldus gives of Fitz Adelm, with that of his (Giraldus's) own uncle Fitz-Stephen, that there was more or less of prejudice in the way; but still when it is considered that William Fitz Adelm De Burgo's character, as drawn by Giraldus, does not much differ from that given of him in the Annals of Clanmacnoise, it is clearly unfair to conclude that both are false, though it may be allowed that both are overdrawn, as Giraldus was undoubtedly prejudiced, and as the Irish ecclesiastic, who compiled the Annals of Clonmacnoise, could not be expected to give a perfectly impartial account of an invader and conqueror, who had plundered the church of Clonmacnoise and all the most sacred churches of Connaught.

* *Iorrus Iarthair*, i. e. the western Iorrus. This is evidently the barony of Erris, in the west of the present county of Mayo. There are other smaller districts called Iorrus verging on the ocean, in the west of the county of Galway, as Iorrus Aitheach, Iorrus Mor, and Iorrus Beag.

of Eochaidh Breac, the son of Dathi, son of Fiachra, some of the latter scattered and dispersed themselves in various territories: Mac Giolla Cheallaigh went to Iorrus Iarthair^x, and some of the O'Clerys into Tir Amhalgaidh mhic Fiachrach^x, and others into Munster, where they dwelt in the vicinity of Kilkenny^y; and others of them called Clann Cleirigh, went to Breifne Ui Raghallaigh^z. There passed also, after some time, from Tir Amhalgaidh mhic Fiachrach into Cinel Conaill mhic Neill^a, a wise man of the O'Clerys, whose name

^x *Tir Amhalgaidh mhic Fiachrach*, i. e. the country of Awley, the son of Fiachra (brother of the monarch Dathi); now contracted to Tirawley, a barony in the north-east of the county of Mayo.

^y *To Munster, where they dwell in the vicinity of Kilkenny*.—This is in accordance with the ancient division of the provinces, not with that in the time of the writer, for then Kilkenny was in the province of Leinster. But, according to the ancient division of the provinces,—which the O'Clerys knew far better than the modern—Urmhumhain, Ormond, or East Munster, extended from Gabhran, now Gowran, in the east of the present county of Kilkenny, westwards to Cnamh-choill, now corruptly *Cleath-choill*, near the town of Tipperary—(not Knawhill, as Haliday states in his translation of the first part of Keating's History of Ireland),—and from Bearnan Eile, now the Devil's Bit Mountain, on the frontiers of the baronies of Ikerrin and Eliogarty, in the county of Tipperary, southwards to Oilean Ui Bhric, or O'Brick's island, near Bunmahon, in the

present county of Waterford.

^z *Breifne Ui Raghallaigh* (anglicised Brennie, and Breffny O'Reilly), was the ancient territory of the O'Reillys, and comprised the entire of the county of Cavan, except the baronies of Tullyhunco (Cealać Ūhunćaca) and Tullyhaw (Cealać Eacćac), which were separated from Breffny O'Rourke, when the county of Cavan was formed.

^a *Cinel Conaill mhic Neill*, i. e. the race of Conall, son of Niall. Here the name of the people is put for that of the territory, which is very usual with Irish writers; but when they wish to distinguish the country from the people they prefix *Tir*, as *Tir Conaill* instead of *Cinel Conaill*. This territory comprised originally the entire of the present county of Donegal, except the territories of Inishowen and Magh Itha, now the barony of Raphoe, which belonged to the Cinel Eoghain, or race of Eoghan, who was the brother of Conall; but in later ages these territories were ceded to O'Donnell, and were considered a part of his country of Tirconnell.

míe Neill, Corpmac mac Diarmada Uí Cléirig a com-aínm, agus
ba raol foirceir ír in dá dlígead, .i. civil agus canón. Ro canraic
manaig

^b *The two laws, civil and canon.*—Connell Mageoghegan says, in a note in his translation of the Annals of Clonmacnoise, at the year 1317, that the old Irish “Fenechus or Brehon Lawe was none other but the Civil Law which the Brehons had to themselves in an obscure and unknown language, which none cou’d understand except those that studied in the open schools they had.” But this assertion, made in 1627 by a man who evidently was not acquainted with the Brehon Laws of Ireland, written “in an obscure and unknown tongue,” or with the civil law contained in the Pandects of Justinian, cannot be considered true, unless we are to suppose that by the word *civil* he meant merely the municipal common law of the Irish. Nothing is more certain than that the Brehon or Fenechus Laws of the Irish had been in use among them for ages before they became acquainted with the Civil Law or Pandects of Justinian; for it does not appear that the Irish had any acquaintance with this law until about the beginning of the thirteenth century, when it was established all over the west of Europe. About the year 1130, a copy of Justinian’s Pandects being discovered at Amalfi, soon brought the civil law into vogue all over the west of Europe, where, before that period, it had been quite laid aside and almost forgotten, though some

traces of its authority remained in Italy, and the eastern provinces of the empire. This now became in a particular manner the favourite law of the clergy, who borrowed the method of many of the maxims of the canon law from it. The study of it was introduced into several Universities abroad, particularly that of Bologna, where exercises were performed, lectures read, and degrees conferred as well in this faculty as in other branches of science: and many nations on the continent, just then recovering from the convulsions consequent upon the overthrow of the Roman empire, and settling by degrees into peaceable forms of government, adopted the civil law, being the best written code then extant, as the basis of their several constitutions, blending and interweaving it among their own customs, in some places with an extensive, in others a confined authority.—See Domat’s Treatise of Law, c. 18, sect. 9, and Epistle of Innocent IV. in M. Paris, at the year 1254.

It appears to have been first introduced into England by Theobald, a Norman abbot, who was elected to the See of Canterbury in the year 1138: he was much attached to this new study, and brought over with him in his retinue many learned proficients in it, and among others Roger, surnamed Vacarius, whom he placed in the University of Oxford to teach it there.

name was Cormac Mac Diarmaid O'Clery, and who was a learned proficient in the two laws, civil and canon^b. The monks and ecclesiastics

How soon after it found its way into Ireland cannot be easily determined. No mention is made of the civil law in the Irish Annals before the thirteenth century, and it is quite evident that *bpeiteamnuir* so often mentioned meant the Brehon and Canon Laws.

At the year 1126 the Four Masters record the death of Maoiliosa Ua Coinne, the most learned of the Irish, in history, in judicature (*bpeiteamnuir*), and in the Urd Padraig; but it will appear from many entries in the Irish Annals that there were professors of the civil and canon laws in Ireland in the thirteenth century, and very many in the beginning of the fourteenth. The following entry, in the Annals of Clonmacnoise, as translated by Connell Mageoghegan, is curious as throwing some light upon this subject:

"A. D. 1328.—Morish O'Gibelan, master of art, one exceeding well learned in the new and old laws, civile and cannon, a cunning and skillfull philosopher, an excellent poet in Irish, an eloquent and exact speaker of the speech, which in Irish is called Ogham, and one that was well seen in many other good sciences. He was a cannon and singer at Twayme, Olfyn, Aghaconary, Killalye, Enaghdown, and Clonfert. He was official and common judge of these dioceses, ended his life this year."

This passage is given by the Four Masters thus:

"A. D. 1328, Maurice O'Gibellain, chief professor of the new Law, the *old Law*, and the canon Law, a truly learned philosopher and a Cananach coradh of Tuam, Elphin, and Achonry, Killala, Annadown and Clonfert, the official and the general Brehon of the archbishoprick, died."

Now it is quite evident that by the *old law* is here meant the old Brehon law of Ireland, which had been modified by the ancient Irish ecclesiastics at various periods, and that by the *new law* is meant the Justinian Code, or civil law, then lately introduced. That the ancient Irish ecclesiastics had adopted the Brehon law as modified by the early saints of the Irish Church, is clear from the laws themselves, which contain several ecclesiastical and monastic rules and regulations; but how far the Justinian Code, or civil law, modified these in the thirteenth or fourteenth centuries is unknown. Various laws of the primitive Irish saints are referred to in the Irish Annals, but whether these were monastic rules or municipal rules or regulations for the people in general, is not yet ascertained. The following laws are mentioned in the Annals of Clonmacnoise as translated by Connell Mageoghegan:—the laws of St. Kieran, at the year 740; the laws of St. Patrick, at

manaiḡ aḡur rruite mainiṛte S. beannaḡo, dia n-ḡaraḡ Mainiṛ-
 tiṛ Eapa Ruaiḡ, eiriḡe aḡ a cāomaiṛilleaḡ, aḡur aḡ a beḡ-ḡeṛaiṛ,
 aḡ a eagna, aḡur aḡ a inncleḡt, aḡur ḡoṛ foḡṛaṛ 1 n-a n-aontaiḡ
 ṛṛi ṛé. ba h-óḡ aoiḡeadhach an ionḡaiḡ ṛin eiriom. Ua Sḡingin
 ba h-ollam ṛeanchura do tiḡearna Ceneoil Conaill, .i, d' Ua Dom-
 naill athaiḡ imchian ṛiar an tan ṛin, aḡur á h-Aṛḡ Channa, a
 Muḡ Luṛḡ an Daḡḡa, dṛ ṛánaicc céṛur ḡo Cenel Conaill.
 Níall ḡaṛḡ, mac Aḡḡa, mic Domnaill Oḡ ba tiḡearna ṛoṛ an
 ḡ-ṛiḡ an tan do n-ánaic an Corḡmac at ṛubṛamoi, aḡur ba h-é
 Ua Sḡingin, .i. Maḡa, ba h-ollam do'n Níall ṛemṛaite iṛ in ionamm
 ṛin, aḡur nṛ ḡo maiṛ do cḡoinḡ aḡ Ua Sḡingin ina beoṛ dia cḡenel iṛ
 in cṛich cen moṛa aḡin inḡean cuchtach ḡo baoi laiṛ, aḡur ḡo
 neanaiṛc do ṛeiriḡ ṛṛiṛ in ti Corḡmac, aḡur ba ṛeaḡ ḡo chuinoḡḡ
 1 n-a tiṛnṛea, céciḡ ṛearṛcal no ḡeiriḡe uaiḡiḡ diḡliniḡ do cḡoṛ
 ṛṛi teṛcclim, aḡur ṛṛi ṛoḡloim ṛeanchura, ó ḡo ṛcaic, aḡur ó ḡo
 diḡḡaite an cenél dia m-baoiriom iṛ in ḡ-ṛiḡh, áṛt maḡ eiriom,
 aḡur an aoin inḡean ḡo earṛaiḡm ṛriṛiom do'n cṛiṛ ṛin. Do ṛin-
 ḡeall ṛom n-dó in ḡo cuinoḡḡ ṛaiṛ, aḡur ḡo comail eiriḡ. Ro
 ḡeanaṛ mac ó'n Corṛmac ṛin, aḡur ó inḡin Uí Sḡingín, ḡiolla
 ḡriḡḡe a cḡomainm, aḡur ba h-1 ṛoṛaiṛmeat, aḡur h-1 ḡ-cuimne
 ḡhiolla ḡriḡḡe Uí Sḡingin, beaṛḡṛaṛaiṛ a máṛar (aḡḡar ollaman
 Cenel

761; the laws of St. Coman, 790; the laws of St. Brandon, 740; the laws of St. Ailbe, 790; the laws of O'Swayne of Rahyne, 740.

* *Eas Ruaidh*.—This abbey which took its name from the celebrated cataract of *Eas Ruaidh*, or *Eas Aodha Ruaidh*, on the River Erne, was erected for monks of the order of St. Bernard by Flaithbheartach O'Muldory, in the year 1184. Its ruins

are still to be seen close to the shore, a short distance to the north-west of the town of Ballyshannon.

* *Ollamh*, pronounced *Ollav*, means a chief professor of any art or science.

* *Ard carna*, now Ardcarne, in the barony of Boyle, and county of Roscommon, and about four miles due east of the town of Boyle, where there are the ruins of a church and village. Maolcaimhghin

siastics of the abbey of St. Bernard, called the abbey of Eas Ruaidh^c, loved him for his education and good morals, for his wisdom and intellect, and detained him among them for some time. He was at this time a young guest. O'Sgingin had been, for a long time before this period, the historical Ollamh^d to O'Donnell, the lord of Cinel Conaill, and he had first come into Cinell Conaill from Ard carna^e, in Magh luirg an Daghdha^f. Niall Garbh^g, son of Aodh, son of Domhnall Og, was lord of the country when the Cormac we have mentioned came thither, and O'Sgingin, viz., Matthew, was at the time Ollamh to the Niall aforesaid. And there lived not of O'Sgingin's children, nor yet of his tribe in the country, but one fair daughter, and he joined her as wife to this Cormac, and what he asked as her dower^h was, that whatever male child should be first born to them should be sent to study and learn history, as all his race had become extinct in the territory except the daughter whom he wedded to him on that occasion. The other promised to comply with his request, and kept his promise indeed. A son was born of this Cormac and the daughter of O'Sgingin, named Giolla Bhrighde; and it was in commemoration and remembrance of Giolla Bhrighde O'Sgingin, the brother of his mother

O'Sgingin, who was herenach of the church of Ardcarne, died in the year 1224, according to the Annals of the Four Masters.

^f *Magh luirg an Daghdha*, i. e. the plain of Daghdha's track, generally anglicised Moylurg. It was the name of the plains of Boyle, that is, of the level part of the present barony of Boyle, lying south of the River Boyle.

^g *Niall Garbh, son of Aodh, &c.*—His death is recorded in the Annals of the Four Masters at the year 1348. His father Aodh died in 1333, and his grand-

father, Domhnall Og, in 1264.

^h *As her dower.*—*Ṭinnrcpa* means a reward, portion, or dower. It was the custom among the ancient Irish, as among the Eastern nations, that the husband should make a present to his wife's father, or to herself upon his marriage. This custom is still in use among the Turks. The meaning of the word *ṫinnrcpa* is established beyond dispute by a passage in the *Leabhar Breac*, which states that Rebecca was the first who received the *ṫinnrcpa* from her husband.

Cenel Conaill, at bát nías an tan rín, an bliadain rí d'aois ar
 d-Tighearna, 1382) do padab an anmain ar Giolla bhríde for
 an mac rín. Mac do'n Giolla bhríde rín Ua Cleirigh Giolla
 riabac, Mac do Giolla riabac Diarmaid na d-erí ríol, .i. ríol
 ríu leigean, ríol ríu reanchur agus ríol ríu dán. Ar do pad
 O'Domnaill, Niall, mac Toirdhealbhaidh an fhiona, an fearonn dia
 n-garar an Chraoibeach, agus no baol a áitreab agus a ionatacht
 atáid ír in b-fearonn rín, la taob na b-fearonn n-aile do padrat
 a rinnirí ríom d' Ua Sgingin feacht ríam, o rop aóma rom ír in
 ealaóain no pad toich do, .i. h-í reanchur. Mac do Dhiarmaid
 na d-erí ríol Taib Camm, ag a m-baol an triur mac oiríderc,
 Tuatal, Giolla riabac, agus Diarmaid; ar leo-ríde do ronab
 na tige cloch i g-Cill bairrainn, dóig ba h-iaoiríde co n-a rinn-
 rearaib noptar fonóiríe h-í g-Cill bairrainn ó aimirí an Corbmaic
 at

ⁱ *In the year of our Lord 1382.* — The death of Giolla Brighde O'Sgingin, "intended Ollamh of Tirconnell," is recorded in the Annals of the Four Masters at this year. This, however, contradicts the assertion that Niall Garbh, the son of Aodh, son of Domhnall Og O'Donnell, was the chief of Tirconnell when Cormac O'Clery first went to that country, for this Niall Garbh O'Donnell, as we have already seen, was slain in the year 1348, and if Giolla Bhrighde O'Sgingin was dead before Cormac O'Clery's marriage with his sister, Cormac O'Clery must have been in Tirconnell at least thirty-four years before his marriage. But the fact undoubtedly was, that Niall Garbh O'Donnell was not the chief of Tirconnell at the time, but his son Toirdhealbhach an fhiona, and

that the first of the O'Clerys settled in the territory about the year 1382, immediately after the death of Giolla Bhrighde O'Sgingin.

^j *Niall, the son of Toirdhealbhach an fhiona.* — This Niall died in the Isle of Mann in the year 1439, a hostage in the hands of the English. His death is thus recorded in the Annals of the Four Masters: — "A. D. 1439, O'Donnell (Niall Garbh) died in the Isle of Mann in captivity. He was the select hostage of Tirconnell and Tirone and all the north of Ireland, and the chief subject of conversation in Leath Chuinn during his time; — harasser and destroyer of the English (until they took revenge for all) and protector and defender of his tribe, against such English and Irish as were his ad-

mother (the intended ollamh of Cinel Conaill, who had died before this period, in the year of the age of our Lord 1382¹), that the name Giolla Bhrighde was given to him. Son to this Giolla Bhrighde O'Clery was Giolla riabhach; son to Giolla riabhach was Diarmaid of the three schools, *so called because he kept* a school of literature, a school of history, and a school of poetry. It was to him that O'Donnell Niall¹, the son of Toirdhealbhadh an fhiona, granted the lands called Craoibheach^{*} (on which he had his dwelling and residence for some time), in addition to the other lands which his (i. e. *O'Donnell's*) ancestors had previously granted to O'Sgingin,—as he was a proficient¹ in the science, which was hereditary to him, namely, history. Son to Diarmaid of the three schools was Tadhg Cam, who had the three celebrated sons, Tuathal, Giolla riabhach, and Diarmaid, by whom the stone-houses were erected at Cill Barrainn^m, for they and their ancestors were freeholders in Cill Barrainn from

the
versaries, both before and after he became chief of his tribe."

^{*} *Craoibheach*, pronounced Creevagh, a district in the parish of Kilbarron, barony of Tirhugh, in the south of the county of Donegal.

¹ *As he was a proficient, &c.*—This sentence is very confused in the original, but there can be no doubt that the meaning intended to be conveyed by the writer is the following:—"This Diarmaid of the three schools, being a great proficient in his hereditary science of history, received from O'Donnell a new grant of lands, called Craoibheach (on which he had his residence for some time), and which he enjoyed, together with the lands which he inherited from the O'Sgingins, to whom O'Donnell's ancestors had made grants of

several townlands." The sentence should be thus constructed in the original:—

"O rop aōma an Diarmait rí in ealaóaim no paó toich oo, .i. h-i fear-chur, oo paó O'Domnaill (Niall, mac Toirdhealbhadh an fhiona), oo an fearonn oia n-garap an Chraoibheach, — i n-a m-baoi a áirpeab agur a ionatact acaib,—la taob na b-fearonn n-aile oo paó-rac a fíonrionm o' Ua Sgingin fearc na m."

^m *Cill Barrainn* (i. e. the church of St. Barrfhionn), now Kilbarron, a townland giving name to a parish in the barony of Tirhugh, in the county of Donegal. For a view of some fragments of these stone houses, situated on a precipitous cliff, see the Irish Penny Journal, January 16th, 1841, p. 225.

at pubhramar tanac céatur co Cenel Conaill; agus ar iad fóir ar pondúire h-1 Ceathramhain na Cuchtrach, agus h-1 g-Ceathramhain an tighe cloiche d' fhearronn mainiurte Eapra Ruaid. Ro bað leó van ó Ua n-Domnaill ceathraime Cille Domhnaiḡ, agus ceathraime Chuile remuir, agus ceathraime Dhroma an éroinn, for Muig Ene.

Clann Tuatail, mic Taidḡ Camm, mic Diarmata na d-erí rcol, .i. Taidḡ Camm, Giolla Riabach, Machḡamhain, Uilliam. Taidḡ Camm diobaḡ, aḡt aoin inḡean for fáḡaib, .i. Síle. Giolla riabac, an dara mac Tuatail, aḡiatt a clann, .i. Tuatail, Maḡḡamhain, Cu-Múman. Maḡḡamhain, mac Tuatail, mac do Diarmata. Mac do'n Diarmata rin an Maolmuire baol ag Ua Neill, Toirprealbac Luineach. Uilliam, mac Tuatail, mic Taidḡ Camm, aḡiatt a clann, Donnchaḡ, Conaire, Domnall, Concobair.

Clann Giolla riabaiḡ, mic Taidḡ Cam, mic Diarmata, na d-erí Scol, Domnall agus Muirir.

Diarmata, mac Taidḡ Camm, mic Diarmata na d-erí rcol, aḡiatt

^a *Ceathramh na Cuchtrach*, i. e. the kitchen quarter. This name is now obsolete in the parish of Kilbarron.

^b *Ceathramh an tighe cloiche*, i. e. the quarter of the stone house; but the name is now obsolete.

^c *Cill Domhnaigh*, now Kildoney, a glebe in the parish of Kilbarron, lying to the south of the River Erne. In an inquisition held at Lifford on the 12th of September, 1609, this townland is called Kildoned, and it is stated to be in the tenure of the sept of the O'Cleries.

^d *Cuil remuir*, was the ancient name of a quarter of land near the sea, in the same parish; but the name is now obsolete.

^e *Druim an chroinn*. There is a townland of this name in the parish of Templecarne, in the Barony of Tírugh.

^f *Magh Ene*.—This is called g-Cedne by Keating and O'Flaherty, Moy-Genne in the Ulster Inquisitions, and Magh Ene by Colgan, Trias Thaum. p. 180, col. 6, where he thus points out its situation:—“Magh ene est campus Tirconnallie ad australem ripam fluminis Ernei inter ipsum et Drobhaois fluvium protensum.” This plain extends from Belleek to Bundrowes, and from the mouth of the River Erne to Lough Melvin.

^g *Who was with O'Neill*, that is, who was poet to O'Neill. He was slain by

the time of the Cormac we have above mentioned, the first who came to Cinel Conaill. They were also the freeholders of Ceathramh na cuchtrach^a, and of Ceathramh an tighe cloiche^o, a part of the lands of the abbey of Eas Ruaidh. They had also, as a gift from O'Donnell, the quarter of Cill Domhnaigh^p and the quarter of Cuil remuir^q, and the quarter of Druim an chroinn^r, in the plain of Magh Ene^s.

The sons of Tuathal, son of Tadhg Cam, son of Diarmaid of the three schools, were Tadhg Cam, Giolla riabhach, Mathghamhain, *and* William. Tadhg Cam left no issue, except one daughter named Celia. Giolla riabhach, the second son of Tuathal, had issue, Tuathal, Mathghamhain, *and* Cu-Mumhan. Mathghamhain, the son of Tuathal, had a son Diarmaid. This Diarmaid had a son Maolmuire, who was with O'Neill^t (Toirdhealbhach Luineach). William, son of Tuathal, son of Tadhg Cam, had three sons, Donnchadh, Conaire, Domhnall, *and* Conchobhar.

The sons of Giolla riabhach, son of Tadhg Cam, son of Diarmaid of the three schools, were Domhnall *and* Maurice.

Diarmaid, son of Tadhg Cam, son of Diarmaid of the three schools,
had

O'Donnell's people in the year 1583, under which year the Four Masters have preserved the following very curious notice. After giving an account of a fierce battle fought between O'Donnell and O'Neill near the river Finn, in which the latter was defeated, they proceed as follows to record the fate of their own distinguished relative :—" On this occasion numbers of O'Neill's people were slain and drowned, and among others O'Gormley (Cormac, son of Hugh) and Maelmuire, son of Diarmaid, son of Math-

ghamhain, who was son of Tuathal O'Clery, the only hostage of O'Neill and the Cinel Eoghain; for his father and O'Neill himself had been born of the same mother, and Maelmuire, on account of his relationship to O'Neill, had been in possession of all O'Neill's wealth, and O'Neill would have given three times the usual price for his ransom, if ransomed he could be, but he was first mortally wounded and afterwards drowned by O'Donnell's people, who were in high spirits and rejoiced greatly at seeing him thus cut off."

aciat a clann, Cuccoirice, Giolla briðe, Corbmac, an bratair
 d'ur S. Francir, agus Muirgear.

Clann Concoirice, mic Diarmata, mic Taidh Cairn, Mac-
 con, Corbmac, Dubtaic, Taidh, Corbmac, agus Muirir balloch.
 Clann Giolla briðe, mic Diarmata, mic Taidh Cairn mic
 Diarmata na d-erí rcol, Fearfeara, Aimirgin, agus Maelmuire.
 Clann Muirgeara, mic Diarmata, mic Taidh Cairn, Diarmata
 agus Cu-Connact.

DO SHEIOCHT DIARMADA, MIC TAIDH CAIRN

Lughaidh, Giolla briðe, Maccon Meirgeac, Cuccoirice, agus
 Dubheann,

clann Meiccon,
 mic Concoirice,
 mic Diarmada,
 mic Taidh Cairn,
 mic Diarmada na d-erí rcol,

mic Giolla riabaidh,
 mic Giolla briðe,
 mic Corbmac, .i. an céir fear
 tánaic d'ob co Cenel Conall.
 mic Diarmada,

mic

"*Maurice Ballach*, i. e. Maurice the
 freckled. He was a learned historian and
 poet, and was hanged in the year 1572,
 together with others of the Irish literati,
 by the Earl of Thomond, who wished to
 exterminate that class in Ireland. The
 Four Masters have the following remark
 on this cruel act:—"This abominable
 deed gave birth to the composition of
 several satirical and denunciatory poems
 against the Earl."

"*Lughaidh*, son of Maccon.—He was the
 head of the Tirconnell branch of the
 O'Clerys, and the most distinguished of
 the Irish literati of the north of Ire-
 land in his time. He was the principal
 poetical combatant on the part of the

northern bards in the contest with those
 of the south of Ireland, which took place
 about the beginning of the seventeenth
 century, respecting the claims of the rival
 dynasties of the northern and southern
 divisions of Ireland to supremacy and re-
 nown. The poems written on the occa-
 sion, styled the *Iomarbadh*, or Contention
 of the Bards, are preserved in several
 Irish MSS., the most ancient of which
 is the O'Gara MS., now preserved in the
 Library of the Royal Irish Academy.
 Besides these poems Lughaidh wrote An-
 nals of his own time, which the Four
 Masters state were used by them in their
 Annals. He held all his lands till the
 year 1609, and was selected as one of the

had these sons, namely, Cucoigriche, Giolla Brighde, Cormac, the friar of the order of St. Francis, and Muirgheas.

The sons of Cucoigriche, son of Diarmaid, son of Tadhg Cam, were Maccon, Cosnamhach, Dubhthach, Tadhg, Cormac, and Maurice Ballach". The sons of Giolla Brighde, son of Diarmaid, son of Tadhg Cam, son of Diarmaid of the three schools, were Fearfeasa, Aimirgin, and Maelmuire. The sons of Muirgheas, son of Diarmaid, son of Tadhg Cam, were Diarmaid and Cuchonnacht.

OF THE RACE OF DIARMAID, SON OF TADHG CAM.

Lughaidh*, Giolla-Brighde, Maccon Meirgeach, Cucoigriche, and Duibhgeann,

sons of Maccon,
son of Cucoigriche,
son of Diarmaid,
son of Tadhg Cam,
son of Diarmaid of the three
schools.

son of Giolla riabhach,
son of Giolla Brighde,
son of Cormac, the first man of
this family who came to Cinel
Conaill,

son

"good and lawful men" of the county of Donegal, appointed to inquire into the king's title to the several escheated and forfeited lands in Ulster. An inquisition was held by these commissioners at Lifford on the 12th of September, 1609, in which it is stated that "the parish of Kilbarron contains five quarters in all, whereof one quarter is Herenach land possessed by the sept of the Cleries as Herenaches, paying thereout yearlie to the lord busshopp of Raphoe thirteen shillings, four-pence Irish per annum, six meathers of butter, and thirty-four meathers of meale; and that there is one quarter named Kildoned" [now Kildoney Glebe], "in the tenure of

the said sept of the Cleries, free from any tithes to the busshop." And again, "that there are in the said parishe three quarters of Collumbkille's land, every quarter conteyning sixe balliboes, in the tenure of Lewe O'Cleerie, to whom the said lands were sithence mortgaged for fortie pounds by the late Earle of Tirconnell, and that the said Lewe hath paid thereout yearly unto his Majestie, sithence the late Earle's departure, four poundes, two muttons, and a pair of gloves, but nothing to the said busshopp." For some account of the lineal descendants of this Lughaidh see the Pedigree of O'Clerie in the Addenda to this volume.

mic Seacain Sgiamaig,
 mic Domnaill,
 mic Giolla Iora,
 mic Taidh,
 mic Muirtheadig,
 mic Tigearnaig,
 mic Giolla na naom,
 mic Domnaill,
 mic Eoghain,
 mic bhaoin, d'ég 1033,
 mic Congaela, 1025,
 mic Giolla Cheallai, 1003,
 mic Comaltáin, 976,
 mic Maolcearada, .i. Flann,
 950,
 mic Mailpabail, 887,
 mic Cleirig ó tāt Uí Cléirig,

mic Cebadai,

mic Cumurthai,
 mic Caemoga,
 mic Torpat,
 mic Feargail,
 mic Artgail,
 mic Guairne Aíone,
 mic Colman,
 mic Cobtaig,
 mic Góibnend,
 mic Conaill,
 mic Eogan,
 mic Eadac bpic,
 mic Daeti,
 mic Fiacrac,
 mic Eadac Muigmeadoin.

Diairmait agur Seacain,
 clann an Chornamais,
 mac Concoigriche,
 mic Diairmada,

mic Taidh Cairn,
 mic Diairmada na d-erí rhol.

Taidh Cam, Flann, agur Concobair,
 clann Dubtaig,
 mic Concoigriche,

mic Diairmada,
 mic Taidh Cairm.

Maolmuire,
 mac Firfeara,
 mic Giolla bpioge,
 mic Diairmata,

mic Taidh Cairm,
 mic Diairmata na d-erí rhol.

son of Diarmaid,
 son of John Sgiamhach,
 son of Domhnall,
 son of Giolla Iosa,
 son of Tadhg,
 son of Muireadhach,
 son of Tighearnach,
 son of Giolla na naomh,
 son of Domhnall,
 son of Eoghan,
 son of Braon, *who* died in 1033,
 son of Cugacla, 1025,
 son of Giolla Cheallaigh, 1003,
 son of Comhaltan, 976,
 son of Maelcerarda, i. e. Flann,
 950,
 son of Maolfabhaill, 887.
 son of Cleireach, from whom the

family of O'Clery,
 son of Ceadadhach,
 son of Cumusgach,
 son of Cathmogh,
 son of Torpa,
 son of Feargal,
 son of Artgal,
 son of Guaire Aidhne,
 son of Colman,
 son of Cobhthach,
 son of Goibhnenn,
 son of Conall,
 son of Eoghan,
 son of Eochaidh Breac,
 son of Dathi,
 son of Fiachra,
 son of Eochaidh Muighmheadh-
 oin.

Diarmaid and John,
 sons of Cosnamhach,
 son of Cu-coigriche,
 son of Diarmaid,

son of Tadhg Cam,
 son of Diarmaid of the three
 schools.

Tadhg Cam, Flann, and Conchobhar,
 sons of Dubhthach,
 son of Cucoigriche,

son of Diarmaid,
 son of Tadhg Cam.

Maolmuire,
 son of Fearfeasa,
 son of Giolla Brighde,
 son of Diarmaid,

son of Tadhg Cam,
 son of Diarmaid of the three
 schools.

DO SHLIOCHT TUAETHAIL.

Cú Muman,
mac Tuathail,
mic Giolla riabaiḡ,
mic Tuathail,

mic Taidḡ Cairn,
mic Diarmata na d-epí rcol.

Maolmuire,
mac Matḡamna,
mic Giolla riabaiḡ,

mic Tuathail,
mic Taidḡ Cairmm.

Uilliam, Conaire, Maolmuire, .i. berranbín, Taḡ an t-Sleibe,
.i. Michel, dá bhrátair d' éirí Obrepuantia,
clann Donncaid,
mic Uilliam,
mic Tuathail,

mic Taidḡ Cairn,
mic Diarmata na d-epí rcol.

DO SHLIOCHT GIOLLA RIABHAIḡH.

Muirir,
mac Concoirce, mic,
mic Muirir,
mic Giolla riabaiḡ,

mic Taidḡ Cairn,
mic Diarmata na d-epí rcol.

Tuathal,
mac Eolupa,
mic Muirir,

mic Giolla riabaiḡ,
mic Taidḡ Cairn.

Maolmuire

† *Conairè*.—He was one of the compilers of the Annals of the Four Masters, and the transcriber of the greater portion of the copy of the second part of that work, preserved in the Library of the Royal Irish Academy.

† *Maolmuire*, i. e. *Bernardin*.—He was

guardian of the convent of Donegal in the year 1632, when the Four Masters commenced the compilation of their Annals, and again in 1636, when the same work was completed, as appears from the testimonium prefixed to the second volume of the work, now in the Library of the Royal

OF THE RACE OF TUATHAL.

Cu-Mumhan,	
son of Tuathal,	son of Tadhg Cam,
son of Giolla riabhach,	son of Diarmaid of the three
son of Tuathal,	schools.

Maolmuire,	
son of Mathghamhain,	son of Tuathal,
son of Giolla riabhach,	son of Tadhg Cam.

William, Conaire^v, Maolmuire, i. e. Bernardin^v, Tadhg of the mountain, i. e. Michael^x; *the two latter were* friars of the order de Observantia,

sons of Donnchadh,	son of Tadhg Cam,
son of William,	son of Diarmaid of the three
son of Tuathal,	schools.

OF THE RACE OF GIOLLA RIABHACH.

Maurice,	
son of Cu-coigriche,	son of Tadhg Cam,
son of Maurice,	son of Diarmaid of the three
son of Giolla riabhach,	schools.

Tuathal,	
son of Eolus,	son of Giolla riabhach,
son of Maurice,	son of Tadhg Cam.

Irish Academy.

^x *Tadhg of the mountain, i. e. Michael.*— He was the chief of the Four Masters, and the author of an Irish Glossary, published at Louvain in 1643, which has been of great use to Lhwyd and all subsequent Irish lexi-

Maolmuire
cographers. He spent ten years travelling through Ireland to collect manuscripts for the use of Colgan in compiling his *Acta Sanctorum*; in the Preface to which work Colgan gives a high character of him.

Maolmhuire,
mac Domnaill,
mic Taidg,
mic Maoilmhuire,

mic Giolla riabaid,
mic Taidg Cairn.

DO MHUINCIR CHLEIRIGH THIRE h-AMHALGADHA.

Seaan Sgiamaic, Daniel, Tomar, agur Corbmac, ceirne,	
meic Domnaill,	mic Giolla na naom,
mic Giolla Iora,	mic Domnaill,
mic Taidg,	mic Eogain,
mic Muireadaid,	mic bpaen,
mic Tigearnaid,	mic Congaeta, 7c.

Seaan Sgiamaic ó d-tát muincir Cléirigh Tíre Conaill; Daniel ó d-tát muincir Cléirigh Thíre h-Amhalgada; Tomar ó d-tát clann Cléirigh bpaen Uí Raigallaid, Corpmac ó d-tát muincir Cléirigh Cille Cairnigh.

DO SHLIOCHT DANIEL.

Maolmhuire,
mac Corbmaic,
mic Diarmata,
mic Ruaidrí,
mic Seain,
mic Tomar,
mic Domnaill,
mic Daniel,

mic Domnaill,
mic Giolla Iora,
mic Taidg,
mic Muireadaid,
mic Tigearnaidh,
mic Giolla na naom, 7c.

Tomar

¹ *The Muintir Cleirigh of Tir-Amhalgatha*, i. e. the O'Clerys of Tirawley, in the county of Mayo. The reader is referred to a note on the pedigree of O'Dowd, where he will find the affidavit of John

O'Cleri, a member of this branch of the family, made in 1452, concerning the descent and former possessions in Tireragh, of Hugh O'Dowde, of Stalinge in Meath.

² *Cill Cainnigh*, i. e. *Cella Sancti Can-*

Maolmuire,	
son of Domhnall,	son of Giolla riabhach,
son of Tadhg,	son of Tadhg Cam.
son of Maolmuire,	

OF THE MUINTIR CLEIRIGH OF TIR-AMHALGADHA⁷.

John Sgiamhach, Daniel, Thomas, and Cormac,	
four sons of Domhnall,	son of Giolla na naomh,
son of Giolla Iosa,	son of Domhnall,
son of Tadhg,	son of Eoghan,
son of Muireadhach,	son of Braen,
son of Tighearnach,	son of Cugaela, &c.

From John Sgiamhach are descended the family of O'Clery of Tir Conaill; from Daniel are the family of O'Clery of Tir Amhalgadha; from Thomas are the Clann Clery of Breifny O'Reilly; and from Cormac are the Muintir Clery of Cill Cainnigh⁸.

OF THE RACE OF DANIEL.

Maolmuire,	
son of Cormac,	son of Domhnall,
son of Diarmaid,	son of Giolla Iosa,
son of Ruaidhri,	son of Tadhg,
son of John,	son of Muireadhach,
son of Thomas,	son of Tighearnach,
son of Domhnall,	son of Giolla na naomh, &c.
son of Daniel,	

Thomas

nici, now Kilkenny. Several of the name Cleary are now to be found throughout Leinster, but the name has been in many instances anglicised to Clarke. The Editor never met any member of the Leinster

Clearys of Leinster, who knew any thing of their pedigree or origin, nor does he believe that the pedigree of any branch has been preserved, except that of the literary Tirconnell family.

Tomar agur ðriar Oð,
clann ðriarinn ná þroige,
mac Ðauðs ðuiðe,
mic Ðonnðarð,

mic Tomar,
mic Ðorinnarill,
mic Daniel.

Ðuibgenð,
mac Emarinn Cþóinn,
mic Emarinn Cþóinn,
mic Corþmaric,

mic Tomar,
mic Ðorinnarill,
mic Daniel.

Maolmuirpe,
mac Firdorþha,
mic Tuatail,
mic Ðonnðarð,

mic Tomar,
mic Ðorinnarill,
mic Daniel.

Ðubalþac,
mac Muirþearþaig,
mic Seasin an Chladarig,
mic ðriarinn,

mic Muirþearþaig,
mic Ðorinnarill,
mic Daniel.

Ðauðs ðuiðe,
mac Tomar,
mic Ðauðs ðuiðe,
mic Ðiarþmata Ðlar,

mic Muirþearþaig,
mac Ðorinnarill,
mic Daniel].

Até and þo ná þroga þo gáðrath Connacta agur Epe vo clóinn
Fiacþach Fholþrnatarig, .i. Ðatí, mac Fiacþac, vo gáð ren þige go
Sliað Alfa, agur þo tábairg an ðhorþma þo tþí gan cat.

Oilioll Molc, mac Ðatí: vo gáð ren þige n-Epeann, gur tábairg
an ðhorþma þo tþí gan cat. Aþrinnvo leabair gur gáð Eapc mac
Oiliolla Muilc þige n-Epeann, agur gur tábairg an ðhorþma gan
cat.

Almarðarð

Thomas and Brian Og,	
sons of Brian na broige,	son of Thomas,
son of David Buidhe [<i>the yellow</i>],	son of Domhnall,
son of Donnchadh,	son of Daniel.

Duibhgenn,	
son of Edmond Cron,	son of Thomas,
son of Edmond Cron,	son of Domhnall,
son of Cormac,	son of Daniel.

Maolmuire,	
son of Fear dorchá,	son of Thomas,
son of Tuathal,	son of Domhnall,
son of Donnchadh,	son of Daniel.

Dubhaltach,	
son of Muircheartach,	son of Muircheartach,
son of John of Cladagh,	son of Domhnall,
son of Brian,	son of Daniel.

David Buidhe,	
son of Thomas,	son of Muircheartach,
son of David Buidhe,	son of Domhnall,
son of Diarmaid Glas,	son of Daniel].

The following are the kings of the race of Fiachra Foltsnathach, who ruled Connaught and Ireland, viz., Dathi, son of Fiachra: he ruled the countries as far as the Alps, and he exacted the Borumeán tribute thrice without a battle.

Oilioll Molt, son of Dathi: he assumed the monarchy of Ireland, and exacted the Borumeán tribute thrice without a battle. *Some* books state that Earc, the son of Oilioll Molt, assumed the monarchy of Ireland, and exacted the Borumha without a battle.

Αμάλγαθ, mac Φιάςρα: do gab ren riḡe Chonnaét. Eoḡan
beul, Ailill Ionbanna, Aod aḡur Crunmaol do gabrao riḡe Con-
naét a Ceara.

Colman, Ḥuairne Aíðne, Muirceartaé aḡur Laiḡnen, ceṛne
riḡ Connaét a h-Aíðne.

Oilill, Catal, Ionbartaé, aḡur Duncáð, ceṛne riḡ a muiḡe
Muaidé anð rin. Conað do cúimniúḡað na rióḡ rin arperit an
file,

Ceṛne riḡ deug do élainn Φιάςρα,
beoða, raétmara na riḡ,
Eoir éear iṛ tuaiḡ ḡaé tpe,
Sluaiḡ aḡ leaṛ ḡaé dine dib.

Ceṛne riḡ ar Chuiḡeao Chonnaét
A cpié Aíðne airo na naom,
Muirceartaé do'n éuaine cómlan,
Laiḡnen, Ḥuairne, Colman Caom.

Ceṛne riḡ Connaét a Ceara,
Crunmaol iṛ Aod na n-arm ḡ-corr,
'S a diaṛ raor, Ailill iṛ Eoḡan
A foirinn na Leoman Lond.

Ceṛne riḡ Ua b-Φιάςρα Muaidé
Duncáð Cpuácna, na ḡ-earo raor
Ionbartaé nári éoirinn taéar,
Oilill aḡur Catal Caom.

Ceaṛraṛ airo-riḡ ḡaḃ-rao Eirinn;
Epe ro móri-rao ḡan muiḡh,
Daéi iṛ Oilill for Eirind,
Αμάλγαθ, Eapc de'n einḡ úir.

Leabaṛ roéair flaéa O b-Φιάςρα
Aea liom runna pá reaé.

Amhalgaidh, son of Fiachra: he assumed the government of Connaught. Eoghan Beul, Ailill Ionbhanna, Aodh, and Crunmhaol assumed the kingship of Connaught and were resident in Ceara.

Colman, Guaire Aidhne, Muircheartach, and Laighnen, were four kings of Connaught *who dwelt* in Aidhne.

Oilioll, Cathal, Ionnrachtach, and Dunchadh were four kings of Connaught *who dwelt* in the plain of Muaidhe [*the Moy*]. To commemorate these kings the poet said :

Fourteen kings of the race of Fiachra,
Vigorous, successful were these kings,
Both south and north of each country,
Each tribe of them was with prosperity.

Four kings of the province of Connaught
Dwelt in great Aidhne, land of saints,
Muircheartach, one of the perfect breed,
Laighnen, Guaire, and Colman Caomh.

Four Connaught kings *dwelt* in Ceara,
Crunmaol and Aodh of weapons bright,
And the noble pair Ailill and Eoghan,
Of the tribe of mighty lions.

Four kings of the Hy-Fiachrach Muaidhe,
Dunchadh of Cruachan, of noble feats,
Iondrachtach, who shunned not the battle,
Oilill and Cathal Caomh.

Of them four monarchs governed Erin;—
Erin they exalted without a cloud,—
Dathi and Oilill over Erin,
Amhalgaidh *and* Earc of the noble lineage.

The Book of the Tributes of the chiefs of Hy-Fiachrach,
Are with me here one and all ;

Ní cluimim map rin a pamlá
Na rir ar calma do éat.

Ceitre.

Sain rir rin a ber duain seancair da'n torac, Fionnac Seancaide
Fear b-Páil.

Trí níg deug ba nioḡda pat,
Do clannaib fiala Fiacrac,
Deubla ar a tuataib gan tar, t,
'Sa Chruacain ceudna Connaet.

Da Fhlaitrí, Feargal por fear,
Guairé, Colman go g-cuibdear,
Map leoman gac ní go rinn,
Dati, Eogan, ir Oilill.

Amalgaid, Ionoraetac an,
Doncetaid, Oilill lonmap
Duncad gan meng, gan meabuil,
Noa leam nac lán-meabuir.

Do geuboe iad-ro ní ar roilepe rob ir in leatanaid 298.

Dati, mac Fiacrac umorpo, 'ra braitre, leo torcair brian,
mac Eatac Muigmeaboin, i g-cae Dam-cluana, agur ar 'n-a éric
do éuit fearonn cloinne Mec n-Earca acht beagan; agur i
b-Tulchaib Domnann do h-aónaicead, do cloinn bhríam, mur ta ir
in leatanaid 247.

GENEALACH

^a *Historical poem*.—This poem is not quoted in the Book of Lecan.

^a *Page 298*.—This reference, and that to page 247, at the end of the next paragraph, are to the pages of our author's MS. written in 1645.

^b *Battle of Damh-chluain*.—This battle

is not recorded in the Annals of Clonmacnoise, the Four Masters, nor in any other authority that the Editor could find, except the Book of Ballymote, fol. 145, b, a. *Damh-chluain* signifies the insulated pasturage or meadow of the oxen. There are many places of the name in Ireland,

I hear not so of any others like them,
They are the bravest men that I have seen.

Fourteen," &c.

Differently from this, however, speaks the historical poem^a beginning "Be it known to the historians of the men of Fail."

"Thirteen kings of kingly prosperity,
 Of the generous race of Fiachra,
 Potent in their countries without thirst,
Reigned in the same Cruachan in Connaught.

Two Flaithri's, Feargal, it is known,
 Guaire, Colman with worthiness;
 As a lion was each king with his spear,
 Dathi, Eoghan, and Oilill.

Amhalgaidh, Iondrachtach the noble,
 Donncathadh, Oilill Ionmar,
 Dunchadh without treachery, without guile,
 It is not by me they are not fully remembered."

These *kings* will be more distinctly found in p. 298^a.

It was by Dathi, the son of Fiachra and his brothers, that Brian, the son of Eochaidh Muighmheadhoin, was slain in the battle of Damh-chluain^b; and it was in eric [*reparation*] for it that the land of Clann Mec n-Earca was forfeited, except a small portion; and it was in Tulach Domhnann^c he was interred, as stated in page 247.

GENEALOGY

now anglicised Doughlone; but the Damh-chluain here referred to, is stated to be situated in the territory of Hy-Briuin Eola (now the barony of Clare, in the county of Galway), on the frontiers of Conmaicne Cuile, now the barony of Kilmaine, in the county of Mayo.

^c *Tulach Domhnann*. This place is called Tulcha Domhnaill in the Book of Ballymote, but it is difficult now to determine which is the more correct name, or where the place is situated. See further remarks on this battle in the Addenda to this volume.

GENEALACH UA DH-FIACHRACH MUAIDHE.

Fiachra Ealgach mac Dathi, Ruad, inġean Airtig Uichte-
leathan, a mātair, doneochabbaē dia bpeē. Uaitē paitear Mul-
lac Ruadā i d-Tír Fiachrac Muaidhe, ar a h-athlacadh i mullac
na tulcā rin; agur ar uirpe ata an capn cloē ril for mullac
na tealcā. Agur Tulac na molt a h-ainm poime rin, uair mian
molt-cāpna do padab d'ā mātair for Oilill Molt an ġ-cēn po
baoi-n'ā bpoimn, agur ġac molt do ġebēi do cum na pioġna ar do ion-
poigina tulcā rin do tionoilit; conab de rin paitear Tulac na molt.
Tulac na Maoile a h-ainm poime rin, tpe for do ġab an Maol-phidiri
inte ar Tāin bó Fhidiri [an comair do bai Fergur ocur Domnall
Dual-buidi a comrag, cor marbad Domnall ir in comrag rin, ocur
an ġamanraid ag tōraigeaēt ar fepaid Epeann and, a n-diaid na
Tana, conab de rin a depar Tulac na Maib nup in cnoc; ocur ir
ó'n

^a *Mullach Ruadha*, now Mullaroe, or Red hill, in the parish of Skreen, barony of Tirerach, and county of Sligo.

• *Hill of the weathers*.—The Rev. Patrick Mac Loughlin, in his abstract of the Book of Lecan, translates this passage thus : “ 'Tis said that Ruad, daughter of Artach Uchtleathan, was wife to Dathi, and mother of Fiachra Ealgach and Oilill Molt. 'Tis said that Ruad being buried in the hill called after her Mullach Rutæ, a *carn cloch* was raised over her, and that she died by the *breath*, or sentence” [recte birth] “of her Fiachra. Before, it was called Tealach na molt, because it was a place near which her sheep were usually

shorn” [recte slaughtered]. But that this is a garbling of the original text will at once be seen by the intelligent Irish scholar. The reader is referred to O’Flaherty’s *Ogygia*, part III. c. 87, and also to Keating’s *History of Ireland* (reign of Oilíoll Molt), in which the story is told in such plain Irish that the drift of it cannot be mistaken. Keating’s words are thus translated by Dr. John Lynch: “*Molli agnomine ideo affectus, quod matrem ejus Orachi filiam illum utero gestantem ovillæ carnis manducandæ cupido incesserit; adstiterat nimirum ovillam expetenti Fiala Eochi Siadi filia, tenuis fortuna femina, quæ infantulo statim ac è materno alvo emersit*

GENEALOGY OF THE HY-FIACHRACH OF THE MOY.

The mother of Fiachra Ealgach, the son of Dathi, was Ruadh, the daughter of Airtech Uichtleathan, who died at his birth. From her is named Mullach Ruadha^d, in Tir Fiachrach of the Moy, from her being buried in the top of that hill; and over her is the cairn of stones which is on the top of the hill. Tulach na molt was its name before that time, from the circumstance that the mother of Oilíoll Molt, while he was in her womb, took a desire for wether-mutton, and all the wethers procured for the queen were brought to this hill, whence it was called Tulach na molt [*i. e. the hill of the wethers*^e]. Tulach na Maoile [*i. e. the hill of Maol*] had been its previous name, from the rest which Maol-Flidhisi took upon it during the excursion of Tain Bo Flidhisi [while Fergus^f and Domhnall Dual-bhuidhe^g were engaged at single combat,—in which combat Domhnall was slain,—while the Gamanradii were in pursuit of the men of Erin here after the cattle spoil. Whence the hill was called Tulach na Maili; and it was from this Fiachra, the son

Molti agnomēn, quod ovem significat, indidit, utpote qui materni uteri claustris adhuc inclusus, ovinae carnis comedendae desideria flagrasse videbatur.” See also p. 22, note ^f.

^f *While Fergus*.—The passage here enclosed in brackets is supplied from the Book of Lecan. The story of Tain Bo Flidhisi is still preserved in a vellum MS. H. 2. 16. in the Library of Trinity College, Dublin. The Fergus here mentioned was the celebrated Fergus Mac Roigh, King of Ulster in the first century, who was de-throned by his successor Conchobhar Mac

Nessa.

^g *Domhnall Dual-bhuidhe*, i. e. Donnell of the yellow locks.—There are many wild legends still told of this Domhnall in Erris, one of which was published by Mr. Patrick Knight in his account of the Irish Highlands. The fort and grave of Domhnall Dual-bhuidhe are to this day pointed out at Dundonnell in the valley of Glen Castle, in Erris. He was one of the chiefs of the fierce and warlike Gamanradii of Erris, who were a tribe of the Firbolgs much celebrated in Irish historical stories.

ó'n Fiaçra rin mac Dathi a verap Tir Fiaçrach]. Cnoc na n-Druadh ainm ele do'n eulais rin, tre beir do draoidib Dhati nuç Epeann innte ag façail feara, gur ob ann do eairrighir-ríod do Dhati go n-geubad flaitear Epeann agur Alban 7ra.

A vér an rliocht ra gur ob í an Ruadh éadna mátair Oililla Muile mac Dati. 7ídeadh ver Doctur Cetin gur ob í Eéne inígean Orach, bean Dati, mátair Oililla Muile; agur céad bean Dati ono, .i. Fial, inígean Eacac, ó ráitear Cnuacán Fele; agur trear bean Dati tra, .i. Ruadh, inígean Airtig Uicé-leatuin, mic Fírcongá, mátair Fiaçrac Ealgaig, ó ráitear Tir Fiaçrac Muaidé.

Fiaçra Ealgaç, mac Dati ono, (ar uada Uí Fhiaçrac Muaidé) dá mac lair, .i. Amalgaib, dia d-tá Inir Amalgaib, for Loc Con, uair ar innte rugadh, agur Maolduib, dia d-ta Dún Maolduib ag laigaiç, in baile i rugadh agur ar h-oileadh e.

Amalgaib, mac Fiaçrac Ealgaig clann móir lair, .i. Cairpre, Leargur, Feargur, Eocaid, Feòlimid, Eundá, Eogan Fionb, Treá, Aongur

^b*Tir-Fiachrach*, now Tireragh, a barony in the north-west of the county of Sligo, on the east side of the Moy. This formed but a small portion of the country of the Hy-Fiachrach, which extended from the river Robe to the river of Drumcliff, below the town of Sligo. The name Hy-Fiachrach, i. e. *Nepotes Fiachri*, was derived from a different Fiachra, namely, from Fiachra, the father of King Dathi, and the grandfather of the Fiachra from whom the country or barony of Tireragh took its appellation.

ⁱ *Obtaining knowledge*.—In the Book of Lecan, fol. 80, b, the reading is ag fáo-

bail feara ocur eoluir, i. e. obtaining knowledge and information. It is to be regretted that the mode of obtaining their information is not mentioned. Perhaps the Druids obtained whatever knowledge they possessed of future events by observing the aspects of the planets and the indications of the heavens from the summit of this conspicuous hill? No other meaning can be reconciled to the situation of the place. The Rev. P. Mac Loughlin translates it, "It was called also Cnoc na n-Druadh, where Dathi *kept* his Druithi;" but this is not the correct translation of the original.

^j *Dr. Keating*.—Dr. Jeffrey Keating

son of Dathi, *that* Tir-Fiachrach^b was named]. Cnoc na n-Druadh was another name for this hill, because the Druids of Dathi, King of Erin were used to be on it obtaining knowledge¹, for it was here they predicted to Dathi that he would attain to the kingdom of Erin, Alba, &c.

This authority states that the same Ruadh was the mother of Oilioll Molt, the son of Dathi; but Doctor Keating¹ says that Eithne, the daughter of Orach, the [*second*] wife of Dathi, was the mother of Oilioll Molt; that the first wife of Dathi was Fial, daughter of Eochaidh, from whom Cruachan Fele is called; and that Dathi's third wife, Ruadh, the daughter of Airtheach Uichtleathan, son of Ferconga, was the mother of Fiachra Ealgach, from whom Tir Fiachrach of the Moy is named.

Fiachra Ealgach, the son of Dathi (from whom are the Hy-Fiachrach of the Moy), had two sons, namely, Amhalgaidh, from whom Inis Amhalgaidh, *an island* in Loch Con^k, is named, for it was on it he was born; and Maoldubh, from whom is called Dun Maoilduibh¹, at Iasgach [Easkey], the place where he was born and bred.

Amhalgaidh, the son of Fiachra Ealgach, had a large family, namely, Cairpre, Learghus, Fergus, Eochaidh, Fedhlimidh, Eunda, Eoghan Fionn, Trea, Aongus, a quo the Ui Aonghusa, Ronan, from whom are the

had finished his History of Ireland in the year 1629, as appears from memoranda in several of the copies, that is, sixteen years before Duaid Mac Firbis commenced the compilation of his larger work in Galway. The authority here referred to by our author is evidently the Book of Lecan, but that from which Keating drew his account of Dathi is unknown to the Editor.

^k *Inis Amhalgaidh, in Loch Con*, now, according to the oldest of the natives of the

district, corrupted to Inishlee, the present name of a small island in Lough Conn.—See notes farther on, and Book of Lecan, fol. 247, *a, a*, where it is stated that the island was a holy habitation, that is, had a church or chapel upon it.

¹ *Dun Maoilduibh, at Iasgach*.—This was the name of an earthen fort near the river Easkey, in the barony of Tireragh, and county of Sligo, about eleven miles and a half north north-east of Ballina.

Alongur a quo Uí Alongura, Rónan ó d-táir Uí Rónain, .i. Taoirigh Muirge b'ron, Cuilen ó d-táir Uí Cuilen Áta Pen.

Ar é Amalgaid, mac Fiacrach Ealgaigh, do ríne Carn Amalgaid do éocailt do cum aonair, agus ardoirneachtair, agus ar ann ro h-áblacaid Amalgaid, conad uad ainmníochtair an carn, .i. Carn Amalgaid. Conid ar an g-carn roin ríochtair gac fear gabair ríge do éloinn Fhiacrach Ealgaigh.

Amalgaid, mac Fiacrach Ealgaigh, mic Daí, da labram a f'pachnaircur, agus Amalgaid mac Daí ferin doneoc d'fagbaidríom i m-b'pachnair, noia n-fagam genealach aic Clann Fhirbairigh go ceachtar díob, amail éirífeam ríorana á leibair éloinne Fhirbairigh ferin.

GENEALACH CHLOINNE FHIRBHISIGH LEACAIN.

Dubaltach Oig, (.i. me fen, fear éagair agus ríghíobta an leabair rí rí in m-b'pachnair d'aoir Chioró, 1666), Pádraigh, Diarmuid, agus Séumair,

mec Giolla Iosa Mhoir,

mic an Dubaltach Mic Fhirbairigh,

mic Diarmada Caoic,

mic Seumoir Mic Fhirbairigh,

mic Domcaid Mhoir,

mic Fhirbairigh,

mic Seadain Oig,

mic Seadain Carrach,

mic Fhirbairigh,

mic

^m *Magh Bron*.—This was the name of a small district in the present barony of Tirawley.—See notes to the Topographical Poem of Giolla Iosa Mor Mac Firbis.

ⁿ *Ath fen*, i. e. the ford of the chariot, now unknown in Tirawley.

^o *Carn Amhlagaidh*.—For the situation of this carn see Note on the inauguration of O'Dowd, further on.

^p *Lecan*, now generally anglicised Lack-

an, on modern maps, though the name is better known to antiquaries by the form Lecan, in consequence of the book compiled by the Mac Firbis at the place having been so called by Irish writers. Lackan is a townland in the parish of Kilglass, barony of Tireragh, and county of Sligo, where are the ruins of a castle built by the family of Mac Firbis, who were hereditary historians to the O'Dowds.—

the Ui Ronain, i. e. the chiefs of Magh Bron^m, and Cuilen, from whom are the Ui Cuilen of Ath Fenⁿ.

It was Amhalgaidh, the son of Fiachra Ealgach, that raised Carn Amhalgaidh^o to serve as a place of fairs and great meetings; and it was in it Amhalgaidh himself was interred, and from him the Carn was called Carn Amhalgaidh, so that it is on that Carn every man of the race of Fiachra Ealgach, that assumes the chieftainship, is inaugurated.

From Amhalgaidh, the son of Fiachra Ealgach, the son of Dathi, of whom we have just spoken, or Amhalgaidh, the son of Dathi himself, whom we left in Bregia, I find no descendants except the Clann-Firbis, who descend from either of them, as I shall set down here from the Books of the Clann Firbis themselves.

PEDIGREE OF THE CLANN FIRBIS OF LECAN^p.

Dubhaltach Og (i. e. myself^a, the compiler and writer of this book in this year of the age of Christ, 1666), Patrick, Diarmaid, and James,

sons of Giolla Iosa Mor,	son of Ferbisigh,
son of Dubhaltach Mac Firbis,	son of John Og,
son of Diarmaid Caoch,	son of John Carrach,
son of James Mac Firbis,	son of Ferbisigh,
son of Donnchadh Mor,	son of Giolla na naomh,

son

See Notes farther on.

^a *Dubhaltach Og*, i. e. *myself*.—This pedigree is marked as defective in the smaller compilation made in 1666, though given consecutively, and as if perfect, in the larger work, compiled at Galway; and certain it is, that twenty-nine generations are not enough to answer the period of

time from Dubhaltach, who commenced this compilation in 1645, up to Dathi, who became monarch of Ireland in 405. One fact, however, must be acknowledged, that it appears from all the authentic Irish pedigrees that more than thirty years, the average standard laid down by Newton, must be allowed to each generation.

mic Giolla na naom,	mic Aongura,
mic Domnaill na rgoile,	mic Loclonn Loça Con,
mic Amlaoib,	mic Eoin,
mic Seacan,	mic Concabaib na conairte,
mic Donnaiù,	mic Euna,
mic Giolla Phadraig ('gar	mic Conaing,
h-oilead Tigeannán Oirig),	mic Muirneaduib,
mic Firdoirig, a quo clann Firdoirig,	mic Feargura,
mic Domnaill Oig,	mic Amlgaiù,
mic Domnaill Mhóir,	mic Daic.

Ní fearadair nár cóir Fiacra Ealgaich eoir Daic agur Amlgaiù, do bhoig gur ob é céo dútecur Cloinne Firdoirig an talam i rugad, agur a raibe Amlgaiù, mac Fiacraic Ealgais, mar a dubhamar ceana, agur mar a deapom ar na dútecuracuib.

mic Seagair, agur Ainriar, agur Tomar Oig,	
mec Tomair Chaim,	mic Seumair,
mic an Dubaltaig,	mic Diarmada Caoic.

Maircu,	
mac Seumair Oig,	mic Seumair.
mic an Dubaltaig,	

Fiteal díobaiù Torra díobaiù Maolmuire díobaiù eirí mec ba iine ag an Dubaltaic, mac Seumair.

hrian Dorca díobaiù raoi reancuide, dara mac Seumair, mic Diarmada Chaoic.

Fearfeara, Aoù, Maolmuire, agur Diarmuib,	
mec Cioetruaid Oig, d'ar dearb-	duide,
raicair Fearbairig,	mec Cioetruaid,
mic Firdara, d'ar dearbdráirte	mic Diarmada Chaoic,
Diarmaid Caoic, agur Aoù	mic Donnada Mhoir.

Seamur

son of Domhnall of the school,	son of Aongus,
son of Amhlaoibh,	son of Lochlainn of Loch Con,
son of John,	son of John,
son of Donnchadh,	son of Conchobhar na Conairte
son of Giolla Phadraig, by whom	[i. e. of the pack of hounds],
St. Tighearnan of Errew was	son of Enna,
fostered,	son of Conaing,
son of Ferbisigh, a quo Clann	son of Muireadhach,
Firbisigh,	son of Feargus,
son of Domhnall Og,	son of Amhalgaidh,
son of Domhnall Mor,	son of Dathi.

I know not but Fiachra Ealgach should come between Dathi and Amhalgaidh, because the land in which Amhalgaidh, the son of Fiachra Ealgach was born, and in which he dwelt, was the first patrimonial inheritance of the Clann Firbis, as we have already mentioned, and as we shall mention again when treating of the inheritors.

Gregory, Andreas, and Thomas Og,	
sons of Thomas Cam,	son of James,
son of Dubhaltach,	son of Diarmaid Caoch.
Mathew,	
son of James Og,	son of James.
son of Dubhaltach,	

Fitheal, Torna, and Maolmuire, who all died without issue, were the three elder sons of Dubhaltach, son of James.

Brian Dorcha, a learned historian, who died without issue, was the second of James, the son of Diarmaid Caoch.

Fearfeasa, Aodh, Maolmuire, and Diarmaid,	
sons of Ciothruadh Og, who had	Aodh Buidhe,
a brother Fear-bisigh,	son of Ciothruadh,
son of Fearfeasa, whose brothers	son of Diarmaid Caoch,
were Diarmaid, Caoch, and	son of Donnchadh Mor.

James

Seamur agur Tóirna,
 mec an Fhirbórcá, mic Diarmada Cnoic,
 mic Tóirna dearbhrátair Cu- mic Donnáid Mhóir.
 conn * * *,

SLIOCHT UILLIAM, MIC DONNCHADH MHOIR MHIC FIRDHISEIGH.

Donnád, Maolmuire, agur Lúgaid,
 tri mec Seanáin (dearbhrátair mec Seáin Oig (d'ár dearb-
 Fhorandain), raíteir Giolla Iora, agur
 mec Fheircéirne (d'ár dearb- Donnád Oig díobairg),
 raíteir Maolmuire, agur mec Uilliam,
 Fearbairg), mic Donnáid Móir.

Fionduine Oig,
 mac Fionduine, mic Uilliam,
 mic Giolla Iora, mic Dunncuid Móir.

Uilliam Oig, no deag, agur Seáin Oig,
 mec Seáin Oig, mic Uilliam,
 mic Giolla Iora, mic Donnáda Móir.

Donnád Oig díobairg,
 mac Uilliam, mic Donnáid Mhóir.

Órian Dorca, Seáin Oig, Seumur, Aod, Taóg Ruad, Eumonn
 buide, agur Maolmuire,
 mec Aodá Oig, mic Donnáda,
 mic Cioéruaid, mic Giolla Iora Mhóir, baol go
 mic Taóg Ruad, bliadana a rgoirgeaict,
 mic Fírbairg, mic Fírbairg,
 mic Tomair Chaim, mic Muirceairtaig,
 mic Giolla Iora Móir, mic Seáin,

[A deircear

James and Torna,	
sons of Feardorcha,	son of Diarmaid Caoch,
son of Torna, brother of Cu-	son of Donnchadh Mor.
chon ^a , * * *	

THE RACE OF WILLIAM, SON OF DONNCHADH MOR MAC FIRBIS.

Donnchadh, Maolmuire, and Lughaidh,	
three sons of Geanann, whose bro-	son of John Og (whose brother
ther was Forannan,	was Giolla Iosa and Donnchadh
son of Fercertne, whose brothers	Og, who died issueless),
were Maolmuire and Fearbi-	son of William,
sigh,	son of Donnchadh Mor.

Fionduine Og,	
son of Fionduine,	son of William,
son of Giolla Iosa,	son of Donnchadh Mor.

William Og, or Beg, and John Og,	
sons of John Og,	son of William,
son of Giolla Iosa,	son of Donnchadh Mor.

Donnchadh Og, who died without issue,	
son of William,	son of Donnchadh Mor.

Brian Dorcha, John Og, James, Aodh, Tadhg Ruadh, Edmond	
Buidhe, and Maolmuire,	
sons of Aodh Og,	son of Donnchadh,
son of Ciothruadh,	son of Giolla Iosa Mor, who was
son of Tadhg Ruadh,	sixty years teaching school,
son of Fearbisigh,	son of Fearbisigh,
son of Thomas Cam,	son of Muircheartach,
son of Giolla Iosa Mor,	son of John.

[It

^a *Cuchonn*.—The original is here effaced, but there is very little wanting.
IRISH ARCH. SOC. 12. P

[Α δεπτεαρ γυρ ιονανν ρλοινεαδ δο Chloinn Fhionbairig Leacain Mic Fhionbairig, in-lb Fiaçpac ip Amalgaid, agur do'n dá cinead ápo-nóraiḡ ele ρι, .i. Foirbairig Opoiminoir in n-Albain, agur in ḡac áit ele α b-fulib 'na n-Albanaca, ip na epí píoḡactaib ρι, agur Cpuibairig α n-allana i b-Fine Ḥhall, ap n-bul, tpe tapm-clannuḡad agur eaçtapaḡad na n-Ḥaoibiol ó'n ḡ-epíc ḡo céle, i n-ḡallbaçt, mur do cuadar cineada iomda ele, do pep na b-ḡad do tapnḡair ḡo m-bedip Ḥaill na n-Ḥaoibeaala, agur Ḥaoibil na n-Ḥalla].

Maoloub, mac Fiaçrach Ealḡairḡ, epí mec ler, .i. Cobtaç, Temean, agur Tiobpaide.

Cobtaç, mac Maoiloub, aon mac laip, .i. Maolubín ó b-táib Uí Maoilbuin, co n-a ḡ-coibneapaib, .i. Mec Ḥiolla na n-eaç, agur Mec Ḥiolla duib na Corcaḡe, agur Uí Duibḡcuile, agur Uí Ailmec.

Temín, mac Maoiloub, o b-táib Clanna Temín, .i. Uí Muirḡeara, agur Uí Maonairḡ, agur Mec Ḥiolla paḡairḡ, Uí Aoba, agur Uí Donncaḡa.

Caomán agur Dúbba,

mec Connairḡ,

mec Duinncaḡa,

mec Caḡair,

mec Ailella,

mec Duncāḡa,

mec Tiobpaide,

mec Maoiloub.

ba

^a *It is said, &c.*—This passage enclosed in brackets is taken from our author's smaller work compiled in 1666.

^b *O'Maoilduin*, now Muldoon, but the name, though common in other parts of Ireland, does not exist in this district.

^c *Mac Gilla na n-each*, now obsolete. *Giolla na n-each* means *juvenis equorum*.

^d *Mac Giolla duibh*, now Gilduff, and cor-

ruptly Kilduff. It is strange that modern usage has almost invariably changed the *Gilla* of the original Irish into *Kill* in the Anglicised form, as *Kilroy* for *Gilroy*, *Kilkenny* for *Gilkenny* or *Giolla Cainnigh*.

^e *O'Dubhsuile*, now obsolete.

^f *O'h-Ailmhec*, now obsolete. It was anglicised *Helwick*.

^g *O'Muirḡeasa*, now *Morissy*, without

[It is said^a the Clann Firis of Lecan Mac Firis in Hy-Fiachrach and Hy-Amhalgaidh, have the same surname with the two aristocratic families of Forbes of Drominoir, in Scotland, or wherever else they are to be found as Scotchmen, in the three kingdoms; as also with the Cruces, formerly of Fingal, having, in the course of the intermixtures and migrations of the Gaels from one country to another, become English, as many other tribes have become, according to the prophets, who foretold that the Galls would be Gaels, and the Gaels would be Galls].

Maoldubh, son of Fiachra Ealgach, had three sons, namely, Cobhthach, Temen, and Tiobraide.

Cobhthach, the son of Maoldubh, had one son, namely, Maolduin, from whom are descended the *families of O'Maolduin*^r, with their correlatives, namely, Mac Giolla na n-each^a, Mac Giolla-duibh^r of Corcach, O'Duibhscuile^u, and O'h-Almhec^r.

From Temen, the son of Maoldubh, are descended the Clanna Temin, namely, the *families of O'Muirgheasa*^r, O'Maonaigh^r, Mac Giolla riabhach^r, O'h-Aodha^r, and O'Donnchadha^a.

Caomhan and Dubhda,
sons of Conmhach,
son of Donn catha,
son of Cathal,
son of Ailell,

son of Dunchadh,
son of Tiobraide,
son of Maoldubh.

Caomhan

the prefix O'.

^a *O'Maonaigh*, now Meeny. This name is still found in Tireragh. In other parts of Ireland it is anglicised Mainy, and sometimes Mooney.

^r *Mac Giolla riabhach*, now Mac Gilrea, and in the north of Ireland barbarously rendered Mac Ilrea, in imitation of the Scotch,

who write Mac Ilwane for Mac Giolla bhain, Mac Ilduff for Mac Giolla duibh, &c.

^r *O'h-Aodha*.—This name is still in Tireragh, and always anglicised Hughes. The same name, but borne by a family of a different race, is rendered O'Hea and Hayes in Munster.

^a *O'Donnchadha*.—This name is now ob-

ba fine Caomán iná Dúbba, gur páoil Caomán go mað leir pen an planteap; conap deonaiḡ Dia do rioḡa for a rlioct; go n-deapnrað bail im ceano na riḡe, .i. a rioḡa tuaite dia dúctap, aḡur leatḡuala riḡ Ua b-ḡiactac aḡ fear ionaid Chaomáin do ḡnear. A eac aḡur a eapnað an tan riḡriḡeap, aḡur teaact fo tpi 'na timceall iar n-a riḡað. Aḡur ap í tuaḡ riḡ iona riḡain, .i. ó Thuaim ba boðap go ḡleóir. Eac, eapnað, aḡur eudað Uí Chaomáin do Mhac ḡhriḡiriḡ, an lá ḡoirḡeap Mac ḡhriḡiriḡ ainm riḡeapna d' O'Dubba.

Caomán umorpo, ó d-taid Uí Caomáin, aon mac leir; .i. Catal.
GENEALACH

solete in Lower Connaught. In Munster it is anglicised O'Donoghoe, in Ulster Donaghy, but the families whose names are so anglicised are of a different race from that in question.

^b *The following agreement.*—Similar privileges were ceded by the O'Conors of Connaught to the O'Finaghtys of Dunamon, chiefs of Clann Conway, in acknowledgment of the seniority of the latter. These privileges are described by our author in the Pedigree of O'Finaghty, and his words are here translated for the satisfaction of the reader :

"Connmhach" [the ancestor of O'Finaghty] "was the eldest son of Muireadhach" [the ancestor of the royal family of Connaught], "and in consequence of this seniority, the descendants of Connmhach [though inferior in power] are entitled to great privileges from the descendants of the other sons of Muireadhach, viz., to drink the first cup at every royal feast

and banquet; and all the descendants of the other sons must rise up before the representative of Connmhach. O'Finaghty was the royal chieftain of Clann Connmhagh, and had, before the English invasion, forty-eight ballys" [i. e. large ancient Irish townlands] "lying on both sides of the River Suck; but the Burkes drove him from his patrimonial inheritance, and there lives not at the time of writing this book" [1645] "any of the family of O'Finaghty more distinguished than the good and pious priest James O'Finaghty, whose brothers are William and Redmond."

^c *Caomhan's representative*, i. e. the chief of the O'Caomhain family. This name is still numerous in Lower Connaught, but has been most generally, though corruptly, anglicised Cavanagh, to assimilate it with that of the more celebrated family of Leinster. In some parts of Lower Connaught, however, it is correctly anglicised Keewan and Kevan. This family sunk into compa-

Caomhan was older than Dubhda, and Caomhan thought that the chieftainship was his own; but God did not permit that kings should be of his posterity; and they came to the following agreement^b about the chieftainship, namely, that Caomhan's^c representative should always possess his choice territory in the principality, and the privilege of being at the *right* side of the king of Hy-Fiachrach; that he should get the king's steed and battle-dress at the time of his inauguration, and should walk round him thrice after his instalment. And the territory he selected was *that extending* from Tuaim da bhodhar^d to the *River* Gleoir^e. The steed, battle-dress, and raiment of O'Caomhain to be given to Mac Firis, the day that Mac Firis shall give the name of lord to O'Dubhda.

Caomhan, from whom the *family of* O'Caomhain is descended, had one son, namely, Cathal.

PEDIGREE

rative insignificance in the fourteenth century, and though they seem to have held their little principality till the beginning of the fifteenth century, the Irish annalists have preserved but few notices of them. Under the year 1294 the Four Masters enter the death of Diarmaid O'Caomhain, and under 1306 that of David O'Caomhain, who was lord of the territory extending from Tuaim da bhodhar to the River Gleoir. But shortly after this period they disappear from history, and they are all at present reduced to obscurity and indigence.

^d *Tuaim da bhodhar*, i. e. the tumulus of the two deaf persons. This place is still well known, and the name is anglicised Toomore. It is the name of a townland

and parish in the north of the barony of Gallen and county of Mayo, containing the little town of Beal casa, now called in English Foxford.

^e *Gleoir*. — According to a local antiquary, who was a very good Irish scholar and a living library of Irish traditions, the late Shane Bane Tympany (Mac Cín Tiompánaigh), this was the ancient name of a small river, now commonly called the river of Coillin, or Liathmhuine, anglicè Leaffony, which rises to the south of the townland of Townalaghta in the parish of Kilglass, barony of Tireragh and county of Sligo, and flowing nearly in a northern direction, empties itself into the bay of Killala at Poll an chaonaigh, anglicè Pol-lacheeny, in the townland of Cabrakeel.

GENEALACH UI CHAOMHAIN.

Daibíð, agur Domnall,

mec Aóð,

míc Daibíð,

míc Tomair,

míc Giolla na naom,

míc Domnaill,

míc Daibíð,

míc Diarmada,

míc Tomair,

míc Domnaill,

míc Tomair,

míc Giolla na naem,

míc Diarmada,

míc Domnaill,

míc Cattaíl,

míc Giolla na naem,

míc Diarmada,

míc Cattaíl,

míc Caomhain, ó u-táð Uí Cao-
máin,

míc Connmaig,

míc Doinncaeta, 7c.

Tomaltac, Maghur, Donncað, Aóð Fionn, agur Seaan, cóig
mec Daibíð, míc Aóða pín.

Tomar Oð, Tomaltac, Níall, agur Cattaíl Riabac, clann
Tomair Mhóir, míc Daibíð, míc Giolla na naom Moir annpín.

UI DUBHDA SIOSANA.

Dubda (mac Connmaig), mac lep .i. Ceallac, atair Aóð, atair
Maolruanaid, atair Maoleaclonn, atair Nell, atair Thaitlig,
agur

^f *David, son of Aodh.*—This David being the twenty-seventh in descent from Dathi, the last pagan monarch of Ireland, seems to have flourished about the year 1447, for the celebrated Maolruanaidh O'Dowd, chief of his name, who was the same number of generations removed from King Dathi, died in that year. It is evi-

dent that the O'Caomhains, or Kavanaghs of Lower Connaught, sunk into insignificance about this period, as Mac Firbis carries down their pedigree no later. The last of this family mentioned in the Annals of the Four Masters is David O'Caomhain, who is styled lord of that tract of country extending from Tuaim da bhodhar to the

PEDIGREE OF O'CAOMHAIN.

David ^f and Domhnall,	
sons of Aodh,	son of Diarmaid,
son of David,	son of Domhnall,
son of Thomas,	son of Cathal,
son of Giolla na naomh,	son of Giolla na naomh,
son of Domhnall,	son of Diarmaid,
son of David,	son of Cathal.
son of Diarmaid,	son of Caomhan, from whom <i>the</i>
son of Thomas,	<i>family of O'Caomhain,</i>
son of Domhnall,	son of Connmhach,
son of Thomas,	son of Donnecatha.
son of Giolla na naomh,	

Tomaltach, Maghnus, Donnchadh, Aodh Fionn, and John, five sons of David, son of that Aodh.

Thomas Og, Tomaltach, Niall, and Cathal Riabhach, were the sons of Thomas Mor, son of David, son of Giolla na naomh Mor.

THE FAMILY OF O'DUBHDA* DOWN HERE.

Dubhda (son of Connmhach) had a son, Ceallach, the father of Aodh, who was father of Maolruanaidh, the father of Maoileachlainn, father

River Gleoir, and who was slain in the year 1306. He was evidently the David given in the above line of pedigree as the twelfth in descent from Caomhan.

* *O'Dubhda*.—This name is variously anglicised, but the form O'Dowd seems to be that most generally adopted, though the present head of the name, Tadhg or Thaddæus O'Dubhda of Muine Chonallain,

now corruptly Bunnyconnellan, always writes it O'Dowda, following the authority of the more ancient of his family deeds, in which the name is generally so written. In the old English Inquisitions, and other documents relating to Lower Connaught, it is generally written O'Dowde, though the native Irish pronunciation is O'Dooda (the *d*'s pronounced thick as in the Spanish and

agur Nell, o d-táid Clann Nell; agur ar iad rin po gab poblámur ar dúdhchur muinire Caomáin, gur marbhad a céle uime, .i. Daibid agur Domnall O'Caomáin do marbhad do Niall, mac Aoda, mic Nell; agur Niall do marbhad do Mhuirceartac Fionn O'Caomáin i n-dioḡal a braitreac, gur gab pen an tairioḡac.

Taitleac umorpo, an dapa mac Nell, mic Maoileacloinn, ar uada an rioḡraib, .i. Muirceartac (mac Aoda, mic Taitlig), aṡair Aoda, aṡair Thaitlig, dhiuain Dheḡ (o d-táid Clann Taitlig Oig), agur Mhuirceartaig.

Maolruanaid (mac Aoda, mic Cealluiḡ, mic Dubda), dá mac lair, .i. Domnall dia rabadar Clann n-Domnall Loṡa Con. Ar é an Domnall rin do tuit le h-Uib ḡaibteacáin ag deapnaig Domnall, i Muig Eleḡ.

Maoileacloinn umorpo, an dapa mac Maolruanaid, ar uada an rioḡraib.

Domnall mac Maolruanaid dno, ar dia Chloinn Caṡbarr, aṡair

Italian languages). Connell Mageoghegan in his translation of the Annals of Clonmacnoise, made in 1627, always renders this name O'Dowdie, which is not very far from the Irish pronunciation. In the south of Ireland, where there are many of this name, and probably of this race, it is anglicised among the peasantry Doody, and in the county of Derry, where there are several of the name, but of a different race, it is anglicised Duddy or Duddie, a form not to be approved of.

^b *Who assumed the chieftainship himself.*
—No account of these slaughters, mutually committed by these families on each other, is to be found in the Annals of the

Four Masters, nor does Duald Mac Firbis himself give any date for them in his Annals of the O'Dowd family. If we calculate by generations we must come to the conclusion that these occurrences took place before the English invasion, for Niall, son of Aodh, son of Niall O'Dowd, who slew David and Domhnall O'Caomhain, was the seventeenth in descent from King Dathi, and Taithleach O'Dowd, lord of Tireragh and Tirawley, who was slain in the year 1192, was the nineteenth generation from the same monarch, so that Niall would appear to have lived about sixty years earlier.

ⁱ *Maolruanaidh, son of Aodh.*—The death

father of Niall, father of Taithleach and Niall, from whom the Clann Neill; and these were they who usurped the inheritance of the O'Caomhains, on account of which mutual slaughters were committed, viz., David and Domhnall O'Caomhain were slain by Niall, son of Aodh, son of Niall; and Niall himself was slain to avenge his brother by Muircheartach Fionn O'Caomhain, who assumed the chieftainship himself^a.

From Taithleach, the second son of Niall, son of Maoileachlainn, the chiefs of the *O'Dowd family* are descended, viz., Muircheartach (son of Aodh, son of Taithleach), father of Aodh, father of Taithleach, of Brian Dearth (from whom are the Clann Taithligh Oig), and of Muircheartach.

Maolruanaidhⁱ (son of Aodh, son of Ceallach, son of Dubhda) had two sons, namely, Domhnall, from whom sprang the Clann Domhnaill, of Loch Con. This is the Domhnall^j who was slain by the O'Gaibhtheachains [*O'Gaughans*], at Bearna Domhnaill, in Magh Eleog^k.

From Maoileachlainn^l, the second son of Maolruanaidh, the chiefs are descended.

Of the sons of Domhnall, son of Maolruanaidh, was Cathbharr,
the

of this Maolruanaidh is entered in the Annals of the Four Masters at the year 1005, where he is called lord of Hy-Fiachrach Muirisce. His father, Aodh, who is called by Mac Firbis, in his Annals of the O'Dowd family, King of North Connaught, died in the year 983.

ⁱ *This is the Domhnall.* — The date of this occurrence is not given in the Annals of the Four Masters; but, as Domhnall's father died in 1005, we may suppose it to

have taken place a few years later.

^k *Magh Eleog* is the ancient name of the level part of the parish of Crossmolina, in the barony of Tirawley, through which the River Deel flows.

^l *Maoileachlainn.* — This Maoileachlainn, Melaglin, or Malachy, from whom almost all the subsequent chiefs of the O'Dowd family descended, died in 1005, the same year in which his father also died.

αταρ Ομοναλλ Φινό, (νιοβαίγ αττ ινջεαν), αγυρ Αοδα, αταρ
 Θατλιγ (νιγ Υα ν-Αμαλγαο αγυρ Υα ν-Φιαρπα), αγυρ αν
 Χορναμταγ Μχοιρ, αρ ε πεαρ κομλαινν σεο ταινιγ πα δερεαδ ε,
 αγυρ Ο'Γλοινιν δο μαρβ ε ιμ σεανν κυλεν con, ι β-πιλ, 'να τινγ φέν
 ι ν-Ινιρ Cua.

Τατλεαδ, mac Αοδα, να mac ιερ, .ι. Αοδ αγυρ Αμλαοιβ.

Δοννκαδ Μόρ, mac Αοδα (mic Τατλιγ, mic Αοδα, mic Μυιρ-
 σεαρταγ, mic Αοδα, mic Τατλιγ, mic Νελ), τρι mec ιερ, .ι. δριαν,
 Μαοιρπαναο, αγυρ Μυιρσεαρταδ, ο υ-ταο Clann Concaδαιρ.

Μαοιρπα νιδ, mac Δοννκυο Μχοιρ, να mac ιερ, .ι. Τατλεαδ
 αγυρ αν Κορναμυιγ, .ι. Αιρσιδεοδαιν Tuama να Γhualann, αγυρ
 αδδαρ αιρδ-Ερρυις.

Τατλεαδ, mac Μαοιρπαναο, τρι mec ιερ, .ι. δριαν Ο'Δυβδα, ρι
 Υα β-Φιαρπα αγυρ Υα ν-Αμαλγαο, αγυρ Δοννκαδ Μόρ Ο'Δυβδα,
 νιογδαμνα

^m *Domhnall Fionn*. — The death of Domhnall Fionn O'Dowd, lord of Hy-Amhalgadh, now Tirawley, is entered in the Annals of the Four Masters at the year 1126, but whether he was this Domhnall Fionn or not, cannot be clearly determined, as the name of his father is omitted by the annalists, a thing very unusual with them. It is, however, highly probable that they were the same.

ⁿ *Taithleach, King of Hy-Amhalgaidh and Hy-Fiachrach*, i. e. of Tirawley and Tireragh. He was slain in the year 1128, in a battle fought at Ardee, between the cavalries of O'Connor, King of Connaught, and Mac Loughlin, Prince of Aileach.

^o *Cosnamhach Mor*. — The murder of this great warrior is mentioned in the

Annals of the Four Masters at the year 1162, but the *trifling cause* is not added. The fighter of an hundred men is a usual expression in Irish stories to denote a man of extraordinary puissance and valour.

^p *Inis Cua*, now Inishcoe, a townland extending into Lough Con, in the south-east of the parish of Crossmolina, in the barony of Tirawley.

^q *Donnchadh Mor, son of Aodh, &c.* — He was a very famous chieftain of the O'Dowds, and flourished about the years 1207, 1213. In 1213, according to our author, in his brief Annals of the O'Dowd family, he sailed with a fleet of fifty-six ships from the Hebrides into Cuan Modh, now Clew Bay, landed on the Island of Inis Raithin there, and compelled Cathal Croibhdhearg,

the father of Domhnall^m Fionn (who had no issue except a daughter), and of Aodh, father of Taithleach^a (King of Hy-Amhalgaidh and Hy-Fiachrach), and of Cosnamhach Mor^o, the only fighter of an hundred that came in latter times, and who was treacherously slain by O'Gloinin in his own house at Inis Cua^p, on account of *a dispute about* a greyhound whelp.

Taithleach, son of Aodh, had two sons, namely, Aodh and Amh-laoibh.

Donnchadh Mor^a, son of Aodh (son of Taithleach, son of Aodh, son of Muircheartach, son of Aodh, son of Taithleach, son of Niall), had three sons, namely, Brian^r, Maolruanaidh^s, and Muircheartach^t, from whom the Clann Conchobhar are sprung.

Maolruanaidh, the son of Donnchadh Mor, had two sons, namely, Taithleach^u and Cosnamhuigh, i. e. Archdeacon of Tuaim da ghualann, and presumptive Archbishop.

Taithleach, the son of Maolruanaidh, had three sons, namely, Brian O'Dubhda^v, King of the Hy-Fiachrach and the Hy-Amhalgaidh, and

or Charles the Redhanded O'Connor, King of Connaught, to give him his own principality free of tribute.

^r *Brian*.—This Brian was chief of the territories Tireragh, Tirawley, and Erris, and was killed in the year 1242, while on his pilgrimage to the abbey of Boyle.

^s *Maolruanaidh*.—He was slain by the O'Conors in the year 1238, according to the Annals of the Four Masters.

^t *Muircheartach*.—He seems to have succeeded his brother Brian in the chieftainship, for in the year 1246 he is called the O'Dowd in the Annals of the Four Masters. He was slain in the year 1248

by the son of Felim O'Connor, under which year he is called by the Four Masters lord of that tract of country extending from Cill Dairbhile [now St. Dervila's church, in the west of Erris] to the strand of Traigh Eothaile.

^u *Taithleach*.—This was the celebrated Taithleach O'Dowd, surnamed Muaidhe, i. e. of the Moy, who was slain by Adam Cusack, on the strand of Traigh Eothuille, in the year 1282.

^v *Brian O'Dubhda*.—He was the celebrated chief of the O'Dowds, generally called Sean Bhrian, i. e. Old Brian, in the pedigrees. He was chief of the O'Dowds

ριγοδάννα Ο Ὑ-Ριάρα: Σλάινε, ἰνγεαν Μhec Μαgnυρα Τhιpe
 Τυαταῖλ, α ματαῖρ αραον. Μαοleacloinn Capραῖ, an mac ele,
 αταῖρ Concaβαῖρ, αταῖρ Μυιρceαρταιḡ, αταῖρ Ohiapmaba ayur
 Maoilnyanaῖδ.

Donnéad Mór mac Tairéilg Uí Dubhá, epí mec lep, .i. Donn-
éad Og, ádbar níg Ua b-Flácpac, Concábar, agur Uilliam, eppoc
Cille h-Alaib. Ingean Uí Fhlóinn macáir na mac roin Donnéad
Mhoir.

Concaban, mac Donnchaid, diobaidh ríde, aet incheana.

Uilliam Eppuc dá mac leir, .i. an Cornamairg, do marbhad ar
maíom na Trágha, agus Uilliam Oge; doibaid iad arson.

Donncad Oḡ, mac Donncad Mhóir, clann mór lair, .i. Muir-
ceartaí Cléireac, aóbar níg agus erpuic, ar eneac agus ar eng-
nam.

in the year 1316, when he fought at the famous battle of Athenry, and died in the year 1354. Our author says, in his short Annals of the O'Dowd family, that this Brian was chief of his name for eighty-four years, but this cannot be considered true, as his father was living in the year 1282, and Conchobhar Conallach O'Dowd, who died in 1291, was lord of Tireragh, according to the annalists.

* *Donnchadh Mor O'Dubhda.*—He was the ancestor of a powerful sept of the O'Dowds seated in the territory of Cuil Cearnadha (Coolcarney), and called the Clann Donnchadha O'Dowd. He died in the year 1337, under which year he is styled by the Four Masters Tanist of Tireragh. For some curious account of the territory of this sept, inserted in a more modern hand on fol. 85, p. 6, of the Book of Lecan, see

the Addenda to this volume. In this account Donnchadh Mor, the ancestor of the Clann Donnchadha O'Dowd, is said to have been the elder brother of Taithealach Muaidhe, who deprived him of his birth-right, but this genealogy being in opposition to the original text of the Book of Lecan, and to the pedigree compiled by our author, cannot be considered authentic; but the whole notice is well worth preserving for the topography and historical facts which it preserves.

* *Mac Maghnus, of Tir Tuathail*.—This Mac Manus was a branch of the Maguires of Fermanagh, and resided at Seanad Mic Maghnusa, now called Ballymacmanus and Bellisle, an island in the upper Lough Erne, to the south of Enniskillen.

¹ *Maileachlainn Carrach*, i.e. Melaghlin, or Malachy the Scabbed, was slain in the

and Donnchadh Mor O'Dubhda⁷, heir apparent of Hy-Fiachrach. Slaine, daughter of Mac Maghnus, of Tir Tuathail⁸, was the mother of both. Maoileachlainn Carrach⁹, the other son, was the father of Conchobhar, who was father of Muircheartach, the father of Diarmaid and Maolruanaidh.

Donnchadh Mor, son of Taithleach O'Dubhda, had three sons, namely, Donnchadh Og², heir apparent to the chieftainship of the Hy-Fiachrach; Conchobhar,³ and William, Bishop of Killala⁴. The daughter of O'Flynn was the mother of these sons of Donnchadh Mor.

Conchobhar, the son of Donnchadh, left no issue, except daughters.

William, the bishop, had two sons, namely, Cosnamhaigh⁵, who was slain in the battle of the Strand, and William Og; both died without issue.

Donnchadh Og, the son of Donnchadh Mor, had a large family, namely, Muircheartach Cleireach⁶, designated king and bishop, for his

famous battle of Athenry, in the year 1316.

² *Donnchadh Og*, i. e. Donogh, or Denis Junior. He was head of the Clann Donnchadha, or Clandonogh O'Dowd, and died in the year 1384.

³ *Conchobhar*, i. e. Conor, or Cornelius. He was slain in the year 1363 by his own people.

⁴ *William, Bishop of Killala*.—He died in the year 1350, and the notice of his death is entered in the Annals of the Four Masters:—"A. D. 1350. William O'Dowd, Bishop of Killala, founder of many churches and sanctuaries, a pious, charitable, and humane prelate, died."

⁵ *Cosnamhaigh*, more correctly Cosnamhasch. He was slain in the year 1367, in a battle fought on the famous strand of Traigh Eothuile, between two chieftains of the house of O'Conor. Traigh Eothuile, which is a very famous locality in Irish history, is a large and beautiful strand at the mouth of the Bellasadare river, in the barony of Tireragh, and county of Sligo. It is about one mile square, extending from the strand road to Beltraw.

⁶ *Muircheartach Cleireach*.—He became chief of the sept called Clann Donnchadha, or Clandonogh O'Dowd, on the death of his father in 1384, and died in 1402. His death is thus noticed in the Annals of the

nam. Taitéleac, Aod an Chopoinn, Lochlainn, brian Clepeac, agur Cormac. Onóra, inígean Rícin báireud, a mátaí rín uile.

Muirceartaic, mac Donnúid, clann mop le r, .i. Domnall, Catal, Concabair agur an Cornamairg. Dearbail, inígean Flaité-beartaig Uí Ruairc, a mátaí rín; agur Donncaó mac ele do, Dearbail, inígean Taitéig Mic Donnchada, a mátaí rín. Uilliam mac Muirceartaig mac ele do.

brian, mac Taitéig Uí Dhubda, clann mop le r, .i. Domnall Clépeac, rí Ua b-Fiacraic, Maolruanaid, Maígnur Clépeac. báireud, inígean Domnall Uí Concabair a mátaí rín. Mec ele do Diarmuid agur Aod, inígean Mic Roibín Laitléir a mátaí rín; an Cornamairg, Niall, Taitéleac, agur brian Oig, Onóra, inígean Mic bhaircín báire do, a mátaí rín.

Maolruanaid, mac brian, aon mac lair, .i. Taitéleac, acaí rín Uilliam, agur brian.

Aod, mac brian, clann maí le r, .i. brian, Diarmaid, (Meaó b inígean

Four Masters :—"A. D. 1402. Muirheartach, son of Donnchadh O'Dowd, a noble and hospitable man, died and was interred at Ard na riagh [Ardnarea abbey]."

^e *Taitheleach*.—He died in the year 1404, according to the Annals of the Four Masters.

^f *Conchobhar*.—He was chief of the Clandonogh O'Dowd, and was slain in the year 1438, under which the Four Masters have the following notice of him :—"A. D. 1438. Conchobhar, the son of Muirheartach O'Dowd, lord of the Clann Donnchadha [Clandonogh] O'Dowd, was treacherously slain by his own kinsmen, namely, Taichleach, the son of Cormac,

who was the son of Donnchadh O'Dowd Ruaidhri, the son of Taichleach, and Lochlainn, the grandson of Lochlainn O'Dowd, assisted by Henry Barrett, and three of his sons."

^g *Donnchadh*.—He was living in 1439, at which year the Four Masters have the following notice of his doings :—"A. D. 1439. Domhnall, son of Ruaidhri, who was son of Taichleach O'Dowd, was deprived of his eyes, and afterwards hanged by Donnchadh, son of Muirheartach O'Dowd; and Cathal, son of Cormac O'Dowd, and his son, were killed by Tadhg Ruadh, the son of Muirheartach O'Dowd, at the instigation of the same

his hospitality and valour; Taithleach^c; Aodh, of Corran; Lochlainn; Brian Cleireach, and Cormac. Honora, the daughter of Rickin Barrett, was the mother of all these.

Muirheartach, the son of Donnchadh Mor, had a large family, namely, Domhnall, Cathal, Conchobhar^f, and Cosnamhaigh, whose mother was Dearbhail, the daughter of Flaithbheartach O'Rourke; and Donnchadh^g, another son of his, whose mother was Dearbhail, the daughter of Tadhg Mac Donogh. William Mac Muirheartaigh was another son of his.

Brian, the son of Taithleach^h O'Dowd, had a large family, namely, Domhnall Cleireachⁱ, King of Hy-Fiachrach; Maolruanaidh^j; Maghnus Cleireach^k. Barrdubh, the daughter of Domhnall O'Conor, was their mother. His other sons were Diarmaid and Aodh, whose mother was the daughter of Roibin Laighleis [*Robin Lawless*], and Cosnamhaigh, Niall, Taithleach, and Brian Og^l, whose mother was Honora, the daughter of Mac Wattin Barrett.

Maolruanaidh, son of Brian, had one son, namely, Taithleach, father of William and of Brian.

Aodh, son of Brian, had good sons, namely, Brian and Diarmaid
(Meadhbh

Donnchadh."

The names of some of these worthies are not to be found in the pedigrees; so that copious as these pedigrees appear to be, they are, nevertheless, clearly imperfect.

^h *Brian, the son of Taithleach.*—This is the celebrated Sen Bhrian, who died in 1354, after having been more than fifty years chief of his name. After completing the genealogy of the Clann Donnchadha, our author here returns to that of the chiefs.

ⁱ *Domhnall Cleireach.*—He succeeded his father in the chieftainship in 1354, and died in 1380.

^j *Maolruanaidh.*—He and his wife, the daughter of Mac Donogh, of Tirerrill, died in the year 1362.

^k *Maghnus Cleireach* died in the year 1359.

^l *Brian Og.*—He was slain by the Barretts in the year 1373. No notice of the other sons of Sen Bhrian is preserved in the Irish Annals.

inġean Domnall Ruaidh Uí Mháile a mátaíṛ arason). Muirċear-
taċ, Loċlainn, aṡur Taitleaċ mec ele do. O'n Loċlainn rin atá
rlioċt Loċlainn buna Finne, aṡur oċt ġ-ċeaċramna fearuinn a
ġ-ċuid dúioċe. Ar iad ar oirċerċa do'n t-rlioċt rin, .i. ċrian,
Feolim, Uilliam, aṡur Eoġan, mec Ruaidhriġ, mic Eoġain, ó Cheaċ-
ramain loċáin.

Domnall Clepeaċ, mac ċrian Uí Dhubba, clann moṛ ler, .i.
Ruaidhri, ri Ua b-Ĥiaċraċ, Eoġan, Maġnur, Maoleaċloinn, ríog-
damna Ua b-Ĥiaċraċ, Taċġ Riabaċ (Ĥionnguala, inġean Domnuill
Ruaidh Uí Mhaille, mátaíṛ na mac roin), Seaan, aṡur Domnall
(Teamaíṛ, inġean Uí Mhuirġeara, a mátaíṛ), Donnċaċ, Diaṛmaio,
Domnall, aṡur Aoċ (Ĥionnguala, inġean Maġnura, mic Caċuil
Uí Conċabaíṛ, a mátaíṛ). Mac ele do Eoġan (inġean Uí Cha-
táin a mátaíṛ).

Taċġ Riabaċ, moṛro, mec maite laíṛ, .i. ċrian, Donnċaċ
Ulltaċ (Eudoin, inġean Domnall, mic Muirċearṫaíġ Uí Chon-
ċabaíṛ, a mátaíṛ); Taċġ ċuide, Seaan, (Maíṛġréġ, inġean Uilliam,

mic

^m *Bun finne*, i. e. mouth of the River Finn, now pronounced *Bun fhinne*, and anglicised Buninna. It is the name of a townland in the parish of Drumard, barony of Tireragh, and county of Sligo. On an old map showing part of the coast of Donegal, Leitrim, and Sligo, preserved in the State Paper Office, London, a castle under the name of "Ca. Bonin," is noted immediately to the north of Tonerigowe [Tonreg], and near the brink of Ballysadare bay, in the parallel of Knocknaree. In the Down Survey this townland is called Carrowcaslane [i. e. *Castle quarter*], *alias* Bonannè; and in the deed of partition of O'Connor Sligo's estate, dated 21st July,

1687, it is called Bonin.

^a *Ceathramha lochain*, i. e. the quarter of the small lake, now Carrowloughaun, situated on the coast in the north of the parish of Screen.

^o *Ruaidhri*, i. e. Rory, Roderic, or Roger. He succeeded his father in the year 1380, and died 1417, at which year the Annals of the Four Masters contain the following notice of his death:— "A. D. 1417. O'Dowd (Ruaidhri, son of Domhnall, son of Brian, son of Taichleach), fountain of the prosperity and wealth of Tireragh, died in his own house after the festival of St. Bridget, and his brother, Tadhg Riabhach, assumed his place."

(Meadhbh, the daughter of Domhnall Ruadh O'Maille, was the mother of both). Muirheartach, Lochlainn, and Taithleach were his other sons. From this Lochlainn are the Sliocht Lochlainn of Bun Finne^m, whose inheritance consists of eight quarters of land. The most distinguished of this sept are Brian, Fedhlim, William, and Eoghan, the sons of Ruaidhri, son of Eoghan of Ceathramha lochainⁿ.

Domhnall Cleireach, the son of Brian O'Dubhda, had a large family, namely, Ruaidhri^o, King of Hy-Fiachrach, Eoghan, Maghnus, Maoil-eachlainn, heir apparent of Hy-Fiachrach, Tadhg Riabhach^p (Fionnghuala, the daughter of Domhnall Ruadh O'Maille, was the mother of these sons); John and Domhnall (Teamhair, the daughter of O'Muirgheasa, was their mother); Donnchadh, Diarmaid^q, Domhnall, and Aodh (Fionnghuala, daughter of Maghnus, son of Cathal O'Conor, was their mother). He had another son, Eoghan^r (the daughter of O'Cathain was his mother).

Tadhg Riabhach had good sons, namely, Brian, Donnchadh Ulltach^s (Eudoin, daughter of Domhnall, son of Muirheartach O'Conor, was their mother); Tadhg Buidhe^t, John (Margaret, daughter

^p *Tadhg Riabhach*, i. e. Teige, Thadæus, or Timothy the Swarthy.—He succeeded his brother, Ruaidhri, in the year 1417, and died in 1432, as we learn from the following notice of him in the Annals of the Four Masters:—"A. D. 1432. Tadhg, the son of Domhnall, who was the son of Brian O'Dowd, lord of Tireragh, a man who had restored the hereditary properties in his territory to the lawful proprietors, both lay and ecclesiastical, and a respecter of learned men and poets, died on the 16th of January." It is stated in the margin of the autograph original of the Annals of the Four Masters, preserved

in the Library of the Royal Irish Academy, that the Book of Lecan was compiled in the time of this chieftain.

^q *Diarmaid*.—He died in the year 1439, under which year he is styled in the Annals of the Four Masters "heir apparent to the chieftainship of Tireragh."

^r *Eoghan*.—He was slain by O'Donnell's cavalry in the year 1420. The other sons of Domhnall Cleireach are not noticed in the Annals.

^s *Donnchadh Ulltach*, i. e. Donogh, or Denis the Ultonian. He died of the plague which raged in Ireland in the year 1439.

^t *Tadhg Buidhe*.—He was chief of the

mic Sír Remuinn a búrc, a maíair). Mec ele do Seaan ele, Níall, Donnall, Aod, agus Tairleac. Tíob mór an clann rin ir ar gab-laig uata, i n-Ard na Riag, in Eirgín Albán, i m-baile Uí Mhoíaine, i m-baile an Chairlen, agus i Longphort Uí Dhubha, ní maírean neac d'á phloct i d-Tír Phiaicrac.

Na bailte reamháite ono, bailte cairlen pleacta Thaidg dhuidhe, mic Taidg Riabai. Tíoll do cógaid baobdún an long-puir, act leaba an Eic dhuidhe do cóg Sean dhrian. Donnac, mac Taidg Riabai, do cógaid baile an Chairlen. Eirgín Albán do cógaid leir in Albánac Mór, oide Taidg dhuidhe, mic Taidg Riabai. Baile Uí Moíaine por cógaid Taidg Riabac Fen. baile

O'Dowds for three years, and was slain by his own cousins, the sons of his uncle, Ruaidhri, in 1443. In our author's smaller work, compiled in 1666, he deduces the descent of Captain Dominic Barrett from this Tadhg Buidhe O'Dowd, as follows :— "Captain Dominic Barrett, son of John Roe Barrett, by Elis, daughter of Tadhg Riabhach, son of Tadhg Buidhe (half brother by the mother of Randal Mor Mac Donnell, who was slain in the battle of Sruthair), son of Cosnamhach, of Ardnarea, son of Magnus, son of Tadhg Buidhe, &c." And he adds, "I have heard that Tadhg Riabhach, the grandfather of Captain Dominic, obtained possession, and received the rents of Longphort Uí Dhubhda, in Tireragh; but he was afterwards hanged by Domhnall O'Connor, at Bel an chlair, in Leyny, O'Hara Reagh's country."

^u *Ard na riagh*, now Ardnarea, on the

east side of the River Moy, and forming a suburb to the town of Ballina.

^v *Eisgín abhann*, i. e. the *esker*, or low ridge at or near the river. This place is mentioned in the Annals of the Four Masters at the year 1512, when the castle was besieged and taken by O'Donnell from Ulick, the son of the Lower Mac William Burke, who had taken it from the lawful proprietor. On an old map preserved in the State Paper Office, London, this castle is shown on the east side of Killala bay, under the name of Uskarowen, which is a tolerable attempt at representing the Irish sound in English letters, but Eskerowen would be more correct. That this is the place now called Iniscrone will be proved in the notes to the poem of Giolla Iosa Mor Mac Fírbis, who calls it by the strange name of Sais Sgrebainn.

^w *Baile Uí Moíaine*, i. e. O'Moghany's town. It is still so called by those who

daughter of William, son of Sir Redmond Burke, was their mother). His other sons were another John, Niall, Domhnall, Aodh, and Taithleach. Though this family, and those who branched off from them, were *once* great at Ard na riagh^u, Esgir Abhann^v, Baile Ui Mhochaine^w, Baile an Chaislen^x, and Longphort Ui Dhubhda^y, not one of their descendants are now living in Tir Fhiachrach [*Tireragh*].

The aforesaid towns were the castle-towns of the race of Tadhg Buidhe, son of Tadhg Riabhach. It was the English that erected *all* the bawn of the Longphort [*Longford*], except Leabha an Eich Bhuidhe^z which was erected by Sen Bhrian [*O'Dowd*]. Donnchadh, the son of Tadhg Riabhach, erected Baile an chaislen [*Castletown*]. Esgir Abhann was erected by the Albanach Mor^a [*Big Scotchman*], the foster-father of Tadhg Buidhe, son of Tadhg Riabhach. Baile Ui Mhochaine [*Ballymoghany*] was erected by Tadhg Riabhach himself.

Baile

speak Irish, and correctly anglicised Ballymoghany. It is a townland in the parish of Castleconor, east of the River Moy, in the barony of Tireragh.

^x *Baile an chaislen*, i. e. the town of the castle. It is still so called in Irish, and properly translated Castletown, which is the name adopted on all modern maps. It is situated in the parish of Easkey, on the west side of the River Easkey, near its mouth.—See Ordnance Map of the County of Sligo, sheet 11.

^y *Longphort Ui Dhubhda*, now Longford, in the parish of Dromard, which lies on the west side of Ballysadare Bay. In the reign of William III. the castle of Longford successfully resisted two attacks of a

detachment of troops under Major Vaughan. In the demesne of Longford, now the property of the Crofton family, are the ruins of an old chapel said to have been built by the O'Dowds.

^z *Leaba an eich bhuidhe*, i. e. the bed of the yellow steed, would be anglicised Labbanehwee, and was undoubtedly the name of some building attached to the bawn of the castle of Longford, but the Editor does not know whether this name is still preserved.

^a *Albanach Mor*.—He was evidently Randal Mor Mac Donnell, mentioned in Note ^t, and who was slain, in the year 1570, in the battle of Sruthair, now the village of Shruile, in the county of Mayo.

baile Aird na Ríag do ponad le Galluib. Do cúio ponna Taidg buíde na bailte rin iaram, agus iomad ele.

Taidg dno ar iad a mēc, .i. Maḡnur, Feolim, Seaan ḡlar, Eogan, Aod, Concabān, agus Donncaō. Tuicid Seaan ḡlar, Eogan, Concabān agus Donncaō tap ceann a n-buidē; tēd Maḡnur agus Feolim i n-uēt Cloinne Uilliam; tēd Aod ar ḡaol a seanmātar ḡo h-Umall Uí Mhaille, ḡo m-baoi tpi páite ann, ag déanam díberge, do éir agus do mui, ar ílioēt Ruaidrí, mic Domnaill Cleirig; ḡur b'aitheac ler a n-beanna i n-aigid Dé, conad aipe rin, agus tpe aiple apane ancoipe iurig, tēd i ḡ-clēt ḡall, do iarrad puaímmir, agus cola n-Dé; agus ar ann do áicig tpi míle alla anoir do Dhroicēat Áta, baile i pugaō mac do d'ár b'ainm

* *Droichead Atha*, i. e. the bridge of the ford, now Drogheda. The truth of this account of the flight of Aodh or Hugh, the son of Tadhg Buidhe, is proved by two affidavits, which he himself caused to be enrolled in Dublin in the year 1452, that is, eight years after the killing of his father by the sept of Ruaidhri. These affidavits are in Latin, and preserved on a Plea Roll, No. 406, preserved in the Bermingham Tower, Dublin, a°. 36. Hen. VI. 1458, and the following translated extracts from them will not be out of place here, as confirming our author's account of the flight of this individual :

"A. D. 1452.—Hugh O'Dowde, of Staling, gentleman, required the following depositions, taken before Nicholas Younge, Notary, in the Taverner's Street, Dublin, to be enrolled.

"In Dei nomine, Amen. Remond Burke,

of Iniscoe, in Connaught, gentleman, being required by Hugh O'Dowda, son of Teige, to declare the truth, and examined on oath says,—that he knows the said Hugh; that the sept of Roger, son of Donell O'Dowda, three years since slew the brothers of the said Hugh, and expelled himself by force from his towns and lands in Tireragh, in Connaught, left to the said Hugh and his brothers by their father Teige; that there were fifty-eight quarters of land; that when the deponent came to Dublin he inquired from the said Hugh why he was in Dublin, and if he was married; Hugh answered that he was glad to see him; that he (Hugh) came to Dublin to see if he could meet with any of his friends; that he dwelt at Staling; that he was married there, and had a son Hugh. Deponent asked him did he wish to return to Connaught? to which he answered,

Baile Aird na riagh [*Ardnarea*] was built by the English. These towns, and many others, were on the territorial division of Tadhg Buidhe.

This Tadhg had these sons, following, viz., Maghnus, Fedhlim, John Glas, Eoghan, Aodh, Conchobhar, and Donnchadh. John Glas, Eoghan, Conchobhar, and Donnchadh fell in defending their native territory. Maghnus and Fedhlim went to the Clann-William [*Burkes*]; and Aodh, from the relationship of his grandmother *to the family of O'Maille*, repaired to Umhall Ui Mhaille, and remained there for three quarters of a year, committing vengeful aggressions by land and sea upon the race of Ruaidhri, son of Domhnall Cleireach, until at length it repented him of what he had committed against God; for which reason, and by the advice of a certain pious anchorite, he betook himself to the protection of the English, to seek repose and the will of God; and where he dwelt was at a place three miles to the east of Droichead Atha*, where a son was born to him whose
name

that his posterity might; but for himself that if he got the whole of Tireragh, he would not think his life safe, and would not live there; that the said Hugh asked the deponent to attend before a notary and testify the truth, which he has now done accordingly."

"John O'Cleri, of Lacan, in Connaught, gentleman, aged sixty years, sworn, says that he was born in Tireragh; that he knew the said Hugh, the son of Teige; and that the sept of Roger, the son of Donell O'Dowda, through envy and avarice, slew the brothers of the said Hugh in defence of their possessions, and expelled he said Hugh out of all his possessions in

Tireragh. That the deponent received for three years the rents of the lands of the said Teige, and knows that the said Teige was seized before his death of the following lands, which he divided among his sons, viz., the towns and lands of Ardnaree, Clounte, Choillin, Clounslegan, Ragibock, Scurmore, Urlare, Caraghmore, Bellacastlan, Boreagh, Castlanlaragh, Cnocan-Mac-Murtagh-Riogh, Tobberbonnac, Mulliroo, Choillin, Floughmoioin, Ballalunog, Lisnarge, &c. That the said Teige died in the peaceable possession of all the said lands, and that the said Hugh is the right heir of all and singular the same."

b'ainm Aodh. Tug bliadhna iaram arbae Aodh Mór, agus pág-
bair a mac ag rólóig raiðbhir do muinntir Cuinn, doneoí por ail
go h-ónórae, agus tug a deirbírur mar mnaoi do, go rug rí tug mec
do, .i. Seón, Tomar, agus hanraoi, agus clann ingean. Iar n-eg
na mná rin, tug re ingean an bhailirig ó'n Seanroiceatt, agus
rug rí mac do, .i. Seoirí, átair Uilliam, Ghiolla Phadraig, Sheón,
Eudbair, Thomar, Rirdeir, agus Ffainra, conaó iad rin craoba
coibneara Ua n-Dubda ríio in Ach cliaé Duiblinne.

Atá umorpo, ar gnátcuimne coitcinn, agus rgruobta i leab-
raib Cloinne Fhribirig, gur ob do Ib Dubda an Dubdalac co n-a
gablaib gaoil, agus gur ob ann deagluib re Tug Fiacrae i n-aimir
marbta Tailteig Muaidhe Uí Dubda re Galluib, Anno Domini
[1282]; gur gairmuib Dubnálug oib ag Galluib, mar mrioir a
rdair fen, buó emilt re a h-aimir runna.

Domnall

^b *Bhailiseach*.—It is doubtful whether our author intended this to represent the name Walsh or Wellesley? Both families were in this district. The Editor knows several of the name Do Bhailisi in the county of Kilkenny, where it is always anglicised Wallace; but this is probably not the true form, as in the Irish the preposition *Do*, which indicates a Norman origin, is always prefixed. The family name Do Bhailisi, which, if analogically rendered, would make in English De Wallisi, also assumes the form Bhailiseach, to denote one of the family. In Kilkenny the family name Walsh is called in Irish Breathnach, i. e. Britannus, never Bhailis, and is considered to be a totally different name from Do Bhailisi; but our author, in his pedigree of the family of Walsh, p. 839, writes the name both Bhailis and Breathnach; so that he

may probably have intended to express by Ingean an bhailirig ó'n Seanroicheatt, the daughter of Walsh of Old Bridge. But this is far from being certain.

^c *John*.—It appears from a Chancery Decree preserved in the Rolls Office, Dublin, dated 2nd May, 1557, that "John Dowde, of Stalinge, as administrator of his father, Hugh Dowde, complained agaynste one Peter Russell, of the Shephouse, husbandman, who married Joan Dowde, daughter of the said Hugh, and who got with her in marriage from the said Hughe, one-third of the land of Stalinge, called Bagots fearme."

^d *Who are now in Ath Cliath*.—Some of the O'Dowds, of Stalinge, on the Boyne, near Drogheda, afterwards removed to Dublin, where they became very wealthy. On the Patent Roll of the fifteenth year of King

name was Aodh Og. Three years after this Aodh Mor died, and left his son with a rich farmer of the family of O'Quin, who reared him honourably, and gave him his sister in marriage, and she brought forth for him three sons, namely, John, Thomas, and Henry, besides daughters. After the death of this wife he married the daughter of Bhaliseach^b of Oldbridge, and she brought forth a son for him, namely, George, the father of William, Giolla-Patrick, John^c, Edward, Thomas, Richard, and Francis. These are the genealogical ramifications of the *family of O'Dubhda*, who are *now* in Ath Cliath^d Duibhlinne [*Dublin*].

It is the general tradition, and it is written in the Books of the Clann Fírbis, that Dowdall, with his correlative kindred, is of the family of O'Dubhda, and that the period at which he left Tir Fiachrach was the time of the killing of Taithleach of the Moy O'Dubhda, by the English, Anno Domini [1282]; so that they were called Dowdalls by the English, as their own history relates^e, which would be tedious to be given here.

Domhnall

James the First, are two deeds relating to the O'Dowds of Dublin, one dated 8th June, 1614, whereby Nicholas Weston, of Dublin city, grants to Francis Dowde and Charles Dowde, of Dublin city, merchants, the pools of Lanagh and Bealagaly, in the River Gadcon, otherwise Kilcomon, in the county of Mayo.

The other is dated 30th June, 1612, whereby Sir Richard Nugent, Baron of Delvin, granted to John Dowde, of Dublin city, alderman, the fishing of Rabran river from the sea to Ballanefanny; the fishings of salmon and other fish within the flow and ebb of the tide in the river or bay of Bonitrahan, and the fishings of salmon and other fish within the flow and ebb of

the tide of the waters of Gadcon, otherwise Killcomayne, from the main sea to Farsindvinegemine, in the county of Mayo. In the will of Lysagh O'Connor (Faly), Esq., dated 5th September, 1626, this alderman John Dowde, of the city of Dublin, is also mentioned; and the testator, who was a gentleman of high rank in the country, appoints him one of the overseers of his will, and bequeaths to him "my blacke Phillippe and cheney cloake lyned with bayse." This will, which is a very curious document, is preserved in the Prerogative Court, Dublin.

^e *Their own history relates*.—This shows that our author had seen a history of the Dowdalls, which traced them to an Irish

Domnall Oḡ, mac Domnaill Cléirig, clann leir, .i. Ruaidrí, Diarmuid, agus Eumonn.

Ruaidrí, mac Domnaill Cléirig, clann lair, .i. Maolruanaid, Concábar, Maḡnur Clepeac (Eileog, inḡean Sheagain Mhic Ḣoir-dellb, a mátair), Muirceartac, Eogan, agus Uilliam (Anabla, inḡean Sír Reumuin a búrc, a mátair).

Cornamairg, mac ḡrian, mic Tairéig Uí Dubda, clann leir, .i. ḡrian, Aod, Muirceartac, Seacan, agus Eumonn.

Maolruanaid mac Ruaidrí, clann lair, .i. Diarmuid, Domnall ballac, Maoileacloinn, agus Muirceartac Caoc, díobairg, agus Maoileacloinn.

Eogan, Fearadóc, Ruaidrí, Cormac bratair, Catal Dub, Daḡi, Seacan Ḣlar, agus ḡrian, mec Concábar, mic Diarmada, mic Maolruanaid.

Fearadac mac lair, .i. Domnall, aḡair Eogain, díobairg.

Ruaidrí mac Concábar, mac lair, .i. Diarmuid, aḡair Ruaidrí, Fearadóg, Domnall, Concábar, Sheagain Ḣhlair.

Daḡi, mac Concábar, clann lair, .i. Fearadac, Donncaḡa, Caḡair, Cormac, Fiacra, agus Amalgaid Daḡle.

Seacan

origin. The general opinion is, that the Dowdalls, who were a very distinguished family in the county of Louth in the fourteenth and fifteenth centuries, are one of the old Anglo-Norman families of the pale; but the name is not found in any of the lists of the chieftains who came over with Strongbow, or any of the subsequent English leaders, nor is there any mention of them in the Anglo-Irish records as early as the period of the killing of Taithleach Muaidhe O'Dowd (1282); so that our author's assertion, that they are of the

O'Dowd race, is not to be rejected without the most direct evidence to prove the contrary.

^f *Maolruanaidh*.—He became chief of the O'Dowds in the year 1432, and enjoyed that dignity for eighteen years, according to our author in his Brief Annals of the O'Dowd family.

^g *William*.—The death of William, son of Ruaidhri O'Dowd, is entered in the Annals of the Four Masters at the year 1438.

^h *Brian*.—He was chief of the O'Dowds for two years.

Domhnall Og, son of Domhnall Cleireach, had issue, namely, Ruaidhri, Diarmaid, and Edmond.

Ruaidhri, son of Domhnall Cleireach, had issue, namely, Maolruanaidh^f, Conchobhar, Maghnus Cleireach (Eileog, daughter of John Mac Costello, was their mother), Muircheartach, Eoghan, and William^g, (Anabla, daughter of Sir Redmond Burke, was their mother).

Cosnamhaigh, son of Brian, son of Taithleach O'Dowd, had issue, namely, Brian^h, Aodh, Muircheartach, John, and Edmondⁱ.

Maolruanaidh, son of Ruaidhri, had issue, namely, Diarmaid, Domhnall Ballach^j, Maoileachlainn, and Muircheartach Caoch, who, died without issue; and *a second*, Maoileachlainn.

Eoghan^k, Fearadhach, Ruaidhri, Cormac the friar, Cathal Dubh^l, Dathi, John Glas, and Brian, were the sons of Conchobhar, son of Diarmaid, son of Maolruanaidh.

Fearadhach had a son Domhnall, father of Eoghan who died issueless.

Ruaidhri, son of Conchobhar, had a son Diarmaid, the father of Ruaidhri, Fearadhach, Domhnall, Conchobhar, and John Glas.

Dathi, son of Conchobhar, had issue, namely, Fearadhach, Donn-catha, Cathaoir, Cormac, Fiachra, and Amhalgaidh of *the River Daoil*.

John

ⁱ *Edmond*. — He was chief of the name for half a year and five weeks.

^j *Domhnall Ballach*. — He succeeded Edmond, son of Cosnamhach, and was the chief O'Dowd for one year.

^k *Eoghan*. — He was chief of the O'Dowds, according to our author, for seven years, and is mentioned in the Annals of the Four Masters at the year 1536, when his

wife, the daughter of Walter Burke, was taken prisoner by O'Donnell.

^l *Cathal Dubh*, i. e. Cahill, or Charles the Black. He succeeded his brother Eoghan as chief of the O'Dowds, but the length of his reign is not mentioned by our author in his short Annals of the O'Dowd family.

Seaan Ḡlar, mac Concábair, dá mac Iep, .i. Cormac agur ḡrian.

Eogan, mac Concábair, clann Iep, .i. Taðg Riabac, Eumonn, Ceallac, agur Concábair, aṭair Taiðg Riabaiḡ, aṭar Eogain agur Eumonn.

Taðg Riabac, mac Eogain, clann Iair, .i. Dáti, Taðg Duide, Fearadoc (aṭair Chaṭail Duib, hpaṭar), Domnall, Maoilpuanaid, uíobaiḡ, Eogan, agur Seaan Og, aṭair Thaidg Riabaiḡ agur Donncaid.

[Dáti Og Ua Dubda, mairpear anoir, 1666,	
mac Sémuir,	mic Aoda,
mic Dáti,	mic Taiṭliḡ,
mic Dáti,	mic Aoda,
mic Taiðg Riabaiḡ,	mic Muirṇearpaiḡ,
mic Eogain I Dubda,	mic Aoda,
mic Concábair,	mic Taiṭliḡ,
mic Diarmada,	mic Nell,
mic Maoilpuanaid,	mic Maoileacloinn,
mic Ruaidriḡ I Dubda,	mic Maoilpuanaid,
mic Domnall Clériḡ I Dubda,	mic Aoda,
mic Sen-ḡhrian I Dubda,	mic Ceallaiḡ,
mic Taiṭliḡ Muaidé,	mic Dubda, a quo an fine,
mic Maoilpuanaid,	mic Connmuḡ,
mic Donncaid,	mic Duinncaṭa,

mic

^m *Tadhg Riabhach*.—He died, according to the Four Masters, in the year 1580, but they give his pedigree wrong, thus: "Tadhg Riabhach, son of Eoghan, son of Concho-bhar, son of Teige." The last generation should be Diarmaid.

ⁿ *Dathi*.—He became chief of the name,

and was slain in the year 1594. His death is thus entered in the Annals of the Four Masters:—"A. D. 1594, O'Dowd, of Tireragh, Dathi, son of Tadhg Riabhach, son of Eoghan, was slain by one of the queen's soldiers in one of his own castles, in Tireragh, on the Moy."

John Glas, son of Conchobhar, had two sons, namely, Cormac and Brian.

Eoghan, son of Conchobhar, had issue, Tadhg Riabhach^m, Edmond, Ceallach, and Conchobhar, the father of Tadhg Riabhach, who was the father of Eoghan and Edmond.

Tadhg Riabhach, the son of Eoghan, had issue, namely, Dathiⁿ, Tadhg Buidhe^o, Fearadhach (father of Cathal Dubh, a friar), Domhnall, Maolruanaidh, who died without issue, Eoghan, and John Og, father of Tadhg Riabhach and Donnchadh.

[Dathi Og ^p O'Dubhda, now living, 1666,	
son of James,	son of Taithleach,
son of Dathi,	son of Aodh,
son of Dathi,	son of Taithleach,
son of Tadhg Riabhach,	son of Aodh,
son of Eoghan, i. e. the O'Dubhda,	son of Muirchertach,
son of Conchobhar,	son of Aodh,
son of Diarmaid,	son of Taithleach,
son of Maolruanaidh,	son of Niall,
son of Ruaidhri, i. e. the O'Dubhda,	son of Maoileachlainn,
son of Domhnall Clereach, i. e.	son of Maolruanaidh,
the O'Dubhda,	son of Aodh,
son of Sen Brian, i. e. the O'Dubhda,	son of Ceallach,
son of Taithleach of the Moy,	son of Dubhda, from whom the
son of Maolruanaidh,	tribe.
son of Donnchadh,	son of Connmhach,
son of Aodh,	son of Donncatha,

son

* *Tadhg Buidhe*. — He was set up as chief of the O'Dowds by O'Donnell in the year 1595, as stated by the Four Masters.

^p *Dathi Og*. — This pedigree, enclosed in

brackets, is given from our author's smaller compilation, made in 1666. — See this pedigree carried down to the present day in the Addenda to this volume.

mic Caéal,	mic Fiacraic Ealgaig,
mic Oilella,	mic Daí, ní Epeann,
mic Dunchaó,	mic Fiacraic,
mic Tiobraide,	mic Eatac Muigmeadoin, ní
mic Maoilbúin, .i. Maolbú,	Epeann].

Uilliam Og, Crioiboir, Daí, agur Fiacra,	
mec Uilliam,	mic Taidg Riabairg.
mic Daí,	

Maolpuanaid, agur Taidg buide, bratair,
mec Taidg buide, .i. mac Taidg Riabairg.

Taidg Riabac, Fearóoc, agur Ruaidrí,	
mec Domnall,	mic Eogain.
mic Taidg Riabairg,	

Domnall bratair, agur Eumonn,	
mec Eogain,	mic Eogain.
mic Taidg Riabairg,	

Caéal Dub, .i. O'Dubda,	
mac Eumuin,	mic Concábir.
mic Eogain,	

Ceallac,	
mac briain,	mic Eogain,
mic Ceallairg,	mic Concábir.

ZORG RUADHRI, MIC CONCHAETHAIR.

Ruaidrí,	
mac Daí,	mic Diaimada,
mic Ruaidrí,	mic Maoilpuanaid,
mic Diaimada,	mic Ruaidrí,
mic Ruaidrí,	mic Domnall Cleirg.
mic Concábir,	

son of Cathal,	son of Fiachra Ealgach,
son of Oilioll,	son of Dathi, King of Ireland,
son of Dunchadh,	son of Fiachra,
son of Tiobraide,	son of Eochaidh Muighmheadhoin,
son of Maolduin, i. e. Maoldubh,	King of Ireland].

William Og, Christopher, Dathi, and Fiachra, are the
 sons of William, son of Tadhg Riabhach, &c.
 son of Dathi,

Maolruanaidh and Tadhg Buidhe, a friar,
 sons of Tadhg Buidhe, son of Tadhg Riabhach, &c.

Tadhg Riabhach, Fearadhach, and Ruaidhri,
 sons of Domhnall, son of Eoghan.
 son of Tadhg Riabhach,

Domhnall, a friar, and Edmond,
 sons of Eoghan, son of Eoghan.
 son of Tadhg Riabhach,

Cathal Dubh, i. e. the O'Dubhda,
 son of Edmond, son of Conchobhar.
 son of Eoghan,

Ceallach,
 son of Brian, son of Eoghan,
 son of Ceallach, son of Conchobhar.

THE RACE OF RUaidhri, SON OF CONCHOBHAR.

Ruaidhri,	
son of Dathi,	son of Diarmaid,
son of Ruaidhri,	son of Maolruanaidh,
son of Diarmaid,	son of Ruaidhri,
son of Ruaidhri,	son of Domhnall Clereach.
son of Conchobhar,	

Brian,

δριαν,
mac Caṡaoir,
mic Feapaḃaig,
mic Diaimaba,

mic Ruaidḃri,
mic Conṡabair.

Domnall Oḡ, aḡur Eoḡan, dá
mac Domnall I Dhubḃa,
mic Diaimaba,

mic Ruaidḃrig,
mic Conṡabair.

ΛΟΡḢ SHEAAN ḢHLAIS, MIC CONCHAḢHAIR.

Seaan Ḣlar, Daṡi, Diaimuib (aṡair Taiḃḡ), Maoleaṡloinn
Caoc, Eoḡan, Sérlur (aṡair Phabraig aḡur Dhomṡaib bpaṡar),
Fiaṡpa (aṡair Thomair), Seón (aṡair Diaimaba),
mec ḃriain, mic Conṡabair,
mic Seaan Ḣlair, mic Diaimaba.

δριαν, Eoḡan,
mec Seaan Ḣhlair, mic Seaan Ḣhlair.
mic ḃriain,

Copmac, Eoḡan, aḡur Domnall Oḡ,
mec Domnuill, mic Seaan Ḣhlair,
mic Copmaic, mic Conṡabair.

Ο ΔΗΥΝ ΝΕΛΛ.

Uilliam Oḡ, Eoḡan Capraṡ, do mapḃaḃ 1 ḡ-Cnoc na n-or, aḡur
Domnall ḃallaṡ, tri
mec Feḃlim, mic Uilliam Oig,
mic Emuinn ḃuide, mic Domnall ḃhallaiḡ,

mic

^a *Dun Neill*, i. e. the dun or fort of Niall, now Duneal or Dunneill, otherwise called Castlequarter, a townland in the parish of Kilmacshalgan, barony of Tire-

ragh, and county of Sligo.

^r *Cnoc na n-os*, i. e. hill of the fawns. There is a well known hill of the name near Buttevant, in the county of Cork, where

Brian,	
son of Cathaoir,	son of Ruaidhri,
son of Fearadhach,	son of Conchobhar.
son of Diarmaid,	

Domhnall Og and Eoghan, two	
sons of Domhnall, i. e. the	son of Ruaidhri,
O'Dubhda,	son of Conchobhar.
son of Diarmaid,	

THE RACE OF JOHN GLAS, SON OF CONCHOBHAR.

John Glas, Dathi, Diarmaid (the father of Tadhg); Maoileachlainn Caoch, Eoghan, Charles (father of Patrick, and of Donnchadh a friar); Fiachra (father of Thomas); and John (father of Diarmaid), were

sons of Brian,	son of Conchobhar,
son of John Glas,	son of Diarmaid.

Brian and Eoghan,	
sons of John Glas,	son of John Glas.
son of Brian,	

Cormac, Eoghan, and Domhnall Og,	
sons of Domhnall,	son of John Glas,
son of Cormac,	son of Conchobhar.

OF DUN NEILL^a.

William Og, Eoghan Carrach, who was slain at Cnoc na n-os', and Domhnall Ballach, three

sons of Fedhlim,	son of William Og,	
son of Edmond Buidhe,	son of Domhnall Ballach,	son

the celebrated Alexander Mac Donnell was	here referred to it is difficult at present to
slain in 1647, but whether it is the place	decide.

mic Maoilpuanaid,
mic Ruaidrí,

mic Domnaill Cleirí.

Calbác,
mac Uilliam Chaolá,
mic an Chalbáig,
mic Taidé,
mic Dháin,

mic Diarmada,
mic Maoilpuanaid,
mic Ruaidrí,
mic Domnaill Cleirí.

SLIOCHT AN CHOSNAMHAIGH ANN SO.

Ruaidrí, Uilliam Dallac, agur Felim,	
mec an Chornamhaigh,	mic Aoda,
mic Seáin,	mic an Chornamhaigh,
mic Felim,	mic Sen-Dháin.

CLANN TAITHELIGH ANN SO.

Corc, Taitheac, agur Seáin, trí	
mec Ruaidrí,	mic Maoileacloinn,
mic Concábair,	mic Dháin Derg,
mic Taithe Oig,	mic Aoda, ag a g-comhairle
mic Muirceartaigh na Fuinn-	agur an ríogruí,
eoige,	mic Nell,
mic Taithe,	mic Maoileacloinn.
mic Aoda Aláin,	

Muirceartaigh Leóinn,	
mac Maoilpuanaid,	mic Dháin Derg, do báitead ar
mic Concábair Dheirí,	rligí na Róma, tar éir a
mic Aoda Aláin,	oilíre.
mic Maoileacloinn,	

Mirbel,

son of Maolruanaidh,
son of Ruaidhri,

son of Domhnall Clereach.

Calbhach,
son of William Caoch,
son of Calbhach,
son of Tadhg,
son of Brian,

son of Diarmaid,
son of Maolruanaidh,
son of Ruaidhri,
son of Domhnall Clereach.

THE RACE OF COSNAMHACH HERE.

Ruaidhri, William Ballach, and Felim,
sons of Cosnamhach,
son of John,
son of Felim,

son of Aodh,
son of Cosnamhach,
son of Sen Brian.

THE CLANN TAITHLIGH HERE.

Corc, Taithleach, and John, three
sons of Ruaidhri,
son of Conchobhar,
son of Taithleach Og,
son of Muircheartach na Fuineoige,
son of Taithleach,
son of Aodh Alainn,

son of Maoileachlainn,
son of Brian Dearg,
son of Aodh, in whom they and
the chiefs meet,
son of Niall,
son of Maoileachlainn.

Muircheartach Leghinn,
son of Maolruanaidh,
son of Conchobhar Dèseach,
son of Aodh Alainn,
son of Maoileachlainn,

son of Brian Dearg, who was
drowned on his way from Rome
after his pilgrimage.

Mirbel, a quo clann Mirbel, agus Mec Finn Uí Dubda, co
n-a g-comhfoigirib,
mac Maoilruanuid, mic Aoda Alainn.
mic Concabair Dhéirig,

Domnall, ppríoir Eacpóir,
mac Taidg, mic Muirceartaig na Fuinn-
mic Domnuill, eoige.
mic Aoda,

Aod Ruad, Diarmuid, agus Taidleach, tpi
mec Concabair, mic Aoda,
mic Taidlig, mic Taidlig,
mic Concabair Conallaiḡ, mic Aoda,
mic Taidlig, mic Muirceartaig.
mic Donncaid Mhoir,

Tomar, agus Maoileacloinn Mor,
mec Aoda, mic Concabair Conallaiḡ.

Ruaidrí Mór,
mic Taidlig, mic Concabair Conallaiḡ.

Soáin cloinne Caomáin, mic Connmuighe, annro, do péir na
n-eolac n-árranta, iar n-a faḡbail do Aod, mac Catáil Uí Chao-
main, ó Cheallac, mac Dubda, agus ó Aod, mac Ceallaiḡ, do
cómáid

⁵ *Eachros*, now Aughris, a townland containing the ruins of an abbey, in the parish of Templeboy, in the barony of Tireragh, and county of Sligo.

⁶ *O'Caomhan*, should be Mac Caomhain, i. e. son of Caomhan, for Cathal was the son, not the O', or grandson of Caomhan.— See pedigree.

⁷ *Aodh, son of Ceallach*.— According to our author, in his short Annals of the O'Dowd family, this Ceallach was king of north Connaught, and died in the year 983, and it is therefore a great anachronism to make this prince cotemporary with one who had been cursed by the Saxon St. Gerald, who died, according to the accurate

Misdel [*Mitchel*], from whom the Clann Misdel and the *family* of Mac Finn O'Dubhda, with their correlatives,

son of Maolruanaidh, son of Aodh Alainn.
son of Conchobhar Deseach,

Domhnall, prior of Eachros',

son of Tadhg, son of Aodh,
son of Domhnall, son of Muircheartach na Fuinneoige.

Aodh Ruadh, Diarmaid, and Taithleach, three

sons of Conchobhar, son of Aodh,
son of Taithleach, son of Taithleach,
son of Conchobhar Conallach, son of Aodh,
son of Taithleach, son of Muircheartach.
son of Donnchadh Mor,

Thomas and Maoileachlainn Mor,

sons of Aodh, son of Conchobhar Conallach.

Ruaidhri Mor,

son of Taithleach, son of Conchobhar Conallach.

The privileges of the race of Caomhan, the son of Connmhach, according to the ancient literati, which were obtained by Aodh, son of Cathal O'Caomhain', from Ceallach, the son of Dubhda, and from Aodh, son of Ceallach", as a compensation and consideration of kindred,

Annals of Tighernach, in the year 732, that is, 251 years before the death of this Aodh O'Dubhda. This story, therefore, is clearly false, for Dubhda, the grandfather of Aodh O'Dubhda, or O'Dowd, who died in 983, could not, according to the laws of nature, have been born before the year 823, so that it cannot for a moment be assumed

that his brother Caomhan could have been cotemporary with St. Gerald of Mayo. The truth is, that this account of the cursing of Caomhan by St. Gerald is a mere legend, written centuries after the time, to sanctify the succession of the O'Dowds, and to account for the laying aside of the O'Caomhains, who are senior

comaird agur do combraithear, iar na earguine do Tharait, do naomh Saxonaic (do péir Leabair bailb Shémuir Mhic Firdirig), go n-a éirí céo naomh, tpe mnaoi Uí Chaomhain d'á diúltad ó dorur caépac Caomhain (d'á n-geirtear Catair mór), depead laoi; gur earguin Tharait Caomhan co n-a ísol, .i. gan ríoga for a n-buócar go brát. Od cuala Aod rin, do gab aitéacáir é, im earguine a jean-aéar do deunam do'n naomh feargac, agur do migmom na mná aingíde, for a raib rliocht; go n-deacaid mar a raib Tharait dia ríodúgac; agur gé ró ríodai, níi éarba do Aod, uair níi deónai Tharait ríe do neac d'á m-biaí ar rliocht na mná ro diúltai ppi, acé do deónai plaítear Ua g-Caomhain do beé ar rliocht Diarmada, mic Catail, mic Caomhain, .i. mac cumuile na mna

to them. A legend exactly similar to this has found its way into the Book of Fenagh from the Book of Kilmacrenan, to account for the elevation of the family of O'Donnell to the chieftainship of Tirconnell, and the downfall of the senior branches of the Cinel Conaill race; and various fables of a like nature have been foisted into the Tripartite Life of St. Patrick, originally written by St. Evin, but afterwards interpolated by various writers, to account for the extinction or obscurity of the races of chieftains, who opposed the saint in his pious intentions. The true account of the laying aside of the family of O'Caomhain is above given by our author, in page 109, and the present fable is not worth attention, except as a specimen of the sort of fabrications resorted to by the bards to flatter the vanity of the families in power.

† *The wife of O'Caomhain*, should be

either the wife of Caomhan, or the wife of Cathal, son of Caomhan.

‡ *Race of Diarmaid, son of Cathal, son of Caomhan*.—Besides the anachronisms of this story, it involves a contradiction, for Diarmaid, son of Cathal, son of Caomhan, would have carried as much of the blood of the offending woman as his brother Aodh, if this wicked woman was the wife of the grandfather, Caomhan, which she would appear to have been, as Caomhan was the person cursed on her account. If she was the wife of Cathal, son of Caomhan, then indeed Diarmaid, who was liberated from the curse, may have had none of her blood, as he was the son of her Cumhal, or handmaid, but then this Cathal could not have been called O'Caomhain, as in the text, but Mac Caomhain. And again, if the wicked woman was really the wife of Cathal, there appears no reason

dred, after he [*i. e. Aodh O'Caomhain*] had been cursed by Gerald, the Saxon saint (according to the Dumb Book of James Mac Firbis), with his three hundred saints, in consequence of the wife of O'Caomhain', who turned him, late in the evening, out of the door of Caomhan's fort (which is called Cathair mhor); so that St. Gerald cursed Caomhan and his seed, and *prayed* that there should not be a king of his race for ever. When Aodh heard this, he became sorrowful for the curse pronounced against his grandfather by the angry saint, in consequence of the misconduct of the malicious woman, who had issue; so that he went to where St. Gerald was to appease him; and though he did appease him, it was of no avail to Aodh, for Gerald did not consent to make peace with any one descended from the woman who had insulted him, but he consented that the chieftainship of the O'Caomhains should be transferred to the race of Diarmaid, son of Cathal, son of Caomhan", that is, to the son

for the saint's curse against Caomhan, his father, for the crime of his son's wife, and should he happen to have had more sons than Cathal, it would have been very unsaintly indeed to curse the descendants of them all for the bad temper of the wife of one of them. The story should be told thus by our author:—"According to ancient writers the following are the privileges of the race of Caomhan, son of Connmhach, which were obtained by Diarmaid, son of Cathal, son of Caomhan, from Ceallach, son of Dubhda, and from his son Aodh, as a compensation for the loss of the chieftainship, and in consideration of kindred. According to the Dumb Book of James Mac Firbis, Gerald, the Saxon saint of

Mayo, with his three hundred monks, had pronounced a curse against the race of Caomhan, in consequence of the conduct of the wife of Cathal, the only son of Caomhan, for she had turned him, late in the evening, out of the door of Caomhan's fort, called Cathair Mhor; and the saint prayed, and while praying foresaw, that there should never be a king of the race of Caomhan, from whom the family were about to be named. When Aodh O'Caomhain, the legitimate son of Cathal, by his wicked wife already mentioned, heard this, he became sorrowful for the curse pronounced against the race of his grandfather, in consequence of the insult offered to the angry saint by his own ill-tem-

mna d'ibíge, agus gan rúil ag neac d'a cloinn f'f'í n'íge. Fup ob í comá no gabrad ar cuib tigeannuir, .i. tuat gaca tíne baol la a m-brátair ó Roöba go Coönaig, agus corac ruibíge 1 d-tíge óil, agus orobúgab cafa lair, agus epge pome gac uair tíg 'n-a ceant 1 cac inab a m-bia, agus túr d'íge do agus potruigete, agus gac neac ceud-gabor arn 'na tír, gomab ó ísol Diarmada, mic Cathail, mic Caomhain geabur; agus luag leara gaca h-inéne n'ig, eac agus

pered mother, from whom all the legitimate descendants of Caomhan were likely to descend; he therefore visited the saint to remonstrate with him about the nature of the curse, in the hope of inducing him to revoke it. But though the saint listened to the remonstrations of this only legitimate representative of the house of Caomhan, and felt that it was rather a cruel case that a whole tribe should labour under a curse for ever, still would he not consent to revoke the denunciation against Aodh, the remonstrant, or any of the descendants of the wicked woman; but he consented to avert the effect of his malediction from Diarmaid O'Caomhain, the illegitimate son of Cathal by the handmaid of the wicked woman, because he had none of the blood of her who had insulted him. To him and his race St. Gerald wished the chieftainship of the tribe of the O'Caomhains only to be transferred, but not that any of his descendants should ever aspire to the chieftainship of all the Hy-Fiachrach. The chieftainship of the Hy-Fiachrach was then vested in the race of Dubhda, but the following compensations

and privileges were ceded to the race of Diarmaid O'Caomhain, the illegitimate son of Cathal, son of Caomhan, in token of the seniority of his family, viz., that their chief should possess a tuath in each territory belonging to the O'Dowd, in the region extending from the River Robe to the River Cowney; that he should have the privilege of first entering the bath, and of first sitting down at the feast, and of taking the first drink; that he should be O'Dowd's chief marshal, pursuivant, and the commander of his forces; that O'Dowd should stand up before him wherever he should meet him on every occasion whatever; that all those who should take arms, that is, military weapons, for the first time in O'Dowd's country, should take them from the hand of the representative of Diarmaid, son of Cathal, son of Caomhan, and from no other person; that O'Caomhain should get the fine called the *Luach leasa* from every chieftain's daughter upon her marriage; that the O'Dowd should never be nominated without the presence and consent of O'Caomhain, who should first pronounce his name

son of the handmaid of the denounced woman, but that none of his race should ever expect to be kings of all the *Hy-Fiachrach*. And the compensations they obtained for this transfer of the lordship were the following, viz., a tuath of every territory which their reigning relative possessed from the river Rodhba², to the river Codhnach³, and the privilege of first sitting in the drinking house, and of arraying the battle; that *O'Dubhda* is to stand up before him whenever he meets him, or wherever he may be; that *O'Caomhain* is to take the first drink and bath; and that whoever takes his first arms⁴ in his territory, he should take them from the descendants of Diarmaid, son of Cathal, son of Caomhan; also that they should get the Luach leasa of every king's

and walk thrice round him after his nomination; that after O'Dowd's inauguration O'Caomhain should receive his steed and battle dress, and that Mac Firbis, the poet of the principality, should receive the like from O'Caomhain. These customs to last for ever." For some account of the inauguration of the ancient Irish chiefs see Addenda.

² *River Rodhba*, now the River Robe, which flows by a very circuitous course through the south of the county of Mayo, passing through the demesne of Castlema-garret and through the town of Ballinrobe, to which it gives name, and discharging itself into Lough Mask opposite the island of Inis Rodhba, which also derives its name from it.

³ *Codhnach*.—This, as will be hereafter shown, was the ancient name of a small river which flows into the bay of Sligo, at the village of Drumcliff, in the barony

of Carbury, and county of Sligo. The distance between these rivers shows the great power of the O'Dowd's in Ireland before they were encroached upon by the O'Conors of Sligo, Barretts, Burkes, and other families.

⁴ *And that whoever takes his first arms, &c.*

—This passage reads in the Book of Lecan thus: Cach nech gebur airm, coma ó ril Diarmada, mic Cathail, mic Caeman, gebur a cheo-gabail airm an tur, ocur luach imríor cáic ingine níg oia nígnaio, ocur each ocur eppao cach níg leo oo gneí, an n-bul fa oívean Dapailt. These words are thus paraphrased by the Rev. Patrick Mac Loughlin, in his abstract of the Book of Lecan, a manuscript in the Library of the Royal Irish Academy:—
“And all those who bore arms were to have their first arms from O'Caomhan, and every daughter born of the chief representative of the family was to have her

αγυρ εαρηαδ ζααα ριζ leo do ζηέαρ, αρ η-α ρίοζαδ, αγυρ α ιονη-
αμυιλ ριν υαιδιδ ρεαν δο'η ollam, .i. do Mhac Fhionnιγ.

No, ζομαδ ε Ζαπαιτ do βαιρδ Dubba, ο υ-αίοδ αν ριοζαδ,
αγυρ ζομαδ ε Caoimán fén fuair na poáir ριν (αμυιλ α ουβρα-
μαρ ιρ ιη αρσδρζαοιλεαδ) ο Ohubba, αρ έεανδ τιζεαρηαιρ, maile
le moían ele.

request granted by the prince." But he has not here given the true meaning of *luac impidhe*, for we know from good authorities that it was the name of a fine paid on several occasions. Distinct mention is made of this fine in the Annals of the Four Masters at the year 1414, as paid by an Englishman to O'Connor Faly and Mageoghegan. "A. D. 1414. A great victory was gained over the English of Meath by Murchadh O'Connor, Lord of Offaly, and Fergal Ruadh Mageoghegan, Lord of Cinel Fiachach mic Neill. The Baron of Skreen, and many of his adherent gentlemen and plebeians, were slain in the conflict, and the son of the Baron of Slane was taken prisoner, for whose ransom fourteen hun-

dred marks were afterwards paid. Dardis the Lawless was also taken prisoner together with numbers of others, for whose ransom twelve hundred marks were obtained, besides the fines called *Luach leasa* and *Luach impidhe*."

Luach leasa literally means reward, or price of welfare, and *Luach impidhe* reward, or price of intercession. Sir John Davis, in his letter to the Earl of Salisbury, makes mention of the latter fine in treating of the origin and duties of the Irish ecclesiastical officer called herenach. His words are: "The herenach was to make a weekly commemoration of the founder in the church; he had always *primam tonsuram*, but took no other orders. He had a voice in the

king's daughter *and* the steed and battle-dress of every king among them for ever, after his being inaugurated; and that the like should be given by them to the Ollamh, that is, to Mac Firbis.

Or, *if we believe others*, it was St. Gerald that baptized Dubhda^a, from whom the chiefs are descended, and it was Caomhan himself that obtained these privileges, together with many others (as we have stated in the genealogy), from Dubhda, in consideration of the chieftainship.

chapter, when they consulted about their revenues, and paid a certain yearly rent to the bishop, besides a fine upon the marriage of every of his daughters, which they call a *Loughinipy*," &c.

The term *Luach leasa* is frequently used by the Irish poets of the sixteenth century in the sense of omen of welfare. It is curious that our author has used the term *Luach leasa* instead of the *Luach impidhe* of the Book of Lecan; indeed it is likely that they are nearly synonymous, and the Editor is of opinion that the modern Anglo-Irish term luck-penny is derived from the latter.

^a *It was St. Gerald that baptized Dubhda.*

—This cannot be true, for it has been already shown (Note "u") that this Dubhda could not have been born before the year 823, whereas, we have the authority of the very accurate annalist, Tighernach, for the fact, that St. Gerald of Mayo died in 732. The truth is, that St. Gerald had nothing at all to do with this compact between the rival brothers Caomhan and Dubhda, but it is highly probable that his comharba, or successor at Mayo, may have interposed to settle their disputes.—See *Addenda*.

DUTHCHUSAIGH CLOINNE FIACHRACH.

DUTHCHUSAIGH CLOINNE FIACHRACH.

DO FHEARAIDH CEARA ANN SO
DUTHCHASDA.

i.e. ceud Ceara, umorro, trí ríoga fuirne, .i.
Nuireaboiḡ, O'ḡormóḡ, agus O'Tigearnaig.
é a fear agus a lán, .i. ó Ródba go Raḡain.
agus ó Phionnḡlaḡ go Máiteóig Ácaḡ gabair, amuil arpear
an rann :

O Ródba go Raḡain ruaid,
Crios Ceara corruḡ na rluaiḡ,

O

The initial letter T has been copied from the Book of Kells, fol. 38. The Society is indebted to Dr. Aquilla Smith for the drawing from which the wood-cut was engraved.

* *Hereditary proprietors.*—As the words *úeaiḡ*, *úeaiḡ*, and *úeaiḡ* occur so frequently in this topographical tract, it will be necessary to explain them here once for all. *Úeaiḡ*, which is still a

living word, signifies a tract of country hereditary in some family, as *úeaiḡ Seorḡeac*, i. e. Joyces' country, in the west of the county of Galway; *úeaiḡ an ḡhappaiḡ Mhóir*, i. e. Barry More's country, or patrimonial inheritance, in the county of Cork. *Úeaiḡ*, when applied philosophically, means inherent nature, innate instinct, but when used topographically it means a hereditary estate, or

HEREDITARY PROPRIETORS^a

OF

THE CLANN FIACHRACH.

OF THE MEN OF CEARA HERE.

HE triocha cheud^b of Ceara; there were three kings over it, namely, O'Muireadhaigh, O'Gormog, and O'Tighernaigh. Its full extent^c is from the Rodhba^d to Rathain^e, and from Fionnghlais^f to Maiteog^g of Achadh gabhair^h, as the rann states :

From Rodhba to Rathain the red
Is the country of Ceara, which the hosts defend,

From

patrimonial inheritance. *Óuēcāpōc*, which makes *óuēcāpōng* in the nominative plural, is a personal noun formed from *óuēcāp*, and signifies an inheritor, or hereditary proprietor. These three words seem to be cognate with the Latin *dos*, whence *dota-rium*, *doarium*, &c., in the mediæval Latin, are derived.

^b *Triocha cheud*.—This was the ancient Irish name for a barony or hundred, and

it appears from various authorities that it comprised thirty Ballybetaghs, or one hundred and twenty quarters of land, each quarter containing one hundred and twenty Irish acres. The Irish *Triocha cheud* would therefore appear to have been larger than the English hundred, or Wapentake, which consisted of ten towns or tithings, or one hundred families.

^c *Its full extent*.—The Rev. P. Mac

O Fhionnghlais, go a t-taúig coin,
Go Maiteog Achadh gabhair.

Taoiúdeact Uí Uada, agus Uí Chindócnaí, ó Mhaiteog go
Callainn, agus ó bhunpeanaí go h-Ábuinn na mallactan.

Tuata

Loughlin, in his abstract of the Book of Lecan, translates this passage thus:—"fol. 81, begins of the men of Ceara. This Tricha ceud had three lords (riga), viz., O'Muiredaig, O'Gormog, and O'Tigernaig, Its full extent in length and breadth,—*a feadh agus allan*—from Rodba to Rathain, and from Finglas to Maiteog Achadh Gobhair." This description of the extent of Ceara is not given in the topographical poem of Giolla Iosa Mor Mac Fírbis, from which it is evident that the prose account of the territories of Hy-Fiachrach was not wholly derived from that authority. As, however, this poem is the oldest named authority for the topography of Hy-Fiachrach, the topographical notes which might be here given, shall be reserved for the elucidation of that poem, and the Editor will only remark, in the notes to this prose list, such differences as appear between it and the poem.

^d *Rodhba*, now the River Robe, which anciently formed the southern boundary of the territory of Ceara, though it does not bound the modern barony of Carra, which retains the old name.

^e *Rathain*, the name of the northern boundary of Ceara, is now called Raithin; it is a townland containing a gentleman's seat, on the boundary between the baro-

nies of Carra and Burrishoole, a short distance to the west of the town of Castlebar.

^f *Fionnghlais*, i. e. the bright stream, was the ancient name of a stream forming the eastern boundary of the territory of Ceara, but it is now obsolete, and it would perhaps be idle to conjecture what stream it is, as the eastern boundary of the modern barony of Carra may not be the same as that of the ancient territory, but if we draw a line from Aghagower, which was on the western boundary of this territory, in an eastern direction, we shall find that it will meet a lake and small stream at Ballyglass, on the boundary of the baronies of Carra and Clanmorris; which stream may have been anciently called Fionnghlais.

^g *Maiteog of Achadh gabhair*.—This is said to have been the ancient name of Maus, or Mace, a townland a short distance to the east of the village of Aghagower, and which is now a considerable distance west of the boundary of the modern barony.

^h *Achadh gabhair*, now Aghagower, a village containing the ruins of an ancient church and round tower, in the barony of Murreask, and county of Mayo. This, though it pretty fairly represents the present pronunciation, is certainly

From Fionnghlais, which the hounds frequent,
To Maiteog of Achadh gabhair.

The chieftainship of O'h-Uada and O'Cinnchnamha from Maiteog to Callainn, and from Bunreamhar¹ to Abhainn na mallachtan¹.

not the true spelling of the name, for we have the authority of the most ancient lives of St. Patrick to show that the ancient form of the name was Achadh Fobhair, and even now it is pronounced *Áchadh Fhoḃhair*. The author of the Tripartite Life of St. Patrick speaks of this place as follows:—"Progressus Patricius pervenit usque in Umalliam, quæ est regio maritima occidentalis Connaciæ. Ibi extractæ ecclesiæ de *Achadh fobhuir* præfecit, et in episcopum consecravit, S. Senachum, virum vitæ innocentia et animi submissione celebrem."—Lib. ii. c. 62. And again, c. 68, "His peractis descendit de monte [Cruach Patraic] Patricius . . . ac in ecclesiâ jam memorata de *Achadh fobhuir* reliquam paschæ celebravit solemnitatem." Colgan, in a note, thus describes the situation of this place:—"Ecclesiæ de Achadh fobhuir est diocesis Tuamensis et comitatûs Mageonensis in Connaciâ. Et licet hodiè sit tantum parrochialis, et caput ruralis decanatus, fuit olim sedes Episcopalis."

The name Achadh gabhair, as in the text, would mean "field of the goat," but the correct ancient name, *Achadh fobhuir*, signifies field of the spring, and the place was so called from a celebrated spring there, now called St. Patrick's Well. Valancey, without knowing the original or-

The thography, translated the name Aghagower, *fire of fires*; and observed that though it was vulgarly believed to mean "ford of the goats," still he could not alter his own opinion of its meaning as long as the round tower, or *fire of fires* was standing at the place; in which process of reasoning he errs in both points of view, for the name does not signify fire of fires, nor does it appear that the tower ever bore such a name, or was used for a purpose that would support such a name, for it is now, and has been from the period of its erection, called *Cloigtheach Achaidh fhobhair*, i. e. the belfry of Aghagower.

¹ *Bunreamhar*, now anglicised Bunrawer, a well-known townland in the parish of Ballintober, in the barony of Carra, and joining the boundary of the parish of Aghagower.—See Ordnance Map of the county of Mayo, sheet 88. This name is not given in the poem of Giolla Iosa Mor Mac Firbis.

¹ *Abhainn na mallachtan*, i. e. the river of the curses. This is called Abhainn induar, i. e. the cold river, in the poem of Giolla Iosa Mor Mac Firbis, which affords an additional proof that the compiler of this prose list had other authorities besides that poem.—See note ¹, p. 152.

Tuata Partraighe ó Ait na mallactan go Glaisi Guirt na Lainne, agus ó Chaol go Fál, agus O'Dhoirniallais a ní, agus O'Dorcaide a taoirioc; no, taoirigeact Uí Dhoircaide amáin, do péir lebuir Shémuir agus Ghiolla Iora Mhic Fhírbirig.

O'Banan ó bhaile Uí bhanán, agus Maglin ó'n Mume, .i. dá Mhac Oglaioic.

Tuat Muige na beirge, .i. ó Callainn go h-Ulunó Caolainn, .i. react m-baile Luíortain, butaib Mec an bhanb.

O

^k *Partraighe*.—These boundaries of Partraighe are not given in the poem of Giolla Iosa Mor Mac Fírbis, and it will be therefore necessary to point out their situations in this place. The name of Partraighe, though not recognized as a baronial or parochial division, is still known in the country, and has been recently applied by the Poor Law Commissioners to a district nearly co-extensive with the parish of Ballyovey, in which there is a range of mountains still called Slieve Partry. It should be further remarked, that the parish of Ballyovey, anciently called Odbha Ceara, is always called the parish of Partry by the Roman Catholics, and that the seat of John Lynch, Esq., situated on Lough Carra, in this parish, is called Partry House, so that the name of this territory has not shared the fate of many others, which are locally lost.

^l *Ath na mallactan*, i. e. the ford of the curses or maledictions. This name is now lost, but the old natives of Partry believe that it was the name of a ford on a stream which rises in the mountain of Formna-

more, and discharges itself into Lough Mask.

^m *Glaisi Guirt na lainne*.—This name is now corrupted to Glais gort, or Glashgort, which is that of a townland in the parish of Ballintober.—See Ordnance Survey of the County of Mayo, sheet 99.

ⁿ *Caol*, now well known as the bridge of Keel,—*onoiceas an Chaol*,—which stands over the narrow strait connecting Lough Carra and Lough Mask, to the north-west of the town of Ballinrobe.

^o *Fal*, now Faul, and sometimes called Kilfaul, which is the name adopted on the Ordnance Map, a townland on the mearing of the parishes of Ballyovey and Ballintober, and bordering on Lough Carra.

^p *Baile Uí Bhanan*.—In Giolla Iosa Mor Mac Fírbis's poem it is expressed O'Banan ó baile féin, O'Banan of his own town, i. e. of the townland called after himself. It is still called Baile Uí Dhánán by the natives, who speak Irish very well, and anglicised Ballybannon or Ballybanaun. It is situated in the parish of Ballyovey, not far from the margin of Lough

The tuath of Partraighe^k extends from Ath na mallachtan^l to Glaisi Guirt na lainne^m, and from Caolⁿ to Fal^o. And O'Gairmiallaigh was its king and O'Dorchaidhe its toparch; or, it was the lordship of O'Dorchaidhe alone, according to the book of James and Giolla Iosa Mac Firbis.

O'Banan of Baile Ui Bhanan^p, and Magilin of Muine^q, i. e. two Mac Oglaoichs^r.

The tuath of Magh na bethighe^s *extends* from Callainn^t to Uluidh Caolainn^u, that is, the seven ballys of Lughortan, the estate of Mac an Bhainbh.

O'h-Aodha

Mask, and contains a Roman Catholic chapel. It is called Ballybanaan on Bald's Map of the County of Mayo.

^q *Magilin of Muine*.—O'Gillin in the poem. Muine, or Carrowmoney, is still the name of a hamlet and townland in the parish of Ballyovey or Partry.

^r *Mac Oglaoichs*.—This is not stated in the poem. The meaning of Mac Oglaoich is not given in any Irish Dictionary, but there can be little doubt that it was the same as the Galloglach of later ages.

^s *Magh na bethighe*, i. e. the plain of the birch. The extent of this district is not given in the poem. The name Magh na bethighe is now lost, but the alias name of Lughortan is well known, being that of a townland in the parish of Ballintober, containing the ruins of a castle said to have been erected by the family of Burke. It is anglicised Luffertaun, which represents the local pronunciation correctly enough, though the same name is rendered Lorton, and even Lowerton and Lower-

town in other parts of Ireland. The true Irish spelling, however, is *Luḡḡortán*, but the orthography was corrupted at an early period, for we learn from Cormac, in his Glossary, that *Luḡḡortan* was the form of *Luḡḡortan*, i. e. an herb garden, in his own time.

^t *Callainn*.—This, which was undoubtedly the name of a river, is now obsolete. It was probably the name of the Clareen river, which falls into Lough Carra. There is a river named Callan in the county of Armagh, another in Kerry, and the town of Callan, in Kilkenny, derived its name from the river on which it is built.

^u *Uluidh Caolainn*, i. e. the carn, stone altar, or penitential station of the virgin St. Caolainn, the patron saint of Termon Caolainn, in the parish of Kilkeevin, near Castlereagh, in the county of Roscommon. The Editor made every search and inquiry for Uluidh Caolainn, in the neighbourhood of Luffertaun, in the year 1838, but was not able to identify it, and is satisfied that

O' h-Aoda o bhaile Craoibe, .i. baile an Tobair.

Dutaid 1 Uatmaráin .i. baile Cagáil.

Dutaid 1 Leargura, .i. baile Chille Buaine.

baile puirt Ceara, .i. Fearc Lotair, agur Loc m-buaduib,
agur an t-Aonac.

Tuat Muige Fhiondalba, cois baile déc, .i. dutaid Uí Chearn-
nais, ó Chriannan Tonnais go Cairiol Cairpre.

Dutaid 1 Eðneacán tri baile Muige na Cnocaisge, agur tri
bhaile Riagain, .i. baile an Chriocáin buide, agur baile an rmo-
cáin, agur baile na Greallda, agur tri baile Fhiod Cruaice, .i.
baile Uí Ruairc, agur baile na Leargan móire.

Dutaid Uí Chiaraigín baile bel na lece.

Dutaid Uí Choigligh, .i. baile Capnan tonnaisde, no Ran ton-
naisde.

Dutaid Mec Giolla Phaolain, .i. baile Mhuige Roipen.

Dutaid

the name is lost, though the monument to which it was applied may remain.

^u *Baile Chille Buaine.* — This is called Baili Chillí Buanaindi in the Book of Lecan, fol. 82, b, a.

^v *It extends.* — This extent of Magh Fhiondalbha is not given in the Topographical Poem of Giolla Iosa Mor Mac Fírbis, which shows that this prose account of the estates and families of Hy-Fiachrach was not derived from that authority only.

^w *Baile Riagain.* — The three sub-divisions of the townland of Baile Riagain are not given in the poem.

^x *Baile an Chriochain bhuidhe,* now Creaghaunboy, in the parish of Magh Fhionnalbha, or, as it is anglicised, Moy-

nulla, or Manulla. — See Ordnance Map of the county of Mayo, sheet 79.

^y *Baile an smotain,* now the townland of Smuttanagh, in the same parish. There is a townland called Gortnasmuttaun, in the parish of Ballyhean. — See Ordnance Map of the County of Mayo, sheets 79 and 90.

^z *Baile na Greallda.* — This name is now obsolete, but it must have been applied to a denomination of land adjoining Creaghaunboy or Smuttanagh, in the parish of Manulla.

^a *Fíodh cruaike,* i. e. the wood of the round hill. The subdivisions of this townland are not given in the poem, and the third denomination is not added in the

O'h-Aodha of Baile Craoibhe, i. e. Baile an Tobair.

The estate of O'h-Uathmharain, i. e. Baile Cagail.

The estate of O'Learghusa, i. e. Baile Cille Buainne^u.

The chief seats of Ceara *are* Feart Lothair, Loch m-Buadhaigh, and Aonach.

The tuath of Magh Fhiondalbha, *containing* fifteen townlands, *is* the estate of O'Cearnaigh. *It extends*^v from Crannan Tornaighe (or Ran Tornaighe) to Caisiol Cairpre.

The estate of O'h-Edhneachain, i. e. the three townlands of Magh na cnocaighe, and the three townlands of Baile Riagain^w, viz., Baile an Chriochain bhuidhe^x, Baile an smotain^y, and Baile na Grealcha^z; and the three townlands of Fiodh Cruaiche^a, viz., Baile Ui Ruairc^b and Baile na Leargan moire.

The estate of O'Ciaragain, the townland of Bel na lece^c.

The estate of O'Coigligh, i. e. Baile Carnan tornaoidhe^d, or Ran tornaoidh.

The estate of Mac Giolla Fhaolain, i. e. the townland of Magh Roisen^e.

The

prose list, either as given by our author, or in the Book of Lecan. It should be also remarked, that neither the name of the large denomination nor any of those of its sub-divisions, are now retained in the barony of Carra.

^b *Baile Ui Ruairc*, i. e. O'Rourke's town, now Ballyrourke, a townland in the parish of Balla.—See Ordnance Map of the County of Mayo, sheet 90.

^c *Bel na leice*, i. e. mouth of the ford of the flag stone. This, which is called by the alias name of Baile an Bhealaigh, i. e. road-town, in the poem, is most probably

the present townland of Ballynalecka, in the parish of Ballintober, and barony of Carra. There is a Baile Ui Chiaragain, i. e. town of O'Ciaragain, now anglicised Ballykerrigan, in the parish of Balla.—See Ordnance Map of the County of Mayo, sheet 90.

^d *Baile Carnan Tornaighe*.—This is called Baile Crannain in both copies of the poem.

^e *Magh Roisen*.—This name is not given in the poem, for it is evidently not the same as Tuath Ruisen, mentioned in Note ^o, p. 156. It is evidently the present townland

Dútaid Uí Chuaáin, baile lír aiche, ar nír a deapap baile an regles.

Dútaid l Maolraite an t-Oipeam, agur an bpaonhor, an t-lomaipe, agur Cúl an daingín.

Dútaid Uí Fhaḡartaig, tpi baile Tulca Spealam.

Dútaid Uí bhpogan, Tulac Spealán.

Taoiriḡeact Uí Cheapnaig fóp, ceḡpe baile pícead Theap-muinn balla.

Do dútaid l Chaomáin i ḡ-Ceara, react m-baile Rora Laoḡ, .i. o Chluain Lír (no Ceara) Néllín ḡo beul áta na lúb; agur ó bhéul áta na ḡ-cárr ḡo Muileann Tiormáin; iar na faḡbál do Chaomán, mac Connmaig, ó Dhubba, ó n-a deapbrátaip, agur do Aoḡ ó Caomán, ó Aoḡ, mac Ceallaiḡ Uí Dhubba, o Ríḡ Ua b-Fiaḡrac; uair n ffríot tuat ḡan duḡcupac do clannuip Epc Chúlbuíde ḡan a díon do dúḡcup aice, act an tuat eolac aité-eacba

of Rusheen, lying between Clogher and Lisrobert.—See Ordnance Map of the County of Mayo, sheet 100.

^f *Baile Lis aiche*.—Not in the poem.

^g *Baile an Regles*.—This is called An Regles, i. e. the church, in the poem, but it is mentioned as the property of Mac Gilla Fhaelain, and O'Cuachain is omitted altogether. The name O'Cuachain is, however, still in the district, but disguised under the anglicised form of Gough.

^h *In Ceara*.—O'Caomhain had other estates elsewhere.

ⁱ *Ros laogh*, now Rosslee, a parish in the barony of Carra, lying about six miles south south-east from the town of Castlebar, on the road to Hollymount. This

name is not given in the Topographical Poem of Giolla Iosa Mor Mac Fírbis, nor are the limits of O'Caomhain's estate, in Ceara, mentioned, except under the name of Tuath Ruisein.

^j *Chlain Lis Néllín*, now obsolete.

^k *Beul atha na lúb*.—This name is still well known in Carra, it being the Irish name of Newbrook, the seat of Lord Clanmorris.

^l *Beul atha na g-carr*, now the townland of Ballygarries, in the parish of Ballyhean, and barony of Carra.

^m *Muilen Tiormáin*.—This name is still retained, but somewhat corrupted, being anglicised Mullencromaun, which is a townland in the parish of Drum, in the

The estate of O'Cuachain *is* Baile lis aiche^f, which is called Baile an Regles^g.

The estate of O'Maolraite *is* Oireamh, and Braonros, Iomaire, and Cul an daingin.

The estate of O'Faghartaigh, the three townlands of Tulach Spealan.

The estate of O'Brogain, Tulach Spealain.

The lordship of O'Cearnaigh also *comprised* the twenty-four townlands of the Termon of Balla.

The estate of O'Caomhain, in Ceara^h, *comprised* the seven townlands of Ros laoghⁱ, i. e. *the tract extending* from Cluain Lis Nellin^j to Beul atha na lub^k, and from Beul atha na g-carr^l to Muilenn Tiormain^m, which estate was obtained by Caomhan, son of Connmhach, from Dubhda, his *own* brother, and by Aodh O'Caomhain from Aodh, son of Ceallach O'Dubhda, King of Hy-Fiachrach, for there was found no district without its hereditary proprietor of the race of Earc Culbhuidhe, except this well known Attacottic districtⁿ, named Tuath Ruisen ;

barony of Carra.

^a *Attacottic district.* — Τῡατ Αἰθεαχά, i. e. territorium Attacotticum, or a district not in the possession of freemen of the Scotie or Milesian blood, but occupied by a tribe of the Firbolgs, the remnants of whom, wherever they were seated, were styled Aitheachs, i. e. Attacotti or Plebeians, by their conquerors. This district is not called Tuath Aitheachda in the poem of Giolla Iosa Mor Mac Firbis, which shows that the compiler of this prose list had his information from other sources. It is very curious to find that a part of

the district here described still retains the name of Tuath Aitheachda, now anglicised Touaghty, for it is the name of a small parish near Beal atha na lub, or Newbrook, in the barony of Carra. The copy of this prose tract, in the Book of Lecan, adds, that this district was conferred on O'Caomhain by O'Dowd, in consequence of his nobility and relationship to the latter, and that it continued in the possession of that family from that to the time of the writer. Ὁ δὲ κόμητᾶς υἱαὶ τοῦ ἀποβατεῖται, κομᾶς ποιεῖται οὐκ ἔστιν ὁ πῶν ἰλλε ἢ τῡατ πῶν.

eaóda rin, .i. Tuat Ruiren a h-ainm, comó puóilir dúócurá do Ib Caomhain í ó rin alle, genmoéta ioltuatá ele ol céana.

Toirigeaét Uí Ruaidín, ó dhéal áta na lub go Tócar Chillín na n-garg, agur ar d'á n-dúócur Uí Chulucáin.

Tairigeaét Uí Dhiern ó tócar Chillín na n-garg go beul áta na perid, agur Róibín beag do'n leat éoir, agur o t-Diúín Ciapáin go Tobair Lúgna.

Tairigeaét Uí Dhoirmgiolla ó Thobair Lúgna go beul Chaoil Partraige, agur ó Róóba go Raiteann, .i. reaét m-baile go leé.

Tri baile an Chriatraig dútaid Uí Mhaoilcána, agur Meic Giolla buide, ó Chillín na m-buidean 'r a' Chriatrac.

Dúócurag Ceara go nuici rin. Giolla an Dhoill Mag Nell, ri dégeanaé no gab Ceara do Dhaoidéaluib; pe lín Taitlíg Mhoir, mic Aóda I Dhubda, no gab ó Róóba go Coónuig, agur a aónacal i m-baile Thobair Pátraig. [Ir h-é pob' earboc pe lind na rig rin, .i. Mael Ipa Mag Mailin.]

CLANN

^o *Tuath Ruiren.* — This, which is the only name for O'Caomhain's estate, in Ceara, given in the poem, is evidently the true ancient name of the territory. Roslaogh, the first name for it, given in this prose list, is evidently the ecclesiastical name of the district, or name of the parish, which was derived from the situation of the parish church in the townland of Roslaogh, now Rosslee.

^p *Cillin na n-garg,* is written Cill na n-gragal in the Book of Lecan, but in both copies of the poem it is Cillin na n-garg, as in the text, which seems to be the true reading.

^q *Baile Tobair Padraig,* i. e. the bally or

townland of St. Patrick's well, now Ballintober, in the barony of Carra, and county of Mayo, where there are the magnificent ruins of a monastery erected by Cathal Croibhdhearg, or Charles the Redhanded O'Conor, in the year 1216.

^r *O'Culachain.* — This name is to be distinguished from Mac Uallachain of Hy-Many, though both are now anglicised Cuolahan. The name O'Culachain is still in Carra, and sometimes correctly anglicised Coolahan.

^s *And the person who was bishop.* — The portion of this passage enclosed in brackets is taken from the copy of this prose list, preserved in the Book of Lecan. The Rev.

Ruisen^o; so that it has been the hereditary patrimony of the *family* of O'Caomhain ever since, besides many other districts.

The lordship of O'Ruaidhin *extends* from Beul atha na lub to the causeway of Cillin na n-garg^p, and of his tribe is the family of O'Culachain^a.

The lordship of O'Birn *extends* from the causeway of Cillin na n-garg to Beul atha na sesidh, Roibin beag being on the east side; and from Sighin Ciarain to Tobar Lughna.

The lordship of O'Goirmghiolla *extends* from Tobar Lughna to the ford of Caol Patraighe, and from the Rodhba to Raithleann. It contains seven townlands and a half.

The three townlands of Criathach *are* the estate of O'Maoilcana, and of the family of Mac Giolla bhuidhe of Cillin na m-buidhean, in Criathrach.

So far the hereditary proprietors of Ceara. Giolla an Ghoill Mac Neill was the last King of the Gaels, who possessed Ceara: he was cotemporary with Taithleach Mor (son of Aodh O'Dubhda), who took possession of the country extending from the River Rodhba to the Codhnach, and was interred at Baile Tobair Padraig. [And the person who was bishop^r in the time of these kings was Mael Isa Mag Mailin].

CLANN

Patrick Mac Loughlin, in his abstract of the Book of Lecan, thus renders this passage:—"Gilla an Ghoill Mac Neill was the last lord of Ceara, in the time of Taithleach Mor, son of Aodh O'Dowde, and" [recte *who*] "possessed from Rodba to Codnach, and was buried at Bally tobair Padraig. Their cotemporary bishop was Maelisa Mac Mailin." The name of this last lord or King of Ceara, of the ancient

Irish race, is not given in the poem of Giolla Iosa Mor Mac Firbis, nor in the Irish annals. Taithleach Mor, the son of Aodh O'Dubhda, or O'Dowda, who was cotemporary with him, was killed in the year 1197, according to the Four Masters. The Bishop Mael Isa Mac Mailin would seem to have been Archbishop of Tuam, but no notice of him is found in the Annals of the Four Masters, or in Ware's Bishops.

CLANN CUAIN SIOSANA.

Clann Cuain umorpo, aada nearam do Cheara ian n-gaol
genealaig, uair ar do cloinn Epc Cúlbuide, mic Fiacrac, dóib
apson.

O'Cunn, O'Maoilfíona, agur Mag Phlannagair, tri taoiriú
Cloinne Cuain. Agur Fír Thipe ainm ele ói, agur Fír Siúipe a
h-ainm ele, o'n abainn d'án h-ainm Siúipe céo láim re Cairlen an
bharrraig amuig.

Cuan (mac Eacac, mic Floinn, mic Fearadraig, mic Rora
Doiméig, mic Maine Muinbrioc, mic Epc Culbuide, mic Fiacrac),
ar dia cloinn Clann Cuain co n-a cineaduib, amuil arperc an
pánn:

Cuan Mop, mac Eacac féil,
Uada Clann Cuain claid-réó,
Agur Fír Típe na d-creab,
Óine gan cion ó credeam.

Ar

^c *In point of genealogical relationship.*—
Vide supra, page 17, where the genealogy
of Cuan, the ancestor of the Clann Cuain,
is given.

^u *A river of the name Siuir.*—This river
is not mentioned in the poem, and the
name is now obsolete, unless Toormore
river be a corruption of it.

^v *Caislen an Bharraigh*, written Caislen
an Bharraich in the Book of Lecan, fol.
82, b, b. This is the name by which the
town of Castlebar, in the barony of Carra,
is called at the present day, and in the
Annals of the Four Masters at the years
1412, 1576, and 1582. It signifies the

castle of Barry, or Barry's castle, and there
can be no doubt that it received that name
from a castle erected there shortly after
the English invasion by one of the family
of De Barry, who was afterwards driven
out. Downing, who wrote a short descrip-
tion of the county of Mayo, about the year
1680, for Sir William Petty's intended
Atlas, thus speaks of this town:

"Next to Belcarra, four miles distant,
stands Castle-Barry, a corporation. It is
called in the king's writ the most western
corporation, and a very fair, large bawn
and two round towers or castles therein,
and a good large house in the possession

CLANN CUAIN DOWN HERE.

The Clann Cuain are the next to *the men of Ceara* in point of genealogical relationship¹, for they are both of the race of Earc Culbuidhe, the son of Fiachra.

O'Cuinn, O'Maoilfhiona, and Mag Fhlannagain *were* the three chiefs of Clann Cuain. They are otherwise called Fir Thire, and also Fir Siuire, from a river of the name Siuir², which flows by the town, at this day called Caislen an Bharraigh³.

Cuan (son of Eochaidh, son of Flann, son of Fearadhach, son of Ros Doimtheach, son of Maine Muinbreac, son of Earc Culbuidhe, son of Fiachra) is the ancestor of the Clann Cuain with their correlatives, as the rann says :

Cuan Mor, son of the generous Eochaidh,
From him *are* the Clann Cuain of smooth mounds,
And the Fir Thire of tribes,
A people without fault in faith.

The

of Sir John Bingham, and his heir, the youngest of the three knights Bingham that commanded since Queen Elizabeth's time; that is, he left it to Sir Henry Bingham's nephew, having no issue of his own body. This castle did formerly belong to the Burkes; first of all after the invasion it is said to have belonged to the Barrys, of whom it took its name."

Again, in speaking of the priory of Ballyhaunis, the same writer has the following notice of the family of Barry having had possessions in this country:—"It" [the priory of Bellahawnus] "stands on

a fair hill over a small river. It is said to have been, before the foundation thereof, a manor-house belonging to the Lord Barry, about the beginning of the English invasion. Certain it is, that upon the beginning thereof, the Fitzgeralds, ancestors of the Earls of Desmond and Kildare, the Lord Barons of Kerry, and the Barrys had large possessions in the counties of Mayo and Sligo, till they were driven thereout by one Burke." He might also have added the family of Butler, for the abbey of Burrishoole was erected by one of them shortly after the English invasion.

Ar í focáinn rgaréana Cloinne Cuain agus Fhear Thíre ne Clannuib Phiaépac, .i. Ruaidhri Mear, mac Taithleig, mic Neill i Dubda, ní 'gá raibé ó Ródba go Coðnaiḡ, do éuaib ar cuairt nḡ go teac Dhomnuill Uí Cuinn, éaoirḡ Cloinne Cuain; agus ar amluib do rála inḡean áluinn aontuḡa ag O'Cuinn an tan rin, agus nḡ gáb O'Dubda gan a beḡ aige a b-fóiréḡean in oibce rin, gur po mairb O'Cuinn i b-fill epion iar na máraḡ, agus do éuaib fén fo dídean Cloinne Maoilruanaib, .i. go Tomaltac Mor Mac Diarmada, agus tugraḡ iad fén, agus a n-dúḡcur dóib ó rin gur anuḡ.

Conib Fír Thíre éuar, agus Fír Siuiré abur iad rin ó'n abainn, amuil a dubḡamar noḡuinn.

CRIOCHAIREACHT UA N-AMHAILGAIÐH, AGUS UA DH-FIACH-
RACH ANNSO, CO N-A N-DUDHCHUSACHAIÐH.

Á h-lorruir ceudamur epnḡḡear an céud dúḡar.

O'Caiteaḡ, umorpo, uirriḡ lorraiḡ, agus O'Ceallaḡáin toirioḡ
lorruir.

^w *Ruaidhri Mear, the son of Taithleach O'Dubhda.*—See Notes to the poem of Giolla Iosa Mor Mac Firbis.

^x *Tomaltach Mor Mac Dermot.*—This sentence should be written thus: "So that O'Cuinn slew him treacherously on the next day, and then fled and placed himself under the protection of the Clann Maoilruanaidh, of whom Tomaltach Mor Mac Dermot was the chief," &c. The Rev. P. Mac Loughlin, in his abstract of the Book of Lecan, understands the above passage as follows:—"Thus were the Clan Cuain, or Fir Tíre, separated from the Clan Fiachra, viz., Roderick Mear, son

of Taithleach, mac Neill O'Dowde being prince from Rodba to Codnach, and going on his *cuaird rig* to the house of Donal O'Quin, the dynast of Clan Cuain, whose beautiful daughter was forcibly dishonoured by that lord. In revenge the father killed him the following day, and fled for refuge to Clan Maelruana, to Tomultach Mor Mac Dermot, who protected him and gave him his *duchas*." This is well explained, except the last clause, "and gave him his *duchas*," which conveys a wrong idea, for the meaning of the original is, that O'Quin transferred his *duchas*, or patrimonial inheritance, to Mac Dermott,

The cause of the separation of the Clann Cuain and the Fir Thire from the Clann Fiachrach, was this: Ruaidhri Mear⁷, the son of Taithleach, son of Niall O'Dubhda, a king who had possession of *the country extending* from the Rodhba to the Codhnach, went on a regal visitation to the house of Domhnall O'Cuinn, chief of Clann Cuain; and it happened that O'Cuinn had at that time a beautiful marriageable daughter, and O'Dubhda did not content himself without getting her by force that night, so that O'Cuinn slew him treacherously on the next day, and went himself under the protection of the Clann Maoilruanaidh, viz., of Tomaltach Mor Mac Dermot⁸, and they [*the Clann Cuain*] gave themselves and their patrimonial inheritance up to them, *which continues so* from that to the present day.

These are called Fir Thire upper, and Fir Siuire abhus (*citra*) from the river, as we have said before.

THE TERRITORIAL DISTRIBUTION OF HY-AMHALGAIDH⁷ AND HY-FIACH-RACH⁸ HERE; WITH THEIR HEREDITARY PROPRIETORS.

In Iorrus first the first estate is bestowed.

O'Caithniadh *was* the chief of Iorrus, and O'Ceallachain the toiseach.

and acknowledged him as his chief lord in place of O'Dowd, to whom, in consequence of his barbarous conduct, he refused to acknowledge fealty for the future.

⁷ *Hy-Amhalgaidh*, now the barony of Tirawley, in the county of Mayo, still called in Irish Tir Amhalgaidh, i. e. the land or territory of Amhalgaidh. It derived that name from Amhalgaidh, King of Connaught, the brother of the monarch Dathi.—See list of the Kings of Connaught further on, and Ussher's Primor-

dia, p. 864, also O'Flaherty's Ogygia, Part III. c. 87.

⁸ *Hy-Fiachrach*, must be here understood as applied to Tir Fhiachrach Muaidhe, or the barony of Tireragh, not to the entire territory of the Hy-Fiachrach, which extended from the River Robe to the River Codhnach at Drumcliff, below the town of Sligo. The people inhabiting this district derived the patronymic appellation of Hy-Fiachrach, i. e. Nepotes Fiachrii, from Fiachra Foltsnathach, the

lorruir. brygāda lorruir, .i. Mec Coinín, agus Uí Conboirne agus Uí Muirneacán, agus Uí Gearadóin, agus Meḡ Fhíonáin.

Dúdcuairḡ Dúna Fíne, .i. Uí Cuinn, agus Meḡ Oðráin, agus Uí Cóimóin, agus Uí Duibleargā, agus Uí deargā, agus Uí bliḡe, agus Uí Duanmaḡe; O'Radubáin ó bhaile an ḡleanḡa. Mec Conletrpeac ó bhaile Mec Conletrpeac, O'Congáile, agus O'Caé-urairḡ, airéinnirḡ Cille Arub. Taoirioḡ an Lagáin, .i. O'Muir-eaḡoirḡ; O'Fionnagáin ó'n Fhionncáilain.

FINEADHA NA BREUDCHA SUND.

O'Toḡda taoirioḡ na breudca; O'Luacán ir in leḡ éiar do'n bhréudairḡ, agus Ua ḡilin; O'ḡloinín ó Ráit na n-ḡoirnḡiall; O'ḡáibḡeacán, agus O'Maoilḡfíona, dá taoirioḡ Chalraḡe; O'Flainn, brygáid Muirḡe h-Eleag; O'Laḡtḡna, taoirioḡ an Da bhac, agus ḡleanḡa Nemḡinne; Laḡtḡna Mac Fírḡbirirḡ; O'Flann-ḡaile ar Loḡ ḡlinne co n-a fearann; O'Floinn i n-Oirḡeáin Loḡa Con; O'Maoilḡuanaid ó h-Arḡacáid, agus ó Chill dealaḡ, no o Chill Ealaḡ; O'h-Eneacán o bhaile Uí Eineaḡáin; O'Leaḡcaile ó bhaile Muirḡe Fuara; Mec Conlena ó Chill moir Muairḡe; O'Dubagáin, agus Uí Airmeaḡoirḡ, ó Loḡ Muirḡe bryón; Clann Fhírḡbirirḡ, fíleaḡa Ua n-Amalḡaid, ó Ror Sepece.

Uí Eacac Muairḡe, .i. ó Ror Sepece ḡo fearraḡo Tpeiri, ar iad ro a cineadairḡ, .i. Uí Maoilḡraḡmair, comorbaḡa Cille h-Allaid, agus Ua Leandáin, Ua Criaḡdḡén, Ua Laḡtḡle, Ua Moḡáin, Ua Maoilairḡḡen, Ua bryoduib, agus Ua Maoilbryenninn.

Ir

father of King Dathi; and the inhabitants of Tireragh received their name of Hy-Fiachrach Muaidhe from Fiachra Ealgach, the son of King Dathi, and grandson of the great ancestor of all the Hy-Fiachrach. It should be remarked that

the descendants of this latter Fiachra subdued the Hy-Amhalgaidh at an early period.

* *Fionnchalamh*, i. e. the fair callow, strath, or holm. This place is not mentioned in the poem, and the name being

toiseach of Iorrus. The Brughaidhs of Iorrus *were the families of* Mac Coinin, O'Conboirne, O'Muimhneachain, O'Gearadhain, and Mag Fhionain.

The hereditary proprietors of Dun Fine *were the families of* O'Cuinn, Mag Odhrain, O'Comhdhain, O'Duibhlearga, O'Bearga, O'Blighe, O'Duanmaighe, O'Radubhain of Baile an ghleanna, Mac Conletreach of Baile Mec Conletreach, O'Conghaile and O'Cathasaigh, airchinnechs of Cill Ardubh. The chief of the Lagan *was* O'Muireadh-aigh; O'Fionnagain of Fionnchalamh^a.

THE TRIBES OF BREUDACH^b [ETC.] HERE.

O'Toghdhawas chief of Breadach; O'Luachain, in the western side of Breudach, and *also* O'Gilin; O'Gloinin of Rath na n-goirmghiall; O'Gaibhtheachain and O'Maoilfhiona, *were the two* chiefs of Calraighe; O'Flainn, brughaidh of Magh h-Eleag; O'Lachtna *was* chief of the two Bacs, and of Gleann Nemhthinne; Lachtna *was* a Mac Firbis; O'Flanngaile *was* over Loch Glinne, with its land; O'Floinn in Oireamh of Loch Con; O'Maoilruaidh of Ard achadh and of Cill Bealad, or Cill Ealad; O'h-Eineachain of Baile Ui Eineachain; O'Leathcaile of the townland of Magh Fuara; Mac Conlena of Cill mor Muaidhe; O'Dubhagain and O'Airmeadhaigh of Loch Muighe Broin, *and* the Clann Firbisigh, the poets of Hy-Amhalgaidh of Ros Serce.

Hy-Eachach Muaidhe extends from Ros Serce to Fearsad Tresi. These are its tribes, viz., O'Maoilfaghmhair, comharbas of Cill Allaidh, O'Leannain, O'Criaidhchen, O'Laitile, O'Mochain, O'Maoil-aithghen, O'Broduibh, and O'Maoilbhrenuinn.

The

lost, it cannot be now satisfactorily identified. It appears from the poem that it was a part of the Lagan, and evidently the south-eastern part of it, adjoining the territory of the Hy-Eathach Muaidhe.—

Vide supra, p. 51.

^b *The tribes of Breudhach here.* — This section includes more than the tribes of Breudach, and the Editor has therefore taken the liberty to add "&c." in brackets.

Ir iad ro cineadais an Chaille (no Chaoile) Chonuill, agus ar ead fead an Chaille, ó Fhearraio Tperi go Traig Murbais, .i. Traig Ceall, agus bo tuais go Cill Cuimín, .i. Ua Dperi, Ua h-Aoda Aird O'n-Aoda, Ua Maolconaire, Ua Flannabha, agus Ua Sehra, agus arr dís Uí Chongadán, no Chonnagáin ó Muig gamnac, O'h-Aráin o Ardgabail. Dutaó an Chaeille ono baile na Leacan ó Fhearraio Go Traig Murbais, gc., a ver lebur ele.

DUDHCUSAIGH TIRE FIACHRACH SIOSANA.

Dutaio Uí Mhóráin, .i. Ard na rias, agus a taoirigeact, .i. an tuat ar ran go Tuaim da Odar; O'bhóráin ó bhectmaigh.

Cepte taoirig fóir Chúil Chearnaða, ó dheul Áta na n-íeadh go bealac bheuctmige, .i. Ua Fionnain, Ua Roeláin, Ua Ionnáin (no Ua Tuatáin), agus Ua Cuinn, O'h-Eana i n-Imleac Loirge. O'Gealágan ó Chill lochtair, .i. an Shráinrioc; O'breplén o Chill Phainle, no Ainle.

Dutaio Uí Chaomáin, ó Thuaim dá bheadh go Gleoir, agus ar iad a pineada dudcra, .i. mac Cailleacán, no Caoilleacán, no Celeacán ó'n Cháir, agus O'Coitil, ó bhaile Uí Choitil, O'Floinn ó'n bheartraig, agus ó Mhuicuib, O'Moáine, ó bhaile Uí Mochuine; O'h-Iomair ó Leacan; Clann Fhirbairig ó Leacan Meic Fhirbairig iaram, baile ar learaigio lebar airpion, annalac, duan, agus ríol reancura, agus i n-ar éoguib, eó cian iaram, Cioctruaio, agus Sémur, dá mac Diarmada Caoic Meic Fhirbairig, agus

^c *Tir Fhiachrach*, pronounced Tiriachrach, now the barony of Tireragh, in the county of Sligo.

^d *Beul atha na n-idheadh*, i. e. mouth of the ford of the washings. This name is not given in the poem, in which the boun-

daries of Cuil Cearnadha are differently described. Beal atha na n-idheadh is still well known, and is the name of a ford on the Abhainn bhuidhe, or Yellow river at Moorbrook, about a mile and a half north from the little town of Fox-

The following are the tribes of Caille (or Caoille) Conaill, which extends from Fearsad Tresi to Traigh Murbhaigh, that is, Traigh Ceall, and northwards to Cill Cuimin, viz., O'Derig, O'h-Aodha of Ard O'n Aodha, O'Maolchonaire, O'Flannabhra, and O'Seaghsa. And of them *also* are *the families of* O'Congadan, or O'Connagain of Magh gamhuach, O'h-Arain of Ardgabhail. The district of Caeille is Baile na leacan, from the Fearsad, to Traigh Murbhaigh, &c., according to another book.

THE HEREDITARY PROPRIETORS OF TIR FHIACHRACH^c DOWN HERE.

The estate of O'Morain, i. e. Ard na riagh, and his chieftainship the district thence to Tuaim da Odhar. O'Brogain of Breachmhagh.

There *were* four chiefs over Cuil Chearnadha, *which extends* from Beul Atha na n-idheadh^d to the road of Breachmhagh, namely, O'Fionain, O'Rothlain, O'h-Iornain (or O'Tuathalain), and O'Cuinn. O'h-Eana of Imleach loisge; O'Gealagain of Cill Iochtair, i. e. Grainseach; O'Breslen of Cill Fhaindle, or Cill Ainne.

The country of O'Caomhain *extends* from Tuaim da bhodhar to Gleoir, and his hereditary tribes or retainers *were the families of* Mac Cailleachan, or Caoilleachan, or Ceallachan of Carn; O'Coitil of Baile Ui Choitil; O'Floinn of Beartrach and of Mucdhubh; O'Mochaine of Baile Ui Mhochaine; O'h-Iomhair of Leacan;—(the Clann Fírbhisigh were of Leacan Mhic Fhírbhisigh afterwards, where they wrote books of history, annals, poetry, and *kept* a school of history; and where, a long time after *their original settlement there*, Ciothruaidh and James, the two sons of Diarmaid Caoch Mac Fírbis, and

ford, in the barony of Gallen, and county of Mayo. Travellers going from Foxford to Ballina cross this ford; and there are four heaps of stones with sticks ex-

tended between them, forming a kind of rude bridge across it, which is frequently carried off by the heavy floods to which the Abhainn bhuidhe is subject.

agur Seasan Oḡ, mac Uilliam, dearbbrátair a n-áta, cairlen
 Leacain Mec Fhirbiriḡ, an bliadain d'aoir Chriost, 1560;—
 O'Loingriócain ó Mhullaḡ páta; O'Sbealain ó'n Choillín, agur
 ar é do rinne an páit mór. O'Fualairḡ ó Rait dearcáin;
 O'Condaḡtain ar in Cabraiḡ.

baile puirt Uí Chaomáin, .i. Sairdín Uirge tar abainn, d'á
 n-ḡoirḡear Inir Sḡneabainn. Ḥé áirníḡear Clann Néll do ḡabail
 an fearuinn rin, ní tpe ḡearc duḡḡura ro ḡabrad, áḡ ar éḡin,
 iar marbaḡ Daibid Uí Chaomáin, agur Domnaill Uí Chaomáin,
 ḡo raibḡ Clann Néll tpeall 'ra tairiḡearḡ, ḡur marbaḡ Niall,
 mac Nell la Muirḡearḡaḡ b-Fionn Ua Caomáin : n-díḡail a
 porba.

O Ḥhleoir ḡo h-lairḡaḡ, O'Muirḡaḡa, no O'Maoilbuidin a
 tairiḡoch. Duḡaid Uí Ruadḡraḡ Liacon, agur loḡtar Ráta.
 O'Fenneaḡa ó Finnḡid, ḡur bean Muirḡear Flannḡaile d'ib í, déḡ
 a ḡ-cora ó n-duḡḡur ó loḡ anuar do Ḥhallaid; O'Maoilbuidin
 a h-lmleac írioll; ó Luacáin ó Ror Laoḡ; ó Duirḡḡaile ó Dún
 Maoilbuidin

* *In the year 1560.*—This passage about the settlement of the Mac Fimbises, at Lecan, is added by our author. There is no mention of the Mac Fimbises being at Lecan in the copy of this prose list preserved in the Book of Lecan, or in the poem of Giolla Iosa Mor Mac Fimbis. This castle does not appear to have been a full century in the possession of the Mac Fimbises, for it is stated in an Inquisition taken at Sligo on the 22nd of August, 1625, that Donnogh O'Dowde was seized of the castle, town, and quarters of Lackan M'Fimbissey and other lands, which he settled by deed, dated the 20th August,

1617, to the use of his wife Onora Ny Connor, for their lives, and then to the use of his own right heirs. This castle is still standing, and now known by the name of Castle Forbes. It is situated east of the Moy in the parish of Kilglass, barony of Tireragh, and county of Sligo.

† *That erected the great rath,* i. e. that formed the great rath or earthen fort in the townland of Coillin. This fact is not mentioned in the poem. The townland of Culleen is situated in the parish of Kilglass, in the barony of Tireragh; it contains several small raths or forts; that which is here called the Rathmor or the

and John Og, the son of William, their father's brother, erected the castle of Leacan Mac Fírbis, in the year of the age of Christ 1560^e;)—O'Loingseachain of Mullach Rathá; O'Sbealain of Coillin, and it was he that erected the great rath^f; O'Fualairg of Rath Bearchain; and O'Connachtain of Cabrach.

The chief seat of O'Caomhain *was* Saidhin Uisge tar abhainn, which is *otherwise* called Inis Sgreabhainn^g. Though it is said that the Clann Neill took these lands, it was not by hereditary right they took them, but by force, after having slain David O'Caomhain and Domhnall O'Caomhain, so that the Clann Neill were for a while in the chieftainship, until Niall, son of Niall, was slain by Muircheartach Fionn O'Caomhain, in revenge for *the loss of* his land.

Of *the tract extending* from the river Gleoir to the Iasgach O'Murchadha, or O'Maolduin, *was* the chieftain. The estate of O'Ruadhrach *was* Lia Con, and Iochtar ratha. O'Fenneadha *was proprietor* of Finnghid until the family of O'Flannghaile^h took it from him, after they had been driven from their *own* estate from the lake downwards by the English. O'Maolduin of Imleach iséal; O'Luachain of Ros laogh; O'Duibhscuile of Dun Maoilduibh. The estate

great fort, was probably at the hamlet of Rath macarkey, at the east side of the Culleen river, but it is now effaced.

^g *Inis Sgreabhainn*, called Sais Sgreabhainn in the poem, but probably by a mistake of the transcriber. This place, which is now called in English Inishcrone, is styled Eiscir abhann, in the Annals of the Four Masters, at the year 1512, and Uskarowen Castle, on an old Map in the State Paper Office, London, showing part of the coast of Donegal, Leitrim, and

Sligo, on which it is placed, near the margin of the "Bay of the Moye" (now Killala bay), opposite the Island of Bartragh, and in the parallel of Killala.

^h *O'Flannghaile*, now Flannelly. It is stated in the poem that the O'Flannellys took possession of this land after the extirpation of the family of O'Feineadha, but no allusion is made to the expulsion of the O'Flannellys from the lake by the English.

Maoilbuiḡ. O'Rothlain ar í a dúctaid Cluain na g-Chiabac, agus Alc Phapannain, gur beanrao Muincir Maonaig dís tre meabuil naḡ rḡriobtar ruid. O'beollan ó Dhún Ulltain; ó Conbúide ó bhaile Mec ḡiollaḡair, agus ó Dhún Nell mic Conbúide, agus Cuanán mac Conbúide, ó b-ḡuil Rait Cuanáin, agus áirmitḡear gur ob é O'Conbúide ar taoirioc ó Dhún Néll go Muirḡe; agus a deḡ Leabair balb Shémuir Mic Fhírbirig, gur ob é O'Conbúide ba taoirioc ó bheul Aḡa Cliaḡ Muirḡe go h-larḡaig. Mec Eóḡain agus Uí Cuanán ó Dhun m-becin; O'Diḡin ó bhaile Uí Dhiḡcín; ó Dunḡaile, agus O'Suibḡearḡa, agus ó Cuain, ó Dhún Uí Chobḡaig; O'Colmain o'n n-ḡráinrig Mhóir; O'Fuala o'n n-ḡráinrig bhirig; O'Ceallair ó Aḡo O'ḡ-Ceallair; O'Loimḡirig, agus O'Caomain an Chuiririg ó Mhuine na b-ḡiaḡ [no Muine diaḡ anu].

O'Flannḡaile i n-Eaḡor; Mac ḡiolla na n-eaḡ, Uí Phlannḡaile, agus Mac ḡiolla duib 'ḡna Copcaḡaib; O'Sionna a Láḡraḡ. Colamuin na ḡḡríne, .i. Mec Concaḡraḡ, agus Uí Oilḡec, agus Meḡ Ródaḡ, agus Uí Sneadairna, agus O'Rabairḡaig. Lebup balb

¹ *By a treachery which shall not be written here.*—This is not in the copy of this prose list preserved in the Book of Lecan, and it seems to have been added by our author from the Dumb Book of James Mac Firbis, which seems to have recorded many curious historical facts, which the families then in possession of tracts of land wished to suppress.

² *Niall, son of Cubuidhe*, i. e. the Niall after whom Dun Neill, i. e. Niall's fort, was called, was a son of Cubuidhe, the progenitor of the family of O'Conbuidhe, now Conway; and the Cuanan from whom

the fort of Rath Cuanain derived that appellation, was another son of the same Cubuidhe. It should be here remarked that the word *Cu*, which enters so largely into the proper names of men in Ireland, makes *Con* in the genitive case, and *Coin* in the dative or ablative. It signifies literally a dog, and figuratively a hero or fierce warrior, and is translated *canis* by the original compiler of the Annals of Ulster.

³ *From Ath cliath Muirege.*—This is not in the copy of this prose list preserved in the Book of Lecan, and has been added

estate of O'Rothlain was Cluain na g-cliabach and Alt Fharannain, until the family of O'Maonaigh deprived them of it by a treachery which shall not be written here¹; O'Beollan of Dun Ulltain; O'Conbhuidhe of Baile Mec Giollachais, and of Dun Neill, *which is called from Niall*, son of Cubuidhe¹, and Cuanan, from whom Rath Cuanain, *was another* son of Cubuidhe; and it is said that O'Conbhuidhe *was once* chief of the tract extending from Dun Neill to Muirisg; and the Dumb Book of James Mac Firbis states that O'Conbhuidhe was chief *of the tract extending* from Ath cliath Muirsge^k to the river Iascach. The families of Mac Eoghain and O'Cuanan of Dun m-Becin; O'Discin of Baile Ui Dhisicin; O'Dunghaile, O'Suidhlearga and O'Cuain of Dun Ui Chobhthaigh; O'Colmain of Grainseach Mor; O'Fuala of Grainseach Beag; O'Ceallaigh of Ard O'g-Ceallaigh; O'Loingsigh and O'Caomhain an Chuirrigh of Muine na bh-fiadh [or Muine dhiadh¹ at this day].

O'Flannghaile in Eachros; *the families of* Mac Giolla na n-each, O'Flannghaile, and Mac Giolla duibh, in the Corcachs; O'Sionna, in Lathrach. The pillars of Sgrin *were the families of* Mac Concathrach, O'h-Oilmhec, Mag Rodan, O'Sneadharna and O'Rabhartaigh.

The

by our author from the Dumb Book of James Mac Firbis. There are many places in Ireland called *Ath cliath*, i. e. the ford of hurdles, which arose from a common practice among the ancient Irish, who were used to make shallow muddy rivers fordable, by means of hurdles or kishes laid down where they desired to pass. This was the ancient name of Dublin, and hence the habit of calling obscure places in remote parts of the country by the name of Dublin, it being considered a proper

translation of their Irish name *Ath cliath*, whereas there is not the slightest analogy between both names. For the situation of the district here called Muirisg, see notes to the topographical poem of Giolla Iosa Mor Mac Firbis.

¹ *Muine dhiadh*.—The words, enclosed in brackets, are in a hand more modern than our author's, and were inserted *inter lineas* in Lord Roden's copy of his larger work, compiled in 1645, evidently by one acquainted with the locality.

balb Shemuir Mic Fhirbiriḡ, Colamuin na Sgríne, .i. Muineir Rabartaíḡ, Mac Carraoín, Uí Flannḡaile, aḡur O'Tarraíḡ, Coloman na Sgríne, aḡur acaib riḡ ó b-Fhiaḡraḡ. Maḡ um aimir pén, ar iad ar dúḡcupaíḡe ad chonaíre aḡ leannmuin ir in Sgrín, .i. Mec Carraoín, Mec ḡiolla na n-eaḡ, aḡur baoi iarirma d'ib Rabartaíḡ innce, ḡen ḡur léḡriob eiriḡiḡḡ ḡallrax Alban a n-dúḡcup dóib.

O'baotḡaile ó Chluain Uí Chorpḡraíḡ; Mec ḡiolla Finn (no Mec Finn Uí Fhlannḡaile), ó'n Leamaíḡ; Mac ḡiolla bpiḡin ó Arḡ na n-ḡlar; Mec ḡiolla mḡr ó Fhionnabair; Mec ḡiolla riabaiḡ ó Chriḡochán; O'Liataḡ ó Muine (no bun) Feḡe; Mec Conluain (no Anluain) ó Chuil Cille bhpiḡin; Mec ḡiolla bhám ó Liop na pcamur; O'Duinḡinn ó Doipe na n-Aḡh; O'h-Aḡḡa ó Thoin pe ḡo; O'Dunḡaḡa ó Choilltib Luḡne ḡo beal áḡa Muice. Liop laḡḡuill baile puirḡ na tualaḡe rin.

O'bhoppaíḡ ḡo Tpaíḡ O'Muirḡeara a d-taopiḡóḡ, aḡur ar d'ib Uí Maonaíḡ. (Sain) Mec Fhirbiriḡ, O'Maonaíḡ, aḡur O'Muirḡeara tiḡearnaḡa na tualaḡe ó bhoppaíḡ ḡo Tpaíḡ. O'bhoppaíḡ ḡo Muirḡe, O'Maoilḡúin taopiḡóḡ na tualaḡe rin.

ḡAILTE PUIRT RIḡH UA ḡH-FIAḡHRACH ANN SO, .i.

Duma Caoḡain la h-loppur, Inir Mochua aḡ Loḡ Con. Eanaḡ Dubain; Ráit bḡanduib i d-Tir Aímaḡaib; Cairlen (no Dun) mic Concabair;

^a *Mac Carraoin*, now anglicised Currin.

^b *O'Tarpaigh*, now anglicised Torpy and Tarpy. The townland possessed by this family in the parish of Skreen is still called in Irish Fearann Uí Tharpaigh, and anglicised Farranyharpy. According to the present tradition in the country the house in which our author was murdered

in 1672, was situated on this townland, but Charles O'Connor states that he was murdered at Dunfin, which is in the same neighbourhood.

^c *Saxon heretics of Alba*.—This passage, and the quotation from the Dumb Book of James Mac Firbis, have been added by our author. The Book of Lecan gives

The Dumb Book of James Mac Firbis *enumerates* the pillars of Sgrin *as follows* :—"The families of O'Rabhartaigh, Mac Carraoin^m, O'Flannghaile, and O'Tarpaigh^a, are the pillars of Sgrin, and the props of the Kings of Hy-Fiachrach." *If I give them as they were* in my own time, the hereditary proprietors which I saw remaining in Sgrin, were the families of Mac Carraoin and Mac Giolla na n-each, and there was a remnant of the O'Rabhartaighs there, but the Saxon heretics of Alba^o did not leave their inheritance to them.

O'Baothghaile of Cluain Ui Chosgraigh; Mac Giolla Finn (or Mac Finn O'Flannghaile) of Leamhach; Mac Giolla Bricin of Ard na n-glas; Mac Giolla mhir of Fionnabhair; Mac Giolla riabhach of Criochan; O'Liathan of Muine Fede, or Bun Fede; Mac Conluain (or Anluain) of Cuil Cille Bricin; Mac Giolla bhain of Lios na reamhur; O'Duinchinn of Doire na n-ath; O'h-Aodha of Toin re go; O'Dunchadha of the tract extending from Coillte Luighne to Beal atha na muice; Lios Ladhghuill is the chief seat of that district.

Of the people who inhabited the tract extending from Borrach to the Strand, O'Muirgheasa is chieftain, and of these O'Maonaigh is one. According to a different authority "*the families of Mac Firbis, O'Maonaigh, and O'Muirgheasa were lords of the tract extending from Borrach to the Strand.*" From Borrach to Muirisg, O'Maoiduin is chief of that district.

THE CHIEF SEATS OF THE KINGS OF THE HY-FLACHRACH HERE, VIZ. :

Dumha Caochain, in Iorrus; Inis Mochua^p, at Loch Con; Eanach Dubhain; Rath Branduibh, in Tir Amhalgaidh; Caislen mic Conchobhair,

only the one list of the pillars of Skreen, namely, the first given in the text. By Saxon heretics of Alba our author means the Scotch settlers in Tireragh, who are

of Saxon, not Milesian or Scotie origin, like many of the old chieftain families of the Highlands.

^p *Inis Mochua*, i. e. the island of St.

Concábair; loctar Ráta; Dun Cíno Treátain (no Dún Contreátain), an da Dhraighnig [Ar lior na Dhraighnige atá baobún ceatpáman an Chairill aniu], agus dun Fínne, i d-Tír Fhiaépac.

baile puirt Uí Chaomáin, .i. Soigen uirge tar abaim, d'a n-geirtear Inirgnebuinn. baile puirt i Mhupáda Imlioc írioll, baile puirt Uí Chonbuidé, Dun Nell.

Ro ósbreadar Goill tra na taoirig rí d'a náicib bunaid (noc do cuirmeamar), no gur bean Sen-dhrián, mac Tairéig Muaidé Uí Dhubda, an tír (go h-aiirigíte Tír Fhiaépac) amac do Ghallaid. Ge do bean, umorpo, raolim nac mói an grem do gabrad iomad do na taoiriocaid ceudna ar a d-tuataib duócuir o rin, óir do roinneadar clanna, ui, agus iarmui Shen-dhriáin an talam eatopra fén, gen go realbuigio aniu, agus for ní mairéann acé píi-beagan do na taoiriocaid réamraite (dá maó ní a plonnaó do beé beo, ní fuil), agus ní h-eaó amáin acé ar iongnad ag aor na n-aimrioi ra a pánuil rián do beé i g-ceannar, tre a n-uaité agus a n-anbfairne aniu. Tídeac ar ruail damna a n-deacra in aité-feugain dól an domuin, agus raobaó na raozal, agus tré ar cuir do airdeacár ar aicmeaóib na cruinne i g-coitcínne, ag cur coimrioc

Mochua. In the poem of Giolla Iosa Mor Mac Firbis, and by the natives at the present day, who speak Irish remarkably well, it is called Iniscua. It is anglicised Inishcoe.

^a *The Bawn of Ceathramh an chaisil.*—This passage, enclosed in parentheses, is not in the copy of this list preserved in the Book of Lecan, but was inserted into our author's text by some person who was acquainted with the locality.

^b *The English drove these chieftains from*

their inheritances.—This passage is not in the copy of this list preserved in the Book of Lecan, but was added by our author from his own knowledge. It is written in a very ancient style of Irish, of which our author was perfect master.

^c *Sen Bhrian.*—He died in the year 1354, after having ruled the Hy-Fiachrach for more than half a century, so that his great grandsons were grown up before his death.

^d *Do not remain.*—It is very curious

chobhair, or Dun mic Conchobhair; Iochtar Ratha, Dun Cinn treathain, or Dun Contreathain, the two Draighneachs [on Lios na Draighnighe is the Bawn of Ceathramh an Chaisil^a at this day], and Bun Finne, in Tir Fhiachrach.

The chief seat of O'Caomhain *was* Soighen Uisge tar abhainn, which is called Inisgreabhunn. The chief seat of O'Murchadha was Imlioch Iseal, and the chief seat of O'Conbhuidhe *was* Dun Neill.

The English drove these chieftains' from their patrimonial inheritances (which we have enumerated), but Sen Bhrian', son of Taithleach Muaidhe O'Dubhda, took the country (particularly Tir Fhiachrach) from the English; but though he did, I think that many of the same *old* chieftains did not get much hold of their hereditary districts from him, for *it is certain that* the sons, grandsons, and great grandsons of Sen Bhrian divided the land among themselves, though they do not possess it at this day. And moreover, but very few of the *descendants of the* chieftains already mentioned *now* exist (even their very surnames, were they of any importance, do not remain'); and this is not all, but the people of these *our own* times wonder that such as they should have ever been in power, in consequence of their fewness and feebleness at this day. But the cause of their wonder is small" *to one* who compares the events of the world and the subversion of ages, which brought such vicissitudes on the tribes of the world in general, driving the potent from territories, as the chieftains

that these family names had become obsolete so early as our author's time, when the English language was but little used in the district. The fact would seem to be, that whole families were either entirely exterminated, or driven out of the territory during the struggles between the families of O'Dowd, De Burgo, and

O'Conor Sligo.

^a *But the cause of their wonder is small.*—
 Ḡiōeab̄ īf̄ ruail̄ b̄anna α n-ocpa, is
 in a very ancient style of Irish, and would
 be thus expressed in the modern language:
 ḡiōeab̄ īf̄ beaḡ áob̄an α n-iongancair̄,
 i. e. but small is the cause of their wonder.

coimrioc ó éiríocháib, mar do cuirtead na tairíuig ri ó n-a criocháib
do cuirpíom pe anair, mar ar pollur i' in duain deapirghaio
(iomda gablan do cloinn Chuinn) 'n-a b-fuilib 231 pann, do pime
Giolla Iora Mór Mac Fírbíuig, ut requiritur :

MAC FÍR BÍ SÍ GH LÉACAIN CECINIT.

Imda gablán do cloinn Chuinn,
a n-iaith banba an fuinn péir-chuinn;
neir na fonn ar tend tarrpaig
Conn i' ceann d'á n-gablanaib.

Clanna

† *Celebrated poem.* — A very good copy of this poem is given by Duald Mac Firbis, in his larger genealogical work, which was commenced at Galway, in 1645; but as the entire of it is preserved in the Book of Lecan, which was compiled by the author of the poem himself, the Editor thinks it more judicious to print the text as in the Book of Lecan, into which it was transcribed by the author's amanuensis, about the year 1417. The only difference between the copy in the Book of Lecan, and that given by Duald Mac Firbis, consists in the difference of orthography, for the latter has in almost every instance modernized the spelling and aspirated and eclipsed the proper consonants. In the ancient copy the grammatical aspirations and eclipses, usual in modern Irish, are scarcely at all adhered to, which renders the text, in many places, so obscure, as wanting the grammatical links, that it would be now very difficult to understand many lines of it, were it not for the as-

sistance to be derived from the transcript of it, made, as has been said, in conformity with more modern grammatical rules, by Duald Mac Firbis. The Editor has compared every word and letter of both copies, and shall, in the following edition of it, occasionally introduce such remarks on their variations, as will give the reader a tolerably correct idea of the difference between the ancient and modern Irish orthography. This poem begins in the Book of Lecan on fol. 83, p. a, col. b, and ends on fol. 85, p. a, col. b.

‡ *Many a branch of the race of Conn,* i. e. Conn of the Hundred Battles, for whose period see page 30, Note 1. — This line is given by Duald Mac Firbis thus: Iomda gablán do cloinn Chuinn, which are exactly the same words with those of the copy in the Book of Lecan, from which the text is printed, the only difference being in the orthography. In the first word, imda, an o was inserted by D. Mac Firbis, to agree with the modern canon of Irish orthogra-

chieftains we have undertaken to describe were driven, as is evident from the celebrated poem⁷ *beginning* "Many a branch of the race of Conn," which contains 231 quatrains, which was composed by Giolla Iosa Mor Mac Firbis, ut sequitur :

MAC FIRBIS OF LECAN CECINIT.

Many a branch of the race of Conn^w

Is in the land of Banba of smooth grass ;

The sovereignty of the lands^x was mightily seized

By Conn, who is the head of their branches⁷.

The

phy called Broad with a Broad, &c., which is strictly adhered to by the modern Irish, and the *o*, a consonant very rarely aspirated in ancient MSS., is marked with an aspiration to conform with the modern pronunciation. The *b* in the second word, *gublaon*, a fork or branch, is also marked with an aspiration by Duaid Mac Firbis. Whether the ancient Irish pronounced those consonants which they left without marks of aspiration, with their primary or aspirate sounds, it is not now easy to determine satisfactorily, but the Editor is of opinion that the pronunciation of the Irish language in Connaught, in the time of Giolla Iosa Mor Mac Firbis, who compiled the Book of Lecan about the year 1417, was very nearly the same as in the time of Duaid Mac Firbis, who wrote in 1645, and that the omission of the aspirations and eclipses of consonants in the Book of Lecan is very often owing to the whim of the transcriber. It must be acknowledged, however, that in ancient

MSS. we very seldom find the consonants *b*, *o*, *g*, *m*, aspirated, but the omission is, perhaps, generally in those positions where the grammatical construction of the sentence, and the ear of the Irish scholar, could easily supply the deficiency.

^x *The sovereignty of the lands.* — Duaid Mac Firbis writes it *neapt na b-ponn ar ceann cappaig*, using the diphthong *ea* for the ancient simple *e* in the words *nept* and *teno*, and eclipsing the initial *f* in *ponn*, which takes place in the genitive plural when the article is used, if the consonant be capable of eclipse. In the words *pono* and *teno* also, instead of the *no* of the ancient copy he writes *nn*, to conform with the modern orthography and pronunciation.

⁷ *Conn, who is the head of their branches.* — Duaid Mac Firbis has it *Conn ar ceann o'd gallánaib*, i. e. Conn of the Hundred Battles, who is the head of her branches, i. e. of the branches or families of Banba, or Ireland.

Clanna Neill, meic Eacac uill,
 gablan cuana do'n cprobuing,
 ni po maicni 'n-a meabair;
 aicme ar mó do mileabairb.
 Do cloimo Chuino móir, mic Pheolm,
 garraib Cpuacna, an élaip leibinn;
 ni dilmair duine o'n feadair,
 riarraib muige Muireabair.
 Sil Pheargna, na fir a tuair,
 as triall go Cpuacain clab-puair,

CO

^a *The race of Niall*, i. e. of Niall of the Nine Hostages, who was the last pagan monarch of Ireland but one, and died in the year 405 or 406. He was the ancestor of the O'Neills, O'Donnells, O'Kanes, O'Dohertys, O'Boyles, and of other powerful families of Ulster, and also of the Southern Hy-Niall in Meath, who were the O'Melaghlinas, Mageoghegans, Foxes, O'Molloys, &c.

^a *They are the greatest tribe of heroes.*—Duald Mac Firbis writes this line aicme ar mó do mileabairb, introducing in the word aicme the final e of the modern orthography for the i of the ancients, and aspirating the consonants m, v, and final b of mileabairb, to conform with the modern pronunciation. At the time that the Book of Lecan was compiled, as will be observed in this word mileabairb and throughout this poem, the Irish writers were beginning to adopt the diphthong ea, which so very seldom appears in the more

ancient MSS. unless, as some have thought, the character f was intended as a contraction for it, an opinion which cannot be admitted, as this character is found not only in Irish, but also in Latin MSS., to represent the simple vowel e. The towering superiority here alluded to of the Hy-Niall, or Race of Niall of the Nine Hostages, called by Adamnan *Nepotes Neill*, is acknowledged by all the northern and western bards, but the southern bards never admitted that the race of Mogh Nuadh-at, in Munster, were inferior to them. This subject was amply discussed in the poems written in the reign of James I., by the northern and southern bards, in a series of poems commonly called the Contention of the Bards, in noticing which, O'Flaherty, in 1685, says that it would be as consistent and proper to say that one pound is equal to an hundred pounds, as that any other Irish family should compare with the line of Heremon in the

The race of Niall^a, son of the great Eochaidh,
 Is a fine branch of the cluster,
 No sept is great in comparison of them;
 They are the greatest tribe of heroes^a.
 Of the race of great Con, son of Feidhlim,
Are the people of Cruachan of the level plain^b;
 No man of the tribe is fruitless (*unmarried*),
 The kings of the plain of Muireadhach^c.
 The seed of Feargna^d, men of the north,
 Passing to Cruachan^e of the red mounds,

And

number of its kings, the propagation of the different branches of its families, the multitude of its saints and illustrious men, or in the extent of its possessions.—*Ogygia*, Part III. c. 86.

^b *The people of Cruachan of the level plain.* — Written by Duald Mac Firbis, Ḑarra Chruacna cláir léinn, where he omits the article before the substantive cláir, which weakens the language. The people of Cruachan were the O'Conors, Kings of Connaught, and their correlative tribes, of whom the most distinguished were the O'Finnaghtys, the Mageraghtys, and the O'Flannagans, families who sunk into obscurity several centuries since.

^c *The plain of Muireadhach*, i. e. the plain of Magh Aoi, now generally called Machaire Chonnacht, i. e. the plain of Connaught, a beautiful and fertile plain in the county of Roscommon, extending from Cloonfree, near Strokestown, to the bridge of Castlereagh, and from a hill a short

distance to the north of the town of Roscommon, northwards to the Turloughs of Mantua, where it meets the plain of Moylurg. The Muireadhach here referred to was the ancestor of the O'Conors of Connaught, and his death is mentioned in the Annals of the Four Masters at the year 700, where he is called Muireadhach Muighe Aoi, *alias* Muireadhach Muileathan.

^d *The seed of Feargna.* — These are the O'Rourkes, O'Reillys, Mac Gaurans, Mac Tiernans, Mac Bradys, and their correlatives, in the county of Leitrim.

^e *Passing to Cruachan.* — Feargal O'Rourke, who was the head of this race of Feargna, became King of Cruachan, or Connaught, in the year 954, and Art O'Rourke, King of Connaught, is mentioned in the Annals of the Four Masters as slain by the Cinel Conaill in the year 1046. Much valuable information on the history of this race of Feargna is preserved in the Book

co Cenannur fonn na fer,
 ferannur do Chonn éneir-geal.
 Tablan uaral do cloino Chuino
 clann Eacac Doimlen dearc-cuirp
 pluag Oirgiall or cac feadain
 'na pmual troim-ghlad éoirteamail.
 beangan aili do cloino Chuino
 clann Máilli, éróda an cprobuig,
 cluinter cac típ 'cá taga,
 ir Muinter mín Muráda.

Clano

of Fenagh, a good copy of which is in the collection of Messrs. Hodges and Smith, Dublin; and also in the Life of St. Maidoc of Ferns, who is the patron of Drumlane, in the county of Cavan, and of Rossinver, in the county of Leitrim.

^f *To Cenannus, land of the heroes.*—

Duald Mac Firbis writes this line thus :—
 Go Ceanannur, fonn na b-ferap, introducing the modern ea for the simple e of the Book of Lecan, and eclipsing the initial f in the word fer, which he writes b-ferap, to show that it is in the genitive plural. The transcriber of the Book of Lecan, we must presume, either omitted the eclipsing b, through carelessness, or deemed it unnecessary to prefix it, as the plural article and the governing noun fonn would immediately suggest to the native reader that the word should be in the genitive plural. The Cenannus here referred to is the town of Kells, in the county of East Meath, which is, to this day, called

Cenannus (the C pron. as K) among those who speak the Irish language. O'Rourke, the head of the race of Feargna, had extended his dominion before the English invasion as far as this place, which is the fact referred to in the text. The name Cenannus signifies the head-seat or residence, and is now translated Headfort in the name of the seat of the present noble proprietor. There is another Cenannus in the county of Kilkenny, which is also anglicised Kells.

^g *Which was the inheritance of the white-skinned Conn.*—Conn of the Hundred Battles, monarch of Ireland, dwelt at Tara, and possessed all Meath as the appanage of the monarchy. His grandson, Cormac O'Cuinn, held his residence for some time at Cenannus.

^h *The race of Eochaidh Doimhlen.*—Eochaidh Doimhlen was the brother of Muireadhach Tireach, who became monarch of Ireland in the year 331; he had

*And to Cenannus, land of the heroes',
Which was the inheritance of the white-skinned Conn*.*

A noble branch of the race of Conn
Is the tribe of Eochaidh Doimhlen^b, the bright-eyed,
The host of Oirghiall, *who*, above every tribe,
Is a bulky blaze of heavy battle.

Another shoot of the race of Conn
Is the Clann Mailliⁱ, valiant the branch,
(Every country is heard selecting them^j),
And the mild Muintir Murchadha^k.

The

three sons called Colla Uais, Colla Meann, and Colla da chrioch, who wrested the territory of Oirghiall from the Ultonians in the year 332, and became the founders of several powerful families, who were seated in the present counties of Louth, Armagh, Monaghan, and Fermanagh, as Mac Mahon, O'Hanlon, Maguire, with other correlative septs, who obtained settlements for themselves in various parts of Ireland.

ⁱ *Clann Mailli*, i. e. the family of O'Malley, chiefs of Umhall, or, as it is Latinised, Umallia, a territory comprising the present baronies of Burrishoole and Murree, in the county of Mayo.

^j *Every country is heard selecting them.*—The O'Malleys were celebrated in Ireland for being expert sailors, as appears from various notices of them in the Irish Annals, particularly those of the Four Masters. O'Dugan, who wrote about the middle of the fourteenth century (he died in 1372), thus speaks of them in his topographical poem :

Duine maic riann ní paíde
D' ís Máille aic 'n-a máraíde ;
Fáide na ríne ríde-rí,
Díne báide ir bhráithirrí.

“ A good man never was there
Of the O'Malleys, but a mariner ;
The prophets of the weather are ye,
A tribe of affection and brotherly love.”

^k *Muintir Murchadha*, anglicised Munter-murroughoe in the Connaught inquisitions of the reign of Queen Elizabeth.—This was the tribe name of the O'Flahertys, and became also that of the territory which they possessed, which was nearly co-extensive with the barony of Clare, in the county of Galway. About the year 1238, when the English Barons of Ireland castellated this territory, the O'Flahertys and their adherents were driven out of it, and they settled in that part of the county of Galway lying west of Lough Orbsen, or Lough Corrib, where they became as powerful as ever they had been in their original territory of Muintir Murchadha.

Cland Fiaçra móir, meic Eacac,
 pegan builid, bind-bréthaç,
 h-l Fhiaçra tuaid ocup tēp
 rial-çat da chuaid ó coimep.

Clann Fiaçra uir ar m'airi,
 lenam lonḡ na laeçraide,
 na plóig ó Themraig Thuatail,
 cóir lenmain a laeç-ruatair.

Fiaçra Foltirnaitheac plebaç
 cuic mic 'con mor-muireraç,
 a n-áirēm ar dú do'n bpoing,
 do dáileo clú d'on cproboing.

Dathi, do ruair caç aicm,
 corantaç cláir Eorairi,
 da gab co h-Ealpa n-énais,
 blaio d'á eçtra a n-úr-rcélaib.

Amalgaid

¹ *A beauteous, sweetly-judging tribe.* — Duaid Mac Firis writes this Featam búilidó bind-bréataç, which is more correct orthography.

^m *The Hy-Fiachrach, north and south,* i. e. the Hy-Fiachrach of the north, or northern Hy-Fiachrach, who possessed the region extending from the river Robe to Drumcliff, below the town of Sligo, and the southern Hy-Fiachrach, who possessed the territory of Aidhne, which comprised the entire of the present diocese of Kilmacduagh, in the south-west of the county of Galway.

ⁿ *The hosts from Tara of Tuathal,* i. e. who sprung from the royal house of Tara,

the place of their great ancestor Tuathal Teachtmhar, monarch of Ireland in the second century.

^o *Fiachra Foltirnaitheach.* — For some account of his descendants see pages 5 and 15.

^p *Who were wont to distribute, &c.* — The meaning is, that it is the duty of the Mac Firis, the hereditary poets and historiographers of the Hy-Fiachrach, who were used to spread the fame of that people by their poems and other compositions, to enumerate and preserve for posterity an account of the sons of their great ancestor Fiachra Foltirnaitheach.

^q *Contender for the plain of Europe.* —

The race of the great Fiachra, son of Eochaidh,
 A beauteous, sweetly-judging tribe¹,
 The Hy-Fiachrach, north and south^m,
 A generous battalion, who have exceeded comparison.
 The race of the noble Fiachra are my care,
 Let us follow the track of the heroes,
 The hosts from Tara of Tuathal^a,
 It is just to trace their noble career.
 Fiachra Foltsnaitheach^o, the festive,
 Five were the sons of that great progenitor,
 To enumerate them is meet for the people,
 Who were wont to distribute fame to the family^p.
 Dathi, who won each sept,
 Was contender for the plain of Europe^a;
 He proceeded to the Alps of birds^r,
It is a part of his adventure celebrated in stories^t.

Amhalgaidh,

Vide supra, pp. 17 to 33, where the whole story is given. The verb *coram*, which is still a living word, signifying to defend, is used in the ancient manuscripts and in the *Annals of the Four Masters* in the sense of *to contend for*; *corantac* is a personal noun formed from *coram*, and means contending, or one who contends. It is curious that Dathi is here set down as if he were the first son of Fiachra.

'He proceeded to the Alps of birds. — Duald Mac Firbis has this *Do gab go h-Ealpa n-euncuig*, where, by inserting a *u* into the first syllable of *encuig*, he shows that he took it to be long, and that he understood the word to be derived from

eun, a bird, not, as might be supposed, a modification of *eanach*, a moor, the first syllable of which is always short.

^t *Celebrated in stories.* — Duald Mac Firbis writes this *Ólaob o'á eactpa n-úiprgeu-luig*, which would mean, "It is a portion of his storied adventure." Here it is necessary to remark, that in O'Reilly's Dictionary the word *uiprgeul* is explained "a fable, story, legend," but this is not the true explanation of the word, for it is derived from *úp*, noble, and *rgeul*, a story, and means a famous story or narrative. O'Brien, in his Dictionary, explains the word *úp* as follows: "Úp, generous, noble-hearted; it is also prefixed as a part of a

Amalgaid fa cuing cāta,
 mac uaral an árd-plata,
 banba o cleacti do'n cuiri,
 bheral calma ir Cónairi.
 Eirc Cúlbuibí craeb co rat,
 mac d'Fhiacra mór, mac Eacac,
 a maer ar Ceara do cuiri,
 taeb caí peada da adaim.
 Da clannairb Eirc, nar faem fell,
 garrao calma naí ceilpem,
 fir Chera na caem crann cuiri,
 maeth-bárr mela ar a moílaib.

Na

compound, and then signifies noble, commendable, as úr-*phioct*, a noble race." This is exactly the sense in which úr, in the compound *ur-réel*, or *ur-réul* is to be here taken, for it is quite clear from the context that Giolla Iosa Mor Mac Firbis did not intend to insult his patron, the O'Dubhda, by telling him that the account of his ancestor, Dathi's, grand expedition to the Alps, was a legend or fable, but, on the contrary, that he wished it to be firmly believed, as indeed it has been by every writer on the subject since his time, not excepting even Moore, the latest historian of Ireland, who despatches the subject of King Dathi's expedition to the Alps, in the following brief words, omitting every thing in the story that might savour of fabrication or fable:—"A. D. 406. To Niall the Great succeeded Dathy, the last of the Pagan monarchs of Ireland,

and not unworthy to follow, as a soldier and adventurer, in the path opened to him by his heroic predecessor. Not only, like Niall, did he venture to invade the coasts of Gaul, but allured by the prospects of plunder, which the state of the province, then falling fast into dismemberment, held forth, forced his way to the foot of the Alps, and was there killed, it is said, by a flash of lightning, leaving the throne of Ireland to be filled thenceforward by a line of Christian kings."—*History of Ireland*, vol. i. pp. 152, 153.

* *Banba was enjoyed by the hero.*—Duald Mac Firbis writes this line, *banba o cleact fan gun cuire*. This seems to intimate that he believed Amhlagaidh, the brother of Dathi, to have been monarch of Ireland, but he is not found in any authentic list of Irish monarchs. He was King of Connaught, and probably made

Amhalgaidh, a prop of battle,
 Was a noble son of the arch-chieftain,
 Banba was enjoyed by the hero[†];
 Bresal the brave and Conairi^u were also his sons.
 Earc Culbhuidhe^v, a prosperous branch,
 Was son of great Fiachra, son of Eochaidh,
 His steward over Ceara he placed^w,
 Which the side of each tree confessed^x.
 Of the descendants of Earc, who consented not to treachery,
 A brave tribe, whom I will not omit,
 Are the men of Ceara of beautiful fruit trees,
 With a mellow top of honey on their pods^y.

Let

some exertion to gain the monarchy, but it appears from all the authentic annals that Dathi succeeded his uncle, Niall of the Nine Hostages, and that Laoghaire, the son of that Niall, succeeded Dathi as monarch of Ireland, and was succeeded by Oilioll Molt, the son of Dathi, who was succeeded by Lughaidh, the son of Laoghaire. See list of the kings of Connaught of the Hy-Fiachrach race, given at the end of this poem.

^u *Bresal the brave and Conairi.*—Vide p. 5, line 6.

^v *Earc Culbhuidhe.*—See p. 5, line 2, where this Earc is mentioned as if he were the eldest son of Fiachra.

^w *His steward over Ceara he placed.*—See pp. 15, 16, 17, where it will be seen that the chiefs of Ceara are descended from this Earc Culbhuidhe. The boundaries of the territory of Ceara have been

already noted in the list of the men of Hy-Fiachrach prefixed to this poem.

^x *Which the side of each tree confessed.*—By this is to be understood that the trees of Ceara produced abundance of fruit during his chieftainship, which was considered one of the indications of his worthiness as a prince.

^y *With a mellow top of honey on their pods.*—Duald Mac Firbis gives this line thus:—Μαοτ-βάρη meala ar a moġluib, where, besides placing the proper aspirations on the consonants, he changes the ancient diphthong æ into the modern ao, in maot, and e into ea in meala. The word βάρη is still used in the living language to denote a *top*, the cream that rises on new milk, and the crop produced by a tilled field, or any field. Moġal, of which moġluib is the ablative case plural, signifies the pod or husk of any fruit.

Ná págbam Ceara na clao,
 can a dúcúr do dénam,
 can beith co reim 'cá rnaibí,
 o'á breit 'ra reim ríghaibí.
 Ar Ceara na call corcra
 cpi rí uairli mmolta,
 pedna can clod ó énaib,
 menma mór 'ca mileabab.
 O'Tighearnaig na tpeb peib,
 O'Gormgaíl nár chuill tabeim,
 rlog can degaíl re debaib,
 mor meabair O'Muireabair.

'8

² *Let us not leave Ceara of the mounds,*
 &c.—Duald Mac Firis gives this quatrain
 as follows :

Ná págbam Ceara na cclao
 Gan a dúcúr do dénam,
 Gan a be' go reim, go rnaibí,
 O'á m-breit 'ra réim ríghaibí.

Here it will be observed, that eclipsing
 consonants are introduced which render
 the text much clearer than that given in
 the Book of Lecan; but it is strange to
 find so excellent a scholar introduce the
 diphthong eu, for which scarcely any au-
 thority is to be found in good MSS., and
 reject the diphthong ei, which is found
 in them all.

^a *Of the brown nuts.*—Written na ccoll
 ccorcra by Duald Mac Firis, who, as
 usual with the Irish writers of his time,
 uses cc for g-c, ff for b-f, tt for o-t.

^b *O'Tighearnaigh of ready tribes.*—Duald

Mac Firis writes this O'Tighearnaig na
 tpeab peib, eclipsing the t in tpeab, to
 show that it is in the genitive case plural.
 The name O'Tighearnaigh is found in
 many parts of Ireland anglicised Tierney;
 but in the barony of Carra it has been
 changed to O'Tighearnain in Irish, and
 anglicised Tiernan. People of this latter
 name are spread throughout the barony
 of Carra, but they have a tradition among
 them that they were originally seated in
 that part of it called Partry. They are
 all at present very poor, not one of them
 holding the rank of even a farmer, but
 living on small holdings of land, of which
 they are choice tillers; they are neverthe-
 less a stout race of men, and very proud
 of their descent, of which, however, they
 know nothing except that their ancestors,
 a long time ago, had estates in Carra, and
 were strong men and courageous fighters.

Let us not leave Ceara of the mounds^a

Without mentioning its inheritors,

Without gently fitting them *to our verse*,

To place them in the regal list.

Over Ceara of the brown nuts^a

There are three noble, laudable kings,

Over tribes who have not been subdued from times remote,

Whose soldiers possess high minds.

O'Tighernaigh of ready tribes^b,

O'Gormghail^c, who merited not reproach,

A host who separate not from the battle,

O'Muireadhaigh^d of great mirth.

To

They look upon themselves as superior to their neighbours of the same rank, and always use a style in their dress, particularly the great coat, by which they are at once distinguishable from others of the same neighbourhood. This gave rise to an Irish saying in Carra, *Ir geall le mórgáil muintire Chigearnaí é*, "It is like the ostentation of the O'Tiernana." For the descent of O'Tighernaigh *vide supra*, p. 17.

^c *O'Gormghail*.—This is the true form of the name, and is still retained in Carra with a very slight alteration, though in the prose list of the men of Ceara, and in the copy of O'Dugan's topographical poem, transcribed by Peregrine O'Clery, it is written O'Gormog. It is now pronounced by the native Irish in Carra as if written O'Gormíúil, but whenever it is written or spoken in English it is made Gorman.

^d *O'Muireadhaigh*.—This line is written by Duald Mac Firbis *Mor meabair O'Muireadhaigh*, with the marks of aspiration on the proper consonants. This name is still to be found in Carra, exactly pronounced by the native Irish as written by Duald Mac Firbis, but anglicised Murray, which is not incorrect, as it represents the sound sufficiently well in English letters. O'Dugan also, in his topographical poem, mentions these three families as the chiefs of Ceara, in the following quatrain:

O'Muireadhaigh co meanmain,
O'Gormócc, O'Tigearnaigh,—
Déig-méin ar ceala bo'n ophuig,—
Ar Cheara aimpéid, áluinn.

"O'Muireadhaigh with spirit,
O'Gormog, O'Tighernaigh,—
A generous mind is innate in this people,—
Rule over the uneven, splendid Ceara."

'ḡ O'Uaba ír fáiríngí fear,
 'ḡ O'Cíndchnama nar cáinead,
 ó Maiteois co Callainn cnuaid,
 ocus go h-abainn inbuair.
 Maith do chorpain fonn na fep
 O'Dorcaibí ír árb aigneab,
 críe Partraiḡi na call cuir,
 le crann alc-buibí a n-imḡuin.
 O'banan ó bailí féin,
 bpuḡaid nac ar cuill tabeim,

O'ḡilin

In the year 1238 the English Barons of Ireland castellated the territory of Ceara, when the power of those Irish chiefs was much crippled, if not nearly destroyed. In the year 1273, as we are informed by the Annals of the Four Masters, Flann O'Tighearnaigh was slain by the O'Muir-eadhaghs (Murrays) in a dispute about the lordship of Ceara. This is the last notice of these families in the Irish Annals as lords of Ceara, and it is quite clear that their power was at an end soon after, for in the year 1300 the Annals of Clonmacnoise, as translated by Connell Ma-geoghegan, record the death of Adam Staunton, lord of Kera, who is called a great baron in the Annals of the Four Masters; and there can be little doubt that there was no lord of Ceara of the above families ever since. The compiler of the Book of Lecan and Duald Mac Firbis state, that the last King of Ceara of the Gael or Milesian Irish race was Giolla an Ghoill Mac Neill, who was cotemporary

with Taithleach Mor O'Dowd (the son of Aodh), who was slain in the year 1192.— See p. 17, where it will be seen that Niall, the progenitor of this Mac Neill, and Tighearnach, the progenitor of O'Tighearnaigh, were brothers.

* *O'h-Uada*.—This name is still in Ceara, but pronounced in Irish O'Fuada, and fancifully translated *Swift*, from the assumption that the name is derived from the verb fuabais, carry away swiftly or violently. For the descent of this family see page 17.

† *O'Cinnchnamha*.—This name is still in the barony of Carra, and anglicised correctly enough Kinnavy. There was a respectable man of this name living in the west of Partry about fifty years ago, but there is none of the name in the district at present that could be called even a farmer. For the situation of the tract of land belonging to these two families see notes to the prose list of the men of Ceara prefixed to this poem.

To O'h-Uada^c of extensive woods,
 To O'Cinnchnamha^f, who was not dispraised,
Belongs the tract stretching from Maiteog to the hard Callainn,
 And to the cool river.
 Well has been defended the land of the men
 By O'Dorchaidhe of the lofty mind,
 The country of Partraighe^g of fine hazle trees,
 With the yellow-knotted *spear*-shaft in the battle.
 O'Banan of his own town^h,
 A brughaidh who merited not reproach,

O'Gilin

^c *The country of Partraighe.* — For the limits of this territory see notes to the prose list of the men of Ceara, prefixed to this poem ; and for some account of the genealogy of the O'Dorchaidhe family see pp. 46–51. It should be added here that the name O'Dorchaidhe is still common in the mountainous districts of Partry and Connamara, where they are beginning to translate it Darkey, as being derived from the adjective *dorcha*, dark. The more respectable portion of the tribe, however, render it Darcey, and will, no doubt, be considered an offset of the D'Arcys of Meath, as soon as they remove from their native mountains. It is not improbable that this is the name which is common in the United States of America, particularly in Virginia and Pennsylvania, as Dorsey, where some of the people who bear it assert that they are of Irish origin, while others contend that they are French.

^h *O'Banan of his own town*, or as the Scotch say, *of that ilk*, i. e. of the town,

seat, or townland called after himself, viz. Baile Ui Bhanain, now Ballybanaun, a townland in the parish of Ballyovey, or Partry, to the west of Lough Mask ; but the maps differ as to its situation and extent. Mr. James O'Flaherty of Galway, who is intimately acquainted with the district of Partry, has thus described its situation in his reply to a number of queries proposed by the Editor :—" Ballybanane is a townland on the side of the mountain of Partry, and is nearly in an angular position, which leaves it west of the mountain lake, and due west of Lough Mask, which it borders. There is a chapel on this townland."—See also Ordnance Map of the County of Mayo, sheets 108, 109, and Balld's Map of the same county. It is probable that Ballybanaun was originally a ballybetagh, or large Irish townland containing about 480 Irish acres, and that it comprised several of the present adjoining denominations.

O'Gilin ó'n Muine meir,
 cuirí cíníl nap cáineab.
 Mac a bhainb na call corcra
 fuair an ríth-brug rægalta,
 tuat Muibí beirigí bino,
 cuirí ir feitíngí airmim.
 Baile na cruibí can éol,
 rir a deapap tra an Tobar,
 fuair ó h-Áoda le feòain,
 cupaid 'cár caemna ar ceo fearaib.
 O'Fuaémapan na n-ec meap
 fuair Cacal le cup claidem,

neapc

¹ *O'Gilin . . . of Muine.*—The name of this family is now obsolete, unless it be that anglicised Killeen. The townland of Muine is well known. It is described by Mr. O'Flaherty as "a townland containing a large village, the flattest and best land in Partry, lying between the bridge of Keel and the house of Port Royal, and mearing the townland of Turin and the village of Newtown Partry." It is evidently the townland called Carrowmoney (i. e. the quarter of Muine), on the Ordnance Map.

² *Mac an Bhainbh.*—This name has long since become obsolete, which indeed is not to be wondered at, as it signifies "son of the sucking pig." It would be anglicised Macan-Banniff, and may have been translated Hogge.

³ *The worldly fairy palace,* i. e. the fairy palace in this world, the fairies not being considered as properly of this world. The

district of Magh na beithighe (i. e. the plain of the birch), here alluded to as the inheritance of Mac an Bhainbh, is called by the *alias* name of Lughortan, in the prose list already given, and said to comprise seven ballys or townlands. It is obvious from the description of it, as "a terrestrial fairy palace," that it must have been the most beautiful district in the country. Mr. James O'Flaherty, who was born in the neighbourhood, writes, "the district extending from Muine to Luffertane must be that anciently called Magh na beithighe, or plain of the birch trees, being a long, plain valley, about five miles in length, now mostly in a high state of cultivation; but I think there is not an acre on the whole line on which the shrubs and roots of birch trees are not still to be found, which are as difficult to eradicate as those of the furze itself, whatever process of

O'Gilin the swift of Muine¹,
 Chief of a tribe who were never dispraised.
 Mac an Bhainbh¹ of scarlet hazles,
 Obtained the terrestrial fairy palace²,
 The sweet district of Magh na beithighe,
 The most vigorous chief I mention.
 Baile na craibhi¹ without stain,
 Which is also called the Tobar,
 O'Aodha^m, with his tribe, obtained,
 Heroes who protect us against puissant men.
 O'Fuathmharan^a of the swift steeds
 Obtained Cacál^o by plying the sword;

The

cultivation be adopted."

¹ *Baile na craibhi*, written by Duaid Mac Fíris Baile na craoibhe (i. e. the town of the bush,) was an ancient *alias* name of Ballintober townland, and the name is still retained in a disguised form in the adjoining townland of Creevagh, i. e. bushy land. This place was otherwise called Baile Tobair Phadruig, i. e. the bally or townland of St. Patrick's well, from a holy well anciently called Tobar Stingle, which was blessed by that saint, near which he erected a church, and where, in the year 1216, Cathal Croibhdhearg O'Conor, King of Connaught, founded a magnificent abbey, the ruins of which still remain in good preservation.

² *O'h-Aodha*. — There are families of this name, of different races, to be found in various parts of Ireland, but they an-

glicise it to O'Hea, Hayes, and more generally Hughes, from the belief that Aodh and Hugh are the same name. There are several families of the name O'h-Aodha still in the parish of Ballintober and all over the barony of Carra, where they have not yet acquired skill enough to render it Hughes, but some of them are beginning to give it an English dress in the shape of Hay or Hayes.

^a *O'Fuathmharain*, written in the prose list O'h-Uathmharain. This name, which would sound so terribly to an English ear, and conveys no pleasing association to an Irish speaker (for it signifies *hated*, *abhorred*), has been corrupted to O'h-Eimhirin, which is Englished Heverine, and Hefferine, and in these forms it may be said still to exist in Carra.

^o *Cacál*, now always called in Irish Cagála, and anglicised Caggaula. This

neapt a lann leabar 'ra lám,
 dligeað cáe am a n-imrad.
 Cill n-aíndi ir úr feadae,
 'c O'Leighua luae-ghreabaé,
 plóig na Cilli nír cáineab,
 gilli ar cóir do comáiream.
 Tuath Muigh h-Indalb na n-ec,
 cupi nae ar luaib leie-bpae,
 'g O'Ceapnaig náir éar éra.
 blað a teglaig cóigéba.
 Tí baí an Ríagán gan roind,
 tí baí an Chnocáin canuim,

ir

townland is still well known, and is situated in the parish of Ballintober, a short distance to the north-east of the great abbey. It contains a small remnant of the ruins of an old church, said to be one of the threemost ancient in Ireland, as appears from the following rhymes current in this district :

Maig eó, Balla, Dhéacmae, Cagála
 aepeae eoir óá móin,
 Na céau éeampuill a n-Éirinn, a bean-
 nuigaeð 'ran Róim.

" Mayo, Balla, Breaghwy, the airy Caggaula between two bogs,
 Were the first churches in Ireland, which were blessed at Rome."

This tradition, however, is not to be depended upon, as almost every county in the Irish parts of Ireland claims to itself the honour of having the three (not four, as in this rhyme) most ancient churches

in Ireland.

^p *Cill n-Aindi of the green woods.*—Duala Mac Firbis writes this line Cill Ua n-Aíndi 'r úr feadae; and in both copies of the prose list prefixed to this poem the place is called Cill Buainne, which might be taken to be the present Kilboyne, the seat of Sir Samuel O'Malley, were it not that the latter is called by the natives in Irish Cillin na buídeanae.

^q *O'Leighua.*—This name is well known in other parts of Ireland, but it is not to be found in Carra at present, unless it be the name shortened to Leasy, which is very probable.

^r *District of Muighe h-Indalbh,* i. e. the tuath or lordship of Magh h-indalbh, called in the prose list Magh Fhiondalbha. It is now anglicised Moynulla, and sometimes shortened to Manulla, and known only as the name of a parish in the barony of

The strength of his large swords and hands
 Deserve renown at every time.
 Cill n-Aindi of the green woods^p
 Belongs to O'Lerghusa^a of swift steeds;
 The host of Cill was never dispraised,
 Youths who ought to be mentioned *in this poem*.
 The district of Magh h-Indalbh^r of steeds,
Belongs to a hero who has not pronounced false sentence,
 To O'Cearnaigh^r, who loved not refusal,
 The fame of his household I will extol.
 The three *townlands* of Baile an Riagan^r without division,
 The three townlands of Cnocan^u, I say,

And

Carra. In the prose list already given this district is said to contain fifteen townlands (or about 7,200 Irish acres), and to extend from Crannan Tornaighe to Caisel Cairpri.

^a *O'Cearnaigh*, now anglicised Kearney and Carney. The Kearneys are still a numerous race in this locality, and we are happy to say that a branch of the tribe has risen from the ranks of the peasantry, among whom they were since the thirteenth century, to that of the gentry. A gentleman of the name lives at present in the town of Castlebar, where he amassed considerable wealth by keeping a tanyard, but he has lately retired from business, and has sufficient wealth to purchase the greater part of Manulla. The Kearneys of this race are to be distinguished from those formerly seated at Cashel, in the county of Tipperary, and in different parts of the south of Ireland.

^r *Baile an Riagan*.—According to the prose list prefixed to this poem Baile an Riagan was a generic name for a district of land comprising the townlands of Baile an Chriochain bhuidhe, Baile an smotain, and Baile na Greallcha. This generic name is now locally forgotten, but those of the subdivisions are still retained, with the exception of one, and applied to townlands in the parish of Manulla. Baile an Smotain, the name of the first division, is now anglicised Smuttanagh; Baile an Chriochain bhuidhe is now simply Creaghan-boy, but the name Baile na Greallcha is forgotten, or at least not recognized as a townland name.

^u *The three townlands of Cnocan*, are called in the prose list the three townlands of Magh na Cnocraighe, but the names of the subdivisions are not added, which renders it impossible now to determine the exact situation or extent of this tract of land.

ir fonn Fíob cruaiáí na pleo,
 fa'n cié-luaiáí coll cneir-gel,
 cabraib caó cruac fa cleé-pál,
 tuat árraib h-l Eíoneáan.
 baib an belais, ar beét lem,
 'g O'Ciaragan, ní celpem,
 noó cóir ceiltí a cabair,
 beirtí ríóill caó ren árrar.
 Ar baib Crammáin can coll,
 brúgaib ar burba comlann,
 na coiglib pábla na fear,
 h-l Choiglib calma an cinead.
 Mec Gíllí Fhaelán can fell,
 brúgaib uairí, áirmem,
 déglar ar a plóg plegac,
 'ra Replér mór-muirerac.

Cúl

^v *Fídh cruaiáí*.—This generic name is now lost, but the prose list states that it comprised Baile Uí Ruairc and Baile na leargan moire, which enables us to fix its position; for Baile Uí Ruairc, now correctly anglicised Ballyrourke, is the name of a townland in the parish of Balla, adjoining the east boundary of the parish of Manulla, and Baile na leargan moire is believed to be the neighbouring townland of Knockmore.

^w *O'h-Eidhneachan*.—This name is still to be found numerous enough in the parish of Manulla, where it is anglicised Heanaghan, without the prefix O', which has been rejected for the last two centuries in this part of Ireland, except among

the Milesian gentry, by whom it is now used as a mark of distinction between themselves and their correlatives, the peasantry of the same race.

^x *Baile an bhealaigh*, i. e. the town of the road or pass. This is called Bel na leice in the prose list, which renders it difficult to determine what place it is. There is a Ballynalecka in the parish of Ballintober, a short distance to the north of the townlands of Caggaula, already mentioned; but it is highly probable, that as this townland belonged to the family of O'Ciaragain; the place here mentioned is the same which is now called Baile Uí Chiaragain, i. e. O'Ciaragain's town, which lies immediately to the south of the village

And the land of Fídh cruai^hi' of banquets,—
 On which are shower-shaken hazles of white bark,
And where each round hill is protected by wattle hedges,—
Constitute the ancient territory of O'h-Eidhnechan^w.
 Baile an bhelaigh^z, it is certain to me,
 Is O'Ciaragan's',—I will not conceal it,—
 Neither should his virtue be concealed,
 The satin-dressed ornament of each old habitation.
 Over Baile Crannain^z, without blemish,
 Are brughaidhs (*farmers*) of fierce conflict,—
 Spare ye not the acquisitions of the men,—
 The O'Coiglidhs^a, a brave tribe.
 The Mac Gilli Fhaelains^b without treachery,
 Noble brughaidhs (*farmers*), I reckon,
 Whose spear-armed host have good array,
 Are in Regles^c of the great family.

Cul

of Balla, in the parish of Balla.

¹ *Is O'Ciaragan's*.—This name is now anglicised Kerrigan, and there are persons of the name to be found in various parts of the barony of Carra, and in the town of Castlebar.

^z *Baili Crannain*.—This name is now unknown in Carra. It appears from the prose list, in which this place is called Crannan Tornaighe or Ran Tornaighe, that it formed one of the boundaries of the territory of Magh Fhiondalbha, now Manulla parish.

^a *O'Coiglidhs*, now always anglicised Quigly. There are but very few of this name at present in Carra, though the name is common in other parts of Ireland.

^b *Mac Gilla Fhaelains*.—This name is

now obsolete, or changed in such a manner that it cannot be identified.

^c *Regles*.—It is strange, that in the prose list the estate of Mac Gilla Fhaelain is called Magh Ruisean, while Regles, or Baile an Regles, i. e. the town of the church, is made the estate of O'Cuachain, a family name totally omitted in the poem. Magh Ruisean is undoubtedly the townland now called *Ruisin*, anglicè Rusheen, situated in the parish of Drum, and lying between Clogher and Lisrobert. Regles must have been the name of an old church in this vicinity. Some say that Regles was the name of an old church in the parish of Balla.

Cúl Daingin, ir braenros bán,
 Oirímh, Imairi imlan,
 'c O'Mailraite, rial an fer,
 ler b'aite cliair ir coindem.
 Tí baile na Tuláa ter,
 'c O'brógán, do fuair aibneir,
 'r 'c O'Faghartaig tuais 'cá tíg,
 ra moltair a n-uair aenais.
 Tearmann balla fa'n binn cluig,
 fonn blait do bennais pádraig,

rluais

^d *Cul daingin*, i. e. the back of the Dangan or fortress. The name is now unknown.

^e *Braen-ros*, i. e. the droppy wood, or wood of drops. Now unknown.

^f *Oireamh*, now well known in Carra, and anglicised Errew on the Ordnance Map, and Errue by Mr. Balda. It is situated in the parish of Ballyhean, and about two miles from the great abbey of Ballin-tober. It is now the fee simple property of James Hardiman, Esq., author of the History of Galway, who has granted ten acres of it for ever, *in purá eleemosinā*, to lay monks of the third order of St. Francis, under the condition stated in their charter, that they shall keep a school for the education of the children of the vicinity in the usual branches of English education, and also in the Irish language. This school has been open since the first of November, 1842, and the pupils, who had previously no opportunity of acquiring

education of any kind, are making rapid progress in the acquirement of English learning, and also in the reading and writing of the native language, which is still fluently spoken in the district.

^g *Imairi* (i. e. the ridge), now obsolete. All these townlands, whose names are now forgotten, and which are set down here as belonging to O'Mailraite, lay in the immediate vicinity of Errew, in the parish of Ballyhean; it is highly probable that the place here called Imairi is the denomination now called Cnoc an iomaire, i. e. the hill of the ridge.

^h *O'Mailraite*.—This name, which, if analogically anglicised, would be O'Mulratty, is now unknown in this neighbourhood under that form, but it is very probable that it is the same which is now anglicised Ratten.

ⁱ *The three townlands of Tulach, south*.—In the prose this tract of land is called Tulach Spealain, i. e. Spellan's Hill; Spel-

Cul Daingin^a and Braenros^c ban [*the white*],
 Oiremh^f and the entire of Imairi^g
Belong to O'Mailraite^h, hospitable the man,
 To whom the literati and the feast were pleasing.
 The three townlands of Tulachⁱ the southern,
 Belong to O'Brogan^j, who has enjoyed happiness,
 And the northern to O'Faghartaigh, who at his house
 Is praised at the time of the assembly.
 The Termon of Balla^k, where sweetly sound the bells,
 A flowery land, which Patrick blest^l,

A

lan, which is now a surname, being the proper name of a man, formerly common in Ireland. It is now known by the synonymous name of Cnoc Spealain, which is the name of a lofty hill lying between the village of Balla and Slieve Carna, in the barony of Carra.

^j *O'Brogan*.—This name is now anglicised Brogan, and there are persons of the name in the townland of Ringarrane and other townlands in the parish of Ballyhean, and throughout the barony of Carra. The name O'Faghartaigh is now unknown in this district, though it is common in the county of Galway under the anglicised form of Faherty.

^k *The Termon of Balla*.—This Termon, according to the prose list, comprised twenty-four ballys or large townlands, each containing about 480 Irish acres, so that it must have comprised the greater part of the present parish of Balla, but the Editor has not been able to find any

record in which these townlands are given by name. This Termon was probably held by O'Cearnaigh, as herenach, or hereditary warden of the church of Balla, but he seems to have been dispossessed by a branch of the Burkes at an early period. These Burkes, styled "*an Tearmoinn*," i. e. of the Termon, cut a conspicuous figure in the Irish Annals, particularly in the reign of Elizabeth, when Shane an Tearmoinn Burke, was the head of that branch.

^l *Which Patrick blest*.—There is no mention made of Balla in any of the lives of St. Patrick, not even in the Tripartite Life, published by Colgan, which mentions the saint's visit to Ceara, unless it be the place called Cuil Chorra. The places mentioned in the Tripartite Life as visited by the saint during his stay in Ceara, are Cuil Corra, and Tobar Stingle, the latter of which is doubtless the present Ballin-tober. We may, however, receive the authority of the Mac Firbis, in 1417, that

rluais ó Tempais 'cá tōga,
 ruair O'Ceannaig céo roga.
 Ruair O'Caeman na colg ren
 tuath Ruirín, ír rian ro mer,
 tuat taircē fearann na fear,
 ren-ponn cnaírech ír claidem.
 Ruair O'Ruaidín na ruas mer
 ó Ath na lub, mar luaiter,
 co fonn Cillí na n-gaig n-glan,
 rinne co h-árb 'cá n-áirern.
 O thačar Chillín na n-gaig
 co h-Ath Seirb na raer bárb,

aḡur

this spot was then believed to have been consecrated by St. Patrick's visit thereto, when he was preaching the Gospel in the territory of Ceara, but the first church seems to have been built at Balla by St. Cronan, otherwise called Mochua, who died in the year 637, and whose memory was celebrated there, according to the Irish calendars, on the 30th of March. Its ancient ecclesiastical importance is sufficiently indicated by the remains of a Round Tower, of the height of which about forty feet remain. Near it are the ruins of a small ancient church, built of the same stone, and evidently of the same date and workmanship as the Tower. For some historical notices of this place see Colgan's *Acta Sanctorum*, p. 790, and the *Annals of the Four Masters*, at the years 637, 1179, 1226, 1236.

^a *A host from Tara, &c.*, that is, others

of the royal race of Tara contending for this Termon. Sluais ó Theimparis 'gá tōga is the reading given by Duaid Mac Fírbis.

^a *Tuath Ruise*.—This tract of land is called, in the prose list prefixed to this poem, by the *alias* name of Ros laogh, which is now the name of a parish in the barony of Carra, anglicised Rosslee, and described as containing seven ballys, and extending from Cluain Lis Nellin to Beul atha na lub, now Newbrook, and from Beul athanag-carr to Muilleann Tiormain. It appears also to have borne the name of Tuath Aitheachda, i. e. *territorium Attacotticum*, from its having been one of the last districts in Connaught held by a tribe of the Belgic race, who were universally called Aitheachs, or plebeians, by their Scotie conquerors. From these facts it appears pretty certain that the district of

A host from Tara selecting it^m,
 O'Cearnaigh obtained, *as his* first choice.
 O'Caomhan of the ancient swords obtained
 Tuath Ruisin^a, vigorous his career,
 A princely district, soil of heroes,
 Old land of lances and swords.
 O'Ruaidhin^o of the rapid onsets got
The tract stretching from Ath na lub^p, as is reported,
 To the land of fair Cill na n-garg^a,
 We are proudly counting them.
 From the causeway of Cillin na n-garg^r,
 To Ath Seisidh^s of the noble bards,

And

Tuath Ruisen comprised all the parish of Tuaghta and the greater part, if not the entire, of that of Rosslee.

^o *O'Ruaidhin*.—This family name has been changed to O'Ruadhain, anglicè Ruane, and there are still people of the name in the tract here described.

^p *Ath na lub*, called in the prose tract Beul atha na lub, which is the name of the place at the present day in Irish; it is now anglicised Newbrook, and is well known under both forms as the seat of Lord Clanmorris.

^a *Cill na n-garg*, called in the prose list Cillinn an-garg, which is the true name, but the poet was here obliged to shorten it by a syllable to fit his heptasyllabic measure. This place is now popularly called Cillin, anglicè Killeen, and lies between Beal atha na lub, or Newbrook, and Brooms-town, in the parish of Robeen, which being

outside the boundary of the present barony of Carra, shows that the modern barony is not co-extensive with the ancient territory whose name it bears.

^r *The causeway of Cillin na n-garg*.—Here the poet gives the true name, his measure admitting the additional syllable in Cillin. This Togher or causeway of Killeen, which is still a remarkable feature on the land, is well known to this day, and now gives name to a distinct town-land and gentleman's seat, adjoining Killeen to the east.

^s *Ath Seisidh*, now corruptly called *Beal atha na siodh*, Bealanashee, and supposed to signify the ford of the fairies—Os vadi lemorum seu geniorum. It is in the parish of Robeen, north of Ballinrobe, and popularly believed to be haunted by the fairies, which induces the country people to hurry home in the winter from the

agur Róibín nínó anair,
 fóibín n' ghrinn le Gallairb.
 O Shigin Chiaráin na clog
 co Tobar Lughna lán-bog,
 fuair O'bhínn in ponn plebach,
 ba'n fill coll fa céib-pebác.
 O'n Tobar co Cael na cath,
 Róiba n' Rathain fa Aenac,

O'Gormgialla

market of Ballinrobe to arrive by day light at this ford, which they must cross whether they take the high road or the short cut through the fields.

[†] *Robin*, now Robeen, the name of a townland bordering on the Robe, where that river winds in a remarkable manner, in the parish of Robeen, lying to the north-east of the town of Ballinrobe.

^u *A little spot which is delightful to the strangers.*—This line clearly shows that Robeen was, in the time of the writer (1417), in the possession of the Galls or strangers, the name by which the Irish then designated the English settlers. There are still to be seen at the place the ruins of a castle and church of considerable antiquity, said to have been erected by the family of Burke. According to the *Annals of the Four Masters* the territories of Muintir Murchadha, now the barony of Clare, in the county of Galway, Conmaicne Cuile Toladh, now the barony of Kilmaine, in the county of Mayo, and Ceara, now the barony of Carra, were castellated by the English Barons of Ire-

land in the year 1238.

^v *Sigin Chiarain of the bells.*—This shows that there was a church at the place. It is supposed to be the place now called Sighean, lying a short distance to the south of Cloonagashel house, in the parish of Ballinrobe, and to the right of the road as you go from the town of Ballinrobe to Cloonagashel.

^w *Tobar Lughna*, i. e. the well of St. Lughna, or Lughnat, the nephew of St. Patrick, who is called in the Irish calendars Lughnat of Loch Measca, the luamaire, or pilot, of St. Patrick.—See Petrie's *Essay on the Round Towers of Ireland*, for further notices of this saint. Tobar Lughna, anglicè Toberloona, is still well known in the country, and the name is still applied to the original object, namely, a holy well dedicated to St. Lughnat, near which are the ruins of an old church close to Cartoon Deer Park, in the parish of Robeen, which is south of the boundary of the modern barony of Carra, in the barony of Kilmaine.

And Robin' being to the east of us,
 A little spot which is delightful to the strangers".
And from Sighin Chiarain of the bells'
 To Tobar Lughna", the soft [i. e. *boggy*],
 O'Birn* obtained that festive land,
 For whom the hazle' waved in hundred tendrils.
 From the Tobar to Caol* of the battles,
 Rodhba and Rathain under Aenach*,

O'Goirmghiolla

* *O'Birn*.—This name is still in the very district here described, but it is anglicised Byrne. In the county of Roscommon the same name is sometimes anglicised Bruin by the peasantry, but O'Beirne by the gentry, and in other parts of Ireland it has been metamorphosed into Byron.

† *For whom the hazel, &c.*—The frequent allusions made to this tree in this poem, and also in the topographical poem of O'Dugan, written nearly a century earlier, show that the Irish valued it highly. They probably used its fruit to feed their herds of swine, and there can be doubt that they used nuts and shamrocks in hard summers to feed themselves.

‡ *From the Tobar to Caol*, i. e. from Tobar Lughna to the Caol, or narrow strait which connects Lough Carra with Lough Mask, and divides Partry from Kilmaine barony. Mr. J. O'Flaherty of Galway says in his reply to queries proposed by the Editor respecting localities in the neighbourhood, that the name Caol, or Keel, is applied to the narrowest part of Lough Carra, where it discharges its

waters into Lough Mask. "There is," he adds, "a bridge over this Caol, or strait, called Keel Bridge, which is on the boundary between the baronies of Carra and Kilmaine; and in the winter the waters of Lough Carra and Lough Mask meet to the south-west of this bridge." This Caol, or strait, may be described as the river by which Lough Carra discharges its superabundant waters into Lough Mask. For the situation of the Bridge which retains the name, and the relative position of these lakes, see Ordnance Map of Mayo, sheet 109, and Balld's Map, sheet 19.

* *Rodhba and Rathain under Aenach*.—The boundaries and extent of this district are better described in the prose list, thus, "The lordship of O'Goirmghiolla extends from Tobar Lughna to the ford of Caol Partraighe, and from the Rodhba to Raithleann." It contains seven ballys [*townlands*] and a half. The place here called Raithleann is now called Realin, and is applied to a woody district on the brink of Lough Carra, between Brownstown house and the bridge of Keel.

O'Goirmghialla fuair a ponh,
 pluais fo trom ghialla ectrann.
 Trí baili an Chriatnaig, can cel,
 'c O'Mailcáná nar cáineo,
 ir Mec Ghillí búio bíno,
 cuiri na Cillí luaidim.

ḡailt-puirt

^b *O'Goirmghialla*.—This name is still in Carra, and generally anglicised Gormilly, though some render it Gormley. This description shows that O'Goirmghialla was not chief of Partry, as stated in the prose list already given, for his district lay east of Keel, which is the eastern limit of the territory of Partry.

^c *Under the heavy thralldom of foreigners*.—This affords an additional evidence that the territory of Ceara was in the possession of the English settlers in the time of the writer. It is quite obvious, from the ruins of the castles and other edifices still remaining, and from the notices preserved in the Irish annals, of others which have been destroyed or modernized, that the English had fortified themselves against the assaults of the native Irish in this beautiful territory at a very early period. These castles are, 1, Caislean na Caillighe, or the Hag's castle, situated in Lough Mask, opposite the mouth of the river Robe; it is a round building of vast circumference, and is mentioned in the Annals of the Four Masters as early as the year 1195; 2, Caislean na Caillighe, on Hag Island, in Lough Carra, opposite Annies; 3, Caislean na Circe, in Lough Carra, on Castle

Island; and, 4, Robeen Castle, already mentioned. The others now remaining are evidently of a later age. To these may be added the great castle of Ballyloughmask, which was rebuilt in the latter end of the reign of Elizabeth, and another very remarkable monument of English power in this territory at an early period, namely, the Abbey of Burriscarra, supposed to have been erected by the Burkes in the thirteenth century for Carmelites or White Friars, but the exact year of its foundation is not on record, or at least is not yet discovered. It was granted by Pope John XXIII. in the year 1412, to Eremites of the Augustinian order. Downing, who wrote a short account of the county of Mayo about the year 1685, for Sir William Petty's intended Atlas, thus describes this barony:—"The barony of Scarra" [*rectè* Carra] "or Burriscarra, lyeth next to Kilmayne, which standeth upon the brinke of a great lough, called Lough Carra, by the ancients Fionnlough Carra, which is said to have been one of the three loughs of Ireland that first sprung. On it is a small abbey, or rather nunnery, called Annagh or Any. It was founded and given by Thomas Burke, the

O'Goirmghialla^b obtained that land
Whose hosts are now under the heavy thralldom of foreigners^c.
 The three townlands of Criathrach^d, without concealment,
Belong to O'Mailcana^e, who was never dispraised,
 And to the melodious Mac Gilli buidhi's^f,
 The host of Cill^g I recount.

The

chief of the Burkes of Mayo, to the abbot of Cong, upon condition that if any woman of his posterity would vow chastity, the abbot of Cong should maintain her during her life, as appears by the several inquisitions after the dissolution of Cong. The next place of note in this barony is the abbey of Burriscarra, of the order of St. Augustine, standing upon the side of the said lake or lough."

^a *The three townlands of Criathrach.*—As the river Robe formed the southern boundary of the territory of Ceara, it is quite clear that these three townlands could not have been on the south side of it. It will follow, therefore, that they were included in the estate of O'Goirmghialla, which extended from the Robe to Raithleann, and from Toberloona to Keel Partry. Hence it must be inferred, that O'Mailcana and Mac Gillibhuidhi were *Brughaidhs*, or tenants to O'Goirmghialla, who, in comparison with them, was a petty chieftain. The name Criathrach is still well known in this district, but anglicised to Creaghe, which is the name of a townland containing the seat of James Cuffe, Esq.

Mr. James O'Flaherty of Galway, in

his letter to the Editor, says, that Creagh, the seat of James Cuffe, Esq., as well as the townland on which it stands, is always called Criaharagh by the natives, in Irish, and that the term *criathrac* is applied in Carra to a flat piece of land intermixed with arable, bogs, sedgy quagmires and brushwood.

^e *O'Mailcana.*—There is no trace of this name now discoverable in the barony of Carra.

^f *Mac Gilli bhuidhi's*, now anglicised Kilboy in this district, but in other parts of Ireland more generally Mac Avoy, which is a strange corruption of the name.

^g *The host of Cill I recount.*—The poet has thrown this description into his verse in a very awkward and obscure manner; but this is not to be wondered at, as it was difficult for him to insert every name into his heptasyllabic metre without lopping off some syllables. More skilful poets were obliged to omit topographical names altogether.

"Quatuor hinc rapimur viginti et millia rhedis,
 Mansuri oppidulo, quod versu dicere non est."

HORACE.

It is much more intelligibly given in the prose list prefixed to this poem, thus:

βαίλι-πυρτ αν τήρι έερ,
 Feart Lothair ap lór d'asbner,
 in τ-Aenach, Loc buadairg bmd.
 ap pluagarib co moç maíóim.
 Do cloind Eirc Chulbuíoi, ad clop,
 Fip Thírí na rreb polup,
 agur Clann Cuan can col,
 nap gann úpan ap ollam.
 Ap Chloind Cuan na cpeç tnom
 τpí ταίριγ do cleç comlonn,

banba

"The three townlands of Criathrach are the estate of O'Maoilcana, and the family of Mac Giolla bhuidhe possess Cillin na m-buidhean, in Criathrach." There can be little doubt that the Cillin na m-buidhean here mentioned was the ancient name of the little church of Cillin or Killeen, lying a short distance to the west of the town of Ballinrobe, for it is quite clear that the district of Criathrach, now Creaghe, which originally contained three ballys, or ancient Irish townlands, or about 1440 Irish acres, was situated on the north side of the river Robe, and extended from Lough Mask eastwards to the point where the river winds southwards before it enters the town of Ballinrobe. It will be necessary here to observe that there are few, if any, townlands now so extensive as the ancient Irish ballybetaghs, thirty of which made a triochoa chead, or 120 quarters, and that the denominations of land in modern times called townlands are generally quarters of the ancient Irish

ballybetaghs. In many instances the ancient names of the ballybetaghs are lost, and the names of their subdivisions only are retained as townland names; but in some instances the name of the ballybetagh remains, although it is not applied to as large a tract of land as it was originally, as exemplified in Criathrach, which is still the name of a townland, but not comprising the one-tenth of the area originally contained under that appellation.—See Adenda for further remarks on the ancient division of territories in Ireland.

^b *Feart Lothair*.—This name is now unknown in Carra. It was the seat of Olioll Inbanda, King of Connaught, who was slain in 544.—See Colgan, *Acta SS.* p. 752.

¹ *Aenach*.—This is probably the place called Annies, situated on Lough Carra, in the north-western extremity of the parish of Robeen. There were a nunnery and a castle at this place. There is no other place in the barony of Carra called by any name like Aenach, which signifies

The chief seats of this southern territory [i. e. Ceara]
 Are Feart Lothair^a of much happiness,
 Aenach¹, and the sweet Loch Buadhaigh¹;
 Before the multitudes I early boast *of them*.
 Of the race of Earc Culbhuidhi, it was heard,
 Are the Fir Thire of pellucid streams,
 And the Clann Cuain without stain,
 Who showed no small kindness to the bard.
 Over Clann Cuain^a of heavy preys
 Were three chieftains accustomed to conflict,

Who

a fair, or meeting of the people, or a place where such meetings are held.

¹ *Lough Buadhaigh*, now probably Lough Boy, in the parish of Manulla; but there is another place of the name in the parish of Islandeady, also in Ceara.

^a *The Clann Cuain*.—The situation of the territory of this clann is distinctly pointed out in the prose tract prefixed to this poem, both as given by Duald Mac Firbis and in the Book of Lecan, thus: "O'Cuinn, O'Maoilfhiona, and Mag Fhlannagain are the three chiefs of Clann Cuain. They are otherwise called Fir Thire, and also Fir Siuire, from a river of the name Sinir, which flows by the town at this day, called Caislen an Bharraigh." This is now called the Castlebar river. It issues from a lake lying a short distance to the west of the town of Castlebar, and flowing through the town it takes a north-eastern course until it passes through the demesne of Turlough, and close by the round tower

of Turlough. At the townland of Drumdaff it unites with a large stream which rises in the parish of Manulla, and their waters flow in a circuitous northern course until they fall into a small lake at Curranear, out of the western side of which their united waters issue, and flow westwards to receive the waters of the Clydagh, which carries with it the tributes of many smaller streams from the mountains. These united streams form a considerable river, which flows in a northern direction between the parishes of Turlough and Templemore, and discharges itself into Lough Cullin, at its extreme southern point.—See Ordnance Map of Mayo, sheets 60, 69, 70, 71, 78, and Balda's Map, sheets 13, 14. From the position of this river it is quite evident that the Fir Siuire, or Clann Cuain, were seated in the parishes of Islandeady, Turlough, and Breaghwy, or Breaffy, which form the northern portion of the present barony of Carra.

banba do tuill d'á toga,
 O'Cuinn calma a céo roga.
 Mag Lannagan na cleth corra,
 leir h-airgead oirear ectrano,
 O'Mailína tall 'na toig,
 pa crann d'ina do damoib.
 Da gab O'Cuinn uair eli
 cairigeet ár tír-ne,
 pa cruaid a comland 'ra céim,
 Domnall, no co fuair oilbéim.
 'C O'Chuinn tápla 'cá taga
 ingean álainn aentama,
 nochar gab ri coma cruib,
 ir í 'ca toga ag triaib.

Tápla

¹ *Who deserved all Banba, &c.*, i. e. who deserved to be monarch of Ireland for his taste and skill in selecting so fertile and beautiful a district.

^m *The brave O'Cuinn*, now anglicised Quin, a name still to be found in Carra, but there was more than one family of this name of a different sept even in the district of the Hy-Fiachrach.

ⁿ *Mag Lannagan*, rectè *Mag Fhlannagan*, i. e. filius Flannagani. It is to be remarked that the old Irish writers sometimes omitted inserting the *í* to mark the genitive case; and that when the initial *f* was aspirated they sometimes left it out altogether, as in the present instance. This name would be anglicised, according to analogy, *Mac*, or *Mag Lanagan*, but the *Mac*, or *Mag* has been long rejected, and

the latter part of the name only retained. There are families of the name *Lanagan* and *Flanagan* still in Carra, but the *O'* and *Mac* are rejected in the anglicised form, though retained in the Irish pronunciation.

^o *O'Mailina*.—This was a different family from *O'Mailina* or *O'Maoilfhiona*, after whom the little town of Crossmolina, in the barony of Tirawley, took its name. For the descent of the latter see page 13. The former was descended from Earc Culbhuidhe, the progenitor of all the men of Ceara.

^p *Of this our territory*, i. e. of the territory of which we are now treating. *Ar, our*, in this line, is used in the same sense as we commonly use “our author,” “our hero,” &c., in English.

Who deserved all Banba [*Ireland*] for selecting it! [*Clann Cuain*],
 The brave O'Cuinn^m was their first choice.
 Mag Lannaganⁿ of the smooth shafts,
 By whom the districts of strangers were plundered,
 And O'Mailina^o, who, yonder at his house,
 Was the sheltering tree of the learned.
 O'Cuinn one time obtained
 The chieftainship of *this* our territory^p,
 Hardy were the conflict and career,
 Of Domhnall^a, until he received disgrace.
 O'Cuinn happened to have
 A beautiful marriageable daughter *who was* wooed;
 She did not receive a gift of cattle^r
 Though she was wooed by chieftains.

There

^a *Domhnall*, i. e. Domhnall was the name of the O'Quin, when this occurrence took place.

^r *A gift of cattle*.—The reward given by the husband to the wife was often called the coibche, or tinnscra, which may be translated by the English word dower, though it rather means a present made to the wife than any fixed estate settled upon her. It appears from a vellum MS. preserved in the Library of Trinity College, Dublin (H. 3. 18. p. 632), that presents of this kind were known by four distinct names, viz., slabhra, coibhche, tochra, and tinnscra. The *slabhra* was a present in live cattle and horse-bridles; the *coibhche* in clothes and warriors; the *tochra* in sheep and swine; and the *tinnscra* in gold, silver, and copper or brass. It is added,

that the first *coibhche* given to each daughter belonged to the father, and that the word *tinnscra* originally meant a bar of gold weighing three ounces. The custom of making presents to the wife and her father also prevailed among the Jews;—see Genesis, xxiv. 22, 53;—and is still observed among the Turks, on which a modern satirist remarks:

“ Though this seems odd,

'Tis true : the reason is, that the Bashaw
 Must make a present to his sire-in-law.”

Cuan O'Lochain, or whoever wrote the old poem on the origin of the name of Tara Hill, also alludes to this ancient Irish custom where he says that Tea, the daughter of Lughaidh, asked this hill as her *ellamh* or dowry, when Heremon was wooing her. The custom is also very frequently

Tápla ne lino ip tip éep
 ní O'Phiácpac fuair aibner,
 Ruaidrí, mac Taitéig na tneb,
 rlat d'ár aithnig cáe inbber.
 Co teé h-l Chuind na tneb te,
 teit O'Dubda á Dún Guaire,
 menne moip fino muige Fáil,
 ar roo ipgaili d'fádbáil.
 Da chí Ruaidrí na ruas meap
 an ingin éen-dub éner gél,
 a n-dorup an grianáin glain,
 polup an ciab nair cobrap.

Γράναίσιρ

alluded to in the most ancient romantic stories about the famous warrior Finn Mac Cumhaill, who appears to have been very liberal in bestowing tinscras on all his wives and concubines.

⁸ *The southern district.*—The territory of Ceara is so called as being the most southern portion of the territory of the northern Hy-Fiachrach.

⁹ *Ruaidhri, son of Taithleach.*—This chieftain is set down by Duald Mac Firbis, in his short annals of the O'Dowd family, as having succeeded Aodh, the son of Muircheartach O'Dowd, who died in the year 1143, and as having preceded Cosnamhach, who was slain in the year 1162. It is, therefore, quite evident that this Ruaidhri was the son of Taithleach, who was the son of Niall, who was son of Maoil-eachlann, who died in 1005, who was son of Maolruanaidh, the son of Aodh, King of

North Connaught, who died in 983.

¹⁰ *A fishing rod to whom every river was known.*—The word *innbher* properly signifies the mouth of a river. This line conveys, it is to be feared, an obscene comparison, which is beneath the dignity of a dry, historical poem of this nature.

¹¹ *Dun Guaire*, i. e. the fort of Guaire. This, which is the real name of a place in the country of the Cinel Guaire, in South Hy-Fiachrach (see p. 67, Note P), is introduced here by a wild poetical license, of which the Irish bards were fond to an extravagance, and which creates a confusion and obscurity difficult to be removed, and which, in some instances, cannot satisfactorily be removed.—See Battle of Magh Rath, where King Domhnall is called of Tailltenn, of Tara, of Uisneach, of Derry, of Dun Baloir, though he never resided at any of those places.

There came at the time into the southern district^a
 The King of Hy-Fiachrach, who had enjoyed happiness,
 Ruaidhri, son of Taithleach^b of the tribes,
 A *fishing* rod to whom every river was known^c.
 To the house of O'Cuinn of fiery tribes
 Went O'Dubhda of Dun Guaire^d,
 The great pillar of the fair plain of Fail^e,
 To get his warlike refection^f.
 Ruaidhri of the rapid onsets viewed
 The black-haired, fair-skinned daughter^g,
 In the door of her beauteous Grianan^h;
 The steady, modest *maiden* was brightnessⁱ.

Ruaidhri

^a *The plain of Fail*, i. e. Ireland.

^b *To get his warlike refection*.—When the chief set out on his regal visitation his sub-chiefs were obliged to entertain himself and his retinue for a certain time; and his demands were sometimes so exorbitant that he was often under the necessity of exacting them by force. Many instances are recorded in the Irish annals of chieftains having forced refection from their subjects by the sword; but it must be acknowledged that in most of those instances the subjects had denied their claim on the grounds that they were not the rightful heirs.

^c *The black-haired, fair-skinned daughter*.—The Irish idea of female beauty is that the black hair is the most beautiful when the skin is fair, but if the skin be yellow it destroys the effect of the colour of the hair. Red hair always accompanies

a fair skin, and, therefore, neither it nor its accompanying fair skin is admired by the Irish. It appears, however, that by far the greater part of the Milesian or Scotie people in Ireland were fair-haired, indeed they are so at the present day, and hence we find their bards admire the fair colour of the hair oftener than any other.

^d *In the door of her beauteous Grianan*.—For a full explanation of the meaning of the word *grianan*, which here means a *boudoir*, the reader is referred to the *Battle of Magh Rath*, p. 7, Note ^a.

^e *The steady modest maiden was brightness*, written by Duald Mac Firbis, *polur an éiab-naí coíraib*. It is impossible to render this line literally into English: it would stand thus in Latin, preserving the order of the Irish words: "*Lux fuit ; crinita-modestè placida*."

Ḑḡádaíḡiḡ Ruaidḡi an ḡuirc cúirḡ
 an ingen aeḡda, áluind ;
 iḡ tḡén táḡla ar a aḡi
 daḡna dḡr do'n dḡḡ-baíli.
 Da ní O'Dubda á Dún Chuind
 ainḡeoin ingine Domnaíll ;
 le tḡén ó táḡḡ arḡeac
 ḡánḡ an ḡcel co ḡcaíḡteac.
 Maḡbḡar ḡí Ráḡa ḡḡanduib
 le O'Cuind do ḡḡḡḡ-lannaib,
 maḡ do bá a m-baḡḡal beḡna,
 'na aenar tḡa an tḡḡeanna.
 Téid, co moḡ ar na máḡac,
 O'Cuind na ḡluag ḡḡḡḡḡac,

vil

^b *Ruaidhri of the bright eye loved.*—It is impossible to translate this quatrain literally into English, preserving the order of the Irish words. It would stand thus in Latin :

" Amat Rodericus oculi acuti
 ḡḡḡ puellam splendidam, formosam ;
 Potenter occurit ejus attentioni [arripuit ani-
 mam],
 Causa lachrymarum ḡḡ bono domo."

The word *baile*, which now means a village, town, and townland, is frequently used in the Irish annals to denote the residence of a chieftain, a castle, or military station, as in the following example in the Annals of the Four Masters at the year 1560 :—Do cúb ar báḡḡ an baile, aḡḡḡ ḡo ḡaíḡe an caḡḡlén ar a cumḡ, i. e. " he went up to the top of the

baile, and proclaimed that the castle was in his power." The word is explained *mac*, a place, in the Book of Lecan, fol. 164, p. b, col. 4 ; and in Cormac's Glossary, the word *ḡac*, a fort, is explained by *baile*. It seems to be derived from the same source as the Greek *πολις*, the Latin *villa*, and the French *ville*.

^c *Of the fort of Conn.*—Dun Cuinn is here merely a poetical name for the residence of O'Dowd, as being a descendant of Conn of the Hundred Battles ; but it leads to great confusion, as one might be apt to believe that Dun Cuinn was the real name of O'Dowd's residence. The orthography of this quatrain is modernised by Duaid Mac Fírbis, as follows :

Do ní O'Dúḡda á Dún Cuinn
 Ainḡeóin ingene Domnuíll ;

Ruaidhri of the bright eye loved^b
 The splendid comely daughter;
 Mightily was his attention engaged
In what became the cause of tears to the goodly mansion.
 O'Dubhda of the fort of Conn^c effected
 The violation of the daughter of Domhnall,
And as by force he entered in
 The report *of the deed* spread widely.
 The King of Rath Branduibh^d is slain
 By O'Cuinn with sharp swords,
 As this lord [*O'Dubhda*] indeed was found
 Alone in the gap of danger^e.
 Early on the morrow went
 O'Cuinn of affectionate hosts,

His

Le tpeun ó cannis irceac,
 Rúinig an rgeul go rgaolceac.

"Effect O'Donda de arce Conni
 Violationem filie Donaldi;
 Et per vim quia venerat intra [domum],
 Ivit q̄ fama diffusæ."

* *Rath Branduibh*, now Rafran, a town-land containing the ruins of an abbey in the parish of Killalla, barony of Tirawley, and county of Mayo. It was one of the *Bailte puirt*, or residences of the chieftains of Hy-Fiachrach, and therefore properly enough introduced here by the poet; though it is to be feared that he would have introduced Tara, or any other remarkable seat of any of O'Dowd's ancestors in its place, if his measure required it.

* *Gap of danger*.—*ðaeḡal-beápnna*, or *beápnna bæḡail*, literally means "gap of

danger;" it is generally used in the Irish annals to denote a perilous pass where the chief usually placed guards to prevent his enemies from making irruptions into his territory; but it is sometimes used to denote danger or forlorn hope. The Irish to this day use the saying *ir é an fear ar an m-beápnna é*, i. e. he is the man on the gap, to denote a man of undoubted courage, principle and integrity; and also the saying *tá rē a m-beápnna an bæḡail*, i. e. "he is in the gap of danger," when they see a man in danger of being ruined in his property or character by his enemy. For a beautiful description of what the Irish and Highlanders of Scotland called a "gap of danger" in the Highlands of Scotland, the reader is referred to *Waverley* by Sir Walter Scott, vol. i. c. 15.

oíl cáé pēbna 'n-a pēapab,
 co ríl meapna Muireabair;
 Tomaltac Mór na tpeab te
 Mac Diarmada, ó bhrúg dóinde,
 pá maep do coib in cinead,
 do pāem dóib a n-ainblicead.
 A táit ó'n ló rin ale
 Clann Cuan, Fir tpeén Tiri,
 can luad cairti 'n-a cenab
 ap pluas maicne Muireabair.

Clann

^f *Sil Muireadhaigh*.—This was the tribe name of the O'Conors and their correlatives, the Mac Dermotts, and other families of Connaught, as already often remarked.

^g *Tomaltach Mor*.—According to the Annals of the Four Masters this Tomaltach Mor Mac Diarmada, or Mac Dermott, became chief of Moylurg in the year 1169, and his death is recorded in the same Annals at the year 1206, in the following words:—"Tomaltach, son of Conchobhar, who was son of Diarmaid, who was son of Tadhg, lord of Magh luirg Airteach and Aicideachta, only prop of the Siol Maolruana, died." From this it would appear that Ruaidhri Mear O'Dowd flourished at a later period than that assigned to him by Duald Mac Firbis in his short annals of the O'Dowd family, namely, between the years 1143 and 1162. There was no other Tomaltach Mac Dermott, chief of Moylurg about this period. His

predecessor in the lordship of Moylurg was Conchobhar, who retired into the monastery of Boyle in the year 1196, and died in 1198, and he was preceded by Maurice, son of Teige, who died in 1187, who was preceded by Diarmaid, son of Tadhg, who died in the year 1159, who had succeeded his brother Maoilseachlainn (son of Tadhg), who was slain in the year 1124; so that if the transfer of the Clann Cuain from O'Dowd to Mac Dermott had really taken place in the time of Tomaltach Mor Mac Dermott, Ruaidhri Mear O'Dowd the cause of this transfer, would have flourished since the year 1196, when Tomaltach Mor succeeded. But there can be no doubt that this is an anachronism of Giolla Iosa Mor Mac Firbis; for it appears from the Annals of the Four Masters that Mac Dermott had possession of the territory of Clann Cuain nine years before Tomaltach Mor became chief of Magh Luirg, namely, in the year 1187, when

His men worthy of any host,
 To the vigorous Sil Muireadhaigh^f;
 To Tomaltach Mor^s of fiery tribes,
 Mac Diarmada of Brugh Boinne^h,
 And under his steward the tribe [of O' Cuinn] submitted themselves,
 He [Mac Diarmada] consenting to their illegal act^l.
 From that day down to this
 The Clann Cuain and mighty Fir Thire^j
 Are without mention of a charter for their tributes
 Among the host of the Sil Muireadhaigh^k.

But

Maurice, son of Tadhg O'Mulrony, was chief of Magh Luirg, and had actually erected a mansion for himself at Claonloch, in the territory of Clann Chuain.

^h *Brugh Boinne*.—This is the reading in both copies. Brugh Boinne was the ancient name of a Pagan cemetery on the river Boyne, near Stackallan, in the county of East Meath; but it looks very strange that Tomaltach Mor Mac Dermott, chief of Moylurg, in the county of Roscommon, should be called of this place, as neither he, nor any of his ancestors, had ever lived at the place. The poet might have easily avoided this incongruity by writing ó bpu Óuille, i. e. from or of the brink of the river Boyle, or ó bpuḡ Óuille, i. e. from the fort on the Boyle; and, were it not that we have the authority of the Book of Lecan, which was compiled by Giolla Iosa Mor himself, for bpuḡ Óoinne, we would be inclined to think that bpuḡ Óuille was the true original reading.

^l *He consenting to their illegal act*.—The poet here wishes his readers to believe that the Clann Cuain had no right to segregate themselves from the chieftain who was of their blood, whatever his conduct towards them might have been; and, therefore, that it was unlawful for Mac Dermott to encourage them to do so.

^j *The Clann Cuain and mighty Fir Thire*.—From this it would appear that the Clann Cuain and Fir Thire were two distinct tribes, though it is distinctly stated in the prose list that Fir Thire was but an *alias* name for the Clann Cuain.

^k *The Sil Muireadhaigh*.—This, as already remarked, was the tribe name of the O'Conors and their correlatives in Connaught. The Mac Dermotts of Moylurg are in reality O'Conors, being descended from Maolruanaidh, son of Tadhg an Eich Ghil (or Teige of the White Steed), O'Conor, king of Connaught, who was slain in the year 1030. "Thadæus an eich ghil (i. e.

Clann Maelruanaid na ruag meap
 gé fuairíreḁ urri áirem,
 a lenmain nī dū do'n dpoing,
 deglegai a cnu pe cpoibing.
 Tucur lim, ir luad fepa,
 do réir na cpaeb coibnepa,
 ó Chloind Maelruanaid, can poind,
 co cpaeb luaraib, map labruim.
 Triallam, cupa rén ropaid,
 ó'n tui fáiríing eplamaig
 co h-lrpuir, 'nap h-oilead ind,
 cūmup na n-airer n-aibind.
 O'Caichmad, nap coigill cpoḁ,
 urri lrpaur nap h-aepad ;

copad

ab equo albo appellatus), genuit Hugonem *an gha bhearnaigh* (i. e. ab obtuso jaculo nomen sortitum), et Mulruanum, a quo Mac Diarmodus de Muighluirgiá originem traxit."—*Dr. John Lynch in Translation of Keating's History of Ireland.*

¹ *The Clann Maoilruanaidh.*—This was the particular tribe name of the Mac Dermott family, which they derived from Maoilruanaidh, who was the son of Tadhg an eich ghil O'Conor, i. e. Teige of the White Steed, and died in the year 1077. From his grandson, Diarmaid, who died in 1165, the family took the name of Mac Diarmada, or Mac Dermott.

² *I have now brought them with me.*—Here the poet throws out no faint suggestion, that his own poem might induce

the Clann Cuain to return from the Clann Maoilruanaidh back to their original chieftain; but it is more than probable that neither Mac Dermott nor O'Dowd had any controul over the Clann Cuain in 1417, when this poem was written. It appears from the annals, however, that the O'Dowd to whom it was addressed had made great efforts to recover the possessions of his ancestors, and it is very likely that this poem, enumerating all the districts in the principality of the O'Dowds, was no weak stimulus to rouse him to exertion. The descent of the Clann Cuain is given already in p. 17.

³ *Of patron saints.*—Eplam means a patron saint, and eplamác, of which eplamaig is the dative or ablative form,

But though the clann Maoilruanaidh¹ of rapid onsets
 Have obtained of them possession,
 To cling to them is not meet for this people;
 Its nut separates from the *parent* branch.
 I have now brought them with me^m, by a reporting of knowledge
 According to the genealogical relationship
 From the Clann Maoilruanaidh, without division,
 To the native stem, as I speak.
 Let us pass, may our journey be felicitous,
 From the wide territory of patron saints^a
 To Irrus^o, where we were fostered,
 That border of delightful districts^p.
 O'Caithniadh^q, who spared not cattle,
Was the chief of Irrus, who was not satirized;

The

means, abounding in patron saints. The patron saints of Ceara were Patrick of Ballintober, Mochus of Balla, Lughnat of Lough Mask, Ciaran of Partry, &c.

^o *Irrus*, now the barony of Erris, forming the north-west portion of the county of Mayo.

^p *That border of delightful districts.*—Written by Duaid Mac Firbis, *ciomar na n-oirpear na n-aoibinn*. The word *oirpear*, of which *na n-oirpear* is here the genitive case plural, is translated *finis* by Colgan in his translation of a part of the Albanic Duan, or poem relating to the Dalriadic kings of Scotland, thus:

Deic mbliadna Loann, léip-élaó
 A 5-flaréar oipir Alban.

"Decem annis Loannus (res nota),

Erat in principatu finium Albanis."

The scenery of Erris is very wild and romantic, but the land is at present so void of trees that it looks awfully naked and desolate; it is evident, however, from the trunks and roots of various kinds of trees found in the bogs, and even on the sea shore, in several places, that it once contained woods of considerable extent. For a curious account of the amenities of the delightful districts of Erris in our own times, the reader is referred to Trotter's Walks through Ireland, and Knight's Connaught Highlands.

^q *O'Caithniadh*. — This family is either now extinct in Erris, or the name has been changed into O'Cathain, or O'Kane. The following notices of this family are preserved in the Annals of the Four Masters:

corab an tóir 'na éuinb,
 molab do'n líne labruim.
 Trí taírig ar tóir rí h-riar,
 a n-lirruir ar úr fornuam,
 ríóig ar mórí fá meabab,
 fine ar cóir do creidemain.
 O'Ceallačan, ceann an t-ríóig,
 O'Muimneacán in mío-óil,
 Me Coinín inn ar cenn ná cuir,
 no min an drem pe dámaib.
 h-l Choinmín, cóir a cuma,
 Meig Phindám 'ra n-árb pulla,
 Mec Conboirni, luaid gar ler,
 róirni do chuaid ó coimeap.

h-l

"A. D. 1180. Aodh O'Caithniadh, lord of Iorrus, was treacherously slain by O'Ceallachain at Cill Chomain [now Kilcommon].

"A. D. 1206. Caithniadh O'Caithniadh, lord of Iorrus, died.

"A. D. 1274. Feargal O'Caithniadh, lord of Iorrus, died in Hy-Mac Caechain [now Dumha Caechain, near Invermore bay, in the north of Erris]."

This is the last notice of the family of O'Caithniadh to be found in the Annals of the Four Masters, and it is highly probable that their power was crippled about this period by Domhnall Iorruis O'Conor (the son of Magnus, who was son of Muircheartach Muimhneach), and that they were soon after totally put down by the

Barretts, who built several castles in this territory. The Editor made every search for the name O'Caithniadh in Erris, in the summer of 1838, but could not find a single individual of the name in the barony, though the old natives have a tradition that such a family once existed. For the descent of O'Caithniadh see page 5, *supra*. Caithniadh, the name of the progenitor of this family, is derived from *cath*, a battle, and *niadh*, a hero.

¹ *The produce of the country is in floods.*—Erris is now any thing but a fertile district, and it is more than probable that it was less fertile in 1417.

² *Excited by metheglin.*—Míó, mead, or metheglin, is very frequently alluded to in the Old Irish poems and romantic tales

The produce of the country is in floods ;
 Praise to the tribe I speak.
 There are three sub-chiefs in this western country,
 In Irrus of splendid aspect,
 A host the most excited by metheglin*,
 A tribe who merited to be believed.
 O'Ceallachain†, head of the host,
 O'Muimhneachain", who drinks the mead,
 Mac Coinin‡, remind us not of him",
 Very kind are those people to the learned.
 The O'Coinminns^x of right condition,
 The Mag Fhionnainns' in the high roll,
 The Mac Conboirnes^x of prosperous name,
 Tribes who have gone beyond comparison.

The

as an intoxicating drink used by the ancient Irish at their feasts.

† *O'Ceallachain*, now Callaghan. — See p. 5 for the descent of this family ; see also Note ^q, p. 216, where one of this family is mentioned as having slain O'Caithniadh, lord of Iorrus.

" *O'Muimhneachain*, now Minahan, a name still common in Erris, and rising into respectability. For the descent of this family see p. 5.

‡ *Mac Coinin*. — For the descent of this family see p. 5, *suprà*.

" *Remind us not of him*, i. e. it is unnecessary to remind us of him, as we can never forget his generosity.

^x *O'Coinminns*. — This name does not occur in the prose list, nor in the pedigrees of the Cinel Feidhlimidh, already

given in pages 5, 6 of this volume. It is now obsolete.

† *Mag Fhionnainns*. — This name is now pronounced in Irish as if written *Ma Gi-onnain*, and anglicised Gannon. — See p. 6 for the descent of this family.

^x *Mac Conboirnes*. — This family is called O'Conboirne in the prose list prefixed to this poem, and also in the genealogical account of the Cinel Feidhlimidh of Iorrus given in pages 5, 6 of this volume ; but Mac Conboirne is the form still retained among the people, and is very probably the true one. This name is now always anglicised Burns, which is a very great corruption, and not to be recommended ; the true form, Mac Conborney, would sound well enough in an English ear.

h-l *Ḑéravan na n-ḡreat reid,*
reovan ar cḡoda caithreim,
do'n ḡarraib ar mór meobair,
cabraib rḡoig fa raep rleobaib.
Mar rin ar léir 'n ár leabair
rḡuas lḡrair can eleabag,
ar cóir áirim na h-aicmí,
rḡoig nár cáinead clannmaicmí.
Fágam lḡrair an fúinb glain,
ḡmállam ḡur an tír dúthair,
dénim co ruain ar ribal,
régam uain caic ollaman.
Mar a deir leabair loma,
poillreócad na fearanna,
ó Dún Phíne co Muaid moill,
nir cḡuaib an líne labroim.
Céad dúcúr a deapair and,
ó Dún Phíne na n-aball,
O'Duiblerga gan ḡráo n-ḡoill,
ceapda 'ran ád do fogloim.

O'Cuind,

^a *O'Gearadhains*, now Gearan. For the descent of this family see p. 6.

^b *Of the fine soil*. — Extensive heathy and boggy mountains, snow-white plains of sand, with here and there a fertile spot, unsheltered against the blasts from the Atlantic, constitute the fine soil of Erris at present.

^c *The native territory*, i. e. Tirawley, in which the ancient patrimonial inheritance of the Mac Firbises was situated.

^d *Bare books*. — *Leabair loma*. The idea here intended to be conveyed by *loma*, the plural form of the adjective *lom*, bare, is not very obvious; perhaps the poet may have intended to distinguish the genuine records, containing the simple naked truth only, from those embellished with romance and fiction.

^e *Dun Fine*, now Dunfeeny, in the north-west of the barony of Tirawley.— *Vide supra*, p. 6, Note ^a.

The O'Geradhains^a of sleek horses,
 A tribe of valorous career,
 A race of great hilarity,
 Whose hosts are firm under their noble spears.
 Thus is obvious in our book *set down*
 The host of Irrus without exception,
 It is meet to enumerate this people,
 A host whose sons have not been dispraised.
 Let us leave Irrus of the fine soil^b,
 Let us pass to the native territory^c,
 Let us quietly pursue our journey,
 Let us observe the opportunity of each ollamh.
 As bare books^d relate,
 I shall point out the lands
 From Dun Fine^e to the sluggish Muaidh^f;
 The race of whom I speak were not penurious.
 The first inheritor who shall be mentioned here,
 At Dun Fine of apple trees,
 Is O'Duibhlearga^g, who loves not the Galls^h,
 An artifex in learning prowess^{hh}.

O'Cuinn

^f *The sluggish Muaidh*, i. e. the sluggish river Moy.—*Vide supra*, pp. 2, 3, for the situation of this river. The epithet *sluggish* is applicable to it in its passage through the plains, but not in the mountains. It is the outlet of the waters of the great Lough Conn, and of all the streams from Slieve Carna and Castlebar lakes northwards to near Killala.

^g *O'Duibhlearga*.—This name is now obsolete. For the descent of the family see

p. 7 of this volume.

^b *Who loves not the Galls*.—The Galls (or foreigners) here alluded to were the English settlers in Tirawley, as the Barretts, Lynotts, Burks, &c.; and O'Duibhlearga's want of love for them doubtlessly contributed in no small degree to bring about the extinction of his own family.

^{hh} *An artifex in learning prowess*, i. e. an adept in learning military exercises and the use of arms.

O'Cuind, fa calma a cinead,
 do'n aicmi nár h-írligead,
 agur O'Comgan can coll,
 i' Meig Obran fa'n fearann.
 O'Duanmuidi fa dígaibh rath,
 agur O'bligi bádach,
 O'berga d'ár élaen na cuill,
 perga na naem do nem thuill.
 O'Radubán, ráb can loct,
 ó baili an Glenna, a glan-porrt,
 an brúgaibh naé bregac blaib,
 cupaibh cébaic an éorram.
 O m-baili péin, ar píp rin,
 Meic Conleirpech an laeárbh,

orpem

¹ *O'Cuinn*, now always anglicised *Quin*, without the *O'*. For the descent of this family, which is different from that of *O'Quin* of *Clann Cuain*, in *Ceara*, *vide supra*, p. 7.

² *O'Comhgan*, called *O'Comhdhan*, in the genealogical account of *Cinel Aongusa*, given in page 7 of this volume, and also in the prose list prefixed to this poem. The name would be anglicised *Cowgan*, but the Editor could not find the name in *Tirawley* in 1838.

³ *Mag Odhrain*. — For his descent see p. 7. This name would be anglicised *Magoran*, but it is not to be found under any recognisable form in *Tirawley* at present. *Magauran*, or *Magowran* of *Tullyhaw*, in the county of *Cavan*, is of a dif-

ferent race, and called in native language *Mag Shamhradhain*.

⁴ *O'Duanmuidhe*. — For his descent see p. 7. The name is now obsolete.

⁵ *O'Blighe*. — For his descent see p. 7. This name is not to be found in *Tirawley* at present. The Editor met persons of the name *Blighe* in *Ulster*, but they do not look upon themselves to be of Irish descent.

⁶ *O'Berga*. — For his descent see p. 7 of this volume. This name is also obsolete.

⁷ *For whom the hazles stoop*, i. e. stoop under the weight of their nuts.

⁸ *O'Radubhain*. — This name, which would be analogically anglicised *Radavan*, is now obsolete.

⁹ *Baile an ghleanna*, i. e. the town, or

O'Cuinn^t of the brave tribe,
One of the people who have not been lowered,
 And O'Comhgan^l, without a stain,
 And Mag Odhrain^k is on that land.
 O'Duanmuidhe^l of happy success,
 And O'Blighe^m the warlike,
 O'Berga^a for whom the hazles stoop^o,
 Who deserved not the anger of the saints.
 O'Radubhain^p,—an assertion without fault,—
 Of Baile an ghleanna^a, his fine seat^f,
 A brughaidh^s of no false fame,
 A hundred-attended hero in defending.
 Of their own town^t, it is true,
 Are the Mac Conleitrechs, the heroes,

A

townland of the glen or valley.—See p. 7, *supra*, where it will be seen that the real name of the glen in which O'Radubhain resided, was Gleann an chairn. The name is now anglicised Ballinglen, and is that of a townland in the parish of Dunfeeny, in Tirawley, near the little town of Ballycastle.

^t *His fine seat*.—*Cl* glan-popt. *Port* means a fort or fortified residence, and is evidently cognate with the English word *fort*. It is used throughout the latter part of the *Annals* of the Four Masters to denote fort, or fortress, as Port Laoighise, the Irish name of the town of Maryborough, in the Queen's County; Port Mor, a large fort erected in the reign of Elizabeth between Lough Key and Lough Arrow, in Connaught; Port Mor, a fort erected by

the English on the Blackwater, in O'Neill's country.—See also the same annals at the year 1595, where O'Farrell's chief castle, in the now county of Longford, is called Port Aireachais Uí Fhearghail, and at the year 1600, where the forts erected, *oo* éinníobh éalman, i. e. of earthen trenches, at Dunnalong, Culmore, and Derry, in Ulster, are called *epí puirt*, i. e. three *ports* or *forts*.

^a *A Brughaidh*, i. e. a farmer.

^t *Of their own town*, i. e. of Baile Mec Conleitreach, which is the name given in the prose list, and which was called after the family themselves. The place is so called to this day in Irish, and correctly anglicised Ballykinlettragh, which is a townland in the north of the parish of Kilfian, in the barony of Tirawley, not far

ɔnem can ɔaɔbɔɪɪɪ um cenɔ ɔɪuɔ,
 aɪ ɪaɔbɔɪɪ ceall nɪ chɪmɔaɔ.
 O Cill Ardub, ɔaɔa an ɔɪɔɔɔ,
 h-l Chaɔaɪaɪ na comlanɔ,
 aɔ ɔul ɔaɪ ɔaɔ ɪaen ɪoɪme,
 'ɪa cɪɪ cáem O'Congaile.
 ɔaɪɪɔɔɔɔ aɪ ɔúɔaɔ ɔóɪb,
 maɪɪɪ menmnaɔ an mór ɪlóɪɔ,
 h-l Muɪɪeaɔaɪɔ, maɪɪɔa a máɪl,
 ɪuɪneaaɪaɪ laemɔa an Laɔán.
 Meɪɔ ɪhɪnnáɪɪ nár eɪɔɪɔ ɪɪɪ,
 ɔ'lb Muɪɪeaɔaɪɔ na meɪɪɔɔɔ,
 ɔo'n maɪɪɪ ɔo chɪnɔ aɪ caɔ,
 ɔo'n aɪɪɪ ɪɪnɔ can anɪaɔh.
 na ɪɪɪ aɔ ɪaɔaɔ ɪa cloɪnn,
 aɔ ɪɪn an Laɔán labɪuɪm.

O

from Ballinglen, mentioned in Note ^a. But though the land has retained the name, the family have either changed their name or have become extinct. For the descent of this family see p. 7, *supra*.

^u *Cill Ardubh*, is so called at this day in Irish, and anglicised Killarduff. It is the name of an ancient church and townland in the parish of Dunfeeny.—See page 8, Note ^b.

^v *O'Catasaighs*, now anglicised O'Ca-seys. For their descent see p. 9 of this volume.

^w *O'Conghaile*, now anglicised Connolly and Conneely.—See p. 9 for the descent of this family.

^x *O'Muireadhaighs*, now Murrays. For

their descent see page 7. They are of a different tribe from the O'Muireadhaighs of Ceara. This family were dispossessed by the Barretts, or Lynotts, about the latter end of the thirteenth century. In the year 1267, according to the Annals of the Four Masters, Aodh, or Hugh O'Murray, was chief of the Lagan, and was slain at Killala by O'Maolfoghmhair, comharba of the church; and in 1268 the O'Murrays slew Aongus O'Maolfoghmhair in revenge for the death of their chief. After this period the O'Murrays of the Lagan disappear from history, and were doubtlessly dispossessed soon after.

^y *The Lagan*.—The name of this territory is written across sheet 3 of Balda's

A people without poverty as to cattle,
 Who have not circumscribed the weal of the churches.
 Of Cill Ardubb^u,—godly the tribe,—
 Are the O'Cathasaighs^v of conflicts,
 Going beyond every road before them,
 And the fair champion O'Conghaile^w.
But the chieftainship is due to those
 High-minded tribes of great hosts,
 The O'Muireadhaighs^x of comely chiefs,
 The majestic pillars of the Lagan^y.
 The Mag Fhinnains^z, who refused not a man,
 Is the Hy-Muireadhaigh of banners,
 Of the tribe who excelled all,
 Of the fair sept without irrationality,
 Men who are kindling *valour* in their sons :
 Such is the Lagan^a I say.

From

Map of the County of Mayo, in such a position that one would infer that he considered it to be co-extensive with the parish of Kilbride, in the north of the barony of Tirawley ; but nothing is more certain than that the Lagan comprises the parish of Dunfeeny also. The name Lagan signifies a hollow, or hollow district between hills or mountains, and, according to the most intelligent of the natives, the district naturally so called is bounded on the east by the hills of Kilbride, on the south by Athleague hill, in the parish of Lackan, and thence by a range of hills as far as Ballinglen, and from Ballinglen it is bounded by the mountains of Dunfeeny, as far

as the sea, which bounds it on the north. But it will appear from this poem that the territory of O'Muireadhaigh called the Lagan originally extended eastwards to the strand of Lacken, where it met the territory of Caeille Conaill.

^u *Mag Fhinnain*.—This family is called O'Fionnagain in the genealogy of the Cinel Aongusa, given in page 7 of this volume, and in the prose list prefixed to this poem, in both which this family is called of Fionnchalamh, which was the ancient name of a district adjoining the territory of Hy-Eathach Muaidhe on the north-west.

^a *Such is the Lagan*. — It is quite clear

O Rath Branduibh ar binn cluig,
co Traigh cell, conair éagmaid,
cric an Chasli nár báid blas,
nár cáime clár na Cruacán.

Conall, mac Feargusa fíno,
uada Clann Conaill ceóil-bíno,
ir í a clann cric an Chasli,
ní fíoch am d'á n-éagaine.

O'h-Aeda nár éir ollam,
drem ar buga buan dhonnad,
ó Ard O'h-Aeda na n-éc,
na craeba ra h-árd einéac.

Inad tairig ar tír thuaidh
fuair O'h-Aeda an airn indfuair,
ar lár an Chasli d'á cloind,
clár ar cáime d'á canoim.

1

from the whole context that the poet has been here treating of the tribes and subdivisions of the Lagan since he left Irrus up to this line. After this he goes into *Caeille Conaill*, the next territory to the south, which was separated from the Lagan by the strand of Traigh Ceall, now generally called Lacken strand.

* *Rath Branduibh*, i. e. the rath or earthen fort of Brandubh, a man's name formerly common in Ireland. The name is now anglicised Rafran, and the place, which is situated near Palmerstown, in the parish of Killala, is well known for its abbey. According to a notice in the genealogy of the Hy Airmeadhaigh, already

given in page 9, the southern limit of this territory of Caeille Conaill, was called Fearsad Treisi, for the situation of which see page 9, Note ¹. It is there stated that Fearsad Treisi is now, and has been for centuries, called Fearsad Rath Bhraín, but as no authority is there quoted, it is necessary to add here that it is distinctly stated in the *Dinnsennchus*, as given in the Book of Lecan, fol. 247, a, a, that Fearsad Treisi was called Fearsad Rath Branduibh in the time of the writer. "Fearsad Treisi whence derived? Not difficult: Treisi, daughter of Nadfraech, and wife of Amhalgaidh, son of Fiachra, son of Eochaidh, was drowned in it; so

From Rath Branduibh^b of the sweet bells^c
 To Traigh Ceall^d, a road which we pass,
Stretches the country of Caeilli of no extinguished fame,
 Not fairer was the plain of Cruachan^e.
 From Conall, son of Fergus, the fair,
 Sprung the musical Clann Conaill^f;
 His race are *in* the territory of Caeille;
 No time is found complaining of them.
 O'h-Aodha^g, who never rejected a man of learning,
 A people of constant liberal bestowing,
 Of Ard O'n-Aodha^h of steeds,
 Branches of high hospitality.
 The place of a chieftain in the northern district
 O'h-Aodha of the cold-weapon has obtained;
 His children are in the centre of Caeilli,
 The fairest plain of those I mention.

The

that it was called from her; but it is called Fearsad Ratha Branduibh at this day."

^c *Of sweet bells*.—This shows that the abbey of Rafran was in existence in the time of the writer.

^d *Traigh Ceall*.—This name is retained to the present day, and is situated at the village of Rathlacken, near Killala.—*Vide supra*, pp. 8, 9, Note ^h, and Ordnance Map of Mayo, sheets 7, 8, 14, 15. This place was anciently called Traigh Murbhaigh, i. e. the strand of the murbhach, or sea-plain.—See p. 8, Note ^h.

^e *The plain of Cruachan*, now the plains of Rathcroghan, in the county of Roscom-

mon, one of the most fertile districts in all Ireland.

^f *Clann Conaill*.—*Vide supra*, p. 9.

^g *O'h-Aodha*.—This name is generally anglicised Hughes in the county of Mayo.

^h *Ard O'n-Aodha*, would be anglicised Ardonea, but the name does not exist. The place was evidently situated near Mullaghnacross, in the parish of Templemurray, which is about the centre of this beautiful territory, anciently called Caeille.—See Ordnance Map, sheet 15. That part of the parish of Kilcummin lying south and east of the strand of Lacken belonged to this district; and St. Cummin, the patron of that church, was of this race.

1 Mailconaire can chol,
 h-1 Flannabhra can leóna,
 h-1 Shégoa pa tend topa,
 bream can éra ollaman.
 Da luaidir, ar luad pera,
 Clann Conaill 'ra coibnepa,
 maí naé nár d'on péim uilí,
 d'á ráo 'ra péim rígnairí.
 h-1 Eacac Muaidhe na maí
 ó Ror Seirce na rreb pulcár,
 co Fearraio Théri pá éuaio,
 fearraio ar théri trom-íluais.
 1 Mailabmar, fuair fleoa,
 h-1 Lenán, laic lán-meípa,
 ní cranda aenairí an fuio,
 clanda Laegairí labruim.
 D'ib Mailpobmar nár éraio cluig,
 na peit n-Érpuic puirt Pádraig,

ocur

ⁱ *O'Mailchonairi*, properly anglicised O'Mulconry, but now generally rendered Conry and Connery.

^j *O'Flannabhra*, now Flannery, but the name, though common in other parts of Ireland, is not in the district of Caeille at present.

^k *O'Seghdhas*.—This name is now anglicised O'Shea, but the respectable families bearing that name are not of this race. For the descent of this race see page 9, where the name is spelled O'Tegha.

^l *Hy-Eathach Muaidhe*, i. e. Nepotes Eochodii de Moda, descended from Eoch-

aidh Breac, son of King Dathi. The poet is proceeding southwards with his description. He first describes the Lagan, the most northern district of Tirawley; he next crosses the strand of Traigh Ceall, at Lacken, to go into the territory of Caeille, and now he crosses the bay of Rafran, to go into the territory of the Hy-Eathach of the Moy, extending from Fearsad Treisi, at Rafran, southwards to Ros Seirce, in the parish of Ballysokeery.—See p. 51 for a curious notice of the extent of the territory of the Hy-Eathach Muaidhe.

^m *Ros Seirce*.—See p. 51, Note 1, *supra*.

The O'Mailchonaire¹ without a blot,
 The O'Flannabhras¹ without oppression,
 The O'Seghdhas² of rich produce,
 Heroes who reject not men of learning.
 I have mentioned, it is a reporting of knowledge,
 The Clann Conaill and their correlatives,
 As it is no shame to all the heroes
 To have them set down in the regal list.
 Hy-Eathach Muaidhe¹ of the plains
Extends from Ros Seirce^m of the bright streams
 To Fearsad Treisi, north,
 A pass of most powerful hosts.
 The O'Mailfaghmhairs^a who prepared the banquets,
 The O'Leanains^o, full vigorous heroes,
 Not decrepid are the hosts of the soil;
 Of the descendants of Laeghaire^p I speak.
 Of the O'Mailfoghmhairs, who violated not bells^q,
 Were the seven bishops of Patrick's city^r,

And

^a *O'Mailfaghmhairs*, now anglicised Milford. For their descent see p. 50. The heads of this family were the herenachs or hereditary wardens of the church of Killala, and they supplied several bishops to that see. For some curious notices of this family, and of the church of Killala, the reader is referred to the *Annals of the Four Masters* at the years 1235, 1253, 1257, 1260, 1267, 1275, 1280, 1306, 1328, 1343, 1350, 1416, 1442.

^o *O'Leanains*.—This name is now anglicised Lennon, and by some Leonard.

^p *Clann Laeghaire*.—For the descent of

the Clann Laeghaire *vide supra*, p. 51.

^q *Who violated not bells*, because they were a hereditary ecclesiastical family.

^r *Patrick's city*, i. e. the ecclesiastical city of Killala, said to have been founded between the years 434 and 441, by St. Patrick, who, during that period, was preaching the gospel and founding churches in the province of Connaught. It is stated that St. Patrick placed one of his disciples as bishop over the church of Killala, where his festival was celebrated on the 12th of August; but it would appear from the pedigree of Muireadhach that he could not

ocur peēt toga co tend
 'pa cōpa aḡ teēt na timceall.
 h-l Criaibcein pa maith mana,
 h-l Flaitilī laempcāpa,
 h-l Močan nār tréig rib treall,
 pa clocán o' éigrib Ereamn.
 h-l Maeilaiḡein na n-ḡruao n-ḡel,
 h-l Maeilbrenainn na m-boirb-ḡleg,
 oream pe h-ḡgaib banba aḡ báio,
 h-l ḡrḡdaib calma h-l Crecáin.
 Aḡ rin h-l Eacac na n-each,
 an orem nār can acēt cept-breath,
 menma mór 'can maicni ḡind,
 an ḡlḡ ar aipci áirmim.
 Triallam annr a' m-ḡrédais m-buig,
 do clect cata ir cḡuar cómpais,
 na cḡoinn ó b-ḡaḡbam feara
 ḡo cloinn arm-duinn Phearḡara.
 O' Togda ar cendḡort do'n cat,
 taircē na ḡrédca ar buadaic,

have lived in St. Patrick's time, for he was the son of Eochaidh, who was the son of Oilioll, son of Guaire, son of Lughaidh, monarch of Ireland, who died in the year 508, who was the son of Laoghair, who was monarch of Ireland for thirty years after the arrival of St. Patrick.—See Book of Lecan fol. 306, a. Of the successors of Muireadhach, in the see of Killala, but very little is recorded in the Irish annals, and the incidental mention of these seven bishops here shows that there was once a

record of the succession of the Bishops of Killala, which is either lost, or not yet accessible to any of our ecclesiastical writers.

¹ *O'Criaidhcheins*.—See p. 51, Note ¹.

² *O'Flaitilies*.—See p. 51, Note ¹.

³ *O'Mochains*, now Mohans. — See pp. 41, 42, 43.

⁴ *The causeway*. — This looks an extraordinary figure, but it is quite intelligible to an Irish speaker.

⁵ *O'Mailaithghins*, now unknown, at

a

And seven who were strongly elected
 In the choir (chapter) who came around them.
 The O'Criaidhcheins^r of goodly plight,
 The lofty-proud O'Flaitilies^r,
 The O'Mochains^u who have not forsaken you, once,
 Who were the causeway^r of the learned of Erin.
 The O'Mailaithghins^w of bright cheeks,
 The O'Mailbhrenainns^x of terrific spears,
 Heroes who contended with the youths of Banba^y,
 The brave O'Broduibhs^z, and the O'Creachains^a.
 These are the Hy-Eachach of the steeds,
 A people who have spoken only a just sentence,
 This fair tribe have a lofty mind,
 They are the most expert host I mention.
 Let us pass into the soft Bredach^b,
 Which is accustomed to battles and hardness of conflict,
 To the scions from whom we shall receive information,
 The Clann Fergus^c of brown weapons.
 O'Toghdha^d is head of the battle,
 Victorious chief of Bredach,

To

least to the Editor. — See the descent of this family in p. 35, *suprà*.

^x *O'Mailbhrenainns*. — This family have anglicised their name to Mulrenin.

^y *Youths of Banba*, i. e. of Ireland.

^z *O'Broduibh*. — This name would be anglicised Brodiff, but it does not exist in the district. — See p. 35.

^a *O'Creachains*. — The name of this family is variously anglicised Crean, Greaghan, Grehan, and the Editor knows an individual of the name who has rendered it

Graham. — See p. 35, *suprà*.

^b *Bredach*. — This territory, which contained fifteen ballys, or sixty quarters of land, comprised the parish of Moygawnagh, in the west of the barony of Tirawley, and a part of that of Kilfian.

^c *Clann Fergus*. — For the descent of this sept see pp. 9, 11.

^d *O'Toghdha*. — The only notice of this family preserved in the Annals of the Four Masters is at the year 1206, under which the death of Ruaidhri O'Toghdha,

α λυαδ νοα δοιιδ δαμ,
 τρυαζ can οιζιη na n-αηηαδ.
 Cuid h-l Luachduib do'n leith e-riar
 do'n δρέδαζ αη βλάιτ ποηηιαμ,
 πλαίτi πα buaid do bunad
 ρλυαζ 'pa maiτi αζ μέδούζυδ.
 O'Gloinin náη coiγill epod,
 O'Gilin na n-αηη n-άδμαη,
 'r á δρέδαζ πα τenn an τόηη
 an drem do μέδαζ mío-óil.
 Ατάιδ ό Μυιζ Σαμναά γλαν
 h-l Deirg na m-brug m-bláetmar,
 ιη h-l Σαδαν γλέηι γλαν,
 παδαδ δ'πέλι αζυρ δ engnam.
 Págam δρέδαά na n-γοητ n-γλαη,
 do cannam dpong d'á dúcar,

dénam

chief of Breadach, in Tirawley, is recorded. Charles O'Connor of Belanagare anglicises it O'Toffey in a translation of a part of these Annals, but the Editor could not find the name in any shape or form in the district, and he is inclined to think that the family was nearly extinct even when this poem was written, as would appear from the words "Pity that there is no heir of the champions."

^d *No heir of the champions.*—In Duaid Mac Firbis's copy is given as an alias reading, τρυαζ γαν οιοη 'n-α φφααδ, i.e. "Pity that there is no heir with them or of them."

^e *O'Luachduibh.*—This name is also ob-

solete. — See p. 11, Note ^x; though it would appear from the line, "The host and their chiefs are increasing," that they were in full bloom in 1417, when this poem was written.

^f *O'Gloinin.*—In the prose list prefixed to this poem it is stated that O'Gloinin was seated at Rath na n-goirmghiall. The name is now either entirely lost or disguised under the anglicised forms of Glen-non, or Glynn. The chief of this family slew the famous warrior, Cosnamhach O'Dowd, in the year 1162, in a dispute about a greyhound whelp.

^g *O'Gilin*, now obsolete. — See p. 11, Note ^y, *suprà*.

To mention him is not grievous to me,
 Pity that there is no heir of the champions^d.
 O'Luachduibh's^e part of the western side
 Of Bredach is of brilliant aspect,
 Chiefs *accustomed to* victory from their foundation,
 The host and their chiefs are increasing.
 O'Gloinin^f who spared not cattle,
 O'Gilin^g of the victorious arms,
 In Bredach powerful their pursuit,
 The people who have increased mede-drinking.
 Of the fine Magh gamhnach^h are
 The O'Deirgsⁱ of flowery habitations
 And the O'Gadans^j of pure honour,
 Glowing with hospitality and valour.
 Let us leave Bredach of the green *corn* fields,
 We have sung of some of its inheritors,

Let

^h *Magh gamhnach*.—This name means the plain of the milch cows or strippers, and is rendered "*campus fætarum sive lactescentium vaccarum*" by Colgan in his translation of the Life of St. Cormac.—See *Acta Sanctorum*, pp. 752, 755. The name is retained to this day, and correctly anglicised Moygawnagh, and is that of a parish in the west of the barony of Tirawley. Of the original church of this parish, which was dedicated to the virgin St. Daria, no vestige now remains, but its graveyard is still used for interment; it is situated in the townland of Knockaculleen, close to the river of Moygawnagh.—See Ordnance Map of the County of Mayo,

sheet 29. This parish comprises the greater part of the territory of Bredach, which extended northwards as far as the territory of the Lagan. It was bounded on the north by the Lagan, on the east by Caeille Conaill and Hy-Eathach Muaidhe, on the south by Calraighe Muighe h-Eleog, and on the west by Erris.

ⁱ *O'Deirgs*.—There are several of this name in the counties of Mayo and Sligo, where it is anglicised Durrig, Derrig, and Derrick.

^j *O'Gadans*.—This name is not in the district, though it exists, in other parts of Ireland, under the anglicised form of God-dan, Godwin, or Goodwin.

dénam ruar ip a' m-bac m-bind,
 ar pnap a chnuar map cluimim.
 Tairígeet h-l Láctna lán,
 cóip a maíom 'ra morbáil,
 in dá bacc ip a Glend glan,
 dar lat ip tenn a tórad.
 Arnd Ácav ar aibind fíó,
 Cill belav, bpuv na filiv,

'c

* *Up into sweet Bac.*—By ruar, *up*, is to this day meant “to the south,” in this part of the country. On examination of the topography of Tirawley it will be seen that the poet, after describing the territories of the Lagan, Caeille Conaill, and Hy-Eathach Muaidhe, next moves westwards into Bredach, and after describing which he moves *upwards*, i. e. in a southern direction, to visit the families of Bac,—in a district commonly called *The Two Bacs* in English, at the present day, which originally extended from Rosserk, in the parish of Ballysokeery, southwards, to the point where Lough Cullin discharges its superabundant waters into the river Moy. The territory of the Two Bacs (an Dá Bhac) was bounded on the north by the territory of the Hy-Eathach Muaidhe, from which it was separated by a small stream falling into the river Moy, near the abbey of Rosserk; on the east by the river Moy, from the point where it receives the abovementioned stream at Rosserk, southwards, to where it receives the waters of Lough Cullin; on the west

by Lough Cullin and Lough Conn. But though such were the undoubted limits of the Two Bacs in ancient times, the name is now applied to a comparatively small district comprising the modern Roman Catholic parish of Bacs, which contains only the ancient parishes of Ballynahaglish and Kibelfad; and it is now generally believed that the Two Bacs never comprised more than the district lying between Lough Conn and the river Moy. So it is shown on Balde's Map of the County of Mayo; and it was described for the Editor in 1838, by the most intelligent of the natives, as divided into two parts called Cul-Bhac and Beal-Bhac, and extending from Rathduff, northwards, to Rehins, near Ballina, and westwards to Cloghans and Shraheen hill, in the parish of Kibelfad. But it is clear from this poem that the territory of the Two Bacs was originally much more extensive, for Ardagh, Kilmoy, and Rosserk, are said to be in it; and Rosserk was on the boundary between it and the country of the Hy-Eathach Muaidhe, which extended,

Let us make *our way* up into sweet Bac^t,
 Quick *grows* its fruit as I hear.
 The full chieftainship of O'Lachtna¹,
 (Just his boast and ostentation),
Comprises the two Bacs and the fair Glenn^m,
 Rich methinks its production.
 Ard achadh^a of delightful woods,
 Cill Belad^o, seat of the poets,

Belongs

according to all the authorities, from Ros Eirc, or Ros Seirce, to Fearsad Treisi. There is a remarkable pillar stone about half a mile to the west of the abbey of Rosserk, which may well be supposed to have marked the boundary between it and the latter territory.

¹ *O'Lachtna*. — This name is still common in many parts of the county of Mayo, and is now always O'Lachtnain in Irish, and anglicised Loughnane, and sometimes even Loftus, as already stated in p. 10, Note ^o. In the Annals of the Four Masters, at the year 1217, the name is written O'Lachtna. "A. D. 1217. Cathal Fionn O'Lachtna, chief of the Two Bacs, was treacherously slain in his own house by O'Flynn of Magh h-Eleog." But at the year 1251, the same annalists write the name O'Lachtnain, exactly as it is pronounced at the present day, thus:—"A. D. 1251. Flann O'Lachtnain, chief of the Two Bacs, died."

^m *The fair Glenn*, i. e. Glenn Nemthinne. In the prose list prefixed to this poem it is stated that O'Lachtna was chief of the Two Bacs and Gleann Nemthinne. This

glen or valley district is situated on the west side of Lough Conn, comprising nearly all the parish of Addergoole, in the barony of Tirawley; its boundary runs from Lough Conn in a south-western direction to Bearna na gaoithe, or Windy Gap, thence westwards to the mountain called Birreencorragh, and thence northwards to Tristia, thence to Ballybrenoge, and thence to Caerthannan, otherwise called Castle Hill, and back again to Lough Conn. It is named Glenn Nemthinne, from a lofty mountain called Cnoc Nemthinne which towers over it to the height of 2646 feet.

^a *Ard achadh*, i. e. high-field, now Ardagh, a parish in the barony of Tirawley.— See p. 11, Note ^t.

^o *Cill belad*, now Kilbelfad, a parish included in the district called the Two Bacs, and verging on the east side of Lough Conn, in the south of the barony of Tirawley. According to tradition Belfad was the name of the patron saint of this parish, and is supposed to have been a bishop, but no notice of him is to be found in the Irish calendars.

'c O'Maílruain nár eirig fear,
 ne h-eirib pluais ag rínead.
 O baile h-l Eimeacán uill
 O'h-Eimeacán fuair orruim,
 'na brúgaid fa buaid can bhois,
 pluais ana tulaig tegaid.
 O'Laecáilli, laec can lén,
 brúgaid do biaéad brianén,
 triat Muigi Fuara na fíed,
 cuipe cuanna nár cáinead.
 O Uir Cumín na n-geor n-geal,
 h-l Cumín cróda an cinead,
 brúgaid nár feall ar aicmí,
 cúbaid cenn na clannmaicmí.
 Meic Conléna na lann fear,
 h-l Dubagán na n-béig-fear,
 ó Chill móir Muaid na maí,
 foir na ba cruaidi cungham.

h-l

^p *O'Maílruain*.—This name would be anglicised Mulroynne, but it does not exist now in this district.

^q *Baile Uí Eimeachain*.—This name, which was undoubtedly applied to a large Ballybetagh, or ancient Irish townland, containing about 480 Irish acres, is now obsolete, and no clue has been discovered to ascertain what position in the territory of the Bacs it occupied, unless that, as it is mentioned immediately after Cill Belad, we may assume that it was in the immediate neighbourhood of the place now called Kilbelfad. The family name,

O'h-Eimeachain, which would be analogically anglicised Emaghan, is also obsolete.

^r *O'Laechaille*, now obsolete.

^s *Magh Fuara*, is now obsolete, and its position in the territory of the Bacs cannot be determined.

^t *Lis Cumín*.—From a notice of this place already given in page 11, it appears that it was situated on the river Moy, but the name is not in existence.

^u *O'Cumins*, now Cummin and Cummins; but there are several families of the name in Ireland, and many of them of English origin.

Belongs to O'Maoilruain^p, who refused not any one,
 Who marches with the wings of the army.
 Of Baile Ui Emeachain^q the great
 Is O'h-Emeachain, who obtained respect,
 A victorious Brughaidh without oppression.
 Hosts to his mansion come.
 O'Laechaille^r, a hero without misfortune,
 A Brughaidh who was wont to feed the ravens,
 Is lord of Magh Fuara^s of banquets,
 A comely hero who was never dispraised.
 Of Lis Cumin^t of the white *corn*-fields
 Are the O'Cumins^u, a brave tribe;
 Brughaidhs who acted treacherously to no people;
 And worthy *of his rank* is the head of the family.
 Mac Conlena^v of ancient swords,
 The O'Dubhagains^w of good men
 Were of Cill mor Muaidhe^x of the plains,
 A troop hardy in *giving* succour.

The

^v *Mac Conlena*, now obsolete.

^w *O'Dubhagains*.—This family now spell their name Duggan, which is a very ugly form of the name. O'Flaherty anglicised it Duvegan in the latter end of the seventeenth century, and in 1758 a very respectable man of the name, Dr. Michael Ignatius Dugan, of Dublin, wrote it Dugan, with a single *g*.

^x *Cill mor Muaidhe*, i. e. the great church of the river Moy, now always anglicised Kilmore-Moy, and is the name of an ancient church situated a short distance to the north-west of the town of Ballina, in

the barony of Tirawley, and giving name to a parish which is partly in the barony of Tirawley, on the west side of the Moy, and partly in that of Tireragh, on the east side of the same river. This church is much celebrated in the lives of St. Patrick, and particularly in the Tripartite Life, under the name of Cill mor Uachtar Muaidhe, as the reader will find by reference to Colgan's *Trias Thaum.* pp. 137, 141. The Editor examined the old church of this place in May, 1838, but found it so patched up with the repairs of various ages, that it would be difficult to determine

h-1 Airmeadhaigh na n-é meir,
 h-1 Ronan do fuair aipeam
 ó Mag m-bróin na call corcra,
 nír gann an rlog romolta;
 Clann Fírburigh nár luais loct,
 ollamain cuigib Connact;
 ó Roperc dóib na deaib;
 nír cóir ceilt a cineadaigh.
 Tar loc riar da reola mé
 ní raic usgi bur faide,


ni

ient extent or characteristics, ex-
 s ancient doorway. Near it is a
 ell dedicated to St. Patrick, the
 and founder, and on a hill imme-
 to the south is an old church-
 n which is a rock anciently called
 manach, on which the Irish spos-
 sed a cross to be inscribed. — See
 ripartit. lib. ii. c. 90. This cross
 : seen at this day inscribed in incise
 a circle, sixteen inches in diameter.
Airmeadhaigh, now either obsolete,
 uised under some strange anglicised

Ronans, anglicised Ronan in Con-
 t, where there are several distinct
 s of the name, and Ronayne in
 er.

agh Broin. — This is one of the
 mentioned in the very early portion
 a history. In the *Dinnsenchus*, as
 red in the Book of Lecan, fol. 247,
 t is called one of the remarkable

places of Tir Amhalgaidh, or Tirawley,
 and said to have been named from one of
 the Tuatha De Dananns, a colony, who
 preceded the Scoti or Milesians in their
 occupation of Ireland, namely, from Bron
 (the son of Alod, and brother of the na-
 vigator, Manannan Mac Lir), who first
 cleared this plain of wood. Though this
 was brought under cultivation at so early
 a period, and seems to have been cele-
 brated by the Irish bards for its beauty
 and fertility, as well as for its antiquity
 and the hospitality of its proprietors, there
 is no person now living in Tirawley that
 ever heard of the name, much less any one
 who is able to point out its position in the
 territory of the Bacs: but it is highly pro-
 bable that the name is retained in Killy-
 brone—which may well be supposed a
 corruption of Cill Mhuighe Broin,—the
 name of a townland containing the ruins
 of a church near Deel Castle, in the parish
 of Ardagh. The beauty, fertility, and level



ní gearr an lánac linde,
 co Glenn napaic Némthindí.
 h-l Mailfína nár éir fear,
 h-l Gaibtheacán na n-gér pleag,
 ag dáil craisic do'n cuiri,
 dá tuiscic cláir Challraige.
 Ar Muig Eleag ar árd rath,
 'na brúgaid calma céadac,
 O'Floind, an féinneag ferba,
 par éirig dhoing déig-delba.

h-l

^d *O'Mailfína*.—This name, which was anglicised O'Mollina, is now scarcely extant. At the year 1269 it is stated in the Annals of the Four Masters that Flaithbheartach O'Maoilfhiona, chief of one half the territory of Calraighe Muighe h-Eleog, was slain by O'Gaibhtheachain, chief of the other half; but no other entry relating to them is found in that chronicle. For the descent of this family see p. 13.

^e *The O'Gaibhtheachains*.—This family have all anglicised their name Gaughan, which is not incorrect. The name is still common, and the family remarkable for their vigour and longevity. The Editor conversed with a man of this name in the town of Westport, who was working at his trade as a mason, in the eighty-ninth year of his age, when he was in vigorous health and in the full possession of his memory and other mental faculties.

^f *Calraighe*.—This is called Calraighe Muighe h-Eleog in the Annals of the Four

Masters, at the year 1269, as above seen in Note ^d. This territory, which contained Cros Ui Mhaoilfhiona, the seat of O'Maoilfhiona, now the little town of Crossmolina, was nearly co-extensive with the present parish of Crossmolina; it was bounded on the north by the territory of Bredach, or the parish of Moygawnagh, on the east by the territory of the Two Bacs, Lough Conn forming, to a great extent, the boundary between them; on the south by Glenn Nephin, which it met at Caerthannan, now Castlehill, and on the west by Erris.

^g *Magh Eleag*, generally written *Magh h-Eleog*, was the plain, or the level part of Calraighe, through which the river Deel flows.

^h *Hundred-cattled brughaidh*.—The ancient Irish brughaidh, or farmer, was called brughaidh ceadach, i. e. the centurion brughaidh, because he was bound by the law to keep one hundred labourers

It is not a short excursion on the water
 To *reach* the prosperous Glenn Nemthinne.
 The O'Mailfhinas^d who refused not any one,
 The O'Gaibhtheachains^e of the sharp spears,
 Distributing lances to the troop,
 Were the two chiefs of the plain of Calraighe^f,
 Over Magh Eleag^g of high prosperity,
 As a brave and hundred-cattled^h Brughaidh
 Is O'Floinnⁱ, the manly champion,
 Under whom a fair-faced race have risen.

The

and one hundred of each kind of cattle of domestic animals, as cows, horses, pigs, sheep, goats, cats, hens, geese, bees, &c. This is distinctly stated in the *Leabhar Buidhe* of the Mac Fimbis of Lecan, col. 921, now in the Library of Trinity College, Dublin.

ⁱ *O'Floinn*, now O'Flynn. It is stated in the prose list prefixed to this poem that O'Floinn was seated at Oireamh of Lough Conn, now Errew, a townland in the parish of Crossmolina, on a point of which, stretching into Lough Conn, stand the ruins of an abbey of considerable extent, but now much decayed, said to have been erected by the Barretts on the site of a very ancient church dedicated to St. Tighearnan of Errew, to whom the more modern monastery was also dedicated, as appears from the following passage in the *Annals of the Four Masters* at the year 1413:—"Henry Barrett was taken prisoner in the church of Airech Locha Con,

by Robert Mac Wattin [Barrett], who led him captive, though he violated the church [by so doing]. But the patron saint of the place (Tighearnan Airigh) appeared every night to Mac Wattin in a vision, requesting him to restore the prisoner; this request was finally agreed to, and Mac Wattin bestowed a quarter of land on St. Tighearnan Airigh for ever, as an *eric* [reparation] for having profaned his church." A holy well, called Tobar Tighearnain, dedicated to this saint, is situated in the south of the townland of Killeen, and a relic, which belonged to him, called Mias Tighearnain, i. e. St. Tighearnan's dish, was preserved for ages in the family of O'Flynn, who are said to have been the herenachs, or hereditary wardens of Errew; but, though they held it in the highest veneration as a relic of the patron saint of their family, they were finally induced, in a hard summer, when provisions were very dear, to sell it to Mr. Knox of Rappa

h-l Flannghail nár luaid loct,
 dhém i' coitcínibí cródaict,
 im Loct Glindí, fá'n fial fear,
 gillí d'ár gíall an gaircead.
 Da cumar, ar fáth fepa,
 do péir na craeb coibnepa,
 pineadaig an tírú táll,
 d'fíleadaib míne Manann;
 mar dlegar dom [no do'n] cleir in chuig,
 do péir gac lebuir labruim.
 Tiucpaó a h-aíclí m'éctpa,
 begán cróga cuidecta
 ní h-aimglic a n-uair lámair,
 tar Muaid m-baill-bhíoc m-bhpadánaig.

Peatb

Castle, in whose possession it now remains. This relic was seized upon by Dr. Lyons, who found it with the peasantry, when one of them was in the act of swearing upon it, by consent, it appears, of Mr. Knox, and while it was in his possession he published a curious description of it, with an account of the superstitious uses made of it by the peasantry. It was afterwards restored to Rappa Castle on condition that it should never again be lent to the peasantry to be sworn upon, or used for any superstitious purposes, and this condition has been honourably observed by the proprietor of Rappa Castle, who sets a high value on the Mias Tighearnain, as being a monument of the primitive Irish Church, and the chief, if not the only relic

of Tirawley, which it is an honour to his family to preserve. For the pedigree of St. Tighearnan, who is stated to have been fostered by an ancestor of the Mac Fimbis, see p. 12, Note *, and the pedigree of Duaid Mac Fimbis, pp. 100-103, *supra*.

† *The O'Flannghailes*.—This family is still in the country, but more numerous in Tireragh. The name is now anglicised Flannelly.

* *Loch Glinne*.—This would be anglicised Lough Glynn, but there is now no lake, or place of the name, in the district which Callraighe Muighe h-Eleog comprised, and as there are so many small lakes in this district bearing names apparently modern, it is now impossible to determine which of them was originally known by

The O'Flannghailes¹, who reported no fault,
 A people of most universal bravery,
 Dwell round Loch Glinne² of hospitable men,
 Youths with whom valour is a hostage.
 I have composed,—it is cause of knowledge,—
 According to the genealogical ramifications,
An account of the tribes of the country beyond the Moy,
 For the poets of the plain of Manann¹.
 Even as the yoke is due to [borne by] the clergy^m
 According to each book I speak.
 I shall advance after my journey *thither*,
 With a small brave company,
 Who are not inexpert at the time of shooting,
 Across the Muaidh^a of speckled salmons.

Throughout

the appellation of Loch Glinne.

¹ *The plain of Manann.*—By this the poet may mean Ireland, or perhaps the province of Connaught, in which Manann, or, more correctly, Manannan, was a famous chieftain and navigator in the time of the Tuatha De Dananna.

^m *Even as the yoke, &c.*—The poet here expresses himself in rather obscure words, but there can be little doubt that what he intends to say is this:—I have now composed, in the order of their genealogical relationship, an account of the inhabitants of the country west of the river Moy, which will be the cause of spreading knowledge among the bards of Ireland; and in this account I have adhered to the authority of the books before me, in giving the descents and localities

of those families, with as scrupulous an adherence to the truth of history as the clergy should observe in attending to the duties imposed on them by the yoke of the Lord, which they have taken upon them.

^a *Across the Muaidh.*—The poet having finished his description of Tirawley, here gives notice of his passing out of it by crossing the river Moy, which formed the boundary between it and the territory of Tir Fhiachrach, the name of which is preserved in that of the present barony of Tireragh, though it is quite clear that the barony is not as extensive as the territory whose name it preserves, for the whole of the district of Coolcarney, extending from the Yellow River to the river Brosnach, which is now a part of the barony of Gal-

Feað na tuathí a táinig me
 rloimrfeað dais,—ir fir firí,—
 co luat do'n geil-feðac glan
 geinealac na tuath tpebar.
 Tuaim da bodar ar bpeit gill,
 ceann na tuathí rí tuirrim,
 Ath Cunga 'n a cend oilí;
 uirra an dpeam d'ár n-dámarib-ní
 Da bí taíreac uair eli
 'ra críe rí ar cloimh Laegairí,
 h-l Eignig ar cend ar cás
 tenn ní eígnig an t-oghlac.
 h-l Gealagán, fir na fled,
 'ra Driainrig ir glan mober,
 Cill íctair ir fearand dóib,
 gel-ponn 'na ríltair penmóir.
 Imleac loirce ir dútaib dóib
 h-l Enda fa tpeom tinóil,
 ó m-bruiduib fa rcenmda rcol,
 'na m-buiduib bpeгда bpiúao.

1

len, was originally a portion of Tir Fiach-
 rach, and belonged to families of the race
 of Fiachra, not to the descendants of Cor-
 mac Gaileng, from whom the barony of
 Gallen derived its name. This shows that
 at the time of the formation of the baro-
 nies the ancient territories were dismem-
 bered, and that though the former retain
 the name of the latter in many instances,
 they do not always preserve their extent
 and boundaries..

° *Tuaim da bhodhar*, called Tuaim dha

odhar in the prose list, now Toomore, the
 name of an old church and parish in the
 barony of Gallen, and county of Mayo.
 The little town of Foxford, on the Moy,
 is in the parish. There are two other
 places of this name in Connaught, one in
 the north-east of the barony of Costello,
 in the county of Mayo, and the other in
 the barony of Corran and county of Sligo.

P *Ath Cunga*, now called Beal Atha
 Cunga in Irish, and anglicised Ballycong.
 It is situated near Ballymore Lough, in

Throughout the region over which I have passed,
 I will name for you,—it is true knowledge,—
 Quickly from the fair bright branches,
 The genealogy of the discreet tribes.
 Tuaim da bodhar^o which won the wagers,
 Is the limit of this country I describe,
 Ath Cunga^p is its other limit;
 The inhabitants are supporters of our bards.
 There was a chief at another time
 In this territory over the race of Laeghaire^q,
 O'h-Eignigh^r, who was head over all,
 No power oppressed the hero.
 The O'Gealagans^s, men of banquets,
 Dwelt in Grainseach^t of bright rivers,
 Cill Ichtair^u is their land,
 Bright soil in which sermons are sown.
 Imleach loisce^v is the inheritance
 Of the O'h-Endas^w of heavy crowds,
 From their forts did burst the shouts;
 They *were* fine septs of brughaidhs.

The

the parish of Attymas, and barony of Gal-
 len.—See Ordnance Map of the County of
 Mayo, sheet 40.

^q *Race of Laeghaire*.—See p. 43, *et se-
 quent*.

^r *O'h-Eignigh*, now unknown. He ap-
 pears to have sunk even before the writer's
 time.

^s *O'Gealagains*, now Gilligans.

^t *Grainseach*.—This name is anglicised
 Grange, or Gransha, in every part of Ire-
 land, but there is no place of the name

now to be found in the district here de-
 scribed.

^u *Cill Ichtair*, i. e. the lower church. It
 is stated in the prose account that this
 was an *alias* name for Grainseach.

^v *Imleach loisce*.—This name would be
 anglicised Emlaghlosky, but it is now un-
 known, unless it be the place called Em-
 laghmoran, which lies to the north-east
 of the townland of Breaghwy, mentioned
 in Note ^z.

^w *O'h-Enda*, now Heany.

I Mongan nar cruaid pe cléir,
 h-l órógan nár tuill tabéim,
 cuilg fa cúbaib do'n cuiri,
 dá bhrúgaib buirib ópreámuigi.
 O bél Áta Cunga cruaid
 na fearaib riar co sean-Muaid,
 'c O'Cuib ip 'c O'Móráin mear,
 ar tuill móir-án na mílead.
 Tar éir h-l Eignis na n-eac,
 téib O'Móráin co maibmeac
 co h-Árd na riab rial a' fear
 do riar éliar ocur coindem.
 D' O'Móráin, do cleaáct caáa,
 a n-inad an árd-pláta,
 Árd na riab do péibis riob,
 rian leir éris ar n-indein.
 Págam ríl Laegairne luib,
 triallam 'rha róbaib rómuib,
 tar Tuaim dá bodar; co binn,
 na rluais 'ca molad maibim.

Callraib

* *O'Mongans*. — This family is still in the district, and have all anglicised the name to Mangan, though Mongan, which is the form of the name adopted in other parts of Ireland, would be more analogical. James Mangan of Ballina, merchant, is of this tribe, but James Mangan of Dublin, the poet, is of the southern O'Mongans. Spenser asserts that the name Mungan, and all those which terminate in *an*, are of English origin; but the Irish annals and authentic genealogical manuscripts

are sufficient to disprove this assertion.

† *Brogans*. — h-l órógán is still the form of the name used in both languages, except that in Irish the genitive case of the name of the progenitor is placed after the O', or its plural form I or U.

* *Breachmhagh*, now anglicised Breaghwy, and sometimes Breaffy. It is the name of a large townland situated in the southern extremity of that part of the parish of Kilmore-Moy, lying east of the river Moy.

The O'Mongans^a, who were not penurious to the clergy,
 The O'Brogans^b, who deserved no reproach,
 Swords were befitting their troops,
 Two *families of* brughaidhs of the plain of Breachmhagh^c.
 From Bel atha Cunga^a the hard,
 The lands westwards to the old *river* Muaidh^b,
 Belong to O'Cuinn^c and O'Moran^d the swift,
 Who deserved the great esteem of the soldiers.
 After O'h-Eignigh of the steeds
 O'Moran goes triumphantly
 To Ard na riagh^e, hospitable the man,
 To tend the learned and the banquets.
 For O'Moran, who was accustomed to battles
 In the place of the *other* arch-chieftain,
 We have allotted Ard na riagh,
 A hero by whom our mind was raised.
 Let us leave the race of puissant Laeghaire,
 Let us traverse the roads before us,
 Over Tuaim da bhodhar; sweetly
 Let us boast of the host by praising them.

Into

^a *Bel atha cunga*, is so called at the present day.—See Note P, *supra*.

^b *Muaidh*, now the Moy. For the present names of the places, and the extent of the tract lying between Ballycong and the river Moy, the reader is referred to the Ordnance Map of the county of Mayo, sheets 39 and 40.

^c *O'Cuinn*, now Quin, but there are several families of the name of different races even in the country of the Hy-Fiachrach, as already more than once observed.

^d *O'Moran*, now Moran, a name still respectable in this district. It is stated in the Annals of the Four Masters, at the year 1208, that Amhlaoibh O'Rothlain, chief of Calruidhe Cuile Cearnadha, was slain by O'Moran. The O'Morans of this race are to be distinguished from the O'Morans of Clann Cathail, near Elphin, in the county of Roscommon.

^e *Ard na riagh*, now Ardnarea. — See p. 34, Note W, *supra*.

Callraibí Chuilí na cneab
 raáab innpi d'á h-áirém,
 Cúil Cearnoga na coll carr
 nembona an bpong d'an duárr.
 Ceatpa caírig ar tír thuár,
 a Callraibí na caem énuar,
 coindem do éaid par cairt-ní,
 cáir ploidem na iar-maicní.
 Ma Cuind ír O'Rothlan réid
 O'h-lannan na n-áim n-áigméil,
 ag dígbáil do'n gléir gall,
 O'Fináin, méní mór crand.
 O dhél Eara na n-eap n-élan,
 fead na tuaité nár' túbad
 Do bhorraig ar teann tuile,

páp

^f *Callraighe of Cuil*, now always called Cuil Cearnadha, and anglicised Coolcarney; it is shown on Balde's Map of the County of Mayo, and also on the Index to the Ordnance Map of the same county, as comprising the parishes of Kilgarvan and Attymas.—See prose list.

^g *Ma Cuinn*, now Mac Quin.

^h *O'Rothlain*.—That O'Rothlain, who was chief of Calruidhe Cuile Cearnadha, in the year 1208, we have already seen in Note ^d, p. 245. The name is now anglicised, very incorrectly, Rowley, and is still respectable in Mayo. Rollan, or Rollin, would represent it in English much better.

ⁱ *O'h-Iarnain*, unknown to the Editor.

The name would be anglicised O'Hearnan, or Hernon.

^j *O'Finain*, now O'Finan. Dr. O'Finan, formerly Roman Catholic Bishop of Kilalala, is of this family, and a native of this very district.

^k *From Beal easa*.—This quatrain is inserted from Duaid Mac Firbis's larger work compiled in 1645. It is probably not correct, for it is stated in the prose account prefixed to this poem, that Cuil Cearnadha extends from Beal atha na n-idheadh to Bealach Breachmhaighe. *Beal easa* is the present Irish name of the little town of Foxford, on the river Moy, in the barony of Gallen, and county of Mayo; it is not now considered to be in the territory of

Into Carllaidhe of Cuil^f na g-cneadh,
 I shall proceed to describe it,
 Cuil Cernogha of the knotty hazles,
 Not unhappy are those in whom it is hereditary.
 Four chieftains are in this upper country,
 In Callraidhe of beautiful fruit-trees,
 A festive party who have entered into our catalogue,
 It is proper to name the noble youths.
 Ma Cuinn^e and O'Rothlainn^a the ready,
 O'h-Iarmain¹ of dreadful arms,
 Who injures the choicest of the foreigners,
 And O'Finain¹, a great sheltering tree.
 [From Bel easa^k of the clear cataracts,
 The extent of the country which was not oppressed,
 To the Brosnach¹ of impetuous current,
 Which

Coolcarney, and it is more than probable that it never was, and that Coolcarney never extended farther to the south than Beal atha na n-idheadh, on the Yellow River, which lies about a mile north of Foxford. This quatrain is, however, also found in a more modern hand in the Book of Lecan, fol. 85, as if quoted from a poem composed in the year 1302, and it has been, therefore, here inserted in the text; but with this caution to the reader, that it seems to be most probably spurious, not only from the inaccuracies already noticed, but also because it is not to be found in the original text of the Book of Lecan, which was compiled by the author of the poem himself.

¹ *The Brosnach of impetuous current.*—This river, which is remarkable for its mountain torrents, rises in the townland of Cloonkeelsaun, in the parish of Castleconor, on the boundary between the barony of Tireragh, in the county of Sligo, and the barony of Gallen in that of Mayo, and after flowing for a short distance in a northern direction, it turns to the south-west, and takes a circuitous course through the parish of Castleconor and that part of Kilmoye-Moy, which lies on the east side of the river Moy, and pays its tribute to the Moy at Bunree, a short distance to the north of the town of Ballina.—See Ordnance Map of Sligo, sheet 29, &c. It may be remarked here, that in the prose account

fáir còbraib ceann Calraighe.
 Fúair O'Caeman, ir cúir gill,
 ó Thuaim dá bodar blait bind,
 ó á n-deóin ir feárr an aicmí,
 co Gleoir, cend na Clann Maicmí
 Mac Cailleacán na cler n-áib,
 fénnib nár gob o Gall-gaib,
 triat Cáinn do córaim a blad,
 a loraím airm ir irgal.
 Fuair O'Coitil na colg noct,
 baib h-l Coitil le cródoct,
 brúgaib mar h-é nocho n-uil,
 cré nír cúbaib 'na comair.
 Ag O'Mócaíne an beoil bind.
 baib h-l Mócaíne, maibim,
 rocaib do caib a crab,
 maib h-l Mócaíne moréar.

Muc

prefixed to this poem the northern limit of Cuil Cearnadha is stated to be Bealach Breachmhaighe; but though there would appear to be a discrepancy here between the two accounts, they are not very different in this particular, as the townland of Breachmhagh, *anglicè* Breaghwy, or Breaffy, extends very close to the river Brosnach.

^m *Which defends the head of Calraighe.*—In an extract from another poem, given in a modern hand in the Book of Lecan, this line reads *Do córaim ceann Callraigí*, i. e. which forms a (northern) boundary and a natural defence to the territory.

ⁿ *O'Caomhain*, now Kavanagh.—See

p. 110, Note ^f.

^o *Tuaim da bhodhar*, now Toomore, near Foxford.—See p. 242, Note ^o, *supra*, and Ordnance Map of the County of Mayo, sheet 61.

^p *Gleoir*, now the river Leafony, in the barony of Tireragh.—See p. 242, Note ^o.

^q *The head of the tribe.*—The language of this quatrain is very much transposed, and it is impossible to translate it into intelligible English without inverting the order of the lines. The natural order is as follows:

“The head of the tribe of O'Caomhain
 (Whose sept are best when acting by their own will),

Which defends the head of Calraighe^m].
 O'Caomhainⁿ,— it is cause of gain,—obtained
The tract from Tuaim da bhodhar^o of flowery hills
 (His tribe are best *when acting* by their own will),
 To Gleoir^p, the head of the tribe^a.
 Mac Cailleachain^r of valorous feats,
 A hero who fled not from foreign javelins
 Is chief of Carn^s, whose fame he defended
 By the valour of his arms and conflict.
 O'Coitil of the naked weapons got
 Baile Ui Choitil^t by his valour,
 A Brughaidh like him there exists not,
 Clay is not fit before him^u.
 To O'Mochaine of the sweet mouth
 Belongs Baile Ui Mhochaine^v, I boast,
 Hosts have consumed his cattle,
 The goodness of O'Mochaine is exalted.

Muc

Obtained the tract from Tuaim da bhodhar of
 flowery hills
 to Gleoir. It is a cause of gain."

^r *Mac Cailleachain*, obsolete, or changed
 to *Callaghan*.

^s *Cam*, now Carns, a townland in the
 south of the parish of Castleconor, in the
 barony of Tireragh, and county of Sligo.
 The river Brosnach, already mentioned in
 Note 1, p. 247, flows between it and the
 townland of Cloonkeelaun, which is on
 the verge of the county.

^t *Baile Ui Choitil*, i. e. the town or
 townland of O'Coitil, now Cottletown, in
 the parish of Castleconor, in which are the
 ruins of a castle, erected by Domhnall

IRISH ARCH. SOC. 12.

Baile Ui Choitil O'Dowd, who became
 chief of his name in the year 1447. — See
 list of the chiefs of the O'Dowd family to-
 wards the end of this volume, and the
 Ordnance Map of the County of Sligo,
 sheet 22. The name O'Coitil is now an-
 glicised Cottle, and is still in the district.

^u *Clay is not fit before him*, i. e. an inert
 man, without warlike fire, is not fit to
 stand before him in battle; a very strange
 metaphor.

^v *Baile Ui Mhochaine*, now Ballymogh-
 any, in the same parish of Castleconor.—
 See Ordnance Map of the County of Sligo,
 sheet 16. The name O'Mochaine is now
 either extinct or changed to Mohan.

Muc dub ir a beapraic bláith
 fuair O'Floinn, ar cuir conaic,
 cupaid nár cláith re tuibi
 brúgaid bláit na beapraigí.

O'h-Imair, nár cupaid re cléir,
 ó Lecan an fuinn fóid réid,
 fear diongmála gac duine,
 an bind malla bárr-buidi.

Mullaic rátha na ród caem
 fuair O'Loingreacán lann cael,
 fonn mar gel-fonn Míoi amach,
 fearann fine d'ib Fhiaicraic.

Fuair O'Spelan na rpor n-óir
 Coillín Aeda, traic timóil,
 pluag noicair féo a páire,
 béo a luad re leic-baile.

Ráith

* *Muc dubh*, i. e. the black pig, now anglicised Muckduff, which is the name of a townland in the north of the parish of Castleconor, adjoining Bartragh. — See Ordnance Map of Sligo, sheet 16. In the south of this townland is shown the grave of the Black Pig, a wonderful magical animal, from which the townland is believed to have taken its name.

* *Beartrach*, called in the Book of Armagh Bertrigia, now Bartragh, a sandy island in the north-west of the parish of Castleconor, on the east side of the river Moy, at its mouth. The word beapraic is understood all round the coasts of Connaught, where the word largely enters

into the topographical names, to designate an oyster bank, and the Editor is acquainted with a learned etymologist who is convinced that the word is compounded of bioir, water, and toppraic, fruitful.

* *O'Floinn*, anglicised O'Flynn. There are various families of the name, of different races, in Ireland. The name is made up of O', nepos, or descendant, and Flonn, the genitive form of Flann, the name of their progenitor.

* *O'h-Imhair*.—This name is anglicised Ivers in some parts of Ireland, and some have changed it to Howard. It is formed of O', nepos, and Imhair, the genitive of Imhar, a man's name, which the Irish

Muc dubh^w and the flowery Beartrach^x
 O'Floinn^y obtained, it is cause of wealth,
 A hero not weak to be opposed,
 The flowery Brughaidh of Beartrach.
 O'h-Imhair^z, who was not penurious to the clergy,
 Is of Leacan^a of the smooth-sodded land,
 A man worthy of every man,
 The melodious yellow-haired chieftain.
 Mullach ratha^b of the fair roads,
 O'Loingseachain^c of the slender swords obtained
 A soil like the fair soil of Meath throughout
 The land of a sept of the Hy-Fiachrach.
 O'Spelan^d of the golden spurs obtained
 Coillin^e Aedha at the time of the meeting,
 His host cannot be watched,
 Pity to mention him *as possessing only* a half townland.
 Rath

borrowed from the Danes, among whom it was written Ivor, Ifars.

^a *Leacan*, now Lackan or Lecan, a townland on the east side of Killala bay, in the parish of Kilglass, in the barony of Tireragh, and county of Sligo.—See Ordnance Map of Sligo, sheet 16. This place afterwards belonged to the Mac Fírbíse, the hereditary antiquaries of the district, as we have already seen p. 168.

^b *Mullach Ratha*, i. e. hill or summit of the rath or earthen fort. It is called lochtar ratha in the prose list. These names are now obsolete, but there can be little doubt that they were *alias* names of the townland of Rathlee, situated in the

parish of Easkey, and to the north of Lackan.—See Ordnance Map of the County of Sligo, sheets 10 and 11.

^c *O'Loingseachain*, now obsolete. In the north of Ireland this name is anglicised Lynch.

^d *O'Spelan*, recte O'Spealain. This name is more common in other parts of Ireland than in this district. It is anglicised Spillaan and Spillaine.

^e *Coillin Aedha*, now the large townland of Culleen, in the parish of Kilglass, and barony of Tireragh. The river anciently called Gleoir runs through the middle of this townland.—See Ordnance Map, sheet

17.

Ráith berçan ar bláith feada,
 fearann a fíth fín-pleada,
 fuair O'Fualairg pleada an fuind,
 leir cruad airc Cera in comluind.

Cill Faindli na m-bárr m-bog
 ag O'breirlen fuair formad,
 drem can dáire, can dolad
 'cár b-ferri aibi olloman.

Cuid h-l Conactan çerna
 don muio fairring oirada,—
 ruatác cáic coll do'n cupi,—
 fonn cruatác Cabraigí.

Da gabrad tend uair eli
 feban do'n péim ríghoibi,
 Clann Néill ar fearann na fear,
 nem-fann ó'n péin a n-áiream.

Tápla d'á céli can col
 Clanna Néill na pleg reòmar
 ocur Clann Chaeman cáma
 na crann cael-bán cataröa.

Marbétar

^f *Rath Berchain*, i.e. arx Berchani. This name is now obsolete, and no clue has been discovered to determine the situation of the place.

^g *O'Fualairg*, now entirely obsolete.

^h *Cill Faindle*, now Killanley, a town-land containing the ruins of an old church, from which it received its name, situated on the east side of the river Moy, in the parish of Castleconor.—See Ordnance Map of Sligo, sheet 22.

ⁱ *O'Breslen*. — The O'Breslens of this race are to be distinguished from those of Tirconnell, who were a far more distinguished family.

^j *O'Connachtan's*, now Connaughtan, but the name is very scarce.

^k *Each hazel is rich from the hero*.—The meaning is, not that he was a good gardener, but that his worthiness caused the fruit trees to be fertile. This affords another example of the value set by the

Rath Berchan^f of flowery woods

Is a land in which wine banquets are found,
O'Fualairg^s obtained the banquets of that soil,
By whom warlike Cera was sore plundered.

Cill Fainnle^a of the soft crops

Is O'Breslens^l who experienced envy,
His people are without oppression or detriment,
With whom the happiness of the Ollamhs was best.

The victorious O'Connachtan's^l portion

Of the wide famous plain,—
Each hazel is rich from the hero^k,—
Is the beautiful land of Cabrach^l.

At one time, by force,

A sept of the regal lineage,
The Clann Neill^m, seized upon the land of these men;
Not feeble from the heroes was their reckoning^a.

They met each other without blemish,

The Clann Neill of expert lances
And the brave Clann Caemhain
Of the slender-white warlike spear-shafts.

Muircheartach

ancient Irish upon the fruit of the hazel tree.

^l *Cabrach*, now Cabragh, a townland lying on the east side of Killala bay, in the parish of Easkey, in the barony of Tireragh.—See Ordnance Map of Sligo, sheets 10 and 11.

^m *The Clann Neill*.—These were a sept of the O'Dowds, who descended from Niall, son of Niall, son of Maoileachlain, son of Maolruanaidg, son of Aodh O'Dubhda, King of North Connaught, who died in the

year 983. They are here called of the regal lineage, because the family of O'Dubhda became the hereditary chiefs or princes of all north Hy-Fiachrach. The attempt of the Clann Neill O'Dubhda to wrest this territory from the O'Keewans was contrary to a solemn compact entered into at an early period between the two families.

^a *Not feeble, &c.*—Duald Mac Firbis gives this line thus;—*Neamh-foinn o'n fén a n-a n-áipeam.*

Μαρβέταρ Μυρτσεαρτάς, mac Neill,
 ocup O'Caemán cneir réio
 pa ceann an tíri rí éep,
 do'n líni rí ar ferrí d'áirmer.
 Τιαγαίω co trén pa telaig
 Clanna Caeman corri-plegaig
 tar nept na h-aicmí elí,
 tre nept áirreí ir átaigthe.
 Ρυαίρ O'Caemán na colg n-ghar,
 Saír Sgrebainí na ríeb íolar,
 ponn bláit taeð-íolur mar éuio,
 ráit na n-ael-dorur n-álainí,
 'na íorir comnaíóí d'á éloinn,
 íorir ar éoll-buíóí éanuim.
 O Gleoír, nár gab ó Gall-gaib,
 co h-larca an íuio aball báin,
 'c O'Mailíóúin óata m-blaí,
 plata 'pa n-uíó ne h-ollam.
 Ρυαίρ O'Ruarác na ruag mer
 Lia con inneoin na n-aigead,

do

° *Muircheartach Mac Neill*.—See an account of this already given in pp. 113, 169.

° *By strength of charter*.—Charter here alludes to the compact made between Dubhda and Caomhan, the progenitors of the families of O'Dowd and O'Keewan, by which Caomhan and his representative was to possess for ever the tract extending from Tuaim da bhodhar to the river Gleoir. For an account of this compact the reader is referred back to pages 109, 139.

° *Saís Sgreabhainn*.—This is the form of the name given in both copies of the poem, though in the prose account of the families and estates of Hy-Fiachrach, prefixed to this poem, it is called Saighin Uisce tar abhainn, otherwise Inis Sgreabhainn, and in the Annals of the Four Masters and other authorities Eiscir abhann! It is now anglicised Inishcrone, and is the name of a small village near which are the ruins of a castle on the east side of Killala

Muircheartach Mac Neill^o is slain
 And O'Caemhain of the smooth skin,
 In a contest for this southern tract,
 By these tribes, the best I have mentioned.
 Then mightily entered on the land
 The Clann Caemhain of sharp spears,
 Beyond the strength of the other sept,
 By strength of charter^p and conflict.
 O'Caomhain of the green swords obtained
 Sais Sgrebhainn^a of the bright streams,
 A flowery land bright-sided as the wave,
 Fort of the splendid lime-doors^r.
 As the mansion seat of his race
 The hazel-yellowest field I sing of.
 From Gleoir, which was not won by foreign javelins,
 To Iasca^r of the land of the white-blossomed apple trees,
 Belongs to the O'Mailduins^r of high renown,
 Scions who respect the ollamh.
 O'Ruarach^u of the rapid onsets got
 Lia Con^v, the support of the strangers,

For

bay, in the parish of Kilglass, and barony of Tireragh.—See Ordnance Map, sheet 16.

^r *Lime-doors*, i. e. white-washed with lime, or perhaps built of lime-stone.

^a *Iasca*, now the river Easkey, which rises in Lough Easkey, on the confines of the baronies of Tireragh and Leyny, and, flowing in a northern direction, discharges itself into the sea a short distance to the north of the village of Easkey, which has derived its name from it.

^r *O'Mailduins*. — This family is now nearly extinct in Tireragh. The name is anglicised Muldoon, but this family is to be distinguished from the O'Muldoons, chiefs of the territory of Lurg, in the north of Fermanagh, who are still numerous.

^u *O'Ruarach*, now obsolete.

^v *Lia con*, written Lia cón, by Duald Mac Fírbis. There is no townland or locality in Tireragh at present bearing this

do cáic fá tend a éorad,
 fáic ar fearr d'a aomolad.
 Tugur, fa calma an cupi
 O'Feindeaba, an fianuidi,
 co Fingid co clár na cath,
 ar nach imgid dám dimbach.
 Ar n-díe h-l Fhéindeaba ann,
 fuair O'Flannghaili in fearann,
 fonn mín 'nac aimpéid re ár,
 mar éir claid-reid na Cruacán.
 Imleac ísill in fearr cupi
 'c O'Mailidúin, mar dearbhuim,
 port mebaic do éir 'rbo tuinn,
 min an tealaic co cógsum.
 Co Muircei dúind 'n a deaio
 ó larca an fuind éigheadais,
 h-l Conbuio ar cend do'n cáic
 tenn a cupi 'gár cumtaic.

O'Luacán

name, unless Leafony be a corruption of it, which, however (as will be seen), is written Liathmhuine in Irish.

^w *O'Feinneadha*, now anglicised Feeny. There are a few poor families of this name still in the parish of Easkey, but none on their own original townland.

^x *Finghid*, now Finned, a townland extending northwards to the sea, in the parish of Easkey, in Tireragh, and lying westwards of the river Finned.

^y *O'Flannghaile*, now anglicised Flannelly, without the prefix O'. This family is very numerous in Aughros and other

places in the parish of Templeboy, in the barony of Tireragh, where they are called Flannellys of the Lough. There are a few of them in the parish of Easkey too, but they are all said to have come thither from the Lough, in the parish of Templeboy.

^z *Not rugged for tillage*. — Written by Duaid Mac Firis, fonn mín nac aimpéid re a ár, which is the better reading. The word ár is still used in this part of Ireland to denote tillage. It seems cognate with the Latin verb *aro*, to plough.

^a *Imleach Isil*. — This was the ancient

For all its produce is abundant,
 Which is the best cause for praising it.
 I have brought,—brave the hero,—
 O'Feinneadha^a, the soldier,
 To Finghid^a, the plain of the battles,
 From which the bards depart not displeased.
 After the extermination of O'Feinneadha there,
 O'Flannghaile^a obtained the land,
 A smooth soil, not rugged for tillage^a,
 Like the smooth-mounded land of Cruachan.
 Imleach Isil^a of the smooth grass
 Belongs to O'Mailduin, as I certify,
 A mede-abounding seat by sea and land,
 So that I love the surface of the land.
 To Muirsce^b let us go after it,
 From the Iasca of the salmon-abounding soil
 The O'Conbhuidhes^c are the head of the tribe,
 Powerful is the host protecting us.

O'Luachain

name of the townland of Castletown, in which are the ruins of a castle, situated on the west of the river Easkey, near its mouth, in the parish of Easkey. The name *Imleach Isil*, i. e. the low imleach, or land verging on the water, is now locally forgotten, but the name is fortunately preserved on the Down Survey of the County of Sligo. This was the mansion seat of O'Muldoon, petty chief of the tract of land lying between the rivers Gleoir and Easkey.

^a *Muirsce*.—This name, which signifies "sea-plain," extended from the river Easkey, eastwards, to the stream which flows into the sea between the townlands of Ballyeeskeen and Dunnacoy. — See Ordnance Map of Sligo, sheet 12. The extent of this district cannot be mistaken, for it comprised, according to this poem, the townlands of Rosslee, Cloonnagleavragh, Alternan, Dunaltan, Ballykilcash, Dunbeakin, Dunneill, and Ballyeeskeen, all lying between the rivers above mentioned, as will be seen by reference to the Ordnance Map of the barony of Tireragh.

^c *O'Conbhuidhes*, now anglicised Conways, Conmys, and Conwys, are still numerous, and are still the head of the tribe, powerful is the host protecting us.

O'Luacán na lann tana
 ar cáic 'na cénd cómpama,
 ó Ror Laeg na caem éirann cuirp,
 raep-clann do faem cáic irguil.
 Cluain na cliabac na call cuirp,
 Alt Fharannain co fepcaib,
 'c O'Rothlán nár cruaid am croob,
 ag moé-dáil buair a bíobob.
 Ar Dún Maeluib na m-brúg m-bláit,
 'n a brúgaid calma conaíc,
 O'Duibrcuili, rciamba a rcor,
 Iapla na n-uili brúgaid.
 Fuair O'beollán, nar ép fear,

Dún

is in the parish of Easkey, in Tire-

'Luachain.—This name is now corrupted to O'Luachair, and translated Rush, which is the name the family wish to be called by. It is so translated from an erroneous belief that it is derived from *luacán*, rushes, for which is not the slightest authority.

'os laegh, now Rosslee, a townland in the parish of Easkey, on the east side of the river Easkey, at its mouth, which seems to be derived from *Emlagheeshal*, or Castle-

It contains the ruins of a castle which is supposed to have been built by the family of O'Luachair. — See Ordnance Map of Sligo, 12.

luain na g-cliabhack, called in the present list *Cluain na g-cliabhrach*, which is the name it bears in Irish at the present

day. It is anglicised Cloonagleavragh, and is applied to a townland in the parish of Easkey, extending along the river Easkey, on the east side. It forms a portion of the demeane of Fortland, the seat of R. Jones, Esq., which extends on both sides of the river Easkey.

Alt Fharannain, i. e. St. Farannan's alt, cliff, or height, now anglicised Altarnan, the name of a townland containing a holy well, called *Dabhach Fharannain*, i. e. St. Farannan's vat or keeve (hence "the miraculous" in the text), in the east of the parish of Easkey, and adjoining the parish of Templeboy. Duaid Mac Fírbis states, in the prose list already given, that O'Rothlain had possessed *Cluain na g-cliabhack* and *Alt Farannain*, until the family of O'Maonaigh, or O'Meeny, deprived them of these lands by an act of treachery,

O'Luachain^c of the thin *sword*-blade.
 Over all is the active head
 At Ros laegh^d of the fair smooth shafts,
 A noble clan who sustained each conflict.
 Cluain na g-cliabhach^e of the smooth hazles,
 Alt Fharannain^f, the miraculous,
Belong to O'Rothlain^g, not penurious of cattle,
 Who freely distributes the cattle of his enemies.
 Over Dun Mailduibh^h of the flowery seats,
 As a brave and affluent Brughaidh,
 Is O'Duibhscuileⁱ, beautiful his stud,
 The Earl of all the Brughaidhs^l!
 O'Beollain^j, who refused no man, obtained

Dun

which he was unwilling to record, and it is remarkable that there are four townlands called Baile Ui Mhaonaigh, anglice Ballymeeny, i. e. O'Meeny's town, in the immediate vicinity of Alternan.

^c *O'Rothlain*, now always anglicised Rowley, though Rollan, or even Rollin, would be a much more analogical form in English. There are persons of the name living in the parish of Kilmacshalgan and Dromard, in the barony of Tireragh.

^h *Dun Mailduibh*, i. e. dun or fort of Maeldubh, who was the son of Fiachra Ealgach, the son of King Dathi, and the ancestor of the O'Dowds. This name is now obsolete, but it is supposed to have been the ancient name of the townland of Rath maol,—(said to have been anciently called Rathmailduibh, which is synonymous with Dun Mailduibh)—situated in the parish of

Easkey, south-west of the village of Easkey, and west of the demesne of Fortland, which this townland originally comprised, and which derived its name from it.

ⁱ *O'Duibhscuile*.—This name, which might be anglicised Duscooley, or Duscully, is now either entirely obsolete or shortened to Scully.

^l *The Earl of all the Brughaidhs*, i. e. the most distinguished of all the farmers. *Earl* was the highest title in use among the English in Ireland when this poem was composed.

^j *O'Beollain*.—This name is still very numerous in Tireragh, and always anglicised Boland, which is not very incorrect, though the *d* must be considered foreign to the name. This family is to be distinguished from the O'Beollains of Thomond, who are of a different race.

Dún Ullcán ír árd inbeap,
 an brúgaid 'cá labra lino,
 cupaid calma d'á cneidind.
 Fuair a ainm ó'n baili bláit
 brúgaid fa calma caem-ráit,
 Mac Gillacair na call cuir,
 can band ar air ó'n irgail.
 O Dún m-becin na m-brúg m-bán
 Meş Eogain, ír Clann Chuanán,
 dá brúgaid 'ra ráit rébairg
 ra tulaig bláith buain-plebairg.
 Fuair O'Doircin, nár diult dám,
 an baili uad co h-implán,
 fonn 'cá ainmneagad ó'n fear,
 d'ár cáim leabair-coll cneir geal.
 Fuair O'Conbuird ar lúo lino,
 na tulaig fairring aibind,

Dún

¹ *Dun Ultain*, i. e. Ultan's dun, or fort, now anglicised Doonaltan. It is the name of a townland containing the remains of a fort, situated on the coast in the north of the parish of Templeboy, in Tireragh.—See Ordnance Map of the County of Sligo, sheets 11 and 12.

^m *Deep river mouth*.—The allusion here is to the mouth of the Ballymeeney river, which discharges itself into the sea between the townlands of Alternan, which is on the west, and Doonaltan, which is on the east side.

ⁿ *Mac Gillachais*.—This name is now obsolete as applied to a family, but it is retained in that of the townland which they

anciently possessed, namely, Baile Mhic Giollachais, now anglicised correctly enough, Ballykilcash. It is situated in the north of the parish of Kilmacahalgan, in the barony of Tireragh.—See Ordnance Map of Sligo, sheet 12. The fair and strong rath referred to in the text still remains, but it is not remarkable for its extent, it having been the enclosure round the house of a brughaidh, or farmer, not the residence of a chieftain.

^o *Dun m-becin*, i. e. Becin's dun or fort. It is called Dunmekin in the old map already referred to, preserved in State Paper Office, London; and is now always written Dunbeakin. It is the name of a

Dun Ultain¹ of the deep river mouth^m,
 The Brughaidh who is mentioned by us
 Is a brave hero, whom I trust.
 His name from the fair townland he has received
 A Brughaidh of fair and strong rath (fort),
 Mac Gillachais^a of the smooth hazels,
 Who never slunk back from the conflict.
 Of Dun in-becin^o of the white edifices
 Are the Mag Eoghains^p and the Clann Cuanan,
 Two Brughaidhs in the happy rath^a
 On the flowery, constantly festive hill.
 O'Discin^r, who refused not the learned, got
 The townland from him *called*, entirely
 The land is named from the man
 For whom the fair-skinned hazel grows fair and large.
 O'Conbhuidhe^s, who is dear to us, obtained
 A wide and beauteous land,

Dun

townland situated in the parish of Kilmacshalgan, in Tireragh. The ruins of the fort of Dun Becin still remain, situated on the west bank of a river of the same name which flows through the townland.—See Ordnance Map of Sligo, sheet 18.

^p *Mac Eoghains*, anglicè Mackeon, but should be properly Mac Owen. There are a few of the name still in the district. This name is to be distinguished from Mac Eoin, of the Glynn, in the county of Antrim, which is a clan name of the Byssets of Scotland, who took that name from Eoin, or John Bysset, their ancestor.

^a *Happy rath*.—This place, Rath Cuain, is still well known, and is a townland in the parish of Kilmacshalgan, in the barony of Tireragh.—See Ordnance Map of the County of Sligo, sheets 17 and 18.

^r *O'Discin*.—This name is now obsolete as applied to a family, but is retained in the name of the townland which was called after the family, viz., Baile Ui Dhiscin, now anglicised Ballyeeskeen. It is a townland in the north of the parish of Templeboy, in Tireragh.—See Ordnance Map of Sligo, sheet 12.

^s *O'Conbhuidhe*, now Conway.—See p. 170, Note 1.

Dún Néill, is niam-ḡlan an ponm,
 ar léir 'nar riaglad nomam.
 Tríallam ó Muirsci meadais
 co bhorraig m-bláith m-bileadais,
 can uicraða ar iath an fíor,
 O'Murcáda a triaé cairis.
 O'Suibleirga, O'Cuan cáin,
 O Duncáda fuair ár-d-aib,
 Dún h-l Chobtaic ponm na fer,
 as ar íocraib ponm raer rleg.
 Fuair O'Colmán, calma an chuio,
 in ḡráinreé mór, Popc pádrais,
 an ḡráinreé bec, buada an ball,
 ceo 'ḡ O'Fuala 'ran fearann.

Fuair

[†] *Dun Neill*, i. e. the fort of Niall, who, according to the prose list already given, was the son of Cubuidhe, the progenitor of the family of O'Conbhuidhe. It is now correctly anglicised Dunneill, and is the name of a townland in the parish of Kilmacshalgan, in Tireragh, containing the remains of a *dun*, or earthen fort, situated on the east side of a river of the same name which flows through the townland. —See Ordnance Map of the County of Sligo, sheets 12 and 18.

^u *Muirsci*.—The most eastern townland in this district is Ballyeeskeen, and it was divided from the adjoining territory of Borrach by Ath cliath Muirsci, a ford on the stream which falls into the sea between the townlands of Carrowmacrory

and Doonycoy, in the parish of Templeboy, and barony of Tireragh.

^v *Borrach*.—The situation of this district of Borrach, which derived its name from a river, cannot be mistaken, as the following townlands were in it, viz., Doonycoy, Grangemore, Grangebeg, Ardokelly, Corcagh, and Dunflin, which retain their ancient names to this day, and the situations of which will go very far towards fixing, not only the position, but the extent of the territory of Borrach here mentioned.

^w *O'Murchadha*, now anglicised Murphy.

^x *O'Luidhlearga*, now entirely obsolete.

^y *O'Cuan*, now anglicised Coyne and Cooney, but the name is very scarce in

Dun Neill¹, soil of bright aspect,
 It is plain in our rule before us.
 Let us pass from the mede-abounding Muirsci²
 To Borrach³ the flowery, arborous,
 There is no misfortune over the land of the man,
 O'Murchadha⁴ is its lordly chieftain.
 O'Suidhlearga⁵, O'Cuain⁶ the comely,
 O'Dunchadha⁷, who enjoyed delight,
 Dun Ui Chobhthaigh⁸ is the land of the men
 With whom a stand of noble spears is placed.
 O'Colman⁹ has a brave share obtained,
 Grainseach mor¹⁰, the seat of Patrick,
 Of Grainseach beag¹¹, victorious the spot,
 O'Fuala¹² has liberty in the land.

O'Ceallaigh

the district.

¹ *O'Donnchadha* would be anglicised Donoghoe, or Donaghy, but the name is not to be found in the district.

² *Dun Ui Chobhthaigh*, i. e. O'Coffey's fort, now anglicised Doonycoy, a townland verging on the coast in the north of the parish of Templeboy, in the barony of Tireragh. It adjoins the territory of Muirsci, and still contains the remains of the ancient *dun*, or fort, originally called Dun Ui Chobhthaigh, which is shown on the Ordnance Map of Sligo, sheet 12, as in the north of the townland, and thirty-eight feet above the level of the sea.

³ *O'Colman*, now Coleman. There are some persons of the name in the parish of Templeboy, in Tireragh, but none in

Grainseach mor at present.

⁴ *Grainseach mor*, i. e. the large Grange, or farm, now Grangemore, a well known townland in the parish of Templeboy, in the barony of Tireragh. — See Ordnance Map of Sligo, sheet 18. The old map in the State Paper Office, already referred to, shows a castle, or large dwelling-house, and a small village at "Grangemoor," nearly due east of Dunmekin.

⁵ *Grainseach beag*, i. e. the Little Grange, now Grangebegg, in the same parish. This is also shown as a castle, or residence, on the old map above referred to, but not exactly in its proper place.

⁶ *O'Fuala*. — This name is not in the district. It is not the name anglicised Foley in other parts of Ireland.

Puaip O'Ceallaig na rleg réim
 Ard O'Ceallaig ne caitérim,
 tug ád na pine d'á fuil;
 clár map Míoi fá maerpaib.
 O'Loingsigh na lann leabuir
 ó'n Corcaig can cuideadai,
 na rlóig a coimbi an cuiri,
 oighi cóir na Corcaighi.
 Dún Loind nap, lamao do lem
 puair O'Murchada maig reid,
 brúg plait-geal ip raer rnaoi,
 áitreb na craeb cúbraoi.
 O'borraig nap ag-loic aip
 triallam co Tríáig can taitáir

da

^f *Ard O'g-Ceallaigh*, i. e. *altitudo nepotum Cellachi*, now anglicised Ardogelly, or Ardokelly, which is the name of a townland in the north of the parish of Templeboy. There are persons of the name O'Ceallaigh, anglicè O'Kelly, still in this neighbourhood. They are to be distinguished from the O'Kellys of Hy-Many, who are of a different race.

^g *O'Loingsigh*. — This name, which is made Lynch and Lynch in most parts of Ireland, is not now to be found in this neighbourhood; but it is highly probable that the name has been corrupted to Ma Gloinsag, which still remains.

^h *Corcach*. — This townland has since been divided into two parts, of which the larger is called Corcachmor, and the smaller Corcachbeg, and is situated near

the sea, in the north of the parish of Templeboy. — See Ordnance Map of the County of Sligo, sheets 12 and 13.

ⁱ *Dun Floinn*, i. e. the dun or fort of Flann, now Dunflin, a townland in the parish of Skreen, in the barony of Tire-
ragh.—See Ordnance Map, sheet 18. It is now divided into two parts, in the more northern of which the dun or fort is situated on the west side of a little river flowing through this townland. This is the place where Duald Mac Firis was murdered in the year 1670, four years after the death of his friend and patron Sir James Ware.

^j *O'Murchadha*, now anglicised Murphy; but this family is to be distinguished from the O'Murphys, chiefs of Hy-Felimy, in the county of Carlow.

O'Ceallaigh of smooth lances obtained
 Ard O'g-Ceallaigh^f with triumph,
 He transmitted the valour of the tribe to his posterity,
 A plain like Meath is under his stewards.
 O'Loingsigh^s of large blades
 Is at Corcach^a without a rival,
 Hosts protect the hero,
 The lawful heir of Corcach.
 Dun Floinn^l, which none durst invade,
 O'Murchadha^l of the smooth plain obtained,
 A white-wattled edifice^k of noble polish,
 Habitation of the sweet-scented branches.
 From Borrach^l, which was not wounded by a satire^m,
 Let us proceed to the strandⁿ without reproach,

To

^k *White-wattled edifice.*—This shows that O'Murchadha lived in a wooden house.

^l *Borrach.*—This was unquestionably the name of a river from which the district lying to the west of it received its name; there can be little doubt that it was originally the name of the stream which rises in the townland of Farranyharpy, in the south-west of the parish of Skreen, and flowing nearly in a due northern direction, falls into the sea at the south-east boundary of the townland of Aughris, in the north of the parish of Templeboy. The only objection that can be urged against this conclusion is, that a portion of the lands of Corcach, which were in the district of Borrach, extends eastwards of this stream, but this is not enough to prove it false, as the greater portion of

Corcaghmore is west of this river, as well as all the other lands mentioned as forming the district of Borrach. The remaining part of the territory of Tire-
 ragh, lying between this stream and the strand of Traigh Eothaile, was called the district of the strand. The extent of this district cannot be mistaken, as the names of almost all the lands mentioned as situated in it are still retained, as will appear from the notes next to be given.

^m *Which was not wounded by a satire.*—It was believed by the ancient Irish that a satire would afflict men with disease, destroy the fertility of rivers, and wither the grass and green corn-fields.

ⁿ *The strand*, i. e. the strand of Traigh Eothaile, near Tonrego, already often alluded to.

da fuirgura ag uaim an fuinb
 fuair O'Muirgura molaim.
 O'Sinua na pleg rona
 fuair Látraic map lán roga,
 raíre ná ren-ponn Sodain,
 fearann naíoi nua-éoraid.
 Triallam, cor ab rén ropaid,
 cur an áitreb n-eplamaid
 dhem d'ár diall cadur ir cáin,
 triall co h-áruir Abdomnám.
 Crobuing ar cóir do cuma
 'ra Scrín atá a trén pulla,

ní

^o *O'Muirgheasa*.—This name is now anglicised Morrissy, and is found in most parts of Ireland, the surest proof that there were many distinct septs of the name.

^p *O'Sinna*, now anglicised Fox. The name is still in the district, but this family is not to be confounded with the Foxes of Teffia, who were a far more famous family.

^q *Lathrach*, now Laragh, a well known townland near the sea, in the parish of Skreen, in Tireragh.—See Ordnance Map of Sligo, sheets 12 and 13. The old map in the State Paper Office, already often referred to, calls this place Larras, and shows it as a castle situated near the coast, midway between "Ardnaglassa" and "Ca: Aghares," which is its true position, or, at least, correct enough for a rude sketch map such as the one alluded to, and almost

every other map of Ireland constructed previously to the Down Survey of Ireland, unquestionably were. It is said that the castle of Larragh stood on the division of land now called Carrowcaslan, which was originally but a subdivision of Laragh, though now considered a distinct townland.

^r *Sodhan*. — This, as the Editor has already shown in the Tract on the territory of Hy-Many (p. 159), was the ancient name of O'Mainnin's country, in the barony of Tiaquin, and county of Galway. The ancient Irish poets were well acquainted with the fertile and beautiful districts of Ireland, and we find them constantly comparing such places as they wished to celebrate for their beauty or fertility with the plain of Croghan, in Connaught; the plain of Meath; the rich lands of Moinmoy, round Loughrea, in the county of

To await them at the cave of the land,
 O'Muirgheasa°, whom I praise, obtained it.
 O'Sinna° of the successful spears
 Obtained Lathrach° as his full choice,
 It is nobler than the old land of Sodhan',
 A fresh land of fruitful produce.
 Let us pass, may it be a felicitous tour,
 To the habitation of the Patron,
 To a people to whom honour and tribute have submitted,
 Let us pass to the habitation of St. Adamnan'.
 A tribe which ought to be recorded
 In Scrin' is their mighty roll [charter],

I

Galway; the plain of the Liffey; the plain of Magh Ailbhe, &c.

* *The habitation of St. Adamnan*, i. e. the church of Screen, which was originally erected by St. Adamnan, or, as they call him there at present, St. Awnan. At Raphoe, of which he is also the patron, he is called St. Eunan, and at Erigal, in the county of Londonderry, he is styled St. Onan. He is the celebrated Adamnan, abbot of Iona, who wrote the Life of St. Columbkille, and is styled by his contemporary Bede, "vir bonus et sapiens, et scientiâ Scripturarum nobilissime instructus."

† *Scrín*, called by Colgan *Scrín Adamnain*, i. e. *Scrínium Sancti Adamnani*, now Skreen, an old church giving name to a townland and parish in the barony of Tír-reragh. This place was originally called Cnoc na Maoili, and was granted by Tip-

raide, chief of Hy-Fiachrach, to St. Columbkille. It derived its present name from a shrine of St. Adamnan, erected here some time afterwards. For the situation of the old church of Skreen the reader is referred to Colgan's *Acta Sanctorum*, p. 340, Note 42, where he has the following notice of the church:—"Est Ecclesia multorum reliquiis nobilis et veneranda Diœcesis Kil-aladen, in regione de Tir Fhiachrach, de qua vide plura in notis ad vitam S. Adamnani, ubi dabitur catalogum reliquiarum in illo scrinio reconditarum." But unfortunately he never published the life of this great saint. See also Ordnance Map of Sligo, sheet 19. Near it is a holy well dedicated to St. Adamnan, and not far to the south is the celebrated hill of Mullach Ruadha, more anciently called Cnoc na Maoile, which was the name of this place in St. Colum-

ní fuicéab damna do'n dhoing,
 cuigear calma do'n cprobuing,
 Meḡ Ródan, h-l Oilmic ann,
 Mec Concaṭrac na comann
 O'Snédarna d'ár gíall gail,
 trén damna aḡ díall re dútaig,
 ra moltair a n-ghom 'ra n-gail
 díb h-l Rabartaib rachmair.
 Cluain h-l Chorghraib na call cuir,
 fearann nár gab ó ḡallaib,
 O'baethgaili fuair a' ponn
 leir truaill aenaiḡi ecṭrann.
 Mec ḡillipíno na n-arm n-ḡér,
 feḋan do biaṭad bṡainén,
 ó'n Lemaig, a laib leḋra
 feḋain t-ṡaírí ro-dealba.

Mec

kille's time.—See Colgan, *Vit. s.*, Faranni, c. 8, *aa. ss.* p. 337.) For the various names of this hill, and the historical recollections connected with it see pp. 96, 97, *supra*. For some notices of Scrin Adamnain see *Annals of the Four Masters* at the years 830, 1022, 1030, 1395. At the last year the death of O'Flannelly, vicar of Scrin Adamnain, is recorded.

^u *Mag Rodan*, now obsolete.

^v *O'h-Oilmhic*, pronounced O'Helwick, or O'Helvick. This name is not found in the district. The townland of Altanelvick, in the parish of Drumard, to the south-east of Skreen, was called after this family. —See Ordnance Map of Sligo, sheet 19.

^w *Mac Concathrach*.—There are persons of this name living in the parish of Templeboy, in Tireragh, but they are beginning to anglicise the name to Mac Carrick. The name is formed by prefixing *mac*, filius, fitz, to Concathrach, the genitive of the name of the progenitor Cucathrach, i. e. the hero of the cathair, or fort.

^x *O'Snedarna*, now entirely obsolete.

^y *O'Rabhartaighs*.—There are a few persons of this name (which is now spelt O'Rafferty) still in the parish of Skreen. Duaid Mac Fírbis states, in the prose list already given, p. 173, that there were a few of the O'Rabhartaighs in his own time, but entirely stripped of their posses-

I shall not omit a representative of the people;
 Five brave men of the cluster are *these that follow*.
 Mag Rodan^a, O'h-Oilmic^r, *are* there,
 Mac Concathrach^m of friends,
 O'Snedarna^r, to whom valour gave a hostage,
 A mighty representative clinging to an inheritance;
 Their deed and their valour are praised,
 Of them are the prosperous O'Rabhartaighs^r.
 Cluain Ui Chosgraidh^r of the smooth hazels,
 A land not won by the strangers,
 O'Baethghaile^a obtained that land
 By whom the meetings of foreigners were stained.
 The Mac Gilli Finns^b of sharp weapons,
 A sept who used to supply food to the ravens^c,
 Are in Leamhach^d, *and* in poetical books^e,
 A noble comely-faced people.

The

sions by the Scotch settlers. There was another family of this name in Tirconnell, who built a castle on Tory Island, off the north coast of the county of Donegal, and another in Meath, where the name is still numerous.

^a *Cluain Ui Chosgraidh*.—This name is now forgotten, and nothing remains to point out its situation in the parish. It was evidently the name of a Ballybetagh, or large ancient Irish townland, and comprised several of the modern denominations.

^b *O'Baethghaile*, would be anglicised Beahilly, but the name is not to be found in the district at present.

^c *Mac Gillifinns*.—Now obsolete.

^c *To supply food to the ravens*, i. e. by giving them human carcasses to feed upon. This is intended as a high compliment to their warlike character.

^d *Leamhach*, now Lavagh, a townland in the parish of Dromard, lying to the south-west of Longford demesne, in Tire-ragh.—See Ordnance Map of Sligo, sheet 19. In some parts of Ireland this name is understood to mean land of elms, in others, land abounding in the herb marsh mallows.

^e *And in poetical books*; i. e. they, themselves, are to be found in the townland of Leamhach, and their deeds are to be found celebrated in poetical books.

Mec Gilli Bricín can béim,
 pedan fa cróda caitérim,
 ó Ard na glar, delbda an drem,
 pedna da clár co coitcheand.

Mec Gillimír nár diúlt dám
 fuair Fínnabhair na fínn-clár,
 brúgaib ar cédaib do cuir,
 do mebaig tulaig Tuathail.

Mec Gilli riabair co rath,
 O' Cricán na rad puntaic,
 mor a mebaig 'ra menma
 fa tulaig a tigeanna.

Mume na Fedi na fled
 'c O'Liáán ar árd aigneo,
 fear fa calma re cneadoib
 a tēg adba d'fíleadaib.

Cúil Cillí Bricín can bhoib,
 fearann nac fácaib namoib,

Mec

^f *Mac Gilli Bricins*, obsolete.

^g *Ard na n-glass*, i. e. *altitudo catenarum*.

This place is shown on the old map already referred to, preserved in the State Paper Office, London, as a large castle situated near the coast, and nearly midway between the castle of Larras and the castle of Bonin. The name is still well known in Tireragh, and is that of a large castle, situated in the townland of Ardnaglass, otherwise Ardabrone, in the parish of Skreen, and barony of Tireragh.—See Ordnance Map of the County of Sligo, sheet 13, on which

the ruins of this great castle are shown, in the north-west of the townland of Ardabrone.

^h *Mac Gillimír*.—This name is still in the district, but anglicised Gilmer, or Gillmor, which is not an incorrect form of it in English.

ⁱ *Fínnabhair*.—This place is still well known in Tireragh, where it is now always anglicised Finnure. It is the name of a townland extending to the sea coast, in the north of the parish of Skreen.

^j *The hill of Tuathail*, i. e. Tara, the seat

The Mac Gilli Bricins^f without reproach,
 A tribe of brave career
 At Ard na n-glass^g, comely the race,
 Tribes have heard it universally.
 Mac Gillimir^h, who refused not the learned,
 Obtained Finnabhairⁱ of the fair plains,
 A Brughaidh who opposed hundreds,
 Who exalted the hill of Tuathal^j.
 Mac Gilli riabhaigh^k with prosperity,
 Is of Crichan^l of the swift hounds,
 Great his mirth and his mind
 On the lands of his lord.
 Muine na fede^m of banquets
Belongs to O'Liathainⁿ of high mind,
 A man who is brave in wounding conflicts,
 Whose house is a residence for poets.
 Of Cuil Cille Bricin^o without bondage,
 A land which enemies have not seen,

Mac

of the monarch Tuathal. By this expression the poet means simply "who is an honour to the royal ragged race of Tara."

^k *Mac Gilli riabhaigh*, now Kilrea; and in some parts of Ireland it is anglicised Mac Ilrea.

^l *Of Crichan*, now Creaghaun, a townland in the parish of Skreen, in Tireragh.

^m *Muine na fede*, called Bun fede in the prose list already given, and Bun na fede at the present day by the native Irish. It is anglicised Bunnafeddia, and is the name

of a townland in the parish of Dromard, in the east of the barony of Tireragh.—See Ordnance Map of Sligo, sheet 19.

ⁿ *O'Liathain*.—This name, which is anglicised Lyons in the county of Cork, is obsolete in this district.

^o *Cuil Cille Bricin*.—This name is now shortened to Ceathramh Bricin, and anglicised Carrowbrickeen, which is the name of a townland in the parish of Dromard, in the north-east of the barony of Tireragh.—See Ordnance Map of Sligo, sheet 13.

Mec Conluain 'ga labra linn
 calma do chuaib o coindtind.
 Lir na remur na pod te,
 fearann ar áillí uirí,
 Mec Gíllibáin fuair a' ponn,
 do cáid co cruaid h-i comland
 O'Duinchind ir cept cuma,
 brúgaid do biaí ectranna,
 Doiri na n-Áth, ponn na fer,
 pa na gnáth cáic coll cno-gel.
 Tón ne Gó, fá'n toirteí tonn,
 fearann áirned ir úball,
 'c O'Áeda nár eirig cléir,
 craeba nac ceilteir caithréim.
 Átáit fá'n tuaithe do mol mé
 dá taírech ir tenn tperi,
 mór do cáemain a clea,
 O'Maenais 'r O'Muirgea.

Lir

^p *Mac Conluain*. — This name still remains in the district, but is rather incorrectly anglicised Mac Colwan.

^q *Lis na remhur*, i. e. arx crassorum. — This place is still well known by this very name, which is correctly anglicised Lisnawer. It is a townland containing the remains of several *lises* or forts, in the parish of Dromard in Tireragh. It is shown on the Ordnance Map of the County of Sligo, sheet 19, as lying immediately to the west of Tonrego.

^r *Mac Gilli bhain*. — This name is still in this neighbourhood, but always made

White in English, that being considered a translation of *Gilla ban*, which means a white youth. In Scotland the same name is anglicised Mac Ilwane, incorrectly for Mac Gilwane.

^s *O'Duinchinn*, now unknown in Tireragh.

^t *Doire na n-ath*, i. e. the oak wood of the fords, *roboretum vadorum*. This name is now entirely lost; it must have been applied to a Ballybetagh, or large Irish townland, near Tonrego. It is useless to speculate on its exact situation, as no trace of the name has been preserved by

Mac Conluain^p is mentioned by us
 Who bravely went beyond emulation.
 Lis na remur^a of hot roads,
 A land of beautiful water,
 Mac Gilli bhain^r obtained the land,
 Who vigorously entered the conflict.
 O'Duinchinn^s of just condition,
 A brughaidh who feeds the strangers,
 Doire na n-ath^t is the land of his men
 On which every fair-nuttet hazel is constantly found.
 Ton re go^u, where the wave is fruitful,
 Land of sloes and apples,
Belongs to O'h-Aodha^v, who refused not the literati,
 Branches whose triumph is not concealed.
 There are upon the land which I have praised
 Two chiefs of powerful sway,
 Whose feats have protected many,
 O'Maenaigh^w and O'Muirgheasa^x.

Lis

tradition, on the Down Survey, or on any
 other old map accessible to the Editor.

Ton re go.—This strange name, which
 was originally that of a hill facing the sea,
 may be correctly translated *podex ad mare*.

It is still preserved, and correctly angli-
 cised as *Tonrege*. It is now the name of a

townland containing the house and de-
 mesne of Colonel Irwin, in the east of the
 parish of Dromard, in the barony of Tire-
 ragh, and adjoining the celebrated strand
 of Traigh Eothaile. There are many town-
 lands in Ireland called *Ton re gaoith*, i. e.
podex ad ventum, anglicised Tandragee,

IRISH ARCH. SOC. 12.

Tonreege, and Tonlegeeth; but there is
 no other *Ton re go* in Ireland except that
 here mentioned, although there are many
 places whose situation would entitle them
 to such a name.

^v *O'h-Aodha*, now made Hayes, Hughes,
 &c., as already often remarked.

^w *O'Maonaigh*, now anglicised Meeny
 in this neighbourhood, though in other
 parts of Ireland it is rendered Mainy and
 even Mooney.

^x *O'Muirgheasa*. — This name is angli-
 cised Morissy in most parts of Ireland, but
 the Editor is informed that it is rendered

Lir Ladghaill fá'n corcra craeb,
 fuair O'Muirgeera, an macraem,
 baili puirte na tuataí thoir
 pána luataí guirte gemoir.
 Fuair O'Dúncada na n-dám
 co glair builid na m-bradán,
 caic leabair da labra lino
 mar dlegair tarba a tuirimim.
 Triallam a Cairpí na caic
 fágam an fonn ra O Fíacrach,
 labram co luath ar cach leath,
 tabram caic tuath d'á taíreach.
 Labram co péir d'á ríghair,
 d'lb Maelclúithi an éaem gúimprair,
 na h-airgí ó lb Néill anoir
 lé féin Chairpí na comair.
 Fuair O'Scanail an beoil bino
 lé tpeir an tíre túirbim,

ponn

Morrison in this part of Ireland. Such is the whim of custom !

¹ *Lis Ladghuill*. — This name, which would be anglicised Lislyle, is now forgotten, and the Editor, after the most patient research and correspondence, has not been able to fix its locality, which he regrets exceedingly.

² *O'Dunchadha*, made Donaghy, Dunphy, Donohoe, &c., in other parts of Ireland, but the name is obsolete in Tire-
ragh.

³ *Beauteous stream of salmons*. — The stream here alluded to is the Ballysadare

river, the mouth of which is the boundary between the country of the Hy-Fiachrach and the territory of Carbury, which originally belonged to the descendants of Cairbre, the son of the monarch Niall of the Nine Hostages ; but as O'Dowd had extended his dominion, by conquest, over that tract of Carbury extending from the great strand of Traigh Eothaile to the river Codhnach, at Drumcliff, the poet feels it his duty to describe the people of this district also, though he acknowledges that they are not of the race of Fiachra.

⁴ *O'Mailclúithi*, written by Duaid Mac

Lis Ladhghaill', where the branch is purple,
 The youth O'Muirghesa obtained
 The head seat of the eastern district,
 Where the corn-fields are quick of growth.
 O'Dunchadha^a of the learned men obtained,
 As far as the beauteous stream of salmons^a,
 Every book that speaks to us,
 As it behoveth advantage I mention,
 Let us pass into Cairbre of the battles,
 Let us leave this soil of the Hy-Fiachrach,
 Let us speak quickly of every side,
 Let us give each district to its chieftain.
 Let us speak quietly of their kings,
 Of the O'Mailcluithis^b of the becoming deeds,
 Of the plunders from the Hy-Niall in the east,
 To the heroes of Cairbre *belong* these acquisitions.
 O'Scannail^c of the sweet mouth obtained,
 By sway of the land we mention,

A

Firbis Uí Mhaolclúice. This name is still common in Carbury, but now metamorphosed into Stone by a strange process of transformation. Maelcluithi signifies the youth of the game, *juvenis ludi seu certaminis*, and might have been correctly enough englished Gamble; but the poor people of Carbury, who are, in those degenerate days, very bad gamblers and worse etymologists, are of opinion that *cluithi*, the latter part of this name, is an oblique form of *clóc*, a stone, not of *cluicé*, a game, and so, without any further investigation of the subject, they have translated the name

of the family by the English word Stone, and this has been adopted by the whole sept as their name in English. An island close to the land in the bay of Sligo, which is named after this family, is called, on the old map of these coasts, already often referred to, Enish O'Molcloigh, and on the Ordnance Map, sheet 14, Inishmulclohy, which is intended to represent the Irish *Inis Uí Mhaolclúice*.

^c *O'Scannail*, now anglicised Scanlan. The name exists in the parish of Calry, near the town of Sligo.

ponn mñ ar fairsingí ár
 do éir glair beiribí Gulban.
 Callraibí Laithim na lann
 O'Nuadhan fuair a fearann,
 ponn bpaenac gaimíobí glan,
 aenac aingibí, íoban,
 Fuair O'Ciardha corab trom
 do críc Chairpí, ní élam,
 d' O'Ciardha na m-bárr m-buibí
 níri éiamda crann cúbraibí.
 Da cúib roiribí ó Fiacrac féin
 críc Chairpí na clár coimríd,

d'lb

^d *Beinn Gulban*, now Binbulbin, a conspicuous mountain in the parish of Drumcliff, to the north of the town of Sligo. The plain between it and the sea, called Machaire Eahba, is remarkable for its fertility. On the old map of these coasts, preserved in the State Paper Office, London, this mountain is called "the high hills of Benbolbin, where yearlie timbereth a falcon esteemed the hardiest in Ireland."

^e *Calraidhe Laithim*. — This territory was nearly co-extensive with the present parish of Calry, near the town of Sligo, in the barony of Carbury.

^f *O'Nuadhain*. — This name is not to be found in this parish at present. It would be anglicised Nuane, or Noone.

^g *O'Ciardha*. — It is very much to be suspected that Giolla Iosa Mor Mac Firbis is in error here, for it would appear from the whole stream of authentic Irish history, that O'Ciardha's Carbury was not in Con-

naught. The authentic Irish Annals show clearly that it was in Leinster, and John Mor O'Dugan of Hy-Many, who wrote his celebrated topographical poem about half a century earlier than Giolla Iosa Mor Mac Firbis, gives us to understand that O'Ciardha, chief of Carbury, was the only chieftain of the blood of Niall of the Nine Hostages who was seated in the southern moiety of Ireland, and in the province of Leinster. His words are as follows :

O'Ciardha ar Chairpíne élaipí,
 D'fíneaduib Néill Naorigiallaig,
 Ní fuil acé iet fein éall éoir
 Do élanuib Néill ar Laigrib.

"O'Ciardha over Carbury of bands,
 Of the race of Niall of the Nine Hostages;
 There is not but themselves yon in the east
 Of the race of Niall in Leinster."

Again, O'Heerin, who wrote about the same period with Giolla Iosa Mor Mac

A small land of most extensive tillage,
 Of the green land of Beinn Gulban^d.
 Of Callraidhe Laithim^e of the swords
 O'Nuadhan^f obtained the land,
 A droppy, sandy, fine land,
 An angelic pure place of meetings.
 O'Ciardha^g obtained heavy profit
 Of the land of Cairbre, I conceal it not,
 For O'Ciardha of the yellow crops
 The fragrant tree was not slow in bearing.
 Of the dividend of the Hy-Fiachrach themselves
 Is the land of Cairbre of the level plains,

But

Firbis, speaks of O'Ciardha as chief of Carbury, in Leinster. His words are :

Ar Chaibne Laigean na leaig
 O'Ciarda na g-colg rlior-oeaig;
 Slat Alman gan caea eair
 Lep' h-aona caea im Chpuacham.

"Over Carbury of Leinster of the plains
Rules O'Ciardha of the red-bladed swords,
 The scion of Almhain, without scarcity in the
 east,
 By whom battles were kindled round Croghan."

Here the designation *Slat Alman*, scion of Allen, "by whom battles were kindled around Croghan," i. e. the conspicuous hill of Croghan, in the north of O'Conor Faly's country, in the present King's County, shows clearly that the Carbury, of which O'Ciardha was chieftain, was no other than the barony of Carbury, in the county of Kildare, in Leinster, which extends southwards to near the hill of

Almhain, or Allen, and is situated in the southern half of Ireland, being south of the Eiscir Riada, which extends from Dublin to Clonard, leaving the barony of Carbury to the south. Whether there was another O'Ciardha who was chief of Carbury, in Sligo, it is but fair to inquire; but the Editor has not been able to find any reference to a family of the name, as seated in Lower Connaught, in the authentic Irish annals, and is therefore satisfied that there was none, and that Giolla Iosa Mor was here dreaming, as he was in making Tomaltach Mor Mac Dermott the chief of Moylurg, who first acquired the territory of Clann Cuain. The name O'Ciardha, which fell into obscurity centuries before the time of Giolla Iosa Mor, is still numerous in the counties of Kildare and Westmeath, where the name is generally anglicised Keary, but sometimes Carey, which is incorrect.

ο'lb Néill pineadaiz na fear,
 réio d' fíleadaib a n-áirem.
 Ḑíó uapal fine na fear,
 clann Cairppri na m-brúg m-bláit-geal,
 pa maer na maicni ri t-riar
 paer an aicni ri o'n áirb-riar.
 O Róba, ar paetmar a réim,
 tugur co cróda an cáithréim,
 co Codnais ar cam tuil
 podnais do bárr boruime.
 Dénam impo tar ar n-air
 co rígnais Ráta Dúrlair,
 do dénoim eoil do'n fedaín,
 le treoir n-glé glain n-geinealaiz.
 Inas caicmi in gac tuait tréin
 r'loindfed do'n fedaín fóid-réio,

cenn

^h *Lineage of the men*, i. e. though the men of Carbury are tributary to the king of the Hy-Fiachrach, they are not of his race, but of the race of Cairbre, son of Niall of the Nine Hostages, from whom they derive their name as well as descent.

ⁱ *Western people*, i. e. the O'Dowds, whose country lies west of Carbury.

^j *From the Rodhba*, i. e. I have now described all the tribes and districts in O'Dowd's country, extending from the river Robe to the river Codhnach, at Drumcliff. O'Dugan also, in his celebrated topographical poem, describing the tribes and territories of the northern moiety of Ireland, mentions these two rivers as the

limits of O'Dowd's country, in the following lines :

O'Choónais ar cuairt ríche,
 Comaréta na coisgeiríche,
 Co tórainn Ródba, ré raó,
 Ar forba álainn iomlán ;
 Ní fuil ní ar cúmga na roin
 Ag O'n-Duoba do úteoid.
 Ceirre ríoga dég do'n oruineg
 Fuair an cuigeas gan comhroinn,
 Tré gníom comhfeadma ir caé,
 Do ríol orneagda Fiachrach.

“ From the Codhnach of gentle flood,
 The mark of the boundary,
 To the boundary of the Rodba, to be mentioned,
 It is a beauteous perfect territory ;

But of the Hy-Neill is the lineage of the men^b,
 Easy for poets to enumerate them.
 Though noble the race of the men,
 The Clann Cairbre of the flowery white mansions,
 Are under the steward of the western peopleⁱ,
 Noble are their people from this high submission.
 From the Rodha^j of prosperous course
 I have bravely pursued my career,
 To the Codhnach of winding current,
 Which serves the bovine crop^k.
 Let us now return back
 To the kings of the Rath Durlais^l,
 To afford knowledge to the race
 By the bright clear guide of genealogy.
 The place of the banquet^m in each powerful territory
 I shall name for the tribes of the smooth sod,

Prominent

There is not a narrower region than this
 In O'Dowd's inheritance.
 Fourteen kings of the family
 Obtained the chief sway of the province without
 division,
 By deeds of puissance and battle,
 Of the illustrious race of Fiachra."

ⁱ *Bovine crop*, i. e. out of which the
 cows grazing on the adjoining fields may
 drink fresh water. *Óann bópuime* literally
 meaning crop of cows, is here used to de-
 note the cattle with which the land was
 stocked. The word *bapp*, however, is
 rather loosely used, as it is properly ap-
 plied to grass, corn, or vegetables.

^j *Rath Durlais*.—This would seem to be
 the place called Rathurlish, or Rathurlisk,

situated near Doonycoy, in the north of
 the parish of Templeboy, in Tireragh,
 where there are still to be seen the re-
 mains of a large fort; but it is strange to
 find it mentioned so conspicuously here,
 as it does not appear ever to have been a
 residence of any of the chiefs of the Hy-
 Fiachrach; and it is to be suspected that
 the poet here, by an unpardonable poetical
 license, alludes to Dun Durlais, or Rath
 Durlais, the seat of Guaire Aidhne, king
 of Connaught in the seventh century,
 which is situated, as already observed, in
 the country of the southern Hy-Fiach-
 rach.

^m *The place of the banquet*, i. e. the head
 seat or residence of the chief.

tenn a líne caó lebaip
 an díne ar fèrr d' aibeadaib.
 Oileac na rís t-riar 'con tuim,
 Duma Caecan, mar canuim,
 aibreac rcaili a n-geort n-gemair,
 dá phoirt ailli ór innberaib.
 Ar teét dam a h-lrpuir fúar
 ploindfod ápuir na n-árb-rluag,
 Dún Fíne na rlog rlegach,
 'con díne mór muirerach.
 Raic éranduib ir rian raeta,
 srada úr inn árb-plaeta,
 'na poirt comnaid ag O'Chuim
 geort fa'n mong-buidi moguill.
 Loc Deala naí delam craeb,
 Inir Cua na m-brec m-ball-caem,

da

^a *Oileach of the kings.* — The poet, after having described the tribes and territories in the country of O'Dowd, now returns to notice the chief residences in each district, and as he began his description of these districts with Erris, he now enumerates the seats in that district first of all. The seat here called Oileach, which would be pronounced Ellagh, most probably stood on Ard Oiligh, or Ardely point, near Bingham's Castle, in the parish of Kilmore Erris, in the peninsula within the Mullet. There is a small hill immediately to the south of the castle called *An cáe-uir*, i. e. the caher, or stone fort, but there are no remains of a fort on it at present.

^o *Dumha Caechain.* — This place is now

called Doonkeeghan. It was the name of an ancient fort on the site of which a castle was erected by one of the Barrett family. It is situated in the townland of Killygalligan, in the parish of Kilcommon, and barony of Erris, about eight miles and a half north-east of the little town of Belmullet. This fort stood on a projecting cliff, half a mile west of the coast-guard station of Rinroe, in the most northern division of Erris, which was called *Dumha Caochain* from the sandbanks which it contains in abundance, and *Hy-Maccaochain* from the tribe which inhabited it. The reader is here to understand that *Dun Caechain*, i. e. Keeghan's dun, or fort, was the true original name

Prominent in the line of each book
 Is this tribe, the best to strangers.
 Oileach of the kings^a west of the wave,
 Dumha Caechain^o, as I sing,
 Prodigious the shadow of their corn-fields,
 Two beautiful forts over estuaries^p.
 After my return from the cold Irrus
 I shall name the habitation of the great hosts,
 Dun Fine^q of the spear-armed troops
 Belongs to a tribe of numerous families.
 Raith Branduibh^r of the track of prosperity,
 The noble mansion of the arch-chieftain,
 Is the mansion seat of Conn's descendant^s,
 A field where the fruit pods are yellow-bearded.
 Loch Deala^t not scarce of bushes,
 Inis Cua^u of the fair-spotted trouts.

Are

of the residence, and that Dumha Caechain was properly the name of the sand-banks in its vicinity.

^p *Over estuaries*; Inbhers, estuaries, or the mouths of rivers. Dun Caochain stood over Invermore, now Broadhaven and Oileach, on the west side of Blacksod Bay.

^q *Dun Fine*, now Dunfeeny, in the north of the barony of Tirawley. For the situation of this dun, or fort, see p. 6, Note ^s, and Ordnance Map of the County of Mayo, sheet 6.

^r *Raith Branduibh*, now Rafran, in Tirawley. — See Ordnance Map of Mayo, sheets 14 and 15.

^s *Conn's descendant*, i. e. O'Dowd, arch-
 IRISH ARCH. SOC. 12.

chief of Hy-Fiachrach, and descendant of Conn of the Hundred Battles.

^t *Loch Deala*.—This place, which is also celebrated in the Tripartite Life of St. Patrick, as published by Colgan in his *Trias Thaum.* (p. 141, col. *b*), still retains this name, which is applied to a lough, in the south-west of the parish of Ballysokeery, in the barony of Tirawley. The townland in which this lough is situated is from it called Ballyloughdalla, but the Lough itself, Lough Dalla, in the anglicised form.—See Ordnance Map of Mayo, sheets 21 and 22.

^u *Inis Cua*, now Inishcoe, situated on the west side of Lough Conn, in the south-

da popt eli 'con pëdaim
 nap doct éri d' aibegaið.
 Eanáð n-Dubán na long luath,
 inab caithmí na caem-tuath,
 popt roigel do h-áiremab ann
 oirer áirned ip uball.
 Dún mic Concobair na cpech
 írtad nár luained leir-bpeth
 létar Ráta pa'n mín muir
 ag gríð pa'ta da riðraib.
 Dún Contre'tain na tonn n-geal
 áruir ana ppuich pin-pled,
 inab caithmí h-l Chuino cpe'ab,
 ar pa'tchi an fuino foib-le'tain.
 An dá Draigis ar deirg bath,
 írðab fairping O Fia'pach,

dun

east of the parish of Crossmolina, in the barony of Tirawley.—See Ordnance Map of the County of Mayo, sheet 38. This was the residence of the celebrated warrior Cosnamhach O'Dowd in 1162, and of Remond Burke in 1458. It is now the seat of M. Pratt, Esq.

† *Eanach Dubhain of the rapid ships*, now called simply Eanach. This is an island in the east side of Lough Conn, lying nearly due east of Inishcoe, above mentioned. It is in the parish of Kilbelfad, and in that part of Tirawley called the Two Bacs.—See Ordnance Map of the County of Mayo, sheet 39. By ships in this line is meant the boats of Lough

Conn. It is curious that the Irish writers, so late as the reign of Elizabeth, were wont to style the boats of Lough Mask, and other large lakes, by the name of longa, ships.

¶ *Dun mhic Conchobhair*.—In the prose list prefixed to this poem this place is called Caislen mhic Conchobhair, or Dun mic Conchobhair. It is now anglicised Castleconor, and is the name of a townland and parish lying on the east side of the river Moy, in the barony of Tireragh, and county of Sligo.—See Ordnance Map of that county, sheet 22. The townland contains the ruins of a castle standing on the site of an ancient dun, or earthen fort,

Are two other mansions of the tribe
 Who gave not strait refusal to strangers.
 Eanach Dubhain of the rapid ships^v
 Is a banquetting place of the fair tribes,
 A very bright fort is mentioned here,
 District of sloes and apples.
 Dun mic Conchobhair^w of plunders,
 A mansion in which no false sentence was passed,
 Ichtar ratha^x at which the sea is smooth,
 With a prosperous griffin of the princes.
 Dun Contreathan^y of the frothy waves,
 A mansion in which winy banquets are found,
 Is the banqueting hall of the plundering descendant of Conn,
 On the green of the wide-sodded land.
 The two Draighneachs^z of red colour,
 The wide mansion of the Hy-Fiachrach,

Bun

on a hill called Cnocan Ui Dhubhda, situated on a point of land extending into the river Moy.

^x *Ichtar ratha*, i. e. the lower district of the fort. This is called Mullach ratha elsewhere, and is undoubtedly the place now called Rath laogh, or Rathlee, situated in the parish of Easkey, in Tireragh.—See Ordnance Map of Sligo, sheets 10 and 11.

^y *Dun Contreathain*.—This is called in the prose list Dun Cinntreathain, or Dun Contreathain, and in the Annals of the Four Masters, at the year 1249, Dun Contreathain. The former form of the name evidently means the dun or fort at the head of the sea; the latter, Cu-Trea-

thain's fort, Cu-Treathain being the name of a man, signifying the hero of the sea. The name of this place is still preserved, but very much obscured under its anglicised form Donaghintraine, which is applied to a townland situated on the coast, in the north of the parish of Templeboy, in the barony of Tireragh.—See Ordnance Map of the County of Sligo, sheet 12. On the old map of these coasts, preserved in the State Paper Office, London, often already referred to, this place is called Duncantroghan, and shown as a castle situated nearly midway between "Rosslee and Augharee."

^z *The two Draighneachs*, now called the

bun Fhinne a n-áitreb oilí,
 ghrinne plait-gel rocoide.
 Triallam, cora triall leira,
 tar éir na craeb coibneira
 co plait Dúrlair, 'cán mór mé,
 ó'n t-plóg do uimair oirne.
 Da geaba, mar fuair các fear,
 toiréi, do céb an coimbed,
 do molad a fuind uilí,
 torad Cuind ir Conairí.
 Re lind Taidg, nar eitig fear,
 O'Dubda do fuair aitem
 eitir chno cúbha na coll
 ní mo úbla na n-aball.

Red

two Draighneachans, anglicè Drynaghans, namely, Drynaghanbeg and Drynaghanmore, two townlands in the parish of Kilglass, in the barony of Tireragh.—See Ordnance Map of Sligo, sheets 16 and 17. In the prose list prefixed to this poem in Duaid Mac Fírbis's Genealogical Book, is the following observation in a different hand from his own, *inter lineas*: — “On Lios na draighnighe is the Bawn of Ceathramh an chaisill at this day.” The Ordnance Map shows two round forts on Drynaghanmore, but no trace of a bawn or castle is now to be seen on the land.

^a *Bun Fhinne*, i. e. the mouth of the river Finn, now Buninna, in the parish of Dromard, in the barony of Tireragh.—See Ordnance Map of the County of Sligo,

sheet 13. See also p. 120, Note ^m, *supra*.

^b *The lord of Durlas*.—By this the poet means O'Dowd, but the introduction of Durlas here is very incorrect, or at least the result of very bad poetical taste. Durlas was the name of the palace of the celebrated Guaire Aidhne, King of Connaught, who was of the Hy-Fiachrach race, but it is situated near Kinvara, in the south-west of the county of Galway, and O'Dowd, who was not descended from Guaire, never had any lordship over it. Here the poet, after describing all the tribes and territories in the principality of Hy-Fiachrach, addresses Tadhg, or Teige O'Dowd, their head chieftain, from whom he demands the reward of his labours, which he was confident would be such gifts

Bun Fhinne^a is another habitation,
 A white wattled pile of hosts.
 Let us proceed,—may it be a prosperous journey,—
 After *giving* the genealogical ramifications,
 To the lord of Durlas^b, with whom I am great,
 From the host who have ornamented us.
 I will obtain, as has each man,
 The fruits, by God's permission,
 Of having praised all his country,
 Fruits *worthy* of Conn and Conaire^c.
 In the time of Tadhg, who refused not a man,
 O'Dubhda, who received obeisance,
 Than the kernels of the fragrant hazel nuts,
 Not larger were the apples of the apple trees^d.

In

as his great ancestor, Conn of the Hundred Battles, would not have been ashamed of conferring.

^c Of Conn and Conaire, that is, we may conjecture, of Conn of the Hundred Battles, the great ancestor of O'Dowd, and his son-in-law Conaire the Second, who succeeded him in the monarchy of Ireland about the year of Christ 212. But the allusion may be to Conaire the First, who was a far more celebrated monarch, and flourished early in the first century, whose reign is celebrated by the Irish bards as having been blessed with peace and plenty, as well as with serenity of the seasons, which they ascribe to his own righteousness and worthiness, and also to the presence of the Redeemer of the world on

earth in human form during thirty-three years of his reign.

^d *The apples of the apple trees*, i. e. the nuts were as large as apples.—In the best and most ancient Irish MSS. the word *úball*, which is evidently cognate with the English word *apple*, is used to denote the apple tree, and *úball*, its fruit, a distinction not at all observed in the modern language. The value set by the ancient Irish upon the hazel nuts is here proved beyond a question, but nothing is said in any part of this poem to show why they were so valuable. We know that they had large herds of swine which fed on masts in the woods, but it is to be suspected that the people used the hazel nuts as an article of food.

Red linn do laigdis tuili,
 a tuir méir-gel Maenmuige,
 cach neé ped éaeb ir trom rath,
 pad maer ar fonn O Fiachrac.
 Táinig torad a talmain
 ped lind, a deirg donn-abraid,
 mar rugair cac falc flecaib,
 tugair laet d'ár loilgeaib.
 A mic Domnaill Duin Guairi,
 minic do fóir á h-anbuaire
 cís Cera duinn ag á dáil
 peda agur úir 'gá admaíl.
 Ir minic beair ó' brúg,
 re coir fíled ir éplum,
 crod a duin laim re Lemaib,
 'con dáim ó búill bileagaid.

Co

^a *The floods have decreased.*—This savours very strongly of Eastern notions.

^f *Maenmagh.*—or “*Maenmuine*,” inserted *inter lineas* in the hand of the original scribe of the Book of Lecan. Here, by a vicious poetical taste, the name of a plain in Hy-Many is introduced merely for its being in Connaught, though neither O'Dowd, nor any of his ancestors, had any dominion over it from a very remote period, never, in fact, except when they became kings of Connaught, which was not the case since they took the surname O'Dowd.

^g *Thou hast brought down every moistening shower.*—See Battle of Magh Rath, p. 101, for a fuller account of this super-

stition among the ancient Irish.

^h *O son of Domhnall.*—The Tadhg, or Teige O'Dowd, to whom this poem was addressed was Tadhg Riabhach, the son of Domhnall Cleireach O'Dowd. He succeeded, as chief of his name, in 1417, the very year in which this poem was composed, and died in 1432. He was one of the most celebrated chiefs of Hy-Fiachrach, being the founder of the Abbey of Ardnarea, and the patron of the compiler of the Book of Lecan.

ⁱ *Dun Guaire.*—This place is in the country of the O'Heynes, in the south-west of the county of Galway, and is introduced here by a wild poetical stretch of the imagination, as it was the palace of

In thy time the floods have decreased^c,
 O white-fingered tower of Maenmagh^f,
 Every person by thy side is of heavy prosperity,
 Under thy steward in the land of Hy-Fiachrach.
 Fertility has come in the land
 In thy time, O ruddy face of brown eye-brows,
 As thou hast brought down every moistening shower^s,
 Thou hast given milk to our milch-cows.
 O son of Domhnall^b of Dun Guaire¹
 Oft have we been relieved from distress
 By the rent of Ceara to us distributed,
 Which the trees and the soil confessed¹.
 Oft is carried from thy palace,
 In the company of poets and saints,
 Cattle from the fort near Leamhach².
 By the fraternity of arborous Buill¹,

To

Guaire Aidhne, King of Connaught, who was of the Hy-Fiachrach race.

¹ *Which the trees and the soil confessed*, i. e. by their fertility they exhibited the clearest signs of the righteousness of thy reign and of the justice with which thou disposest of the tributes rendered thee by the inhabitants. It is very much to be doubted, however, that the Tadhg O'Dowd to whom this poem was addressed, was in receipt of the tributes of Ceara, and it is greatly to be feared that the poet has here converted his *creacha*, or preys, into his lawful tributes peaceably rendered him.

² *The fort near Leamhach*. — We have already seen that Leamhach, now anglicè

Lavagh, is the name of a townland in the parish of Dromard, in Tireragh, and it is quite obvious that the fort here alluded to is the celebrated castle of Longford, which was originally built by the English, but which was taken from them by the grandfather of the hero of this poem, who erected there an addition to the Bawn of Longford, which he called Leaba an eich bhuidhe, i. e. the bed of the yellow steed.

¹ *The fraternity of the arborous Buill*, i. e. the friars of the abbey of Boyle, in the county of Roscommon, to whom O'Dowd, the hero of this poem, appears to have been liberal in his presents of cattle.

Co Cruacáin ar corcra fíob,
 éirí ar ríict na rínnírep,
 caic do feal a múr Meabba,
 ben do'n dún a domenna.
 Da beir caic dám, tig a tuaid,
 dá cógrair riar tar ren-Múaid,
 gell ó Arainb mín Murbhaig,
 do Thir álainb Amalgaid.
 Na tréig ar Chruacain clann Chuind
 Maḡ Muaidi na mūr n-dígaib,
 nár can a fíob-muigi d'ár
 ag ingairi clair Chruacain.
 Dó asbino Cruaca na clár,
 ir Cera na craeb comlán,
 feárr comnaíoi an tíri é-riar,
 fonn muigi mine Maicniab.

Ráit

^m *Cruachan*, i. e. Rathcroghan, near Belanagare, in the county of Roscommon, the ancient seat of the Kings of Connaught.

ⁿ *The fort of Meadhbh.* — Rathcroghan, so called from the celebrated heroine Meadhbh, i. e. Meave, or Mauda, queen of Connaught, who dwelt in this fort in the first century, and who is more celebrated in Irish stories than any other female character of ancient times in Ireland.

^o *Its dejection*, i. e. make it cheerful by thy presence. This is casting a slight slur on the O'Conors of Croghan, whose power at this period had been very much crippled by the Burkes and other families

of English descent, in Connaught. The last of the O'Conors who was inaugurated king of the Irish of Connaught, was slain eleven years before this poem was composed, so that the poet had just reason to represent the fort of Meave as gloomy and dejected, there being then no king of the hereditary race of Croghan to cheer it with his festivities.

^p *Ara of the plain of Murbhach.* — This is the great island of Aran, in the bay of Galway, which contains a small plain called Murbhach, i. e. *sea-plain*, situated towards its north-west end, at a place called Cill Murbhaigh, anglicé Kilmurvy.

^q *Tir Amhalgaidh*, now Tirawley.

To Cruachan^m of the purple-berried trees
 Proceed in the track of thy ancestors,
 Pass thy time in the fort of Meadhbh^a,
 Remove from that fort its dejection^o.
 Every band of *the literati* that comes to the north,
 Whom thou invitest westwards across the old Muaidh,
 Brings a pledge from Ara of the plain of Murbhach^p
 To the beauteous Tir Amhalgaidh^a.
 Forsake not for Cruachan of the race of Conn,
 The plain of the Muaidh of the defensive forts,
 It would be a shame to neglect the cultivation of its fair plain
 While caring the plain of Cruachan.
 Though delightful is Cruachan of the plains,
 And Ceara^r of the full-grown bushes,
 It is better to dwell in the western land,
 The level soil of Maicnia's plain^s.

The

^r *And Ceara*.—This clearly shows that the hero of the poem was not in possession of Ceara, as already hinted.

^s *Maicnia's plain*, an appellation given to all Ireland by the Irish bards, by a vicious poetical license which often obscures their writings. This Maicnia was the father of Lughaidh Mac Con, who usurped the throne of Tara in the third century.—See O'Flaherty's *Ogygia*, Part III. c. 67; and Keating in the reign of Lughaidh Mac Con; but as Maicnia himself was never monarch of all Ireland, it was very incorrect to call the whole country after his name. The learned O'Flaherty, in treating of the different

names by which Ireland was known to the ancients, says that the Irish poets frequently formed other appellations for her from the names of the more celebrated of her monarchs; in corroboration of which he quotes a quatrain from a poem by Hugh, the son of O'Donnell. His words are:—"Denique non rarè a Poetis patriis quorundam celebriorum Insulæ regum adjectis nominibus, hujus, vel illius Regis (expresso nomine) regio, plaga, terra, campus, regia, curia, aut quod simile cognominatur; ut in sequentibus ex Hugone O'Donnelli filio:

"Ḵoiréar ceac Tuacail o' Eirinn,
 Cpó Cuinn ir fonn finn-Fhéolaim,

Ráit Dúplair iṛ dígairṁ blaṁ
 ná tréig ar clár na Cpuacán,
 raic brait-gel na m-bilead m-bog,
 áitreab fílead iṛ eppog.
 Co Duplur da tógairṁ triall,
 a meic Domnaill Dúin Gailian,
 len aitéir na rís noime,
 a grib áit-lir Conaire.
 Diaid umad ag eṛgi amac
 caírig na fonn-ra O Fhiaćpac,
 iṛ triac an tíri rí eall
 le ríni-rí a n-iaṁ eacṛand,
 dheic uaṁad nī dúṁad duio
 a h-l Dubda Dúin Cormaic,
 ríóll 'cob maicnī fáṁ medaib,
 ríóg iṛ aipṛi o' fíleṁaib.
 Ríṁairṁ Cera fáṁ dheic n-duind,
 rluag Ippuir do éar éomluind,
 h-l Amalgaid, ríóig na rleg,
 do'n Gamanraib móir Milead.

Sluaig

Iac Ugaine, iṛ ácaio Aipe,
 Crioć Choṁṁaig iṛ clár Chopmaic.
 "Dieta Tuathalii domus Eria, regia Quinti:
 Fedlimii fundus, plaga Cobthaca, et Hugonis
 arvum:
 Arturi regio, vestrum et Cormace, theatrum."

Ogygia, p. 19.

¹ *The fort of Durlas*.—This is a hint to the O'Dowd that he had a right to the country of the southern Hy-Fiachrach, that is, the country of Aidhne, co-exten-

sive with the diocese of Kilmacduagh, in the county of Galway, of which country Durlus, now called Dun Guaire, was the head residence.

² *Fort of Gailian*.—It is hard to conjecture what fort the poet has here in view. The country of the Gailians, a sept of the Firbolgs of Connaught, comprised the present baronies of Gallen, Leyny, and other districts which bordered on O'Dowd's country; and it is very pro-

The fort of Durlas' of lasting fame
 Forsake not for the plain of Cruachan,
 The white-sheeted fort of soft trees
 Habitation of poets and bishops.
 To Durlas shouldst thou desire to go
 O son of Domhnall of the fort of Gailian^u,
 Pursue the example of the kings before thee,
 O griffin of the battle-fort of Conaire^v.
 There will be around thee rising out
 The chieftains of this land of Hy-Fiachrach,
 And the lord of this yonder country
 With whom thou mayest march into the land of strangers.
 To be alone is not hereditary to thee,
 O O'Dubhda of the fort of Cormac^w!
 Thy people have satin under thy medes,
 A host the most ripe for poets.
 The chiefs of Ceara under thy bright aspect,
 The host of Irrus to urge the conflict,
 The Hy-Amhalgaidh, host of lances,
 Of the great Milesian Gamanradii^x.

Should

bable that the place here mentioned was the ancient name of some one of O'Dowd's seats, the site of which might have been originally occupied by a Firbolgic fort; but the Editor has discovered nothing to throw any light upon the subject.

^v *Battle-fort of Conaire.* — O'Dowd had no residence of this name, and it is very likely that the poet is here going outside the bounds of true chorography by styling his hero chief of forts to which he had no

just claim.

^w *Fort of Cormac.* — This is a made name too, and by it the poet evidently means Tara, the seat of Cormac O'Cuinn, the great ancestor of the chieftain families of the north and west of Ireland, and of O'Dowd among the rest.

^x *Milesian Gamanradii.* — The Gamanraidhi were a fierce and warlike tribe of the Firbolgs seated in Erris in the first century; and their character for bravery

Sluaig ecctann da n-erdi duib,
 fa'n oilen ra puirte Pádraig,
 can luad aithní ar aroili
 'con t-pluag d'aílel i ngaili.
 A meic Domnaill á Dun Chuind,
 tú ir oigri d' ingin Domnaill,
 clú in da Domnall ad degeoib
 páo éru a comlann cuingebais.
 Ní dúca duib Maḡ Muaidi,
 'ná fonn Tempa taeb uaine,
 fíic ag am rcol na rḡneabera,
 'ra cpié roir co reir Ealpa.
 Clann Fiacraic ag erdi amac,
 fa'n rí rí ar fonn O Fiacraic,
 pluag fuaicta re cac feobain
 buar Cpuacna 'ca céib fepaib.
 Gluairib, cora rén ropaid,
 co Cpuacain clann Concobair,
 a neit ar Chpuacain do cuir,
 tre ceit h-l Tuacail Teictmair.

Ní

and dexterity at arms was such that the poet here intends to compliment the descendants of their conquerors by styling them Milesian Gamanraidhi. Some very curious accounts of Ferdia Mac Damain, who was the principal champion of this sept in the first century, are preserved in the very ancient historical tales called *Tain Bo Cuailgne*, and *Tain Bo Flidhisi*, of which there are ancient copies on vellum preserved in the Library of Trinity

College, Dublin.

¹ *The island of Patrick's city.*—This is another shift to form a poetical name for Ireland! Patrick's city here denotes Armagh, and the Island of Patrick's city means Ireland, of which Armagh is the chief ecclesiastical city!

² *Fort of Conn*, i. e. Tara, the fort of Conn of the Hundred Battles, who is O'Dowd's great ancestor.

³ *Daughter of Domhnall.*—According to

Should a host of strangers meet thee
To contend for this island of Patrick's city⁷,
 That host would not recognize each other
 After encountering thee in battle.
 O son of Domhnall of the fort of Conn⁸,
 Thou art the heir of the daughter of Domhnall^a;
 The fame of the two Domhnalls^b follow thee,
 Which will sustain thy blood in the conflict.
 Not more hereditary to thee is the plain of Muaidh,
 Than the land of the green-sided Tara,
 As is found by my school in their writings,
 And the region east of the old Alps^c.
 The race of Fiachra when rising out
 Under this king of the land of Hy-Fiachrach,
 Are a host dreaded by every tribe,
 The kine of Cruachan are obtained by their chief men.
 Let them proceed,—may it be a felicitous journey,—
 To Cruachan of the Clann Conchobhair^d,
 His sway over Cruachan to enforce,
 In right of the heir of Tuathal Teachtmhar^e.

He

⁷ Duaid Mac Firbis, in his brief Annals of the O'Dowd family, the daughter of O'Malley was the mother of this Tadhg, or Teige O'Dowd, and of his brother and predecessor, Ruaidhri, or Rory.

^a *The fame of the two Domhnalls*, i. e. the fame of his maternal grandfather, Domhnall, or Donnell O'Malley, and of his own father, Domhnall Cleireach O'Dowd.
^b *The region east to the old Alps*.—This alludes to King Dathi's expedition to the Alps, already often referred to.

^d *Clann Conchobhair*, i. e. the O'Conors of Connaught, who held the sovereignty of Connaught to a later period than the Hy-Fiachrach or O'Dowd line.

^e *Heir of Tuathal Teachtmhar*.—The law of primogeniture being disregarded, as it unquestionably was in Ireland, the O'Dowds are as much the heirs of King Tuathal Teachtmhar, as the O'Neills, O'Conors, or any other family who claimed the monarchy in right of descent from him.

Ní h-antár rir á rinb gliað,
 mac mic brian, ar blaitb fornam,
 ar in fáidchí i n-uair aza,
 rluais 'ga aithe ir edána.
 Ar aitéir na ríge roime,
 O'Dubba a Dún Laegairí,
 teac Tuathal ar airi an fír,
 'r cac baili um Cruacain cóill-gil.
 Tell ar denam 'cá bpeic n-duinb
 ar engnam ir ar orruim
 do uair a h-ailei págla
 buaid n-aichní agur n-uplabra.
 Adobar meabairte menma
 da tennait do tigeirna
 eang nuaidi mín do'n mall muir
 pá chí n-uaine n-Amalzaio.
 A deapaid dama an domain
 pé h-oirí an fuinn érlomais,
 ar lór mar cáitir a crab
 mór cac maiteur ó mórað.
 Mac Domnaill ó múr Meabba,
 féinb marclac mór-delba,

pa

^f *The grandson of Brian.* — Tadhg, or Teige O'Dowd, to whom this poem was addressed, was the grandson of the celebrated Sen Bhrian O'Dowd, who drove all the Anglo-Norman settlers out of Tíreragh, and died in the year 1354.

^g *Fort of Laeghaire.* — Dún Laegairí. This is intended as a name for Tara, as having been the seat of Laeghaire, son of

Niall of the Nine Hostages, who was monarch of Ireland when St. Patrick arrived in 432. Dunleary, near Dublin, is supposed to have taken its name from the same monarch, but no historical proof of the fact has yet been discovered.

^h *House of Tuathal.* — This is another name for Tara, from its having been the seat of the Irish monarch Tuathal Teachtmhar.

He does not shrink from the spear of battle,
 The grandson of Brian^f of splendid aspect,
 In the field at the hour of valour,
 The host who recognize him are timid.
 In imitation of the kings before him,
 O'Dubhda, hero of the fort of Laeghaire^g,
 Has his attention fixed on the house of Tuathal^h,
 And on every town round Cruachan of fair hazels.
 The palm for beauty has his brunette-face won,
 And eke for valour and submission,
 He has got besides these acquirements
 The gift of recognition and eloquence.
 Cause of exaltation of mind
 For this lord, that he has stoutly contested
 A new smooth angle of the calm sea
 Along the green Tir Amhalgaidhⁱ.
 The bards of the world will say
 To the heir of this land of saints,
 Sufficiently has he expended his wealth,
 It is great to exalt each goodness.
 The son of Domhnall of the fort of Meadhbh^j,
 A manly great-faced hero,

Has

ⁱ *Of the green Tir Amhalgaidh.*—From this it would seem that the hero of this poem had been contending with the Barretts, or Burkes, for a section of the sea bordering on Tirawley; probably that part at the mouth of the river Moy, which was valuable for the salmon fishery. In the record of this chieftain's death, given in the Annals of the Four Masters at the year 1432, it is stated that "he was lord of Tireragh,"

and that "he had restored the hereditary estates in his principality, both lay and ecclesiastical, to the lawful proprietors." But it does not appear that he ever possessed any part of Tirawley.

^j *Fort of Meadhbh*, i. e. Croghan, or Rathcroghan, the seat of Meave, a celebrated queen of Connaught, already often referred to.

pa uga do éait a crab
 ca maít ar buga bhonnear.
 Cá h-uairli cliapa élanb Cuinb
 do molab deig-mic Domnaill
 ná torab an tírli éiar
 do molab gribi Gailian.
 Muna éanab Fearfeasa,
 do éanfaib cræb coibnefa,
 d' O'Dubba d'ar teg Temair,
 'ra lurgá gel geinealaig.
 Da cumur d'á éneap mar éuinb,
 oigri deig-brietaé Domnaill,
 fir gnaít-dúcair caé duine
 co ráitb clum-éair Codnair.
 Rígán uaral do éloinb Chuinb,
 ingean déib-geal h-l Domnaill,
 ní teapc buab ar mnai Murbair,
 do'n gnaí fuair ó ollumnaib.

Ingen

^k *Gailian*. — The ancient sept of the Firbolga, called Gailians, had certainly possessed a part of Hy-Fiachrach before the descendants of Eochaidh Muighmheadh-oin, monarch of Ireland, had obtained settlements in Connaught; and this is the reason that O'Dowd is called here Griffin of Gailian, and a few lines higher up (p. 291) "of the fort of Gailian." The Gailians of the Firbolgic race are to be distinguished from the people called Galenga, who were of the Milesian race, and the descendants of Cormac Gaileng, a Munster chieftain,

who settled here.

^l *Had not Ferfeasa sung*. — This was not the Ferfeasa Mac Firis whose pedigree has been given in page 103, *supra*. It is quite obvious from this allusion that this Ferfeasa had written a poem on the genealogy of the O'Dowds previously to the composition of the present poem, but the Editor has not been able to find it.

^m *Fort of Codhnach*. — This was the name of some fort near Drumcliff, in the barony of Carbury, below the town of Sligo, for the river here called Codhnach

Has in profusion spent his wealth;
 That which is bestowed well is the most generously bestowed.
 Not more nobly do the learned of the race of Conn
 Panegyryze the good son of Domhnall,
 Than does the produce of the western country
 Praise that griffin of Gailian^k.
 Had not Fearfeasa' sung
 I would *now* sing the family tree
 For O'Dubhda, whose house is Tara,
 And his fair genealogical lineage.
 I have composed for this skin like the wave,
 For the just-judging heir of Domhnall,
 An account, of the constant inheritance of each man
 As far as the soft-feathered fort of Codhnach^m.
 A noble queen of the race of Conn,
 The white-toothed daughter of O'Donnell^a,
 Not small is the victory of the woman of Murbhach^o
 From the beauty she received from the Ollamhs^p.

The

(pronounced Cownagh) was the ancient name of the river which discharges itself into the bay of Sligo, near the village of Drumcliff. There are many celebrated forts in the vicinity of this river, but it is impossible to conjecture what fort in this vicinity the poet had here in view.

^a *The white-toothed daughter of O'Donnell*.—She was undoubtedly the wife of Tadhg O'Dowd.

^o *Murbhach*.—There are many places of this name in Tirconnell, or the county of Donegal, where the word is understood to mean a flat spot of land verging on the sea,

and such as the *Murrow* on the strand of Wicklow, &c., the Editor has not, however, found that Murbhach was the name of any celebrated seat of O'Donnell at this period; but he is inclined to think that it is not a mere fancy name made by Mac Firbis to answer his rhyme, as the O'Donnells are called *laócharaí Murbhaig*, or heroes of Murbhach, in several other poems.

^p *From the beauty she received from the ollamhs*, i. e. the celebrity which the ollamhs, or chief poets, have given alike to her beauty and goodness in their panegyrical poems.

Ingen h-I Domnaill Doiri,
 beangán do'n réim ríghoibí,
 gnai na m-ban riar far plait-ní
 ní gar do rian Ragnailt.
 Imba mairbailí Muirne
 máthair Ira póit-buibí
 do bac can brón na baile ;
 mor a mac a mairbailí.
 O gein Cuirte do corain blas
 cor a' duain rí do dearbhad,
 ceitra céo ir milí meap,
 ní bprez an line luaiter,
 peét m-bliadna déz can dubí,
 ní tiamba an tréid toghuibí.

Arísle do plaitaib Ua n-Dubda, gur an gairm do berrid leabair
 ariurín dóib, .i. gairm ríog, agus gíó comhgeac rín anu, nír b'eab
 'm an am rín ag Saoidealuib, do péir a n-dligib pen an uair rín,
 agus do péir cinead ele rór; feuc péirí tángattar Clann Ippael
 go Trí Tairrighine go m-báatar trocha ríog ; n-én pé ar an trí
 rín, agus gan ní ar mó ina dá ceud míle ar fad agus caogad míle
 ar

^a *O'Donnell of Derry.*—Here O'Donnell is called of Derry merely because Derry was then within his principality, not because he ever had a residence there, for it is absolutely certain that he never had; and it was not until the fifteenth century that he had possession of Derry at all, for it and the territory of Inishowen, in which it was originally situated, belonged to O'Neill.

^r *Many are the miracles of Mary, i. e. of*

the Blessed Virgin Mary. This is thrown in without any connexion whatever with the foregoing part of the poem. The ancient Irish poets thought it their duty to end all long poems of this kind with some religious remarks, to show that they were Christians, and humble believers in the intercession of saints; and their pious ejaculations on such occasions often contrast strongly with the sentiments expressed in the previous part of their poems.

The daughter of O'Donnell of Derry^a
 Is a branch of the regal lineage;
 The beauty of the women in the west under chieftains
 Approach not the mien of Raghnaile.

Many are the miracles of Mary^r,
 Mother of Jesus of the yellow hair^{rr},
 Who brought forth, without sorrow in her town;
 Great is her son in miracles.

From the birth of Christ, who defended fame, i. e. *character*,
 Until this poem was proved,
 Are four hundred and one thousand fleeting *years*,
 Not false the age that is mentioned,
And seventeen years^s without obscurity;
 Not obscure is the select flock^t.

Here follow some of the chieftains of the O'Dubhdas, with the title which historical books give them, namely, the title of king, and though strange this *appears* at this day^u, it was not so then among the Gaels according to their own laws at that time, and according to other nations also. Behold before the coming of the children of Israel to the land of promise, how there were thirty kings together in that country, and it not more than two hundred miles in length

^{rr} *Mother of Jesus of the yellow hair*.—In a short tract, preserved in the Book of Ballymote, fol. 7, b. b. on the personal appearance of Christ and his Apostles, Christ is described as having *folc dub-donn*, i. e. dark-brown hair, and long curling forked beard.

^s *And seventeen years*, i. e. 1417, the very year in which, according to the Annals of the Four Masters, Tadhg, the son of

Domhnall O'Dowd, became chief of Tire-
 ragh.

^t *Not obscure is the select flock*.—This is a religious observation added merely to fill up the quatrain and complete the poem.

^u *Though strange this appears at this day*.—See more of this subject in O'Flaherty's Ogygia, pp. 31, 32, and the tract on the pedigrees and customs of Hy-Many, pp. 63, 64, Note ¹.

ar leatad innce. Do'n tior rin do gairéi Tír Canaan, ó Chanán, mac Caím, mic Naoi; Tír Tairrighire iarann ó Dhia d'á geallad do Abrahám ir d'á íol; Ippael iar rin ó Chlannuib Ippael; Iudaea ó Iudaiuib; Paleστina ó na Philísteuib, agus an Talam Naomta ó obair ar Slánuighe do deunam innce, agus gin ir ceapad Chrioste, 7c.

Tuig gur ob iad annala eacca na b-plaé ra ríor ríghíobtar fuo annro.

Anno Chriosti,

983. Aodh Ua Dubda, Rí tuairgirt Connacht uile, d'éacc.

1005. Maolruanaidh Ua Dúbda, Rí Ua Fiachraí Muirirge.

1096. Muirceartach Ua Dubda, Rí Ua n-Amalgaidh, agus Ua b-Fiachraí, agus Ceara occirur ept.

1126. Domhnall Fionn Ua Dubda, Rí Ua n-Amalgaidh, Ua Fiachraí, agus Ceara, do bábad ag tabairt creche a Tír Conaill.

1143. Aodh, mac Muirceartaigh Uí Dubda, Rí Ua n-Amalgaidh, agus Ua b-Fiachraí an tuairgirt.

Ruaidrí Meán mac Tailcigh, mec Nell í Dubda, rí ó Roba go Coönuiğ.

1162.

† *Aodh O'Dubhda*.—The Four Masters have collected no notices of this chieftain. Our author obviously extracted this entry from the Annals of Lecan, of which the Four Masters had no copy when compiling their work.

† *Maolruanaidh O'Dubhda*.—The Annals of the Four Masters notice the death of this chieftain under the same year, thus:—"1005. Maolruanaidh, son of Aodh O'Dowd, lord of Hy-Fiachrach Muirisce, and his son Maolseachlainn, and his brother Gebhennach, the son of Aodh, died."

* *Muircheartach O'Dubhda*.—The Annals of the Four Masters notice the death of this chieftain at the same year, but style him lord of Hy-Amhalgaidh, i. e. Tirawley only. "A. D. 1096. Muircheartach O'Dowd, i. e. the Cullach [the Boar], lord of Hy-Amhalgaidh, was slain by his own tribe."

† *Domhnall Fionn O'Dubhda*.—The Four Masters agree with this in every particular, except that they style Domhnall Fionn lord of Hy-Amhalgaidh, or Tirawley, only. But it is much more likely that

length and fifty miles in breadth. This country was called the Land of Canaan from Canan, son of Cam, son of Noah; afterwards the Land of Promise, because God had promised it to Abraham and his seed; Israel after that, from the children of Israel; Judæa, from the Jews; Palestine, from the Philistines; and the Holy Land, from the work of our salvation having been effected in it, and the birth and crucifixion of Christ.

Understand that it is the Annals of the deaths of the chiefs that are written down here, as follows :

Anno Christi,

983. Aodh O'Dubhda', King of all North Connaught, died.

1005. Maolruanaidh^m O'Dubhda, King of Hy-Fiachrach of Muirsge [died].

1096. Muircheartach O'Dubhda^s, King of Hy-Amhalgaidh, Hy-Fiachrach, and Ceara, was slain.

1126. Domhnall Fionn O'Dubhda', King of Hy-Amhalgaidh, Hy-Fiachrach, and Ceara, was drowned as he was carrying off a prey from Tirconnell.

1143. Aodh, son of Muircheartach O'Dubhda^s, King of Hy-Amhalgaidh, and the Northern Hy-Fiachrach [died].

Ruaidhri Mear^a, son of Taithleach, son of Niall O'Dubhda, *was King of the country extending from the Roba to the Codhnach.*

1162.

Duald Mac Firbis is right.

² *Aodh, son of Muircheartach O'Dubhda.*

—The Four Masters agree with this word for word, and enter his death under the same year.

^a *Ruaidhri Mear*, i. e. Rory or Roger the Swift O'Dowd. The Four Masters have collected no notice of this chieftain,

and it is quite evident that Duald Mac Firbis has inserted him here without a date on the authority of the poem of Giolla Iosa Mor Mac Firbis, already given. This was the Ruaidhri who violated the daughter of O'Quin, chief of Clann Cuain, which caused the separation of that territory from his family.

1162. An Cornamuiḡ Ua Dubba, tigeapna Ua n-Ámalḡaib, occirur.

1180. Ir in bliadain ri ceapna Saob, ingean Mhuirḡeara, mic Taidḡ Uí Maolruanaib, bean Taidḡ Uí Dubba; 'ḡá roibe ó Rodba ḡo Códnuiḡ.

1181. An Cornamuiḡ, mac an Chornamuiḡ Uí Dubba, riḡdamna Ua n-Ámalḡaib, occirur.

1213. Donncaib Ua Dubba ḡo-ḡ-coblaic ḡ6 long á h-Inrib ḡall, ḡur ḡab cuan 1 n-Inur Raitin ar Inrib Moib, 1 n-Umull, ḡur bean a fearonn fén raor ḡan cáin do Chatal Chroib-deirḡ Ua Concabair.

1242. brian Deairḡ Ua Dubba, mac Donncaib, Rí Ua b-Fiac-rac, Ua n-Ámalḡaib, aḡur Iorruir, occirur.

1282. Tairleac, mac Maolruanaib Uí Dubba, Rí Ua b-Fiac-rac aḡur Ua n-Ámalḡaib, occirur.

1291.

^b *Cosnamhaigh O'Dowd.*—The Four Masters style him lord of Hy-Amhalgaidh, or Tirawley, under the same year, and add that he was slain by his own tribe. This was the great warrior already mentioned in the pedigree of the O'Dowds, as having been slain at his own house on Inis Cua, by O'Gloinin, in a dispute about a greyhound whelp!

^c *Sadhbh, i. e. Sabia.* The Four Masters have no notice of this lady, but at the year 1192 they notice the murder of Taithleach, or Taichleach O'Dowd, who was undoubtedly her husband, in these words: "A. D. 1192. Taithleach O'Dowd, lord of Tirawley and Tireragh, on the Moy, was impiously slain by his own two grandsons." Her father died in 1817. See p. 212.

^d *From the Rodhba to the Codmach.*—He was lord of the tract of country extending from the river Robe to the river Cowney, which discharges itself into the bay of Sligo, at Drumcliff. This, as already often remarked, was the original extent of O'Dowd's country.

^e *Cosnamhaigh, son of Cosnamhaigh.*—There is no notice of him in the Annals of the Four Masters.

^f *Donnchadh O'Dubha.*—There is no memorial of this great exploit in the Annals of the Four Masters. It was evidently extracted by our author, Duaid Mac Firbis, from the Annals of Lecan, not now to be found. The Four Masters have one notice of this Donnchadh at the year 1207, where they style him lord of Tirawley

1162. Cosnamhaigh^b O'Dubhda, heir apparent of Hy-Amhalgaidh, was slain.

1180. In this year departed Sadhbh^c, daughter of Muirgheas, son of Tadhg O'Maoilruanaidh, and the wife of Taithleach O'Dubhda, who possessed the country extending from the Robha to the Codhnach^d.

1181. Cosnamhaigh, son of Cosnamhaigh^c O'Dubhda, heir apparent of the Hy-Amhalgaidh, was slain.

1213. Donnchadh O'Dubhda^f sailed with a fleet of fifty-six ships from the Insi Gall^e, and landed on Inis Raithin^h, one of the Insi Modhⁱ, in Umball^j, and wrested his own land free of tribute from Cathal Croibhdhearg^k O'Conor.

1242. Brian Dearg O'Dubhda^l, son of Donnchadh, King of Hy-Fiachrach, Hy-Amhalgaidh, and Iorrus, was slain.

1282. Taithleach, son of Maolruanaidh O'Dubhda^m, King of Hy-Fiachrach and Hy-Amhalgaidh, was slain.

1291.

and Tireragh.

^a *Insi Gall*, i. e. the Hebrides, or western islands of Scotland. — See O'Flaherty's *Ogygia*, Part III., c. 63 and 75.

^b *Inis Raithin*.—This island, which is also mentioned in the *Annals of the Four Masters* at the year 1235, is now called *Inishraher*, and is situated in the bay of Westport, in the west of the county of Mayo.—See *Ordnance Map* of that county, sheet 87.

ⁱ *Insi Modh*.—This is the ancient and present Irish name of the islands in Clew Bay, in the west of the county of Mayo.

^j *Umball*.—This territory, which was the patrimonial inheritance of the family of O'Malley, is now popularly called the *Owlea*.—See p. 181, Note ¹.

^k *Cathal Croibhdhearg*, i. e. Cahill, or Charles the Redhanded O'Conor, King of Connaught. He died in 1234. The meaning of this passage is, that O'Dowd compelled the King of Connaught to give up every claim to the tributes which the latter demanded out of the principality of Hy-Fiachrach.

^l *Brian Dearg*, i. e. Brian the Red. His death is thus entered in the *Annals of the Four Masters* at the same year :—"A. D. 1242. Brian Dearg, the son of Donnchadh O'Dowd, lord of Tireragh, Tirawley, and Iorrus, was killed on the road, while on his pilgrimage to the abbey of Boyle."

^m *Taithleach, son of Maolruanaidh O'Dubhda*.—This is the celebrated Taithleach O'Dowd, surnamed *Muidhe*, or of

1291. Conchobair Conallac Ua Dubda, tigearna Ua b-Fiacrac do bádað ar Sionuinn.

1337. Donncað Mór Ua Dubda, áðbar ríð Ua b-Fiacrac, d'éacc.

1350. Uilliam Ua Dubda, Erroc Cille h-Alaib, do éacc.

1354. ðrian 6 Dubda, Rí Ua b-Fiacrac agur Ua n-Amalgaid, d'éð 'na tíð fén iar m-beð 84 bliaðna i d-tigearnur.

1380. Domnall Clépeac, mac ðrian Uí Dubda, Rí Ua b-Fiacrac agur Ua n-Amalgaid, d'éð iar b-flaitiur 36 bliaðan.

1417. Ruaidrí, mac Domnall Cleiríð, Rí Ua b-Fiacrac, agur Ua n-Amalgaid, d'éð i n-Dún Néll, iar b-flaitiur 37 bháðan.

1432. Taðð Riabac Ua Dubda, mac Domnall Cléiríð, Rí Ua b-Fiacrac d'éð i n-Erðir Abann, iar b-flaitiur 15 bliaðan. Ingean Uí Mháille mátair Ruaidrí peampáite, agur an Taðð rín.

1432.

the river Moy. He was slain by Adam Cusack in 1282, and the Four Masters have the following notice of him:—"A. D. 1282. Taithleach, the son of Maolruanaidh O'Dowd, lord of Tireragh, the most hospitable and warlike of his tribe in his time, was slain by Adam Cusack on the strand of Traigh Eothaile." His death is also noticed in the *Historia Familiæ De Burgo*, preserved in the MS. Library of Trinity College, Dublin, in the following words:—"Bellum apud Mayn [Moyn] de Kilro per Adam Cymnog ex unâ parte et William Bareth ex altera parte, ubi vulneratus et captus est idem William, et postea de hiis vulneribus mortuus fuit Adam Fleming, et multi alii. A. D. 1282. Occiditur Tailteach O'Dubda per Adam Cim-

sog." In a notice inserted in a more modern hand in the Book of Lecan, it is stated that this Taithleach O'Dowd was slain at Bel atha Taitligh, in Coillte Lughna, which seems correct, as the lands of Coillte Lughna, or Luighne, border on the great strand of Traigh Eothaile.

^a *Conchobhar Conallach*, i. e. Conor the Conallian, so called because he was fostered in Tirconnell. The Four Masters notice his death in the same words used by our author in the text.

^o *Donnachadh Mor*.—The Four Masters agree with this.

^p *William O'Dubda, Bishop of Killala*.—The Four Masters agree.

^q *Brian O'Dubda*.—This was the celebrated Sen Bhrian, or old Brian O'Dowd,

1291. Conchobhar Conallach^a O'Dubhda, lord of Hy-Fiachrach, was drowned in the Shannon.

1337. Donnchadh Mor O'Dubhda^o, heir apparent to the throne of Hy-Fiachrach, died.

1350. William O'Dubhda, Bishop of Killala^p, died.

1534. Brian O'Dubhda^a, King of Hy-Fiachrach and Hy-Amhalgaidh, died in his own house after having been eighty-four [*recte* fifty-four] years in the lordship.

1380. Domhnall Clereach^r, son of Brian O'Dubhda, King of Hy-Fiachrach and Hy-Amhalgaidh, died after a reign of thirty-six years.

1417. Ruaidhriⁱ, son of Domhnall Clereach O'Dubhda, King of Hy-Fiachrach and Hy-Amhalgaidh, died at Dun Neill after a reign of thirty seven years.

1432. Tadhg Riabhach^r O'Dubhda, son of Domhnall Clereach King of Hy-Fiachrach, died at Esgir Abhann^u after a reign of fifteen years. The daughter of O'Malley was the mother of the aforesaid Ruaidhri and Tadhg.

Maolruanaidh,

who drove the English entirely out of Tire-
ragh. The Four Masters notice his death
at 1354, but do not add the length of his
reign, and we have already seen that he
could not have reigned so long as eighty-
four years. In a list of the chiefs of the
O'Dowd family, inserted in a modern hand
in the Book of Lecan, it is stated that he
was King of Hy-Fiachrach for fifty-four
years, which is no doubt the true length of
his reign.

^r *Domhnall Clereach*. — The Four Mas-
ters agree in this date of his death, but
the list in the Book of Lecan gives him a
reign of forty-nine years and a half, and

adds that he died at Dun Neill.

^a *Ruaidhri*. — The Four Masters agree
with this date. The list in the Book of
Lecan gives him a reign of forty-two
years, and adds that the daughter of
O'Malley was his mother.

^r *Tadhg Riabhach*. — This is the chief to
whom Giolla Iosa Mor Mac Firbis addressed
his poem in 1417, and for whom the Book
of Lecan was compiled.

^u *Esgir Abhann*. — In the list in the
Book of Lecan this place is called *Inis*
Sgrebhoinn, which, as we have already seen,
was one of the ancient names of Inishcrone,
an old castle near the river Moy in Tireragh.

Maolruanaid, mac Ruaidrí Uí Dubba, Rí Tíre Fiaclaí 18 bliadhna. Ingean Mec Góirbelb a mḡtair. Anno 1432 do pineadh Ua Dubba de ro.

Domnall baile Uí Choitil 'na Ua Dubba reacht m-bliadhna, agus a n-anno 1447 do pineadh Ua Dubba de ro.

Tadhg buide, mac Tadhg Riabaird, 3 bliadhna.

Seaan Glas, a dearbhrádaí, 14 bliadhna.

Eumonn, mac an Chornamuiḡ, cuig reachtmuine 17 leé-bliadhain.

Domnall ballac, bliadhain.

Brian Cam, mac an Chornamuiḡ, 2 bliadhain.

Eogan Caoc, mac Ruaidrí, 14.

Uilliam, mac Domnuill ballairḡ, leé-bliadhain.

Brian Og, leé-bliadhain.

Donncadh Ullac, bliadhain.

Maḡnur, mac Tadhg buidhe, bliadhain.

Pélim,

^v *Maolruanaidh*.—The list in the Book of Lecan agrees with this, and adds that he died at Liathmhuine, now Leafony, in the parish of Kilglass, and barony of Tireragh. — See Ordnance Map of Sligo, sheet 11.

^w *Domhnall of Baile Uí Choitil*, i. e. Donell, or Daniel O'Dowd, of Cottlestown. It is added in the list inserted in a modern hand in the Book of Lecan, that he died at Baile Uí Choitil, and that the daughter of Magnus, son of Cathal Og O'Connor, was his mother.

^x *Tadhg Buidhe*. — It is added in the list in the Book of Lecan, that his mother was the daughter of Sir Redmond Burke, and that he was slain by the posterity of Ruaidhri O'Dowd. — See Depositions of

Redmond Burke, already given in p. 124.

^y *John Glas*, i. e. John the Green. The list in the Book of Lecan adds that he died at Inis Sgreabhainn, now Inishcrone.

^z *Edmond, son of Cosnamhach*. — The list in the Book of Lecan adds that the daughter of Conchobhar Mac Donogh was his mother, and that he died at Ard na n-glass, now Ardnaglass, in the north of the parish of Skreen, in Tireragh, where the extensive ruins of his castle are still visible.

^a *Domhnall Ballach*. — The list in the Book of Lecan adds that the daughter of Mac Wattin [Barrett] was his mother, and that he died at Dun Neill.

^b *Brian Cam*. — The list in the Book of Lecan adds that the daughter of Concho-

Maolruanaidh^v, son of Ruaidhri O'Dubhda, *was* lord of Tir Fiachrach for eighteen years. The daughter of Mac Costello was his mother. He was made O'Dubhda in the year 1432.

Domhnall of Baile Ui Choitil^w, was O'Dubhda for seven years, and was made O'Dubhda in the year 1447.

Tadhg Buidhe^x, son of Tadhg Riabhach, three years.

John Glas^y, his brother, fourteen years.

Edmond, son of Cosnamhach^z, half a year and five weeks.

Domhnall Ballach^a, one year.

Brian Cam, son of Cosnamhach, two years^b.

Eoghan Caoch^c, son of Ruaidhri, fourteen years.

William, son of Domhnall Ballach^d, half a year.

Brian Og^e, half a year.

Donnchadh Ultach^f one year.

Maghnus, son of Tadhg Buidhe^g, one year.

Felim,

bhar Mac Donogh was his mother, and that he died at Ard na n-glass.

^c *Eoghan Caoch*.—The list in the Book of Lecan adds, that the daughter of John O'Connor was his mother, and that he was slain by O'Donnell. He was slain, according to the Annals of the Four Masters, at Sligo, in the year 1495, when he marched his forces to the relief of that town, then besieged by Conn, the son of Hugh Roe O'Donnell.

^d *William, son of Domhnall Ballach*.—He died, according to the Annals of the Four Masters, in the year 1496, and was succeeded by Brian Og, the son of Brian O'Dowd.

^e *Brian Og*.—The list in the Book of Lecan adds, that the daughter of Mac

Wattin [Barrett] was his mother, that he was chief for one year, and that he died at the Longphort, now Longford castle, in the parish of Dromard.

^f *Donnchadh Ultach*.—The list in the Book of Lecan adds that the daughter of Cormac O'Hara was his mother, and that he died at Inis Sgreabhainn, now Inish-crone, near the Moy.

^g *Maghnus, son of Tadhg Buidhe*.—The list in the Book of Lecan adds, that the daughter of Mac Jordan was his mother, and that he died at Ard na riagh. The date of his death is not given by the Four Masters, but calculating by the length of the reigns we must come to the conclusion that he died about the year 1500. The O'Dowds held the castle of Ardnarea till

Félim, mac Taidg Buidé, 19.

Concábar, mac Diarmada, mic Maoilruanaid, 30.

Eoghan, mac Concábair, 7.

Catal Dub, mac Concábair.

Rioġa Connaċt do ċloinn Fiaċraċ umorro, aċt ġé do rġríoċur iad céana, ar áil leam labairt nár foirleċne orra runna, á rleactaib reanċad oile.

Fiaċra, mac Eataċ Muigheadoin, 12 bliadoin i riġe Connaċt. Iar marbad ċhríam, a dearbdaċar, la Laignib, aġur iar m-beċ o' Fiaċra 'n a ċuairġnib caċa i n-ionad ċhríam aġ a n-dearbdaċair ele, .i. Niall Naoigiallaċ, Rí Eneann; do ċuaid Fiaċra do ċobad ċíora an riġ Néll ir in Múmain. Do ċuirriod Muimniġ caċ Caonraiġe re Fiaċra, aġur ro bhiríod an caċ re b-Fiaċra orro, aġur ġabar ġell Múman. Aċt céana do ġonad Fiaċra, ir in caċ rin, re Maiġe Meaporaċ, do ċurnuib, aġur iompair ġo ġ-corġur aġur ġialla ler ġo Teampaiġ; aġur do fellaċad ġell Múman

the year 1533, when it was assaulted by night and taken from them by the sons of Thomas Burke; and it appears that the O'Dowds were never after able to recover it. They still, however, had an anxious expectation of regaining it, but so feeble did they become in comparison to the Burkes about this period, that their expectation of Ardnarea became a proverb, or by-word in the country. Thus, when any person is represented as expecting to obtain any thing of which he has not the slightest prospect, it is said that his look out is like the expectation of O'Dowd to regain Ardnarea. Map Súil Uí Dhúboá le h-Áro na riag.

^b *Félim, son of Tadhg Buidhe.*—The list in the Book of Lecan gives him but a reign of nine years, but adds that he and his predecessor, Maghnus, were born of the same mother, and that he died at Ard na riagh.

¹ *Conchobhar, son of Diarmaid.*—The list in the Book of Lecan adds, that he died in Mainister na Maighne [the abbey of Moyne] in the habit of St. Francis.

¹ *Eoghan, son of Conchobhar.*—The writer of the list in the Book of Lecan adds, that Margaret, the daughter of Thomas Roe Burke, was his mother, and that he was married to Sadhbh, or Sabia, the daughter of Walter, the son of Richard Burke, and

Felim, son of Tadhg Buidhe^b, nineteen years.

Conchobhar, son of Diarmaid^l, son of Maolruanaidh, thirty years.

Eoghan, son of Conchobhar^l, seven years.

Cathal Dubh, son of Conchobhar^k.

Here follows a list of the Kings of Connaught of the Clann Fiachrach; for though I have given them already^l, I wish to speak of them more fully here from the remains of other historians.

Fiachra, son of Eochaidh Muighmheadhoin^m, was twelve years in the government of Connaught. After his brother Brian had been slain by the Lagenians, Fiachra had served in his place as general of battle to their other brother, namely, Niall of the Nine Hostages, King of Ireland; Fiachra went to exact the rents of King Niall into Munster; and the Momonians fought the battle of Caonraigheⁿ against Fiachra, in which battle he defeated them and took the hostages of Munster. Howbeit, Fiachra was wounded in that battle by Maighe Meascoradh, one of the Ernaans^o, and he returned with the hostages in triumph for Tara; but the Munster hostages acted treacherously towards

that they were buried together at Moyne; and the writer, who evidently knew them, "prays that God may have mercy on them." This Eoghan O'Dowd was living in the year 1536, in which year, according to the *Annals of the Four Masters*, his wife, the daughter of Walter Burke, was taken prisoner by O'Donnell.

^k *Cathal Dubh, son of Conchobhar*.—He is the last chief given by the writer of the list in the *Book of Lecan*, and as he does not add the length of his reign, we may fairly assume that they were cotemporaries. It is stated in the *Historia Familiæ De Burgo* that this Cathal Dubh O'Dowd

consented to pay five marks a year to the Lower Mac William as a *clor copanta*, i. e. rent for protection.—See Addenda to this volume.

^l *For though I have given them already*.—The list here alluded to will be found from p. 93 to 95 of this volume.

^m *Fiachra, son of Eochaidh Muighmheadhoin*.—See Pedigree of O'Dowd in the Addenda to this volume.

ⁿ *Caenraighe*, now Keury, a barony in the county of Limerick, on the south side of the Shannon.

^o *Ernaans*, a celebrated Munster tribe seated in Desmond.

Mumhan ar 1 n-a ostarlige, iar na págbail 1 m-baozal, go po aónaí-
ruid beo po éalmain é, 1 n-Uið Mec Uair òreğ, gur h-òisigeaò é
amluò.

Daí mac Fiaçraç peampáite, gabuir áirðrige Connact agur
Ereann a Connactaib, remear 23 bliaðna, co n-eurbail ag Sliab
Ealpa do raighén tinteige.

Amalgaid, mac Fiaçraç, mic Eataç Muigmeaðoin, céo pí do
Connactaib do éireo do naom Pádraig. Uaò ainmnigeteaí Tír
Amalgada. 32 bliaðain do 1 rige Connact gur éğ go maíe.

Oíill Molt, mac Daí, mic Fiaçraç, 20 bliaðain 1 rige Chon-
nact céadur, agur píe bliaðain ele a ríge Ereann. Iar rin
torchaí 1 g-caè Ocha pe Uigaid, mac Laoğaire, agur pe Muir-
ceartaç mac Earca, agur pe Fearğur Ceppbeul, mac Connuill
Cremtuinn, agur pe Fiaçra lonn, Rí Dail Araide.

Eogan

^o *Hy-Mac Uais, in Bregia*, now the barony of Moygoish, in the north of the county of Westmeath; but our author must be wrong in placing it in Bregia, for Bregia, which comprised only five triochoeada or baronies of East Meath, could not have extended so far to the west as to comprise the present barony of Ui Mac Uais, or Moygoish.

^a *Dathi, son of the aforesaid Fiachra*.—For the history of Dathi see p. 17 to 33 of this volume.

^r *Amhalgaidh, son of Fiachra*.—He is mentioned by Jocelin in the Life of St. Patrick, c. 59, and also by the writer of the Tripartite Life of Patrick, as converted to Christianity by the Irish apostle, and all the ancient lives of this saint would indicate that his conversion took place in

the year 434. — See Ussher's Primordia, p. 1103. He is also mentioned in four ancient catalogues of the Kings of Connaught, referred to by Colgan in his Trias Thaum., p. 180, Note 138. He died, according to the Annals of the Four Masters, in the year 449, that is, fifteen years after his conversion.

^b *Tir-Amhalgaidh is named from him*, now Tirawley. Ussher, in treating of the conversion of the sons of Amhalgaidh, states the same. “Sed maximè memorabile est, quod de septem filiis Amalgaidh, sivè Amhlaich, regis Connaciæ (à quo tractus terræ in eâdem provinciâ *Uir-eul* dictus nomen accepisse putatur) et XII. hominum millibus uno die ad fidem a Patricio conversis et baptizatis refertur: cui populo noviter ad Christum converso ma-

towards him, having found him unprotected in his sickness, and they buried him alive in the earth in Hy-Mac Uais, in Bregia^p, and thus did he fall a victim !

Dathi, son of the aforesaid Fiachra^q, assumed the chief government of Connaught and of Ireland, in Connaught, for a period of twenty-three years, when he was killed at the mountain of the Alps by a flash of lightning.

Amhalgaidh, son of Fiachra^r, son of Eochaidh Muighmheadhoin, the first of the Connaught kings who believed on *the preaching of St. Patrick*. Tir Amhalgaidh is named from him^s. He was thirty-two years in the government of Connaught when he died well.

Oilioll Molt^t, son of Dathi, son of Fiachra, was first, for twenty years in the kingdom of Connaught, and afterwards, twenty years more in the monarchy of Ireland. After this he was slain in the battle of Ocha, by Lughaidh, son of Laoghaire^u, Muircheartach^v Mac Earca, Fergus Ceirrbheul, son of Conall Cremhthuinn^w, and Fiachra Lonn, King of Dal Araidhe^x.

Eoghan

gistrum Mancenum, virum religiosum et optimè in scripturis sanctis exercitatum, (Jocelin, c. 59) ille præfecisse legitur."—*Primordia*, p. 864. For some account of the acts of St. Patrick in the country of Tirawley and the neighbouring districts, see Addenda to this volume.

^t *Oilioll Molt*.—This monarch died in the year 483, and had been, therefore, raised to the throne of Connaught in the year 443 ; from which it would appear that Amhalgaidh must have resigned the sceptre of Connaught to him six years before his death.

^u *Lughaidh, son of Laoghaire*.—He succeeded Oilioll Molt as monarch of Ireland

in the year 483, and died, according to O'Flaherty, in 508.

^v *Muircheartach*.—This was the celebrated Muircheartach Mor Mac Earca,—the great grandson of Niall of the Nine Hostages,—who became monarch of Ireland in the year 513, and reigned twenty-one years.—See Annals of Tighernach, and O'Flaherty's *Ogygia*, p. iii. c. 93.

^w *Fergus Ceirrbheul, son of Conall Cremhthuinn*.—He was the grandson of Niall of the Nine Hostages, and the father of the monarch Diarmaid, who succeeded in the year 544.

^x *Fiachra Lonn, King of Dal Araidhe*.—He is mentioned in the Annals of the

Eogan beul, mac Ceallaiḡ, mic Oililla Muile, 36 bliadhna i
riḡe Connaḡt, ḡo v-topḡair i ḡ-caḡ Sligiḡe re Fearḡur aḡur re
Domnall dá mac Mhuirḡearḡaiḡ mic Earca.

Oilill Iarbanna, no Anbanna, mac Muirḡeadoiḡ, mic Eoḡain
bel, mic Ceallaiḡ, mic Oililla Muile, naoi m-bliadhna, ḡo v-top-
ḡair la h-Aoḡ, mac Eataḡ Tioḡmḡarna, do riol bhiḡain, mic
Eataḡ Muirḡeadoiḡ.

Colman, mac Cobḡaiḡ, mic ḡoibhinn, mic Conuill, mic Eoḡain,
mic Eataḡ bhiḡ, mic Daḡi, 21 bliadhna i riḡe, ḡur ḡuit i ḡ-caḡ
Chinnbuḡa, re Raḡallaḡ, mac Uadaḡ, mic Aoḡa.

Lairḡneḡun, mac Colmaḡn, mic Cobḡaiḡ, reaḡt m-bliadhna i riḡe
Connaḡt, ḡur ḡuit.

ḡuairḡe Aioḡne, mac Colmaḡn, mic Cobḡaiḡ, 13 bliadhna i riḡe
Connaḡt,

Four Masters at the year 478, under which the following notice of the battle of Ocha is given :—"A. D. 478. Oilíoll Molt, the son of Dathi, son of Fiachra, after having been twenty years on the throne of Ireland, was slain in the battle of Ocha by Lughaidh, the son of Laoghaire, Muir-cheartach Mac Earca, Fergus Cerbhel, son of Conall Cremthainne, Fiachra Lonn, son of Laoghaire, King of Dal n-Araidhe, and Cremhthann, son of Enna Cennsellach, King of Leinster. It was on this occasion that the territories of Lee and Cairloegh were given to Fiachra, as a territorial reward for [his services in] the battle." The reader is referred to the *Rerum Hibernicarum Scriptores*, vol. iii. pp. 126, 127, for a strange translation of this plain passage, and for additional references to the battle of Ocha. The country of Dal

Araidhe, of which Fiachra Lonn was king, extended, according to the ancient Irish authorities, from Newry to the mountain Mis, now Slemmish, in the county of Antrim, and the territory of Lee, which he got as a reward for his services in the battle, was situated on the west side of the river Bann, in the present county of Londonderry.

¹ *The battle of Sligeach*, i. e. of Sligo. This battle was fought, according to the Four Masters, in the year 537, at which year, they add, that Fergus and Domhnall were assisted in this battle by Aimmire, son of Sedna, and Ainnidh, son of Duach Galach.

² *Fergus and Domhnall*.—"They afterwards became joint monarchs of Ireland, and reigned one year, A. D. 565.

³ *Oilíoll Iorbhanna*.—According to the

Eoghan Beul, son of Ceallach, son of Oilioll Molt, was thirty years in the government of Connaught, when he fell in the battle of Sligeach⁷ by Fergus and Domhnall⁸, two sons of Muircheartach Mac Earca.

Oilioll Ianbhanna⁹, or Anbhanna, son of Muireadhach, son of Eoghan Beul, son of Ceallach, son of Oilioll Molt, nine years, when he fell by Aodh, son of Eochaidh Tiormcharna, of the race of Brian, son of Eochaidh Muighmheadhoin.

Colman, son of Cobhthach¹⁰, son of Goibhnenn, son of Conall, son of Eoghan, son of Eochaidh Breac, son of Dathi, was twenty-one years in the government of Connaught, when he fell in the battle of Ceann Bugha^c, by Raghallach, son of Uadach, son of Aodh.

Lairgneun, son of Colman^d, son of Cobhthach, was seven years in the government of Connaught when he fell.

Guaire Aidhne, son of Colman^e, son of Cobhthach, was thirteen years

Annals of the Four Masters he was slain in the battle of Cuil Conaire, in the territory of Ceara, in the year 544, by Fergus and Domhnall, the two sons of Muircheartach Mac Earca. Their words are:—
“A. D. 544. The battle of Cuil Conaire, in Ceara, was fought by Fergus and Domhnall, the two sons of Muircheartach Mac Earca, against Ailill Inbanda, King of Connaught, and Aodh Fortamhail, in which Ailill and Aodh were slain.”

^b *Colman, son of Cobhthach.*—He was the father of the celebrated Guaire Aidhne, King of Connaught, and ancestor of the O’Heynes and other families in South Hy-Fiachrach; but, strange to say, there is no notice of him in the Irish Annals.

^c *Ceann Bugha*, now Cambo, recte Canboe, near Roscommon. The Editor has not been able to discover the date of this battle in the authentic annals.

^d *Lairgneun, son of Colman.*—The Four Masters have collected no notice of this king.

^e *Guaire Aidhne, son of Colman.*—This is the renowned Guaire, King of Connaught, who is celebrated by the Irish poets as the very personification of hospitality and generosity. The reader will find several stories relating to him in Keating’s History of Ireland, reign of Conall and Ceallach. He was defeated in the battle of Carn Conaill, in his own territory of Aidhne, in the year 645, by

Connaé, gur éug go h-aítrígeac, agur po h-aónaicead i g-Cluain Mec Noir go n-onóir agur airmidom móir.

Duncad Muirge, mac Tiobraid, mic Maoilbuid (no Maoilbuid), mic Fiacraí Calgaig, mic Daí, mic Fiacraí, ceirre bliadna i n-ge Connac, gur éir i g-caé Corunn re Feargur, cigeanna Chinel Chairbre.

Feargal Aíone, mac Arégaile, mic Gúire Aíone, mic Colmáin, i3 bliadna, gur éug.

Inbreacac, mac Duncada Muirge, mic Tiobraid, da bliadain do i n-ge, gur éir re Feargal, mac Loinnig, cigeanna Chinel Conuill, agur re Feargal, mac Maoilbuid, cigeanna Chinéol Eogain.

Oíll, mac Ionniacraig, mic Duncada Muirge, oé m-bliadna do i n-ge Connac, go n-eapbailt, iap n-deag-beataid.

Donnacraig,

Diarmaid, son of King Aodh Slaine. Our authorities differ materially in the year of Guaire's death, but the true year seems to be 662, though Colgan, in giving the life of his cotemporary, St. Colman Mac Duach, *Acta Sanctorum*, p. 219, n. 39, says that he died in 642. Dr. O'Connor, in a note upon the entry of his death in the Annals of the Four Masters, at the year 662, gives a list of the Kings of Connaught of the Hy-Fiachrach race down to Guaire, in which he omits Lairgneun, son of Colman, mentioned above in Note ^d. Dr. O'Connor here says that Keating errs in calling St. Colman the brother of King Guaire Aidhne, but he should have known that Keating himself does not call him so, although his translator ignorantly does ;

for the word bráear, which he uses, meant in his time, and still means all over the south of Ireland, not brother, but cousin or kinsman ; and whether this be its original meaning or not, we should not find fault with the honest Keating for using a word in the sense which was its ordinary signification in his own time.

^f *Dunchadh Muirge*, i. e. Dunchadh of Muirisg, a district in the north of Tireragh, county of Sligo. The death of this prince is noticed by the Four Masters under the year 681, as follows :—"A. D. 681. Dunchadh Muirisce, son of Maoldubh, King of Connaught, was slain in the battle of Corann, in which were also slain Colga, son of Blathmac, and Fergus, son of Maolduin, chief of Cinel Cairbre."

years in the government of Connaught when he died penitently, and was interred at Clonmacnoise with great honour and veneration.

Dunchadh Muirsge^f, son of Tiobraidhe, son of Maolduin (or Maoldubh), son of Fiachra Ealgach, son of Dathi, son of Fiachra, was four years in the government of Connaught, when he fell in the battle of Corann by Fergus, lord of Cinel Cairbre.

Feargal of Aidhne^f, son of Artghal, son of Guaire Aidhne, son of Colman, thirteen years, when he died.

Innreachtach, son of Dunchadh Muirsge^b, son of Tiobradhe, was two years in the government of Connaught, when he fell by Feargal, son of Loingseach, lord of Cinel Conaill, and by Feargal, son of Maolduin, lord of Cinel Eoghain.

Oilioll, son of Innreachtach¹, son of Dunchadh Muirsge, was eight years in the government of Connaught when he died, after *having spent* a virtuous life.

Donncathaigh,

^f *Feargal of Aidhne.*—The Four Masters place his death at the year 694, but they state incorrectly that he was the son of Guaire Aidhne. "A. D. 694. Feargal Aidhne, King of Connaught, died. He was the son" [*rectè* grandson] "of Guaire Aidhne."—See Book of Lecan, fol. 80, p. b, and pp. 61, 62, 63 of this volume, where the true pedigree of this king will be found.

^b *Innreachtach, son of Dunchadh Muirsge.* According to a notice inserted in a modern hand into the Stowe copy of the Annals of the Four Masters, at the year 718, this king was slain in the battle of Almuin, fought in that year between the monarch Feargal, son of Maolduin, and Dunchadh,

King of Leinster; but this interpolation is not correct according to our text.

¹ *Oilioll, son of Innreachtach.*—The date of his death is not given in the Annals of the Four Masters, nor in any other annals accessible to the Editor. At the year 719 the Four Masters enter the death of Innreachtach, son of Muiredhach, King of Connaught; at 722 that of Domhnall, son of Ceallach, King of Connaught; at 730, that of Cathal, son of Muiredhach, King of Connaught; at 737, that of Aodh Balbh, son of Innreachtach, King of Connaught; at 738, that of Ceallach, son of Rogallach, King of Connaught; at 751, that of Fergus, son of Ceallach, King of Connaught, and the same entry is repeated

Donncaataig, mac Cathail, mic Oililla, mic Duncada Muirge,
15 bliadhna, gur eug.

Բլաւրի, մա՛հ Ծոմնուլլ, յօ ի՛նչ Զարե, ցե՛րք եւա՛ծնա յօ Ի ռիճե
 Ըննա՛ճ, ճըր եւճ ճօ հ-աւրիճեա՛ճ.

Πλαίτηρ ele δά βλιαδαιν ι ριζε Connaçt, zo po épég a ρίζε ap
 Dia, agur do cóid zo h-l Choluum Cille, do deunam epábad, zo po
 euz innre ι n-a oiliépe, iar m-breç buadā ó doman agur ó deamān.
 Feç leatānāç 259, 260.

[Clanna Fiaclaíac neamháite, trá, anallana, baò moira raeta
a Ríog agus a naom, mar ar léir iir in leabhar ra, gur lingeadar
eactrainn agus Eneannaiğ fén porro,—dail blígteac De òingior
ríor ar a rúide Ríogh na h-ápo-plaite uairbige imrío a n-ancu-
mácta; iarr an Sean-focal ra, “Ceart cáig a mail a neart,” tper a
n-gabaid glóir raogalta, agus neam-glóir neamda. Sompla ar
rin rinríor na n-Đaoideal uile a g-coirtinn re a g-coibnearaib a
nallana, dar beanrao do bunao Alba do Cruicrib, agus do
Đheacrauib,

under the year 759 ; and at 763 they enter the death of Dubhinrecht, son of Cathal, King of Connaught. These kings were, however, all of the Hy-Briuin line, and it is very much to be doubted that Oilioll, son of Innreachtach, of the race of Fiachra, had room to step in between them, and it is not improbable that he was King of Lower Connaught only.

Donnecathaigh, son of Cathal.—His death is entered in the Annals of the Four Masters at the year 768.

^k *Flaithri, son of Domhnall*.—The death of Flaithri mac Domhnaill, King of Connaught, is entered in the *Annals* of the *Four Masters* under the year 768.

¹ *Another Flaithri*.—His death is entered in the *Annals of the Four Masters* under the year 774.

^m *Of the Clann Fiachrach aforesaid.*—All this passage enclosed in brackets is an after insertion by our author into his larger work in the year 1664.

ⁿ *Strangers and the Irish themselves.*—The O'Conors of Sligo, the Burkes, and Barretts were the principal families that crippled the power of the O'Dowds. In the year 1581 O'Connor Sligo claimed jurisdiction over that tract of country extending from Magh g-Ceidne and the river Drowes, which separates Connaught from Ulster, to Ceis Corainn, in the county of Sligo,

Donncathaigh, son of Cathal^l, son of Oilioll, son of Dunchadh Muirsge, fifteen years, when he died.

Flaithri, son of Domhnall^k, of the race of Guaire, was four years in the government of Connaught, when he died penitently.

Another Flaithri^l was two years in the government of Connaught, when he resigned his kingdom for God, and went to Hy-Columbkille to apply himself to devotion, where he died on his pilgrimage victorious over the world and the devil.—See pages 259, 260 [of Duaid Mac Firbis's genealogical book].

[Of the Clann Fiachrach aforesaid^m, in ancient times, great was the prosperity of the kings and saints, as is obvious in this book, until strangers, and the Irish themselvesⁿ, attacked them, *according to the righteous decrees of God*, who hurls down from their kingly thrones the proud monarchs, who exercise their tyrannical power; according to the old saying, "the right of every one is according to his strength," by which they assume earthly glory and heavenly ingloriousness. An example of this is afforded by the ancestors of the Gaels, who were in ancient times at strife with their neighbours, when they took Alba from the Cruithni and the Britons^o, and who were

and from the river Moy eastwards to the boundary of O'Rourke's country, in the county of Leitrim. — See *Annals of the Four Masters*, ad ann. 1581. If this be true he was lord of all O'Dowd's country in this year. But, according to the *Historia Familiæ De Burgo*, preserved in the MS. Library of Trinity College, Dublin, Cathal Dubh O'Dowd, who was the chief of the family about this period, paid a tribute of five marks a year to the Lower Mac William, as a *cíor corann*, i. e. rent of defence, or protection.—See Addenda.

^o *When they took Alba from the Cruithni and Britons.*—According to Irish history an Irish colony was planted in Scotland, then called Alba, under Cairbre Riada, about the middle of the third century; and in the year 504 a more numerous colony from Ireland migrated thither under the conduct of the sons of Erek, whose descendants became, in course of time, so powerful that in the reign of Kineth Mac Alpin, in the ninth century, they totally subdued and obtained dominion over the Pictish nation.

dhreacnuib, nár lór leó rin gan rioḡac̃ta iom̃a ele do ionraig̃ib, mar do rine Niall Naoigiallaḡ, agur apoile, agur fó̃r Daḡi, mac Fiaḡpaḡ neam̃raite, do ionraig̃ Alba, dhreatain, Típe ḡall, .i. Fpaingc̃ 7c. agur ḡo Sliab Alpa, mar ar lér linn anu iḡríob̃ta a c̃aitẽpém, ir na crioḡaib rin, a ḡar agur a aḡnacal, amuil d'p̃águib Torna Eḡear na diaig̃, do m̃air 1 n-aimẽrin Dhaḡi, agur do c̃uir-riob eoluiḡ ele an ḡ-céona 1 ḡ-cuim̃ne 1 raoḡaluib ráine iar rin. Uair Plann agur Eoc̃uib Eolaḡ Ua Cérín, ar-iaḡ po éionóil na neḡe rin á leab̃ar Eoc̃aḡa Uí Phlannaḡain 1 n-Ár̃o Maḡa, agur á luḡbar Maimẽr̃oeaḡ, agur ar na leḡraib toḡaib̃e ele, .i. ar an Leḡbar m-ḡuib̃e, teap̃a ir in ḡ-carcair Ár̃o Maḡa, agur ar an Leab̃ar ḡeárin baol 1 Maimẽr̃uib, ar e ruḡ an mac leḡinn lẽr tap m̃uir 1 n-ḡoib, agur ni f̃riḡ m̃am̃, 7c.

Miri

^p *Niall of the Nine Hostages.* — All our writers agree that this monarch infested Britain and the coasts of Gaul, following in the track of his predecessor, Criomthann Mor Mac Fidaigh, who planted a colony of Munstermen in Wales. The devastations of Niall in Britain are thus referred to in a very ancient life of St. Patrick, formerly in the possession of Archbishop Ussher, who gave the following quotation from it in his *Primordia*, p. 587 :—“*Scoti de Hiberniā sub rege suo Neill Næigiallach multum diversas provincias Britannię contra Romanum Imperium, regnante Constantio filio Constantini, devastabant : contendere incipientes Aquilonalem plagam Britannię. Et post tempus, bellis et classibus Hibernienses expulerunt habitatores terrę illius ; et habitaverunt ipsi ibi.*”

The devastations of Niall in Britain and Gaul are thus alluded to by Mr. Moore, who justly considers this within the authentic period of Irish history :—“The tottering state of the Roman dominion in Gaul, as well as in every other quarter, at this period, encouraged the hero of the Nine Hostages to extend his enterprises to the coast of Britany, where, after ravaging all the maritime districts of the north-west of Gaul, he was at length assassinated, with a poisoned arrow, by one of his own followers, near the Portus Iccius, not far, it is supposed, from the site of the present Boulogne. It was in the course of this predatory expedition that, in one of their descents on the coast of Armoric Gaul the soldiers of Niall carried off with them, among other captives, a youth then in his sixteenth year, whom Providence had des-

were not satisfied with this, without invading many other countries, as did Niall of the Nine Hostages^p and others, and also Dathi, son of Fiachra above mentioned, who invaded Alba, Britain, the country of the Gauls, i. e. France, &c., and as far as the mountain of the Alps^q, for his triumphs are obvious to us at this day, as also his death and burial, as Torna Eigeas^r, who lived in the time of Dathi, left written after him, and other learned men have, in successive ages, transmitted a memorial of the same. For it was Flann^s and Eochaidh Eolach O'Ceirín^t that collected these things from the book of Eochaidh O'Flannagan^u, at Armagh, and from the book of the Monastery^v, and other choice books, such as the Yellow Book^w, which was missed out of the prison at Armagh, and from the Leabhar Gearr^x, which was at Mainister, and which the student carried with him by stealth over the sea, and was never discovered afterwards, &c.

I

tioned to be the author of a great religious revolution in their country; and whom the strangely fated land to which he was then borne, a stranger and a slave, has now, for fourteen hundred years, commemorated as its great Christian apostle."—*History of Ireland*, vol. i. p. 152.

^q *The Alps*.—*Vide supra*, pp. 17–33.

^r *Torna Eigeas*.—See pp. 25, 26, Note ^u, above.

^s *Flann*.—This is Flann, abbot of Monasterboice, in the now county of Louth, who died in the year 1056.

^t *Eochaidh Eolach O'Ceirín*, i. e. Eochy the learned, O'Kerín. The Editor has not discovered any particulars of the history of this writer.

^u *Eochaidh O'Flannagan*.—His history or period unknown to the Editor.

^v *The Book of the Monastery*.—By the monastery is here meant Mainistir Buite, now Monasterboice, in the county of Louth, in which a celebrated historical book was preserved for ages.

^w *The Yellow Book*.—The period at which this book was missed is unknown to the Editor.

^x *The Leabharr Gearr*.—A book of this name is mentioned in the Annals of the Four Masters at the year 1416, but it does not appear to be the same as that here referred to by our author. "A. D. 1416. The church of Inis mor, in Loch Gile [now Lough Gill, near Sligo] was burned, and Screaptra Uí Chuirnin [O'Curnin's manuscripts] and the Leabhar Gearr [i. e. short book] of the O'Cuirnins and many other precious articles were also burned."

Miri an Dubaltac Mac Firdirig, do rghioð na h-úgðoréair
 rin ar loig liere Lúgðac Uí Chleire na h-íomarbaidé, aét cib-
 ionnur gur fearmóin rsoğalta map bavar Gaoiðil in ionbuid rin
 ag gabáil na g-críoc i g-cén ir a b-fogur, agur gan áit a adnacail
 o'á fearonn ag an céadmað buine do uairlib Gaoiðeal amu, gé
 atá a rúil ler anoir ir in m-bliadain ri, 1664.

Ní h-í ro locc aimir an leabair ri aét teaglam do cúipear
 ler aétad iaram.]

¹ Lughaidh O'Clery of the Contention.—

For some account of this Lughaidh see pp. 82, 83, Note ¹, of this volume. He is styled "of the Contention," because he acted a conspicuous part in the contention which took place between the poets of the northern and southern parts of Ireland in the beginning of the seventeenth century. The account of the authorities above referred to is given nearly the same as in our text in *Leabhar na h-Uidhri*, which must have been in the possession of Lughaidh O'Clery as O'Donnell's chief historian, and it is not improbable that he had made a copy of that book, as our author quotes this passage from his handwriting.

² Conquering the countries far and near.—

This humiliating observation of our author shows the subdued tone of the Irish people at this period, and there can be little doubt that many of them were then in the habit of acknowledging that their downfall was caused by the just visitation of heaven, in consequence of the ambition and cruelty of their ancestors. The idea was taken hold of by Sir Richard Cox, who flourished not long after this period, to prove the just causes King Henry II. of England had for invading Ireland. This writer observes, "But however that were" [i. e. the granting of Ireland by the King of the Britons to the sons of Milesius], "yet the King had just Cause of War against the Irish, because of the Pyracies

I am Dubhaltach Mac Firbisigh, who transcribed these authorities from the hand-writing of Lughaidh O'Clery of the Contention⁷. It is no doubt a worldly lesson to consider how the Gaels were at this time conquering the countries far and near^a, and that not one in a hundred of the Irish nobles, at this day, possesses as much of his land as he could be buried in^a, though they expect it in this year, 1664^b.

This is not the time or place of compiling this book, but this extract I have added some time after.]

and Outrages they daily committed against his subjects, and the barbarous cruelties they exercised on the English whensoever they fell in their Power, buying and selling them as slaves, and using Turkish Tyranny over their bodies, so that the *Irish* themselves afterwards acknowledged, That it was just their Land should be transferr'd to the Nation they had so cruelly handled. Wherefore the King, as well to revenge those injuries, as to recover that Kingdom, put on a resolution to invade it."—*Hibernia Anglicana*, pp. 1, 2.

^a *As much of his land as he could be buried in.*—This, and many other strong

passages to the same effect, show that the Irish in our author's time were in an awful state of destitution, and it is highly probable that he himself was begging from door to door at the time that he inserted this passage.

^b *They expect it in this year, 1664.*—It appears from the marriage articles of David Oge O'Dowda, drawn up in the year 1656, to which our author was a subscribing witness, that the O'Dowds had then strong expectations of being restored to their estates.—See more on this subject in the pedigree of O'Dowda, in the Adenda to this volume.

DO DHREACTHNUIDH

I N-16h amhaizaidh mic fíachrach.



DO BHREATHNUÍBH I N-ÍBH AMHAUZAIÖH MIC FÍACHRACh,

Sliocht oile ann ro á leabrais Chloinne Fhíbhírig.

epe Fíonn bheathnách, dearbhácar Uilliam Fínn
Chille Comáin, re ráitear Uilliam Mór na
Maigne; an Laigleiríoch; Clann an Fhailge; Seóairg
éar Chonnaic; Clann héil, Meg Uigilin an Rúta;
c bhailiríoch; bairídirg na Múnan; Mac bhairín
, ó d-táir bairéaduirg Tíre Amalgair; Clann
Toimín Iorruir; Clann Ainríu an bhair; Clann Ricín, .i. Ricín
Og,

The ornamented initial letter R is taken from the Book of Kells, fol. 92.

^a This portion of the work contains indigested gleanings made by our author from the manuscripts of his ancestors.

^{aa} *The White Knight*.—The Irish annals preserve no notice of this personage.

^b *William Fíonn*, i. e. the Fair. He is elsewhere called William Breathnach, or

Walsh, by our author; but he was unquestionably the head of the Barretts, and it is therefore probable that Breathnach, as applied to him, means Welshman.

^c *Cill Comáin*.—There are two places of this name in the county of Mayo, one in Erris, and the other in the barony of Kilmaine, to the east of Ballinrobe, but it is not easy to conjecture which of them is

OF THE WELSHMEN

OF

HY-AMHALGAIDH MIC FIACHRACH,

ANOTHER EXTRACT HERE FROM THE BOOKS OF THE CLANN FIBBIS^a.

HE Welshmen of Ireland were the Welsh White Knight^a, who was the brother of William Fionn^b of Cill Comain^c, who was called William Mor na Maighne^d; Laighleisioch^e, Clann an Fhailghe^f; the Seoagh^g, of the west of Connaught; the Clann Heil^h; the Mac Uighilinsⁱ of the Ruta; the Mac Bhaillseachs^j; the Baroideachs of Munster^k; Mac Bhaitin Baired^l, from whom are the Baireadachs of Tir Amhalgaidh; the Clann Toimin of Iorrus;

here alluded to.

^a *William Mor na Maighne*, William the Great of Moyne.—See Note^r, p. 326, *infra*.

^e *Laighleisioch*.—One of the family of Lawless would be called Laighleisioch by the native Irish at the present day.

^f *Clann an Fhailghe*, unknown to the Editor. There is one notice of this Welsh

tribe preserved in Mageoghegan's Translation of the Annals of Clonmacnoise at the year 1316, but no evidence has been discovered to prove where they were seated or what the surname was.

^g *The Seoagh*, i. e. the Joyces, who inhabited the barony of Ross, in the north-west of the county of Galway.

Og, mac Ricín, ó u-taib Clann Ricín; Toimilín ó u-taib Clann Toimilín; hoirbeḡ, mac Membric, ó u-taib Clann hoirbeḡ.

I n-aimpūir Gall-Shaxon do tēact i n-Éirinn le Diarmuid Mac Murchada,

^a *The Clann Heil*, i. e. the descendants of Hoel, or Howell. *Quere*, if this be not the name now anglicised Mac Hale, which is still numerous in Tirawley?

¹ *The Mac Uighilins*, i. e. the Mac Quilins, who inhabited the Rout, in the north of the present county of Antrim. The name is supposed to be a corruption of Mac Lhlewellin.

² *The Mac Bhailisiochs*. — See p. 126, Note ^b, of this volume.

³ *Baroideachs of Munster*, i. e. the Barretts of Munster. The district which they possessed still retains their name, and is situated in the county of Cork, to the north-west of the city.

⁴ *Mac Bhaitin Bared*, i. e. Mac Wattin Barrett. The head of the Barretts of Tirawley took that Irish appellation from an ancestor called Wattin, or little Walter. It is curious to remark that the name Barrett is, in Munster, called in Irish Óápóio, and in Connaught Óaipéao.

^m *The Clann Toimin of Iorris*. — This was the clan name of a branch of the Barretts who were seated in the barony of Erris, in Mayo.

ⁿ *Clann Aindriu*. — This was the name of another branch of the Barretts of Tirawley, who were seated in the district called the Two Bacs, lying between Lough Conn and the river Moy. The name is

now anglicised Mac Andrew, and is very common in the district.

^o *Clann Ricin*, unknown to the Editor. It was probably the local name of a sept of the Barretts.

^p *Clann Toimilin*, now Tomlyn.

^q *Clann Hostegh*. — This name is still common in the counties of Mayo and Galway, where it is always anglicised Hosty. According to the tradition in the country, Hosty, the ancestor of this Welsh family, was the original builder of the castle of Dunmore, below Tuam, from which he was afterwards driven by the family of Bermingham.

^r *At the time of the arrival of the English*. — This, with a part of the succeeding paragraph, is very imperfectly written, as appears from the facts recorded in the succeeding part of the narrative. It should have been stated thus: — “It was at the time of the arrival of the English into Ireland with Diarmaid Mac Murchadha, King of Leinster, that the families above enumerated came to Ireland. They landed in Tirawley, and attempted to wrest the territory by force from the race of Fiachra, and, according to some writers, succeeded in doing so. About a century afterwards the four families following, namely, the Cusacks, Petits, Browns, and Moores landed in Tirawley, and essayed

Iorrus^m; the Clann Aindriu of Bacⁿ; the Clann Ricin^o, *who descend from Ricin Og*, son of Ricin; Toimilin, from whom are the Clann Toimilin^p; Hosdegh, son of Membhric, from whom are the Clann Hosdegh^a.

It was at the time of the arrival of the English^r in Ireland with
Diarmaid

to take that territory from these Welsh tribes. They fortified themselves at a place called Mileac an locha, where they erected a strong castle in which they kept a ward. When the Welsh settlers of Tirawley had perceived their intentions of conquest, they sent word to William Fionn of Kilcommon, afterwards known as William Mor na Maighne, who had been for a long time previously the president and defender of his kinsmen in Tirawley, to remonstrate with him about the maraudings of the new invaders, and William sent letters to the invaders ordering them to desist from their designs and quit the territory, or meet him in battle, and the result was," &c. &c., as in the text.

Though it is stated here on the authority of the books of the Mac Firbises, that these Welsh tribes landed in Tirawley and wrested that territory from the Hy-Fiachrach at the period of the English invasion; it is, nevertheless, not true that they drove out the Hy-Fiachrach so early, and it may be rationally suspected that they did not land in Tirawley for near a century later. To prove that the Hy-Fiachrach were not driven out we have the testimony of the

authentic Irish annals, which show that the native chiefs of the Hy-Fiachrach race were in possession of Tirawley in the middle of the thirteenth century, as will appear from the following entries in the Annals of the Four Masters :

"A. D. 1217. Cathal Fionn O'Lachtna, chief of the Two Bacs, was treacherously slain in his own house by O'Flynn of Magh h-Eleog.

"A. D. 1251. Flann O'Lachtain, chief of the Two Bacs, died.

"A. D. 1267. Aodh O'Muireadhaigh [O'Murray], chief of the Lagan, was slain at Killala by O'Maolfoghmbhair, comharba of the church, on Sunday after hearing mass.

"A. D. 1268. Aongus O'Maolfoghmbhair was slain by the O'Muireadhaighs [O'Murrays] in revenge for the death of their chief.

"A. D. 1269. Flaithbheartach O'Maoilfhiona [Flaherty O'Molina], chief of half the territory of Calraighe Muighe h-Eleog, was slain by O'Gaibhtheachain [O'Gaughan], chief of the other half.

"A. D. 1274. Fergal O'Caithniadh, lord of Iorrus, died in Hy-Mac Caechain."

From these passages it can be fairly in-

Murcaba, Ríð Laiðean, táinig an dromg peampráite go h-Eirinn, agus gabuio cuan i d-Tír Amalgaid míc Fiacraic, agus mar an g-ceudna do gabrad Ciorógaid, Petric, Brunuic, agus Muruic, ceirne fineadaca iadribe, agus do cairgriob na ceirne fineada rin an tír do gabáil ar éigin ar Chlannuib Fiacraic, agus avel phioct ele gur gabadar na fineada rin oppa í.

baoi Uilliam Fionn Chille Comain (.i. Uilliam Mor na Maighe), ór cionn Tíre Amalgaid real pava peme rin, mar uactarán d'a cúmbac. Acasoinio luét an tíre an foirneart rin pe h-Uilliam, agus cuirir Uilliam lircadaca gur na Galluib rin d'a ráo riu corc d'a n-olc, agus an tír do rágbáil, nó a pceagha im cat; agus de rin cuirtear cat mór na Maighe etorra, gur muid ar na Galluib rin, gur éuit an Ciorógac ann go n-iomad d'a muintir, agus do na Galluib bádar apasoir. Conad de rin ráitear Uilliam mór na Maighe riu in Uilliam rin. Ionraigir Uilliam iarum áit a rabadar dromg do na Galluib rin ag bárdacé, agus ag cornam an tíre,

ferred that the Barretts had made no conquest in Tirawley or Erris till the time of William Mor of the battle of Moyne, and that he may have invaded Tirawley and Erris some fifteen years before his death in 1282.

^a *Cissogachs*, i. e. the Cusacks.

^c *Petit*, now written Petty.

^u *Brunachs*.—The Brownes are still so called in Irish, and the name was often Latinized Brunus.

^v *Murachs*, i. e. the Moores.

^w *Battle of Maighin*, of Moyne, near the mouth of the river Moy, in the parish of Killala, where are the ruins of a beautiful abbey, built in the year 1460. According

to the *Historia Familiæ De Burgo* this battle was fought in the year 1281. “Bellum apud Mayn de Kilro per Adam Cymsoq [Cusack] ex unâ parte, et William Bareth ex ulterâ parte, ubi vulneratus et captus est idem William. Et postea de hiis vulneribus mortuus fuit. Adam Fleming et multi alii” [*occisi sunt*]. The place here called Kilro retains that name to this day, and is remarkable for the remains of an old church erected in the time of St. Patrick. Moyne adjoins it to the south-east. In Grace's Annals this occurrence is entered under the year 1281, thus:—“Adam Cusacke Junior interfecit Gulielmum Baret et alios quamplures in Con-

Diarmaid Mac Murchadha, King of Leinster, that the people aforesaid came to Ireland; they landed in Tir Amhalgaidh Mic Fiachrach [*now Tirawley*], as did likewise [*some time after*] these four tribes, namely, Ciosogachs', Petits', Brunachs", and Murachs', and these four tribes assayed to wrest the territory by force from the race of Fiachra; and another authority adds, that these tribes did wrest it from them.

William Fionn of Cill Comain (i. e. William Mor na Maighne) had been for a long time before this as a president over Tir Amhalgaidh guarding it. The natives of this territory remonstrated with this William about this oppression, and William sends letters to these strangers, telling them to desist from their evil deeds, and quit the country, or meet him in battle; the result was, that the great battle of Maighin" [*now Moyne*] was fought between them, in which the strangers [*i. e. new invaders*] were defeated, and in which fell the Ciosogach with many of his people*. Hence this William was called William Mor na Maighne. William afterwards attacks the place where a party of these strangers had a ward to defend the country, namely, the

nacia." The Four Masters have the following notice of this battle under the year 1281, but without naming the place:—"A. D. 1281. A battle was fought between the Barretts and Cusack, in which the Barretts were defeated with the loss of William Barrett, Adam Fleming, and many others. Cusack was assisted in this contest by two of the Irish, viz., Taithleach O'Boyle, and Taithleach O'Dowd, both renowned for their bravery and valour in battle and their agility and dexterity at arms." This passage is also

given under the same year in Mageoghegan's translation of the Annals of Clonmacnoise.

* *In which fell the Ciosogach*.—This is undoubtedly incorrect, for the Ciosogach, or head of the Cusacks, was not slain in this battle. In the next year he turned his arms against his friend Taithleach O'Dowd, whom he slew at Bel atha Tailtigh, on the margin of the great strand of Traigh Eothuile, and he fought Maghnus O'Connor in the year 1285, and died, according to the Four Masters, in the year 1287.

τίρη, .i. Cuirte mór Mhíleac an loá. Gabuir an cúirt orra, agur ionarbuir iad uile erce, agur pannuir an tior iarum eoir a bráirib fén, agur tug do Mhac dhaitir dhairéad an cúirt, agur an tior uile [agur taid ag a rliocht] ó ta rion gur amu. Sonad é Mac dhaitín atá 'n a tírat agur 'n a tígearna or a g-cionn gur antan ro.

Shíocht ele a der Uilliam Mór d'breathnác rir in Uilliam peamráite, per túit an Cíorógad peamráite, agur an tan do ronat Cairlén na ceirci lar an Uilliam Mór (d'breathnác) ro na Maighe, do rionn ré an tior eoir a dhaitíreacá bunuio fén. Tug ar túr Gleann Oirdeg do Oirdec, mac Meirc (no Membric), agur Gleann Némtenne

^y *Mileac of the lake*, now Meelick, a townland in the parish of Killala, in the barony of Tirawley, a short distance to the north-west of Moyne, where this battle was fought. The ruins of a castle are still to be seen here.—See Ordnance Map of the County of Mayo, sheet 22.

^z *He took the court from them*.—This is evidently false history; but it is very probable that William Mor of Moyne had made the distribution of the lands here mentioned several years before Adam Cusack had made any descent upon Tirawley. . Indeed it is clear that this must have been the case, for Hosty Merrick, one of those who got a share of the lands mentioned, was slain, according to the Irish annals, in 1272, ten years before the battle of Moyne was fought. This account of the conquest of Adam Cusack by William Mor Barrett, was evidently a vague traditional story, penned by one of the Mac Fimbises to flatter the pride of the Mac Watin Barrett of the day; but it cannot be

received for true history, as all the authentic annals are in direct opposition to it.

^a *William Mor Breathnach*.—Breathnach is the usual name by which the Irish, even at the present day, call the family of Walsh; but the William Mor of the battle of Moyne, here referred to, was the head of the Barretts. Our author, in giving the pedigree of the family of Walsh, on the authority of Laurence Walsh, who wrote in 1588, states that Walynus, the progenitor of the family of Walsh, and Barrett, the progenitor of the Barretts, were brothers, and the sons of Guyndally, high steward of the lordship of the house of Camelot, and that Walynus came to Ireland with Maurice Fitzgerald, a lieutenant of fifty archers and fifty foot, in the year 1169, and that some of his descendants had adhered to the descendants of said Maurice to Laurence Walsh's time (1588). It is not, therefore, to be wondered at, that some old Irish writers should have styled William Mor Barrett

the great Court of Mileac of the lake⁷. He took the court from them², drives them all from it, and then divides the territory between his own kinsmen; he gave to Mac Bhaitin Baired the court, and all the territory which his family have retained from that day till this, so that he, Mac Bhaitin, is chief and lord over them to this present time.

Another authority gives the name of William Mor Breathnach^a to the William aforesaid, by whom fell Cusack^b aforesaid, and states that when Caislen na Circe^c was erected by this William Mor Breathnach na Maighne he divided the country among kinsmen of his tribe. He gave, first, Gleann Oisdegh^d to Osdec Mac Meric^e (or Membric);

of the battle of Moyne by the cognomen of Breathnach, which may have meant simply "The Welshman," for Breathnach in Irish means Brittanicus, and to the present day denotes Welsh, i. e. belonging to Wales, as well as a Welshman, and one of the family called Walsh.

^b *By whom fell Cusack.*—This clause should be reversed, and written "who fell by Cusack;" the error is possibly owing to the ignorance of some transcriber; but it is extraordinary that our learned author did not correct so gross a blunder. "Miror doctum Dualdum Firbisium ita errasse!" as Dr. O'Connor says in reference to another oversight of our author.

^c *When Caislen na Circe was erected by this William.*—This is not the Caislen na Circe in Lough Corrib—(which had been erected, according to the Annals of the Four Masters, before 1233, "by the power of the sons of King Roderic O'Connor and Mac William Burke")—but Castle-Kirk,

in Lough Carra, not many miles from Kilcommon, where this William Mor Barrett of the battle of Moyne seems to have resided. The erection of this castle then may fairly be attributed to about the year 1266, which is therefore the true period of the descent of the Welsh families upon the territory of Tirawley, not, as stated by our author, 1169 or 1172, when the English first came over to assist the King of Leinster.

^d *Gleann Oisdegh.*—This place is still well known, and is anglicised Glenhest. It is a valley district, west of Glen Nephin, partly in the barony of Burrishoole and partly in that of Tirawley, in the county of Mayo. It is divided from Glen Nephin by the Boghadoon river, and lies between Lough Feeagh, which bounds it on the west, and Beltraw lough, which bounds it on the south-east.—See Balds' Map of Mayo, and Ordnance Map.

^e *Osdec Mac Meric.*—He is still vividly

Néménne do Ricín, agus an dá dhac do Shíu Maigiu an dhac, ó b-puil Clann Ainorui dairé. Tug ó Phearraio Tperi go Traig Murbaiú do Shíu Uilliam Laiglé, .i. an Laigleirí, agus coméad agus cornam triocáid céo lorrui ag Toimín, agus ag Philip, no Philpín, .i. mac mec deardrátar do Thoimín an Philip, no an Pílpín rín, agus ar a ríocht atá Mac Philib, no Philbín, agus ar uad tángadar clann Philib, no Philbín; ní mearta gur ob é an Philpín céo go duncacuib. Síu Uilliam Laiglé, mac Roibé, mic Uilliam, mic Niocláir, ainm an Laigleirí d'a d-tug Uilliam Mór na Maighe an fearann ra, .i. ó Phearraio Tperi go Traig Murbaiú.

Clann Mec Roibé a dubhadar luét an fórmáid agus an aineoluir eatorra fén gur do ríocht Domnuill lorrui Uí Chon-cabair dóib, acé adar Mac Phirbúirí, .i. Sémur, mac Diarmada,
nac

remembered in the tradition of the country, according to which the Hoiste, after whom Gleann Hoiste was called, was slain and beheaded by one of the O'Malleys after he had nearly exterminated the whole of that family; but, strange to say, this tradition states that he was one of the Danes, and flourished during the tyrannical sway of that people in Ireland before the period of the battle of Clontarf! This affords a striking instance of the fallacy of oral tradition as a chronicler of events, for, according to the Annals of the Four Masters, Hoitsi Mebric (Hosty Merrick) and his neighbour, Henry Butler, lord of Umhall [O'Malley's country] were slain by Cathal, son of Conor Roe O'Conor, and the sons of Muirheartach O'Conor, in the year 1272. In Mageoghegan's translation of the Annals of Clonmacnoise this

passage is given as follows:—"A. D. 1272. Henry Butler, lord of the territory of Omaille and Hodge Mebric, were killed by Cahall Mac Connor Roe and some of the Irish Nobilitie of Connaught." The family name Merrick is still in this neighbourhood, and a sobriquet added which cannot be mentioned here. The name Hosty is also common, of which see more above, p. 326, Note ^q.

^f *Gleann Nemhthenne*.—For the extent of this valley district see p. 233, Note ^m.

^g *The Two Bacs*.—For the original extent of this district, lying principally between Lough Conn and the River Moy, in Tirawley, see p. 232, Note ^k.

^h *Sir Maigiu*, i. e. Sir Maigiu Barrett, ancestor of Mac Andrew, chief of the Two Bacs, in Tirawley. This Sir Maigiu is still vividly remembered in the traditions

Membric) ; Gleann Nemhthenne^f to Ricin, and the Two Bacs^g to Sir Maigi^h of Bac, from whom are the Clann Andrew Barrett. He gave *the tract extending* from Fearsad Tresi to Traigh Murbhaighⁱ to Sir William Lawless, i. e. the Lawless^j ; and he committed the keeping and defence of the barony of Iorrus [*Erris*] to Toimin and to Philip, or Philpin, the grandson of Toimin's brother, and of his race is Mac Philip, or Mac Philbin^k, and from him the Clann Philip, or Philbin, are descended ; and it is not to be supposed that he is the Philbin who is traced to the Burkes. Sir William Lawless, son of Robert, son of William, son of Nicholas, was the name of the Lawless to whom William Mor na Maighne^l gave this tract of land extending from Fearsad Tresi to Traigh Murbhaigh^m.

Envious and ignorant people have said between themselves that the Clann Mac Robert are of the race of Domhnall Iorruis O'Conorⁿ, but Mac Firbis, namely, James, son of Diarmaid^o, says that they are not

of the country.

¹ *From Fearsad Tresi to Traigh Murbhaigh*, i. e. the country of the Hy-Eathach Musaidhe.—See p. 232, Note ^k.

^j *The Lawless*, i. e. the head of the family of that name.

^k *Mac Philbin*.—He lived in the castle of Dun Mugdord, now Doon castle, about four miles to the east of Westport, in the county of Mayo.

^l *To whom William Mor na Maighne gave this tract of land*.—The probability is, that William Mor na Maighne had really made this distribution of the lands of Erris and Tirawley, and that the only error in this story is in stating that he made his distribution of these lands *after*

the battle of Moyne.

^m *From Fearsad Tresi to Traigh Murbhaigh*, i. e. the territory of Caeilli.—See pp. 8, 9, 224, 225, where the situation of this district is distinctly pointed out.

ⁿ *Domhnall Iorruis O'Conor*.—He was the son of Maghnus, who was the son of the celebrated Muircheartach Muimhneach O'Conor. He made great efforts to conquer Erris, and dwelt in that territory for some time, but was driven thence in the year 1273, according to the Annals of the Four Masters, which do not mention by whom, but we may well conjecture it was by William Mor Barrett of Kilcommon, who was very powerful in this district at the time.

^o *Mac Firbis, namely, James, son of Di-*

nað h-eað céana, aét mac mec do Uilliam, mic Uilliam Mhoir, na Maighe, agur ar í a n-bútaig coir Daoile i d-tír Amalgaid.

A deirid apoile gur do hepbearnaðiuib (ne raitear hepbearnaig) .i. hepbertaig a g-Condae Luimnig an clann Mec Roibeir, no Mec hepbear doir.

Sleaéta raine. Carrúnuið do éaét i n-Eirinn le rlióct Uilliam Congceir (tuig búrc) Lionóidig do éaét i n-Eirinn le rlióct an Iarla Ruaid. Slióct raine. Le rlióct Uilliam Congceir tainig Carrunaig agur do bunad Saxonaig iad, aét a deirid apoile gur do rlióct Chataoir Mhoir dóib; agur rir in Iarla Ruaid tán-gadair.

Slióct raine. Do na h-uairlib táinig anair le rlióct Uilliam Congceir, .i. Philib Mor, mac Sir beannaib Sdonbun, a quo Mac a'Mhílið Cheara, Uaiter, mac Roibeair, Sir Daibid Duilpineac, Roibeair bapóid, Sir Uilliam Carrún; coir em mar atáid búrc, bairid, agur Carrún i g-Connaétaib, atá búrc, bapóid, agur Carrún i Mumain.

Poéann teaéta búrcac i b-pearraunur i d-Tír Amalgaid.

Peaét

armaid.—See pedigree of the Mac Fimbis in p. 102. This James was evidently the compiler of the Leabhar Balbh, or Dumb Book, which is so often referred to as authority by our author.

^p *Daoil*, now anglicè Deel, a well known river in Tirawley. — *Vide supra*, p. 8, Note 5.

^q *Carrunachs*. — This is the name by which the Irish still call the Carews of Munster. For some account of this family see Smith's History of the County of Cork, vol. i. pp. 51 and 93, and vol. ii. pp. 45 and 68.

^r *William the Conqueror*, i. e. William Fitz Adelm De Burgo.—See p. 71, Note v.

^s *Lionoideachs*, i. e. the Lynotts of Tirawley.

^t *The Red Earl*.—The celebrated Richard De Burgo, Earl of Ulster, who died in the year 1326.

^u *Cathair Mor*. — He was monarch of Ireland in the latter part of the second century, and the ancestor of almost all the chieftain families of Leinster. There seems to be no truth in the assertion that the Carews are descended from him.

^v *Sdonbun*, now written Staunton.

not, but that *Robert, their ancestor*, was the grandson of William, the son of William Mor na Maighne, and their inheritance lies along the Daoil^p, in Tir Amhalgaidh.

Others say that this Clann Mac Robert, or Mac Herbert, is of the Herbeardachs (who are called Hearbardaigh), i. e. the Herberts of the county of Limerick.

From different fragments. The Carrunachs^a came to Ireland with the descendants of William the Conqueror^r (understand Burk). The Lionoideachs^r came to Ireland with the descendants of the Red Earl^l. Another authority says that the Carrunachs came with the descendants of William the Conqueror, and that they are of Saxon origin, while others say that they are of the race of Cathaoir Mor^u, and that they came with the Red Earl.

Another authority. Of the nobles who came from the East [England] with the descendants of William the Conqueror were the following, viz., Philip Mor, the son of Sir Bernard Sdondun^v a quo Mac a Mhilidh^w of Ceara, Walter Fitz Robert, Sir David Dulpin^x, Robert Baroid^y, Sir William Carrun. It is right to observe, that as there are Burc, Baired, and Carrun, in Connaught; there are Burc, Baroid, and Carrun, in Munster.

The cause of the coming of the Burkes to take possession of
lands

^w *Mac a Mhilidh*, i. e. son of the Knight. This name is still common in the barony of Carra, in the county of Mayo, and anglicised Mac Aveely, but many of the family have resumed the original name of Staunton.

^x *Dulpin*.—*Quere*, Dolphin?

^y *Baroid*.—The family of Barrett, as already remarked, is called in Irish, *Baróid*, the *o* being pronounced long, in Munster, but *Bairéad*, the *e* being long, in Con-

naught. From this it would appear that they are not the same family, and that the name of the Munster family should be properly written Barrott in English.

^z *Sgornach bhuid bhearrtha*.—This sobriquet, indicating that the steward was a glutton and a libertine, must remain concealed under the veil of the original language.

^a *Tobar na Sgornaighe*, i. e. *fons Gulæ*. This well has since run dry, but the old

Peaict dia m-báttar bairéaduib a d-creirí Thíne Amalgada (mar a dubairm), gur cuirpíod a maor d'á n-gairtí Sgórnach buio beárrta, do tógbáil éirí ar Liónóideacuib; marbuid Liónóidigh an maor rin, agus cuirpíod é iaram i d-tobar d'á n-gairítear. Tobar na Sgornnaisge, láim rin in Tharrán ár, taob éar do cairlén Carra, i d-Tír Amalgaid; ar b-fágail an rgeoil rin do dhairéadacuib, cionóid do h-arrta ar amur na Liónóideach, go rug nearc orra, gur ob í roga tugrao bairéaduib do Liónóideacuib, a b-fir do dallad no do rrocaó; conad í roga rugrao Liónóidigh, tré aile aróile reanóire doib féin, a n-dallad, do bhrí go n-giníde ó dalluib, agus nac giníde ó fearuib rrocaó. Gabuid báiréadigh do rnataduib i rúilib Liónóideac, agus gac fear mar do dalluir díob, do cuirpíod do imteact Chlocaín na n-dall láim le Carra iad, d'fior an m-beé a beag do padarc aca, agus gibe díob do imgead an clocaín go ceart, do h-at-dallta é! Acaid iaram rmuaid Liónóidigh cionnur do dígeoldaoir a n-anbpolta ar dháiréadacuib, gonad í airag meanman fuairpíod ó a rinpíod, dalta do glacaó ó'n aróile cumactac do Chloinn Uilliam dúrc, badoir ma rin ó Shliab ruar, conad cuige rin do beataigh an Liónóideac eac uaidreac, noc rugrao Liónóidigh leó do glacaó an dalta, ionnur gomad

natives of the place point out its situation to the north of an old road leading through the townland of Carn, within twenty perches of the townland of Garranard, in the parish of Moygawnagh, and barony of Tirawley.

^b *The castle of Carns.*—For the situation of this castle, and the townland of Garranard, in Tirawley, see Ordnance Map of Mayo, sheet 21.

^c *Clochan na n-dall*, i. e. the causeway or stepping-stones of the blind men. This

Clochan, or row of stepping-stones, is still pointed out near Carn Castle, in the townland of Garranard, parish of Moygawnagh, and barony of Tirawley.

^d *One derived from their ancestors*, that is, the ancestors of the Lynotts had seen that their tribe were fast sinking under the Barretts, and they instilled into the minds of their descendants that the only way in which they could check their tyranny was by adopting one of the Burkes as their leader, by means of whom they

lands in Tir Amhalgaidh. At one time when the Barretts had supremacy over Tir Amhalgaidh (as we have said), they sent their steward, who was called Sgornach bhuid bhearrtha*, to exact rents from the Lynotts. The Lynotts killed this steward, and cast his body into a well called Tobar na Sgornaighe*, near Garranard, to the west of the castle of Carns^b in Tir Amhalgaidh. When the Barretts had received intelligence of this, they assembled their armed forces and attacked the Lynotts, and subdued them. And the Barretts gave the Lynotts their choice of *two modes of punishment*, namely, to have their men either blinded or emasculated; and the Lynotts, by advice of some of the elders among them, took the choice of being blinded, because blind men could propagate their species, whereas emasculated men could not. The Barretts then thrust needles into the eyes of the Lynotts, and accordingly as each man of them was blinded, they compelled him to cross over the stepping-stones of Clochan na n-dall, near Carns^c, to see if more or less of sight remained with them, and if any of them crossed the Clochan without stumbling he was taken back and re-blinded! Some time after this the Lynotts meditated how they could revenge their animosities on the Barretts, and the contrivance which occurred to their minds,—one derived from their ancestors^d,—was to procure a *dalta*^e, [i.e. *an adopted son*], from some powerful man of the Clann William Burke, who, previously to this period, had inhabited the south of the mountain [Nephrin]; and to this end Lynott fed a spirited horse which the Lynotts took with them to receive the adopted son, in order that

might not only shake off the yoke of their oppressors, but perhaps finally subdue them.

* *A dalta*.—This word is generally used by Irish writers in the sense of an alum-

nus, a foster-son, a ward; but in this passage it cannot be understood as applied to a child to be nursed or fostered, but must be translated a ward or adopted son.

gomad é buð dalta doib an dúrcac do imriadrad an t-eac rin; go
 páinix leo mar rin Teapoid Maoil dúrc do dalta, noc do marbad
 le dáiréadacuib iarom. Conad i n-a éric rin tugattur daiρέδαix
 oet g-ceatramna deug fearoinn do dhurcadacuib; como cuio do iarri
 an Lioinódeac, oide Teapoid, do'n éric, .i. poinn na h-éarica, agur
 í poinn tug uirre, a págbail na foideadla ar fead Tine Amalgada
 uile, go m-bedir dúrcaix in gac áit innce, do doirb ar dháiréa-
 dacuib i d-Tin Amalgaid, gur beanrad a b-fearonna díob
 d'urmór; agur gur beanrad fa deoirg, anno domini. 1652, Eirix
 Saxonca Oihber Cromuell díob uile é, mar ar léir anoir gan
 dáiréadac na dúrcach, ní áirbim Clanna Fiacrac, i b-fearonnur
 dóib.

' Killed by the Barretts. — This is still
 vividly remembered in the traditions of
 the country, and the spot is pointed out
 where Teaboid Maol (i. e. the Bald) Burke
 was killed by the Barretts. The recollection
 of it has been kept alive in certain verses
 which were composed on the occasion, of
 which the following quatrains are often re-
 peated in the barony of Tyrawley.

Tángaoar dáiréadac na tíre,
 Rinneaoar gníom nac raib cearte,
 Dhoireaoar fuil do b' uairle iná an
 fíon,
 Ag feadán caol Chuinn na rac.

" The Barretts of the county came,
 They perpetrated a deed, which was not just,
 They shed blood which was nobler than wine
 At the narrow brook of Cornasack."

that the Burke who should break that steed might be their adopted son. And thus they obtained Teaboid Maol Burke as an adopted son, who was afterwards killed by the Barretts^f. So that it was in eric for him that the Barretts gave up to the Burkes eighteen quarters of land^g; and the share which Lynott, the adopted father of Teaboid, asked of this eric was the distribution of the mulct, and the distribution he made of it was, that it should be divided throughout all Tir Amhalgaidh, in order that the Burkes might be stationed in every part of it as plagues to the Barretts, and to draw the country from them. And thus the Burkes came over the Barretts in Tir Amhalgaidh, and took nearly the whole of their lands from them; but at length the Saxon heretics of Oliver Cromwell took it from them all, in the year of our Lord 1652; so that now there is neither Barrett nor Burke, not to mention the Clann Fiachrach, in possession of any lands there.

^g *Eighteen quarters of land.*—A quarter of land, generally containing one hundred and twenty acres, is the fourth part of a Ballybetagh, which was the thirtieth part of a *triocha ched*, or barony. The exact period at which the Burkes, or Lower

Clann William, first settled in Tirawley has not yet been exactly determined, but it must have been before the year 1458, as we have already seen that a Remond Burke was then living at Iniscoe.—See p. 124, and Addenda.

ADDENDA.

ADDENDA.

A.

PEDIGREE OF O'DOWD, OR O'DOWDA.

THE large Genealogical Table, which will be found at the end of this volume, exhibits the descent of the principal families of the Hy-Fiachrach race in the order of their seniority, as far as that has been discovered, from their great ancestor FIACHRA, the son of Eochaidh Muighmheadhoin, who was the sixth from Conn of the Hundred Battles, to as late a period as the Editor has been able to trace them by the evidence of authentic genealogical manuscripts, the Irish Annals, the English-Irish records, and family documents. As in the pedigrees of the Hy-Many race, it has been thought advisable to place all the principal lines in one view, on a single sheet, that it might be afterwards referred to in the account which will be given of each line separately.

1. *Eochaidh Muighmheadhoin* (pronounced Eochy Moyvane), King of Connaught, was proclaimed monarch of Ireland in the year 358, and, after a reign of eight years, died at Tara. He married Mongfinn, daughter of Fidach, of the royal family of Munster, and sister of Crimthann Mor Mac Fidaigh, who succeeded Eochaidh as monarch of Ireland, according to the Four Masters, in the year 366. — (See Battle of Magh Rath, Additional Notes L.) By Mongfinn this monarch had four sons, namely, 1, Brian, the ancestor of the Hy-Briuin tribes, of whom the O'Conors of Connaught were the most distinguished; 2, Fiachra, the ancestor of the Hy-Fiachrach tribes, of whom the O'Dowds, O'Heynes, and O'Shaughnessys were, at least in later ages, by far the most distinguished families; 3, Fergus; and, 4, Oilioll, from whom Tir Oiliolla, now the barony of Tirerill, in the county of Sligo, received its name. Queen Mongfinn, like the Empress Agrippina, actuated by motives of ambition, for the aggrandizement of her offspring, poisoned her brother, the monarch Crimthann, on Inis Dornglas, a small island in the river Moy, in the hope that her eldest son, Brian, might be immediately seated on the throne of Ireland; and in order the more effectually to deceive her brother as to the contents of the proffered cup, she drank of it herself first,
and

and died of the poison soon after; her brother, on his way home to Munster, died at a place in the south of the present county of Clare, which, from that memorable event, received the appellation of Sliabh Oighidh an righ, or the mountain of the death of the king. It has been, however, remarked by ancient and modern Irish writers that this execrable act of Mongfinn had not the desired effect, for that neither her son Brian, nor any of her posterity, was ever monarch of Ireland, except Turlogh O'Connor and his son Roderic. According to all our ancient authorities King Eochaidh had a second wife, Carinna, who is said to have been of old Saxon descent, and who was the mother of the youngest, though by far the most celebrated, of his sons, namely, Niall of the Nine Hostages, the ancestor of O'Neill of Ulster, and all the other families of the Hy-Niall race. It is stated in the Book of Ballymote, fol. 145, b, a, that the poisoning of her brother Crimthann was of no avail to Queen Mongfinn, for that Niall of the Nine Hostages, the son of King Eochaidh by his second wife, and who had been the general of King Crimthann's forces, succeeded as monarch of Ireland immediately after the poisoning of Crimthann. This clearly shows either that Carinna was Eochaidh's first wife, or that he had the two together, for Mongfinn survived him thirteen years, and Niall of the Nine Hostages, the son, as we are told, of the second wife, was of age to succeed as monarch immediately after Mongfinn had poisoned her brother and herself. However this may have been, we read that in the life-time of Niall of the Nine Hostages, Brian, his brother of the half blood, became King of Connaught, and his second eldest brother of the half blood, Fiachra, the ancestor of the O'Dowds and of all the Hy-Fiachrach tribes, became chief of the district extending from Carn Fearadh-aigh, near Limerick, to Magh Mucroimhe, near Athenry. But dissensions soon arose between Brian and his brother Fiachra, and the result was that a battle was fought between them, in which the latter was defeated, captured, and delivered as a hostage into the hands of his half brother, Niall of the Nine Hostages. After this, however, Dathi, the son of Fiachra, a very warlike youth, waged war on his uncle Brian, and challenged him to a pitched battle, at a place called Damh-chluain, situated not far from Knockmaa hill, near Tuam, in the now county of Galway. In this battle, in which Dathi was assisted by Crimthann, son of Enna Cennselach, King of Leinster, Brian and his forces were routed, and pursued from the field of battle to Tulcha Domhnaill, where he was overtaken and slain by Crimthann, son of Enna Cennselach. The body of Brian was buried at the place where he fell, but after a long lapse of years St. Beo Aedh, or *Aidus vivax*, of Roscam, near Galway, removed his bones from that place, and buried them at Roscam; and the writer of the tract on the battle of Damh-chluain, preserved in the Book of Ballymote, adds, "the burial-place of Brian is to be seen there at this day."

2. *Fiachra*

2. *Fiachra Foltsnathach*, i. e. of the flowing hair, son of King Eochaidh.—After the fall of Brian, the eldest son of King Eochaidh, as before recited, Fiachra, the second son, was set at liberty, and installed King of Connaught, and enjoyed that dignity for twelve years, during which period he was general of the forces of his brother Niall. His death happened in the following manner, according to the Lecan records :—He went on one occasion with the king's forces to raise tribute in Munster, but the inhabitants of that province, who detested him and his race, on account of the conduct of his mother in having poisoned the preceding monarch, who was of their own province and blood, refused to pay the tributes to King Niall, and defied him to battle. They met the king's forces in the territory of Caenraighe, now the barony of Kenry, situated in the county of Limerick, on the south side of the Shannon, where they were defeated, and obliged to give up hostages for their future allegiance. In this battle, however, Fiachra was severely wounded by Maighe Mescora, one of the warlike tribe of the Ernaans of Munster, and he set out in triumph for Tara ; but when they had arrived in the territory of Hy-Mac Uais, in Meath, the Munster hostages found Brian unprotected and in a very feeble state from his wounds, and being suddenly actuated by motives of revenge, they seized upon his person and buried him alive in the earth ! Thus fell Fiachra a victim to his own incautiousness, according to the Lecan records, which do not tell us a word about what his own chieftains were doing, when he was left thus barbarously unprotected. According to the Book of Lecan this Fiachra had five sons, and if we can rely upon the order in which they are mentioned we should feel inclined to think that the monarch Dathi was the youngest. They are mentioned in the following order :—1, Earc Culbhuidhe, i. e. of the yellow hair, so called because his hair was of the colour of pure gold, who was the ancestor of the men of Ceara ; 2, Breasal, whose race became extinct ; 3, Conaire, from whom a St. Sechnall is said to have sprung ; 4, Amhalgaidh, or Awley, King of Connaught (and ancestor of several ancient families in Tirawley and Erris, in the county of Mayo), who died in the year 449 ; for some account of whom the reader is referred back to pp. 5–13 of this volume. The seven sons of this Amhalgaidh, together with twelve thousand men, are said to have been baptized in one day by St. Patrick, at Forrach Mac n-Amhalgaidh, near Killala—(See Jocelin's Life of St. Patrick, c. 59, and Colgan, Trias Thaum. p. 141, col. 2) ; and, 5, Dathi, the youngest, but most illustrious, of the sons of Fiachra, and the ancestor of all the chiefs of the Hy-Fiachrach race.

3. *Dathi, son of Fiachra Foltsnathach*.—On the death of his father, Fiachra, this warlike chieftain became King of Connaught, and on the death of his uncle, Niall of the Nine Hostages, in the year 405 or 406, he became monarch of Ireland, leaving the government of Connaught to his less warlike brother Amhalgaidh, or Awley, who

lived to receive the doctrines of Christianity from the lips of the Irish apostle, Patrick, and who is set down in all the lists of the kings of Connaught, as the first Christian king of that province. King Dathi, following the example of his predecessor, Niall, not only ventured to invade the coasts of Gaul, but forced his way to the very foot of the Alps, where he was killed, it is said, by a flash of lightning, leaving the throne of Ireland to be filled by a line of Christian kings. His body was carried home by his son Amhalgaidh, who took the command of the Irish forces after the death of his father, and by his four servants of trust, Dungal, Flannus, Tuathal, and Tomaltach, who carried it to the royal cemetery at Cruachan, called Reilig na riogh, where it was interred, and where, to this day, the spot is marked by a red pillar stone.—*Vide supra*, p. 24, Note ^m.

After the death of King Dathi, Laoghaire, or Leary, the son of Niall of the Nine Hostages, became monarch of Ireland, and enjoyed that dignity, as the Book of Lecan states, for thirty years after the arrival of St. Patrick.

The monarch Dathi married three wives, but the Irish authorities differ much about their order; the fact therefore probably was that he had the three together; be this, however, as it may, the Book of Lecan states that he married Ruadh, or Rufina, the daughter of Airti Uichtleathan, by whom he had Oilíoll Molt, monarch of Ireland, and Fiachra Ealgach, the ancestor of O'Dowd; he married, secondly, Fial, the daughter of Eochaidh, by whom he had Eochaidh Breac, the ancestor of O'Heyne and O'Shaughnessy; and, thirdly, Eithne, the daughter of Orach, or Conrach Cas, who, according to some authorities, was the mother of his son King Oilíoll Molt. But as it would be now idle to speculate on which of Dathi's sons were youngest or eldest, the Editor will here follow the authority of the Book of Lecan, which states that Dathi had twenty-four sons, of whom, however, only twenty are given by name, and set down in the following order:—1, Oilíoll Molt: he succeeded as king of Connaught in the year 449, and after the death of the monarch Laoghaire, in 463, became monarch of all Ireland, and reigned twenty years. His two grandsons, Eoghan Bel and Oilíoll Inbanna, became Kings of Connaught, but his race became extinct in his great grandsons; 2, Fiachra Ealgach, the ancestor of O'Dowd, and several other families; 3, Eochaidh Breac, i. e. Eochy the Freckled, the ancestor of O'Heyne, O'Shaughnessy, and many other families; 4, Eochaidh Meann; 5, Fiachra, who is said to have been detained as a hostage in the hands of King Niall of the Nine Hostages, and who is said to have left a family called Hy-Fiachrach, at a place called Cuil Fabhair, in Meath; 6, Earc; 7, Corc; 8, Onbecc; 9, Beccon; 10, Mac Uais; 11, Aengus the Longhanded; 12, Cathal; 13, Faelchu, from whom are descended the tribe of Hy-Faelchon; 14, Dunghal; 15, Conrach; 16, Nears; 17, Amhalgaidh, the son

son of Rufina, the daughter of Airtigh Uichtleathan, who was born on Inis Awley, in Lough Conn (Lib. Lec. fol. 247), from whom descended the tribe called Cinel Becon, in Meath, and the Mac Firbises of Lecan; 18, Blachadh; 19, Cugamhna, from whom descended the family called Mac Congamhna, who were located in Cinel Fechin, in the south of the now county of Galway: and, 20, Aedh, the ancestor of the Hy-Aedha, who were seated in Burren, in Thomond.

If the sons of Dathi be here set down according to their ages it will follow that Fiachra Ealgach was his second son, and that upon the failure of issue in the line of Oilioll Molt, the representative of Dathi is to be sought for in the line of Fiachra Ealgach. O'Flaherty, however, though he had the Book of Lecan before him, says that Eochaidh Breac, the ancestor of the Hy-Fiachrach Aidhne, was the eldest son of Dathi, that Oilioll Molt, monarch of Ireland, was the second, and Fiachra Ealgach, the ancestor of the Hy-Fiachrach of the Moy, the third son. But, as already observed, it would be now idle to conjecture which is right, and the Editor has followed the Book of Lecan, which, as being the local authority, is more likely to be correct in the genealogy of this race than any other manuscript.

4. *Fiachra Ealgach, son of Dathi.*—The Irish annals have preserved no memorial of this Fiachra, as the descendants of the monarch Oilioll Molt, the eldest son of Dathi, were dominant in Connaught in his reign, but the Lecan genealogical books inform us that he was detained as a hostage in the hands of the monarch Niall of the Nine Hostages,—which however is scarcely credible,—and that the territory of Tir Fiachrach Muaidhe, now the barony of Tireragh, on the east side of the river Moy, took its name from him. He had, according to these records, two sons, namely, 1, Amhalgaidh, or Awley, from whom descended several families formerly seated in the barony of Tirawley, among whom, according to some authorities, are to be reckoned the family of Mac Firbis, but this is very uncertain, as is every thing connected with the early history of that family. By this Amhalgaidh was erected the celebrated Carn Amhalgaidh, on which the chiefs of the northern Hy-Fiachrach were afterwards for ages inaugurated, concerning which see more in the article on the inauguration of the O'Dowds. Fiachra had, 2, Maoldubh, or Maolduin, the ancestor of the subsequent chiefs.

5. *Maoldubh, or Maolduin, son of Fiachra Ealgach.*—No memorial of this personage is preserved in the authentic Irish annals, nor in the genealogical books of the Mac Firbises, except that he is said to have given name to a fort called Dun Maolduibh, near the River Easkey, where he was born and fostered.

6. *Tiobraide.*—He was chief of Hy-Fiachrach in the time of St. Columbkille, to whom he granted a tract of land around the hill of Cnoc na Maili, now the Red Hill

of Skreen, and on which the church of Skreen was afterwards erected by St. Adamnan. He was the father of

7. *Donnchadh Muirisce*, i. e. Donogh of Muirisc, a district in the territory of Tír Fiachrach of the Moy. He was King of Connaught for four years, and was slain, according to the Four Masters, in the battle of Corann, in the year 681. "A. D. 681. Donnchadh Muirisce [*son of Tiobraide*], son of Maoldubh, King of Connaught, was slain in the battle of Corann, in which were also slain Colga, the son of Blathmac, and Fergus, the son of Maolduin, chief of the Cinel Cairbre."

In this entry the Four Masters state that Donnchadh Muirisce was the son of Maoldubh, but we know from the most ancient and authentic lists of the Kings of Connaught, that he was the grandson of Maolduin, and the son of Tiobraide. He had two sons, Innreachtach, King of Connaught for two years, who had a son Oilioll, King of Connaught for eight years, who had a son Cathal mac Oiliolla, who became chief of Hy-Fiachrach, and died in the year 812, but of whose race no further account is preserved. The second son of Donnchadh Muirisce was Oilioll, the ancestor of O'Dowd, through whom the line of chiefs was continued.

8. *Oilioll son of Donnchadh Muirisce*.—No memorial of him is preserved in any of our records except the mere statement that he was the son of Donnchadh Muirisce, King of Connaught, and the brother of Innreachtach, King of Connaught, who was slain in the year 718.

9. *Cathal, son of Oilioll*.—No account of him is found in history, except that he is mentioned as the grandson of a King of Connaught, and the father of another, namely, of

10. *Donncatha Mac Cathail*.—In the authentic lists of the Kings of Connaught this Donncatha, who is called son of Cathal, son of Oilioll, son of Donnchadh Muirisce, is said to have governed Connaught for eighteen years; and his death is entered in the Annals of the Four Masters, at the year 768.

11. *Connmhach*.—In the time of this Connmhach the government of the kingdom of Connaught was transferred to the race of Guaire Aidhne, who resided in the south of the province, and soon after wholly to the Hy-Briuin, of whom the O'Conors of Connaught were the principal family; so that Connmhach did not figure among the conspicuous characters of his age, and the Irish annalists have therefore preserved no notice of him. The genealogical books of the Mac Fírbíse, however, inform us that he was the ancestor of all the succeeding chiefs of the Northern Hy-Fiachrach race, whose country, before the Anglo-Norman invasion, extended from the River Robe to the River Cowney, at Drumcliff, and from the coasts of Erris, eastwards, to the boundary of O'Rourke's country. He had two sons, Caomhan, the ancestor of the
O'Caomhan

O'Caomhan family, who sunk into obscurity in the fifteenth century, and Dubhda, or Dowda, the ancestor of the O'Dowd, or O'Dowda family.

The genealogical books of the Mac Firbises contain some amusing stories, purporting to give a reason why the race of Caomhan, the eldest son of Connmhach, was set aside and the race of Dubhda put in their place as chiefs of the Northern Hy-Fiachrach, but as these have been already given from the text of Duald Mac Firis, it is only necessary to remark here that whatever truth there may be in the seniority of Caomhan, his race was considered in later times the senior branch of the descendants of the monarch Dathi, and therefore their chief enjoyed many privileges which no other family of the race were entitled to; such as to take the first place at the banquet, to be the chief man at the inauguration of the O'Dowd, and to give out their first arms, or military weapons, to the youth of Hy-Fiachrach. How they first lost the chieftainship of the Hy-Fiachrach it would be now useless to inquire, but it may be remarked that they are not the only senior branch of a great race in Ireland who have been laid aside by more powerful junior rivals, and we cannot now admit any reason for O'Dowd's superiority to them than that his tribe became more numerous and more warlike, and compelled them to surrender all claims to the chieftainship of the Northern Hy-Fiachrach by force of arms.

12. *Dubhda*, the second son of Connmhach. He is the ancestor after whom the family of O'Dubhda, anglicè O'Dowda, or O'Dowd, have taken their surname. The name Dubhda signifies a black complexioned or black-haired man, and the prefix O' denotes grandson, and, in a wider sense, a descendant in any degree, and is translated *nepos* by Adamnan in his life of St. Columbkille; so that O'Dubhda signifies *nepos Doudai*, or descendant of Dubhda, or Dowda, and the O' should be prefixed, not only to the name of the chieftain of the race, but also to that of each individual of the family, as well in all the collateral branches as in the direct line. The exact period at which this Dubhda, or Dowda lived, cannot now be satisfactorily ascertained, as the Irish annals preserve no memorial of him, but we have two periods fixed by the authentic annalists, between which he must have flourished, namely, that of his grandfather Donnacatha, King of Connaught, who died in 768, and that of his own grandson Aodh, King of North Connaught, who died in the year 983, and by striking a mean between these two dates we shall have the year 876, which may therefore be considered the year about which this Dowda died. The genealogical books of the Mac Firbises do not give us the name of his wife, and the sum of what they have handed down respecting him is, that he had one son, namely,

13. *Ceallach Mac Dubhda*, of whom nothing is recorded, except that he was the father of

14. *Aodh*,

14. *Aodh, or Hugh O'Dubhda, or O'Dowda, King of Lower Connaught, who died in the year 983, according to the Annals of Lecan, as quoted by Duald Mac Firbis. This Aodh, or Hugh, was the first who could have added the prefix O' to his surname, as being the O', nepos, or grandson of Dubhda, for his father would have been called Mac Dubhda. He seems also to have been the first who obtained sway over the descendants of Caomhan, his grandfather's eldest brother; for the Lecan records inform us that he granted to Aodh, or Hugh, the grandson of Caomhan, the district extending from Tuaim da bhodhar to Gleoir, and also the tract of land in Carra, called Tuath Ruisen, which till then had been in the possession of a sept of the Firbolga, besides other tracts in the principality of Hy-Fiachrach, in consideration of Aodh, the grandson of Caomhan, having resigned to him and his race all claims to the chieftainship of the Hy-Fiachrach. The genealogical books of the Mac Firbises give him but one son, Maolruanaidh, the ancestor of all the branches of the O'Dowd family; but we learn from the Annals of the Four Masters that he had another son, Gebhennach, who died in 1005.*

15. *Maolruanaidh, or Mulrony, son of Aodh, or Hugh O'Dubhda.*—According to Duald Mac Firbis this Mulrony, who was chief of Hy-Fiachrach Muirisce, died in the year 1005, and the Four Masters have the following notice of his death under the same year:—"A. D. 1005. Maolruanaidh, son of Aodh O'Dubhda, lord of Hy-Fiachrach Muirisce, and his son Maolseachlainn, and his brother Gebhennach Mac Aodha, died."

This Maolruanaidh, or Mulrony, had, according to the Mac Firbises, two sons, namely, 1, Maoileachlainn, or Maolseachlainn, the ancestor of the greater number of the succeeding chieftains, and, 2, Domhnall, or Donnell, the ancestor of a celebrated sept of the O'Dowda, called the Clann Domhnaill, or Clandonnell of Lough Conn, of whom were many distinguished warriors, chiefs of Tirawley, and among others Cosnamhach Mor, anglicè Cosney More, who, according to the Mac Firbises, was the last of the Irish race who was called the fighter of an hundred men, but who was killed in his own house at Inishcoe, on Lough Conn, by O'Gloinin, one of his own sub-chieftains, in 1162.

16. *Maolseachlainn, i. e. Melaghlín, or Malachy O'Dubhda.*—He died in 1005, the same year in which his father and uncle also died. The Mac Firbises mention but one of his sons, namely, Niall.

17. *Niall, son of Maolseachlainn O'Dubhda.*—He had three sons; 1, Niall, ancestor of the Clann Neill O'Dowd, who made strong efforts to wrest their little territory from the family of O'Caomhain, but without success; 2, Taithleach, the ancestor of nearly all the subsequent chiefs, and 3, Aodh, the ancestor of several septs, but whose pedigrees are not carried down.

18. *Taithleach, son of Niall O'Dubhda.*—He had two sons, namely, 1, Ruaidhri Mear,

or

or Rory the Swift O'Dubhdha, who was lord of the country extending from the river Robe to Drumcliff, and who was murdered by Domhnall, or Donnell O'Quin, chief of Clann Cuain, whose daughter he had violated, and who renounced his allegiance to O'Dowd, and placed himself under the protection of Mac Dermot, chief of Moylurg. This must have occurred early in the twelfth century. He had, 2, Aodh, or Hugh O'Dowd, the ancestor of the subsequent chiefs.

19. *Aodh, or Hugh, son of Taithleach O'Dubhdha*, father of

20. *Muirheartach O'Dubhdha*, who was the father of

21. *Aodh, or Hugh O'Dubhdha*.—He had three sons ; 1, Taithleach, ancestor of the subsequent chiefs ; 2, Brian Dearg, from whom the Clann Taithligh Oig [Clan-tahilly Og] O'Dowd are descended ; and, 3, Muirheartach. He was probably the Aodh, son of Muirheartach O'Dubhdha, lord of Tireragh and Tirawley, who died in 1143.

22. *Taithleach, or Tahilly, son of Aodh, or Hugh O'Dubhdha*.—He seems to be the Taithleach O'Dubhdha, lord of Tirawley and Tireragh, who was killed by his own two wicked grandsons in the year 1192. He had one son.

23. *Aodh, or Hugh, son of Taithleach*, who was father of the celebrated

24. *Donnchadh Mor, or Donogh More O'Dubhdha*.—He appears first in the Irish annals at the year 1207, under which he is called by the Four Masters lord of Tirawley and Tireragh. In this year he joined Diarmaid, son of Maghnus O'Conor, Cormac Mac Dermot, and O'Hara, lord of Leyny, to oppose Cathal Carrach O'Conor, who had invaded and plundered Mac Dermott's country. A battle ensued between them, in which Cathal Carrach was defeated, taken prisoner, and deprived of his eyes, in order that by being maimed, he might have no further pretensions to chieftainship.

In the year 1213 he hired a fleet of fifty-six ships at the Hebrides, which he joined with his own, and sailed into the bay of Cuan Modh, now Clew Bay, where he landed on Inis Raithin, and compelled Cathal Croibhdhearg, or Charles the Redhanded O'Conor, King of Connaught, to give up to him his territory, extending from the river Robe to Drumcliff, free of tribute.

Having now carried the pedigree of this family down to a period at which their history becomes very certain, and pregnant with facts, the Editor will next glance back at the line of descent, to show that the genealogical books of the Mac Firthises have not preserved to us all the branches that sprang from the main trunk of the genealogical tree of this great race. This will be sufficiently obvious from the following passages in the Annals of the Four Masters :

"A. D. 899. Joseph of Loch Con, abbot of Clonmacnoise, died. He was of the sept of the northern Hy-Fiachrach."

"A. D.

"A. D. 905. Aodh, son of Maolpatraig, lord of Hy-Fiachrach, was slain by Niall, son of Aodh.

"A. D. 1059. Aedhuan O'Dubhda, lord of Hy-Amhalgaidh, was slain by his own tribe."

"A. D. 1096. Muirheartach O'Dubhda, surnamed an Cullach, i. e. *the Boar*, lord of Hy-Amhalgaidh, was slain by his own tribe."

"A. D. 1126. Domhnall Fionn O'Dubhda, lord of Hy-Amhalgaidh, was drowned after having taken a prey in Tirconnell."

"A. D. 1128. The son of Aodh O'Dubhda, lord of Hy-Amhalgaidh, was slain at Ardee in a battle fought between the cavalries of Conchobhar, the son of Mac Loughlin, prince of Aileach, and of Tiernan O'Rourke, chief of Breifny."

"A. D. 1132. Conchobhar, son of Maoileachlainn O'Dubhda, was slain by his kinsman, i. e. by the son of Niall O'Dubhda."

"A. D. 1135. O'Maille was slain by the son of Domhnall O'Dubhda, in the Domhliag, or stone-church of Nuachongbhail."—*Chron. Scot.*

"A. D. 1135. Amhlaoibh, son of Domhnall Fionn O'Dubhda, lord of Hy-Amhalgaidh, was slain by the northern Hy-Fiachrach."

"A. D. 1136. The son of Domhnall O'Dubhda, lord of Hy-Amhalgaidh, was slain."

In 1139 Mathghamhain, or Mahon O'Dubhda, chief of the race of Flaithbheartach, is mentioned, but he was of the O'Dubhdas or Duddies of Ulster. See p. 112, Note 9.

"A. D. 1143. Aodh, son of Muirheartach O'Dubhda, lord of the northern Hy-Fiachrach and Hy-Amhalgaidh, died." This Aodh may have been Aodh, No. 21, in the above pedigree, but this is far from certain, as the number of generations from him to Maoileachlainn, No. 16, who died in 1005, would be too many.

"A. D. 1153. Brian O'Dubhda, lord of the northern Hy-Fiachrach, was slain in the battle of Craebh tinne."

"A. D. 1154. A fleet was sent out by King Toirdhealbhach, or Turlogh O'Conor, to coast Ireland towards the north, consisting of the fleets of Dun Gaillmhe [Galway fort], Connmhaicne mara [now Connamara], Hy-Amhalgaidh, and Hy-Fiachrach, over all which Cosnamhach O'Dubhda was placed as chief commander. These plundered Tirconnell and Inishowen. The Cinel Eoghain, with their chief Muirheartach, son of Niall, observing their designs, went over the sea to hire the fleets of the Gall-Gadelians of Arann, Cantire, the Isle of Mann, and of other parts of Scotland, over all which Mac Scellig was chosen as commander. When they came near Inishowen the Connacian fleet met them, and a fierce and obstinate sea fight ensued between them which continued from morning till evening, during which many of the Connacians were slain by the strangers, and among the rest their chief commander Cosnamhach O'Dubhda.

The

The strangers were however defeated and slaughtered, and deprived of their ships, and Mac Scellig, their leader, lost his teeth."

"A. D. 1162. Cosnamhach O'Dubhda, lord of Tirawley, was slain by his own tribe." This was the celebrated Cosnamhach (son of Aodh, son of Cathbharr, son of Domhnall, son of Maolruanaidh), who was killed by O'Gloinin at Inishcoe. He had a son Cosnamhach, who was slain in 1181.

"A. D. 1182. Murchadh, the son of Taithleach O'Dubhda, was slain by Maelseachlainn O'Mulrony."

By a comparison of these entries in the Annals with the line of the pedigree of the O'Dowds as preserved by the Mac Furbises, and as fully displayed in the large Genealogical Table, it will be seen that there were several distinguished members of the family whose names have not been entered in the pedigree. The truth evidently is, that the Mac Furbises have preserved no more than the direct line of this pedigree, from the progenitor Dubhda, or Dowda, down to Donnchadh Mor, No. 24, excepting the names of a few of the senior or junior branches, such as they knew had become the founders of distinct septs. To return to the pedigree, Donnchadh Mor, No. 24, *supra*, had four sons, namely, Brian Dearg O'Dubhda, lord of Tireragh, Tirawley, and Erris, who, according to the Annals of the Four Masters, was killed on the road while on his pilgrimage to the abbey of Boyle; 2, Maolruanaidh, the ancestor of the subsequent chiefs; 3, Muirheartach, or Murtogh, ancestor of the Clann Conchobhair, who, on the death of his brother, Brian Dearg, in 1242, became chief of Hy-Fiachrach, and was, during his short career, a powerful chieftain, and at constant strife with the O'Conors. In the year 1246 he slew Maelseachlainn, the son of Conchobhar Ruadh, who was son of Muirheartach Muimhneach, or Murtogh, the Momonian O'Conor, for which he was banished over sea; but in the year following, 1247, he returned, accompanied by his friend O'Boyle, with a fleet, and made a descent upon the coast of Carbury, to be revenged on the O'Conors by plundering that territory, but on this occasion the crew of one of his ships, who were under the command of Magnus O'Boyle, were drowned at the island of Inis tuathrass, on the coast of Carbury. But his career of glory was short; he was slain in the year 1248 by the son of Felim O'Conor, as thus recorded in the Annals of the Four Masters:—"A. D. 1248. Muirheartach O'Dubhda, surnamed the Aithchleireach, lord of that tract of country extending from Cill Dairbhile [now Termon Dervilla], in Erris, to the strand [i. e. the strand of Traigh Eothuille], was slain by the son of Felim O'Conor." The fourth son of Donnchadh Mor was Taithleach, who was the father of Conchobhar, or Conor Conallach O'Dubhda, who became chief of Tireragh and was drowned in the Shannon in the year 1291, but his race seems to have become extinct in a few generations. Donn-

chadh Mor had a daughter Mor, who became the wife of O'Boyle, the chief of the opposite coast, and who died in the year 1249.

One of the sons of this Donnchadh Mor O'Dubhda is charged with a very atrocious crime by the Irish annalists, who fortunately do not afford us the clue to discover which of the sons to brand with it. The Four Masters speak of it as follows in their Annals:—"A. D. 1244. Maoliosa Mac an Easpuig O'Maoilfoghmhair [Malisa Mac-anespie O'Mulfover], parson of Tireragh and Tirawley, who, from his wisdom, was intended for the episcopal dignity, was killed by the son of Donnchadh O'Dubhda, a deed strange to his family, for none of the O'Dubhdas had ever before that time killed an ecclesiastic."

25. *Maolruanaidh, or Mulrony, son of Donnchadh Mor O'Dubhda.*—Though this Mulroney was the progenitor of the subsequent chiefs he does not appear to have ever been chief himself, for, in the record of his death given in the Annals of the Four Masters at the year 1238, he is styled Maolruanaidh, son of Donnchadh O'Dubhda:—"A. D. 1238. Maolruanaidh, the son of Donnchadh O'Dubhda, was slain by Maoilseachlainn, son of Conchobhar Ruadh, who was the son of Muirheartach Muimhneach O'Conor, assisted by the son of Tighearnan, who was the son of Cathal Mac Arnain O'Conor."

According to a modern account of the descendants of this Mulrony O'Dubhda, inserted in a modern hand in the Book of Lecan, and which shall be given in these Addenda, he had three sons, viz., Taithleach, Muaidhe, Donnchadh Mor, ancestor of the Clann Donogh O'Dubhda, formerly seated in the district of Coolcarney, and Cosnamhach, *archbishop* of Tuam; but that this genealogy is spurious is obvious from the fact that it totally differs from the original text of the Book of Lecan, as well as from the account given by Duald Mac Firbis; and that it appears from the Irish annals that Donnchadh Mor O'Dubhda, the ancestor of the Clann Donogh, could not have been the son of Mulrony who was slain in 1238, for Donnchadh died Tanist of Hy-Fiachrach in the year 1337, that is, ninety-nine years after the death of his supposed father. But the truth clearly is, that Donnchadh Mor was, as the original text of the Book of Lecan makes him, the grandson of Maolruanaidh, or Mulroney, and the son, not the brother, of Taithleach Muaidhe, who was slain in 1282. According to the Book of Lecan and Duald Mac Firbis this Maolruanaidh, or Mulroney, had two sons, namely, Taithleach Muaidhe, or Tahilly of the Moy, of whom presently, and Cosnamhach, *archdeacon* [not *archbishop*] of Tuam, and a daughter Dervorgilla, who was the mother of Tomalltach O'Conor, *archbishop* of Tuam, and died in 1265.

26. *Taithleach Muaidhe, or Tahilly of the Moy, son of Mulrony O'Dubhda.*—This warlike chieftain, in order to be revenged of William Mor Barrett, who had wrested from

from him the entire of the territory of Tirawley, joined Adam Cusack,—who was then making strong efforts to conquer this part of Connaught,—against the Barretts, and a fierce battle was fought between them at Moyne, near Killala (where a great monastery was a long time after erected). In this battle, wherein O'Dubhda was assisted by his neighbour O'Boyle, William Mor Barrett was defeated, mortally wounded, and taken prisoner. But Adam Cusack, notwithstanding the assistance received from O'Dubhda in this battle, turned his arms against him the year following, and slew him at a place called, from that circumstance, *Bel atha Tailtigh*, i. e. the mouth of Tahilly's ford, situated near the margin of Traigh Eothuille, on the lands of Coillte Luighne, near Ballysadare. These facts are stated by the Four Masters in their Annals, and are also given in the Annals of Clonmacnoise, as we learn from the following quaint translation of the two passages by Connell Mageoghegan :

“A. D. 1281. There was a feild fought between the Barretts of the one side and the Cusackes of the other side, where the Barretts were vanquished ; William Barrett and Adam Fflemying, with many others, were slain. There were two Irishmen of Cusack's side that surpassed the companys of both sides for prowes, manhood, dexteritie of handling of arms, hardiness, and all other parts of activity, named Taihleagh O'Dowdie and Taihleagh O'Boyle.”

“A. D. 1282. Taihleagh mac Moyleronie O'Dowdie (before spoken of), prince of the contrey of Offiaghrach Moye, one of great prowes and bounty, and of great and continuall dissention with the English, and all foreigners, in defence of his contry, was killed by Adam Cusack at Beerhaven.”

Here Mageoghegan renders Traigh Eothuille by Beerhaven, an error equalled only by that of Haliday, who, in his translation of the first part of Keating's History of Ireland, renders it Youghal, and evidently takes it to be the strand of Youghal, in the south-east of the county of Cork.

This Adam Cusack was defeated by Maghnus O'Conor at Ballysadare in the year 1285, on which occasion Collin Cusack, his brother, and many others, were slain. He died in the year 1287, after which we hear of no more triumphs of the Cusacks in Connaught, and the Barretts appear to have recovered all their possessions in Tirawley, of which he seems for a time to have deprived them.

Taithleach Muaidhe O'Dubhda had three sons, viz., Sen Bhrian, of whom presently, Donnchadh Mor, ancestor of the Clann Donogh O'Dubhda, who died in 1337, and Maoileachlainn Carrach, who was slain in 1316. There were many distinguished men among this sept of the family, as William, Bishop of Killala, who died in 1350; Muir-cheartach Cleireach, chief of the Clann Donogh, who died in 1402, but they disappear from history about the middle of the fifteenth century.

27. *Sen Bhrian, or old Brian, the son of Taithleach Muaidhe O'Dubhda*.—Duald Mac Firbis states in his short annals of this family, that this Brian was eighty-four years chief of his name; but we must conclude from the authentic Irish annals that he could not have reigned so long, and we may well believe that fifty-four years, as given in a more modern hand in the Book of Lecan, was the true period. The first notice of this chieftain to be found in the Annals of the Four Masters is at the year 1278, in which he and Art na g-Capall [of the horses] O'Hara, lord of Leyny, gave battle to the Berminghams, and defeated them, killing the two sons of Meyler Mor, Conor Roe Bermingham and others. This was in the life-time of his father, and still he does not appear to have succeeded his father, for the Annals record the death, by drowning, of Conchobhar, or Conor Conallach O'Dubhda, lord of Tir Fiachrach, in the year 1291. In the year 1308, as we learn from the Annals of Clonmacnoise, he joined the English of Leyny and Tireragh to plunder the O'Conors of Carbury. But in 1316 he joined Felim O'Connor and the Irish in the memorable battle of Athenry, where the English had mustered the best appointed and most formidable army that they had ever before sent against the native Irish. In this battle, in which the English were well armed, and drawn up in regular military array, and the Irish without armour^a, eleven thousand of the Irish were slain, and tradition says that the O'Conors were so completely defeated that throughout all Connaught not one man of the name, Felim's brother excepted, could be found who was able to bear arms.

According to the Annals of the Four Masters Brian O'Dubhda, lord of Tireragh, commanded his people in this battle, and lost therein his brother Maoileachlainn Carrach and two of the principal men of his name. The following account of this battle is given in the Annals of Clonmacnoise as translated, in the year 1627, by Connell Mageoghegan:

"A. D. 1316. Felym O'Connor [after having slain Rory O'Connor, who had usurped the throne of Connaught] took all the preys and spoyles of all that belonged to Rowry O'Connor, or that partaked with him before, and took himself the government and name of King of Connought, as before he had, which extends from Easroe, in Ulster, to Eaghtge; took hostages, for the preservation of allegiance, of the Breniemen, and constituted Ualargge O'Roirke as their king; alsoe he took the hostages of the
O'Kellys,

^a Polydore Virgil says that at the battle of Newark, in the reign of Henry VII. the Irish fought with astonishing bravery, but that having their bodies uncovered, according to the custom of their country, they were cut to pieces. "Con-

tra Hiberni etiam praelium magnis animis adebant, attamen cum patris more nullis armis corpora tecta haberent, ante omnes passim cadebant, eorumque caedes aliis multo maxime formidini erat." *Hist. Aug.* p. 729.

O'Kellys, O'Maddens, O'Dermodaes, O'Haras, O'Dowdies; and after setting himself [up] he prepared an army with whom he went to banish the English [out] of Connaught; immediately burnt the towne of Athleathan, killed Stephen D'Exeter therein, Miles Cogan, William Prendergrass, and John Stanton, Knights, and also William Lawless, with a great slaughter of their people. He burnt all the contrey from the place called Castle Corran to Roba, took all their preys and spoyles; returned to his house with a ritche booty of his enemies, and a fortunate success in his affairs.

"King Felym having thus returned to his house made no long stay, but went to Milick to meet with those of Munster and Leathmoye, where he burnt and fell down the castle at first. Mortagh O'Bryen, prince of Thomond, came to his house, and all the families of the O'Briens face to face, with whom he returned to Roscomon to fall the Castle thereof to the Earth.

"Felym O'Connor hearing of the returne of William Burke to Connought from Scotland, he proclaimed that all his people from all parts where they were, with such as wou'd joyn with them, wou'd gather together to banish William Burke from out of Connought, at whose command all the Irishrie of Connought from Easroe to Eghtge were obedient and came to that place of meeting. Donnogh O'Bryen, prince of Thomond, O'Melaughlyn, king of Meath, O'Royrck of the Breffinè, O'Ferall, chieftain of the Analie, called the Convackne, Teig O'Kelly, king of Imaine, with many others of the nobilitie of Ireland, came to this assembly, and marched towards Athenrie to meet with William Burke, the Lord Bremyngham and others, the English of the province of Connought, where they met and gave battle in a place neer the said towne, the Irishmen in which battle were discomfitted and quite overthrown.

"Felym O'Connor, King of Connaught, was therein killed, also Teig O'Kelly, King of Imaine, and eight and twenty of the chieftest of that family. Magnus mac Dermott O'Connor, Tanist of all Connaught, Art O'Hara, prince of Lwynè; Melaghlyn Carragh O'Dowdie; Connor Oge O'Dowdie; Mortagh mac Connor O'Dowdie; Dermott Mac Dermott, Tanist of Moylorge; Mortagh mac Taithleagh Mac Dermoda; Mortagh mac Dermoda O'Fferall; Mullronie Oge Mac Magnosa; John mac Morrogh O'Madden; Donnell O'Boyle; Donnogh O'Molloye of Fearkeal, with his people; the son of Murrogh Mac Mahon with a hundred of his people; Neal Ffox, prince of Teaffie-men, with his people; Ferrall mac John Gallda O'Ferall; William mac Hugh Oge O'Fferalle; Thomas Mac Awley O'Fferall; Tomaltagh, Morragh, Connor, Mortagh, and Melaughlyn Mac Donnough; John Mackeigan, O'Connor's chief Judge; Connor and Gillernew, the sons of Dalredocker O'Dovelen, the man called Fear imchar na h-onchon [i. e. O'Connor's standard bearer], Thomas O'Connolan of the king's guard; all which persons, with many others of Munster, Meath, and Connaught (which were tedious

tedious to recite) were slain in that battle, as a certain Irish poet pitifully in an Irish verse said :

Mór mac ríḡ naḡ abraim ainm
Do marbaidh ír an mór-maíom,
Do ḡuaḡ Míde ír Muman,
Ḥuaḡ lem éirí in caeḡuaidh^b.

"This battle was given [fought] upon the day of St. Lawrence the Martyr. Felym then being but of the age of twenty-three years, in the fifth year of whose reign Rowrye mac Cahall Roe O'Connor (before mentioned) deposed him for one half year, who being killed, as before is described, Felym succeeded for another half year, untill he was slain at Athenrie aforesaid.

"Rowry, surnamed Rowry na ffidh, mac Donnogh, mac Owen, mac Rowrie, succeeded next as King of Connaught."

Sir Richard Cox states (Hist. of Ireland, p. 97) that after this battle the Berminghams took a prey of two thousand cows from the O'Conors, and that eight thousand of the Irish were slain ; and that the King of England, on receiving the news of this victory, granted to Sir Richard De Bermingham the title of Baron of Athenree, which his descendants have enjoyed ever since.

This Brian O'Dubhda died, according to the Irish annals, in the year 1354, when he must have been at least a century old, for he was in active service in the field as early as 1278. Duaid Mac Fírbis says that he recovered a great portion of the original territory, particularly Tireragh, from the English, and divided it among his own sons, grandsons, and great grandsons. He married Una, the daughter of Felim, who was the son of Cathal Croibhdhearg O'Conor, King of Connaught, and had by her eight sons, viz., Domhnall Cleireach, his successor, of whom presently ; 2, Maolruanaidh, or Mulroney, who died in 1362 ; 3, Maghnus Cleireach, who died in 1359 ; 4, Diarmaid ; 5, Aodh, the father of Brian Cam, and Edmond, chiefs of Tireragh ; 6, Cosnamhach ; 7, Niall ; 8, Brian Og, who was slain by the Barretts in 1373.

28. *Domhnall Cleireach, or Donnell the Cleric, son of Old Brian O'Dubhda.*—He succeeded his father in 1354, and died in 1380. In his time the English made strong efforts to get possession of his territory of Tireragh, which was all that remained with the O'Dowds at this period, though they still laid claim to Tirawley ; but in the year

1371

^b Mageoghegan does not translate these lines, which is contrary to his usual mode : they sound thus in English ;
A great number of the sons of kings, whose names

I do not mention,
Were slain in the great conflict,
Of the host of Meath and Munster ;
Pity to my heart is the battling.

1371 he drove the English out of his territory and took possession of the castles of Ardnarea and Castleconor, in which they had strengthened themselves, and then divided the lands among his brothers and followers. The Four Masters have the following notice of his death :—" A. D. 1380. Domhnall, the son of Brian O'Dubhda, lord of Tireragh and Tirawley, defender of his principality against his English and Irish enemies, died at his own mansion seat [Dun Neill] on the third of May, and his son Ruaidhri assumed his place."

According to a list of the chiefs of the O'Dubhda family, inserted in a modern hand in the Book of Lecan, he was chief for forty-nine years and a half, but, according to Duaid Mac Firbis, he reigned but thirty-six years, and if we date the commencement of his reign in 1354, when his father died, we cannot allow him a longer period than twenty-six years, but it is highly probable that his father had resigned the chieftainship to him several years before his death.

Domhnall Cleireach O'Dubhda married the daughter of O'Malley, chief of Umhall, and had by her ten sons, viz., 1, Ruaidhri, his successor, of whom presently; 2, Maghnus, who, in 1461, according to Ware, slew Connor O'Connell, Bishop of Killala; 3, Maoileachlainn; 4, Tadhg Riabhach, or Teige Reagh, who succeeded as chief of Tireragh in 1417, and died in 1432. It was in the time of this Teige Reagh that the abbey of Ardnarea, the ruins of which still remain in good preservation, was founded for monks of the order of St. Augustin, A. D. 1427.—See De Burgo Hibernia Dominicana and Archdall's Monasticon. It was in his time also the Book of Lecan was compiled by Giolla Iosa Mor Mac Firbis, who, in 1417, addressed to him the topographical poem, published in this volume: though it would appear from a memorandum at the bottom of folio 40, that the work had been commenced in the time of his brother Ruaidhri, who died in that year. This Teige Reagh was the ancestor of several chiefs of Tireragh, and of the famous family of the Dowds of Dublin, but the Editor being of opinion that this family is now extinct, deems it unnecessary to give their pedigree in this place, as it has been already given, though without dates, in the text of Duaid Mac Firbis. But should the Dowds of Dublin be extant they will see the line of their descent, traced for thirty-four generations, in the large Genealogical Table hereunto prefixed. Domhnall Cleireach had, 5, John; 6, Domhnall Og; 7, Donnchadh; 8, Diarmaid, who died in 1439; 9, Aodh; and, 10, Eoghan, who was living in 1420.

19. *Ruaidhri, Rory, or Roger, son of Domhnall Cleireach O'Dubhda.*—He succeeded his father in the year 1380, and died in the year 1417, under which the Four Masters have the following notice of his death :—" A. D. 1417. O'Dubhda (Ruaidhri, son of Domhnall, who was son of Brian, son of Taithleach), fountain of the prosperity and
wealth

wealth of Tireragh, died at his own mansion seat [Dun Neill] after the festival of St. Bridget, and his brother Tadhg Riabhach assumed his place."

This Ruaidhri married the daughter of Mac Costello, and had by her, 1, Maolruanaidh, his successor, of whom presently; 2, Conchobhar, or Conor; 3, Maghnus Cleireach; 4, Muirheartach; 5, Eoghan Caoch; 6, William, who died in 1438.

30. *Maolruanaidh, or Mulrony, son of Ruaidhri O'Dubhda.*—He was elected chief of his name in 1432, according to Duald Mac Firbis, and died at Liathmhuine, now Leafony, in 1447. He married the daughter of Mac Wattin Barrett, and had, 1, Diarmaid; 2, Domhnall Ballach, who was chief of the name for one year, and who was the father of William, chief of his name, who died in 1496; 3, Maoileachlainn; 4, Muirheartach Caoch.

31. *Diarmaid, son of Maolruanaidh O'Dubhda.*—He never attained to the chieftainship, though he was the senior of the race, and the ancestor of almost all the subsequent heads of the family. The name of his wife is not given, but it is stated that he had two sons, namely, 1, Conchobhar, or Conor O'Dubhda, of whom presently; 2, Brian.

32. *Conchobhar, or Conor, son of Diarmaid O'Dubhda.*—He succeeded Felim, the son of Tadhg Buidhe, or Teige Boy O'Dubhda, in the year 1508, and died in the abbey of Moyne about the year 1538, after having been thirty years chief of his name. In the year 1527 he took Mac Donogh prisoner. In 1532 his sons took the castle of Ardnarea from the sons of John Burke, in consequence of which great dissensions arose between them and the descendants of Richard Burke, and many depredations and slaughters were committed on both sides, and in the next year the Burkes got possession of Ardnarea, since which the O'Dubhdas, or O'Dowds, never recovered it. He married Margaret, daughter of Thomas Roe Burke, and had by her, 1, Eoghan, his successor, of whom presently; 2, Fearadhach; 3, Ruaidhri; 4, Cormac, a friar; 5, Cathal Dubh, who became chief of his name, and consented to pay tribute to the Lower Mac William Burke; 6, Dathi; 7, John Glas; and, 8, Brian.

33. *Eoghan, or Owen, son of Conchobhar O'Dubhda.*—He succeeded his father about the year 1538, and was chief of his name for seven years. He married Sabia (the daughter of Walter, son of Richard) Burke, who was taken prisoner by O'Donnell in 1536. He was himself taken prisoner by Mac William of Clanrickard in 1542, as we are informed by the Four Masters, but we know no more of his history, except that he and his wife were interred in the same tomb in the abbey of Moyne. He had four sons, viz., 1, Tadhg Riabhach, or Teige Reagh, his successor; 2, Edmond; 3, Ceallach; and, 4, Conchobhar, or Conor.

34. *Tadhg, or Teige Reagh, son of Eoghan O'Dubhda.*—He seems to have succeeded his father about the year 1545, and we learn from the Four Masters that he died in
the

the year 1580. "A. D. 1580. Tadhg Riabhach, son of Eoghan, son of Conchobhar O'Dowd, died." The name of his wife is not given by Mac Firbis, who informs us that he had seven sons: 1, Dathi, of whom presently; 2, Tadhg Buidhe, or Teige Boy, who was made O'Dubhda by O'Donnell in 1595; 3, Fearadhach; 4, Domhnall, or Donnell, the father of Teige Reagh, mentioned in the settlement of 1656, to be presently given; 5, Maolruanaidh; 6, Eoghan; 7, John Og.

35. *Dathi, or David, son of Tadhg Riabhach O'Dubhda.*—He was slain in the year 1594, under which he is styled chief of his name by the Four Masters. "A. D. 1544. O'Dubhda of Tireragh (Dathi, son of Tadhg Riabhach, son of Eoghan) was slain by one of the queen's soldiers in one of his own castles in Tireragh of the Moy."

He married Miss Ellenor Lyens, afterwards Lady Ellenor Ghest, by whom he had two sons, viz., Dathi, or David O'Dubhda, his heir, and William O'Dubhda. This appears from an inquisition taken at Sligo on the third of April, 1623, preserved in the Rolls Office, Dublin, which finds "that David O'Dowde, late of Castleconnor, Esq., deceased, was seised of that castle and several other lands; that he died, leaving David O'Dowde, junior, his son and heir; that Ellenor Lyens, *alias* Dowde (now Lady Ellenor Ghest), was the lawful wife of the said David O'Dowde, senior, and that she is dowable of the one-third of all his lands; that after the death of the said David O'Dowde she married three several husbands, viz., Sir Lionell Ghest, Knight, who died; then William May, Esq., who also died; and after his death, and in the reign of our present sovereign Lord [Charles I.] she married Gerald Fitz-Morrice Fitzgerald, who is now [1633] living."

36. *Dathi, or David, junior, son of David O'Dubhda.*—On the third Patent Roll of the first year of the reign of King James I., there is enrolled "A Grant to Lionel Geste, or Ghest, of the wardship of David O'Dowde, son and heir of David O'Dowde, late of Killinglass, in the county of Sligo, Gent., deceased, for the fine of ten pounds Irish, and an annual rent of seven pounds, retaining five pounds thereof for his (the ward's) maintenance and education in the English religion and habits, and in Trinity College, Dublin, from the twelfth to the eighteenth year of his age.—Dated 1st Nov., 1603."

It appears that when this David, junior, came of age, in 1612, he entered upon and took possession of his father's lands without suing out livery of seisin from His Majesty, which the law then required to make his title good; upon which William Chapman of Rossleagh made a discovery of same unto His Majesty, upon which His Majesty, in consideration of such service, as was then the custom, by his letters patent under the great seal of England, dated the first day of December, in the eleventh year of his reign, granted unto the said William Chapman "the benefitt and profit of three

fourth partes of all Intrusions, fynes for alienations, mesne profitts, and other emoluments and profitts whatsoever due unto His Majestie by reason of any warship and primer seisin, ousterlemayne, or any cause whatsoever uppon any mannors, castles, lands, and tenements of David O'Dowde of Killglasse, in the coontee of Sligo, Gent., by reason of the death of his ffather, or any other of his ancestors, or of any lands that is found by office that David O'Dowde, father unto the said David, died seised of."

The original letters patent to William Chapman, Esq., are now in very good preservation, and in the possession of the O'Dowda of Bunnyconnellan. On the third day of December, 1613, this William Chapman sold his right to these fines to William May, of Castleconnor, Esq., who was young David O'Dowda's step-father, being, as appears from the inquisition already quoted, the third husband of his mother, Lady Ellenor Gheat.

From an original deed in the possession of the present O'Dowda, it appears that this David O'Dowda, of Castleconnor, Esq., was married to Joan Burke, by whom he had,

37. *James O'Dowda*.—He married on the 23rd [effaced] 1632, Evelyn Burke, daughter of Walter Burke, of Turlough, Esq., as appears by his marriage settlement, now in very bad preservation, in the possession of the present O'Dowda. This James died many years before his father. He was living in 1639, as appears by a deed in the possession of the present O'Dowda, dated 10th April, 1639, in which he is called James Dowde, of Castleconnor, Gentleman; but he was dead in 1641, as appears by another deed, dated last day of October, 1641, whereby his father, David O'Dowda, of Castleconnor, Esq., enfeoffs unto Fearil O'Garrae of Moyh [Moy O'Gara, in Coolavin] and Walter Burke of Ardagh, in the county of Mayo, Gentleman, of the castle of Castleconnor, and three quarters of land thereunto adjoining, viz., the quarter of Slievnamasgiry, the quarter of Cloonalangy, and the quarter of Ballinaleynagh, in the barony of Tireragh, to the use of said David and Jewane Burke, his wife, during their lives, and after the death of the said David, the heirs or assigns of James O'Dowda (son and heir of the said David,) shall pass an assurance unto the said Jewane of lands to the clear yearly value of forty pounds of good, fine, pure silver, every year during her life.

By this Evelyn Burke, James O'Dowda had one son, namely,

38. *Dathi Og, or David, junior, O'Dowda*.—He is the last generation given by Duaid Mac Firbis, who states in his smaller genealogical compilation that he was living in the year 1666, and we shall see presently that they were acquaintances. He married in 1656 Dorothy, daughter of Teige Reagh O'Dowda (son of Donnell, son of Teige Reagh, No. 34, *supra*), by whom he got a considerable fortune, though he had lost all his estate during the civil wars. His marriage articles, which are signed by the Irish antiquary

antiquary Duaid Mac Firbis, are dated the 17th of April, 1656, and as they throw a curious light upon the history of the times, they are given here word for word.

" Indented Articles of Agreement concluded, covenanted, and agreed upon this seventeenth Day of April, Anno Domini One Thousand Six Hundred Fifty and Six, by and between David Dowda the younger, of Castleconnor, in the County of Sligo, Gentleman, of the one part, and Teig Reagh O'Dowd of Castletown, of the said County, Gentleman, of the other parte, for and concerning a Marriage to be had and solemnized between the said David and Dorothy Dowda, Daughter to the said Teig.

" First, it is agreed, covenanted, and graunted by and between the said parties that the said David shall, at or before the last day of May next ensuing the date hereof, wedd, marry, and take to wife the said Dorothy, according to the rites, laws, and customs of the Holy Catholic Church, and that the said Dorothy shall accordingly wedd, marry, and take to husband the said David.

" Item, it is covenanted and agreed upon by and between the said parties that the said Teige shall, in consideration of the said marriage, give and satisfie unto the said David, as marriage portion to and with the said Dorothy, the number of cows, sheep, cattle following, viz., fourty great cows, to be milch cows next summer, fifteen heffers of two years old, fifteen yearling heffers, one hundred sheep, one horse, and one plough. Item, it is covenanted and agreed upon by and between the said parties, and the said David for himself, his heirs and assigns, to and with the said Teig, his executors and assigns, in consideration of the said marriage and marriage portion, doth covenant, grant, and agree to be and stand seised and possessed of and in one moyety of such proportion of lands and tenements as he the said David shall recover, and that shall be recovered, in the right, title, and interest of David O'Dowda, grandfather of the said David the younger, to the use and behoof of the said David the younger, and of the said Dorothy and the longer liver of them, for and during their or either of their natural lives, and after their decease to the use of the heirs males to be begotten on the body of the said Dorothy by the said David the younger; and for the securing, making, and confirming of the premises, according to the true meaning, purport, and intent of these presents, the said David Dowda the younger and David O'Dowda the elder, and either of them, shall, at the due request of the said Teig, his executors or assigns, make such assurance and assurances, by conveyance or otherwise, in writing, as by the said Teig, his heirs, executors, or assigns, or his and their council learned in the law shall be devised and advised. And the said David the younger, for himself, his heirs and assigns, for the considerations

aforesaid, to and with the said Teig, his heirs, executors, and assigns, doth covenant, grant, and agree that if in case the said David the younger shall dye having issue female by the said Dorothy, the estate whereof the said David shall dye seised and possessed shall be charged with a sum of money for the preferment and livelyhood of such issue female as by the said Teig Reagh Dowd, Teibot Burk fitz Walter of Turlogh, in the county of Mayo, Esq., and Henry Albonogh of Rathlee, in the said county of Sligoe, Gent., or by any two of them, or by the heirs of any two of them, shall be thought fit and sett down.

“ And that the said David the younger shall, at the request of the said Teig, his heirs, executors, or assigns, give such power and writing to the said Teig, Tibott, and Henery, and to any two of them, and the heirs of any two of them, to that purpose, as by the said Teige, his heirs, executors, or assigns, or his or their counsel learned in the law shall be devised and advised, Provided there be no issue male surviving the said David the younger of the body of the said Dorothy.

“ Item, it is covenanted and agreed upon by and between the said parties, and the said David the younger doth covenant and graunt for himself, his executors and administrators, to and with the said Teig, his executors and assigns, for the considerations aforesaid, that if in case the estate in these presents mentioned shall not be recovered in manner as is above expressed, whereby a jointure may not be secured for the said Dorothy as is hereby intended, and if in case the said David the younger shall happen to dye, the said Dorothy surviving him, that then, and in such cases the said Dorothy shall be satisfied in quantity and quality the said marriage portion, and a moiety of what goods over and above the said marriage portion as shall be then in the possession of the said David the younger at the time of his death. And it is further covenanted and agreed upon by and between the said parties, and the said David the younger, for himself, his heirs, executors, and administrators, to and with the said Teig, his executors and assigns, doth covenant and graunt for the considerations aforesaid, that whereas the said Teig, his executors and assigns, are by these presents graunted to have a moiety of such goods as should be in the possession of the said David the younger at the time of his death, in case he shall happen to survive the said Dorothy, having no issue by her, if in case any part of the said marriage portion shall be employed or disposed by the said David the younger in recovering his estate, whereby the marriage portion, or the value thereof in goods shall not be extant at the time of the death of the said Dorothy, as is last mentioned, without issue, that then and in such case the said David the younger shall, out of such parte of his estate as shall be recovered as aforesaid, make up such parte of the said moiety as shall be in that case wanting, and which estate shall be recovered by the help of the said marriage portion.

“ Item,

"Item, it is covenanted and graunted by and between the said parties that in case the whole real estate of the said David O'Dowda the elder, and of the said David Dowd the younger, shall be left unto them or some of them, their heirs or assigns, or other lands in lieu of them, without disallowance in respect of qualification, that then the said Dorothy shall have for her jointure but the third parte of the same, any thing in these presents contained to the contrary notwithstanding. In witness of all and singular the premises the said parties have to these presents interchangeably put their hands and seals the day and year above written.

THADY DOWDA.

"Being present at the signing, sealing, and delivery of the abovewritten articles, and at the interlineing of the words as is hereby intended, &c., twixt the 59 and 60 lines, we whose names duely ensure.

" DUDLY FERBISSY.	MYLES FERBISSY.
FRANCIS DOWDA.	JAMES FERBISSY."
DANIEL DOWDE.	

This Dorothy, who became the wife of this Dathi, was the daughter of Teige O'Dowd by Margery Bermingham, daughter of John, a younger son of the Lord Baron of Athenry, and this Margery being an heiress, the O'Dowds became, as would appear from the family papers, entitled to quarter the Bermingham or Athenry arms with their own, but this they have not done.

It appears from the foregoing marriage articles that David Dowda, junior, was left without any estate, but that he had a strong expectation of being soon restored, and in this he was not disappointed, for the Commissioners appointed for the setting out of Lands to the Irish in Connaught and the County of Clare, restored him in August, 1656, to a small estate in the parish of Kilgarvan, barony of Gallen, and county of Mayo, the ancient patrimony of the Clann Donogh O'Dubhda. This appears from the original grant in the possession of the present O'Dowda, which is as follows :

" By the Commissioners for setting out lands to the Irish in the province of Connaught and county of Clare.

" In consequence of the Decree of the Commissioners for adjudication of the Claimes and qualifications of the Irish, graunted on behalfe of David O'Dowda, of Leafonye, in the county of Sligoe, whereby hee is adjudged to have two third partes of his estates by virtue of the right qualification wherein he is compressed, sett out to him in the province of Connaght, or county of Clare ; it is ordered and heerby impowered to enter
into

into, and take possession of one thousand five hundred and forty-six acres in the land hereafter specified, viz., in the two quarters of Carowcrum and Carcacrum, one hundred and thirty-two acres; in the two quarters of Boneconelan two hundred and seventy-six acres; Carrowlaban, one quarter, one hundred and fifty-three acres; Carrowreagh, one quarter, one hundred and twenty-nine acres; Kilnegarvan one hundred and fifty acres; Raredane, two quarters, two hundred and ninety-seven acres; Carrownegloon-tagh, one quarter, one hundred and fifteen acres; Carrownecarra, one quarter, one hundred and ninety-nine acres; and in Carrownegloch, one quarter, ninety-five acres; all lying in the parish of Kilnegarvan, barony of Galleng, and county of Mayo, to have and to hold all and singular the said lands, with all the houses, buildings, mills, fishing weyres, water courses, and other improvements and appurtenances, to him, the said David O'Dowda, his heyres and assignes for ever, in full satisfaction of his estate, according to the tenor of the said Decree; and the High Sheriff of the said county, or his Deputy, is hereby required and authorized to put him in full and quiet possession of the premises, takinge for his paynes five shillings, and no more. Dated at Loughreagh, this 4th of August, 1656.

"HENRY GREENEWAY.
CHARLES HOLCROFT.
JA. CUFFE.

"Entered and examined,
EDW. HURD."

This David had by Dorothy, his wife, four sons, namely, 1, David, who was more than seven feet tall, was an officer in the service of King James II., and was slain at the battle of the Boyne; 2, James, who was also an officer in King James II.'s service, and fought at the Boyne, which he survived, and distinguished himself at the siege of Athlone and battle of Aughrim, in which latter engagement he was slain; when his body was discovered his sword was found in his hand, which was so swollen from exertion that the guard of his sword had to be filed off before the hand could be disengaged from it; 3, Thady, or Teige, who was an officer in the service of the King of France, and subsequently admitted to the honour of nobility in Venice, and who died of a fever in France, without issue; 4, Dominic O'Dowda, No. 39, by whom the line was continued; and 5, Francis Dowd, who left no issue. See Will of 1731, next page.

39. *Dominic O'Dowda, fourth son of David.*—He married, in 1703, Ellice Dillon, daughter of Theobald Dillon, Esq., whose brother was a colonel in the service of James II., and died in 1737, leaving by her David O'Dowda, his eldest son (see Lodge's Peerage by Archdall, vol. ii. p. 182), who married Letitia Browne, daughter of James Browne

Browne of Kilticolla, afterwards Brownehall, in the county of Mayo, Esq., and died without issue. This is the David mentioned by the venerable Charles O'Connor, in his dissertations on the History of Ireland, in 1753, as the head of the O'Dowds. On the 6th of August, 1776, he and his wife Letitia O'Dowda, otherwise Browne, obtained a decree in Chancery against George Fitzgerald, Esq., of Turlough, in the county of Mayo; 2, James, an officer in the French service, who died without issue; and, 3, Thady O'Dowda, a colonel in the army of the Emperor Joseph.

His Will is dated 18th September, 1731, and is as follows:

"In nomine Dei. Amen.

"I, Dominic O'Dowd, of Bunicunilane, weak and feeble of body, and troubled by many distempers, yet of sound memorie, sence, and reason, the Lord be praised, understanding my later days to approach, and fearing lest I should be surprised by death, do order and settle my last Will and Testament as followeth:

"Imprimis, I bequeath my soul and body upon my Redeemer, and my body to be buried in my ancestors' Tomb, in Moyne, if allowed, otherwise where my relations will think fit.

"2ndly. I order for my married wife, pursuant to the articles of intermarriage, the same forty pounds sterling per annum mentioned in said articles.

"3rdly. I order for my eldest daughter Molly Dowd three hundred pounds sterling.

"4thly. I order for my son James Dowd two hundred pounds sterling.

"5thly. I order for my daughter Evelin Dowd hundred and fifty pounds sterling.

"6thly. I order for my son Thady Dowd hundred and fifty pounds sterling.

"These sums I order to be paid out of my real estate.

"7thly. I order for the convent of Moyne five pounds sterling, and also for the convent of Ardnaree five pounds more, and lastly, for the convent of Strade two pounds ten shillings sterling. Further, I order for my parish priest, father David Henry, the sum of two pounds sterling, and to fr. Francis Beolan twenty shillings.

"8thly. I order for my niece Molly Dillon ten big cows. All these aforesaid legacies I order to be deducted, or paid out of the personal estate.

"9thly. I order twenty pounds sterling to be paid towards my funeral expenses.

"Lastly. I do nominate and appoint Coll^d. Morgan Vaughan, Counsellor Richard Cormick, and Mr. Toby Burk my true and lawful executors, to oversee my wife and children, and this my last will and testament executed. In witness, and for the true performance of all and singular the premises, I have hereunto set my hand and seal, this the eighteenth of September, in the year one thousand seven hundred and thirty-one.

"Memorandum.—I do order and bequeath to my brother Francis Dowd the sum
of

of two hundred pounds sterling, together with three years' interest, ending the first of November next, which sum was ordered by my father, David O'Dowd, and by myself as child's portion for him ; and I do appoint that it should be paid out of my real estate. In witness and for the true performance of all and singular the premises, I do hereunto set my hand and seal, this the eighteenth day of September, 1731, thirty-one.

“DOMINIC O'DOWD.

“Signed, sealed, and delivered in presence of us,

“HENRY JORDAN.

HUGH O'DONNELL.

FRANCIS MOORE.

“A true copy.”

Of David, his eldest son, the venerable Charles O'Connor of Belanagare wrote the following notice in the first edition of his *Dissertations on the History of Ireland*, published in 1753, pp. 234, 235 :

“The *Hy-Fiachras*, whose great ancestor *Dathy*, carried the Terror of the *Scotic* Name to the Foot of the *Alps*, possessed the Countries of Tir Fiachra and Tir Awly, from the fifth Century to the fifteenth. Our old Annals pay a large Tribute of Praise to this family, and it is represented at present by a Gentleman of the strictest Probity, *David*, or properly *Dathy O'Dowda*, of Ballycollanan [*rectius* Bunnyconnellan], in the County of Mayo, Esquire.”

40. *Thady, Teige, or Thaddæus O'Dowda, third son of Dominic O'Dowda*.—Sir Richard Musgrave states, in his *Memoirs of the different Rebellions in Ireland*, that this “Thady being a younger brother, and having neither property nor employment at home, went out a volunteer to Germany at the age of twenty-five years, and in the course of time was promoted, in the Hungarian service, to the rank of captain [*rectè* colonel], having previously married a German lady, sister to the Baron Wipler [*rectè* Vippler], of whom James O'Doude was the issue.”

According to the tradition in the family this Thaddæus O'Dowda, who was called at home Tadhg Riabhach O'Dubhda, went out to Germany and entered the Austrian service, accompanied by Manus O'Donnell, who was promoted to the rank of general, and also by George Fitzgerald of Turlough, the father of the celebrated George Robert Fitzgerald. That he was promoted to the rank of colonel, and was one of the largest and bravest men in Germany, and that Antonia Vippler, the sister of Baron Vippler, residing in Silesia, fell in love with him, to whom, after much opposition on the part of her family, who threw many difficulties in his way, and even procured his imprisonment,

he

he was finally married, and through whom he was introduced to the highest circles in Germany. By her he had issue James O'Dowda, who was commonly called the Baron O'Dowda, of whom presently, and another son, who died young in Germany.

41. *Captain James O'Dowda*, commonly called Baron O'Dowda. Sir Richard Musgrave states, in his *Memoirs of the different Rebellions in Ireland*, that this James O'Dowda was born and educated in the Hungarian service, and that he had only arrived at the rank of lieutenant, "in which station," he adds, "he served, when the death of his uncle, David O'Doude, who possessed the family estate, and died without issue, was announced to him. In consequence of this event," adds this historian, "he left the army, came to Ireland, and took possession of the paternal property, which proved to be worth about £500 a year, and which he applied himself to the cultivation of with great attention."

It appears from the family papers, and particularly from a letter in the handwriting of his uncle, the Baron Vippler, that this James returned to Ireland shortly before the year 1788. In the will of Letitia Browne, *alias* O'Dowda, the widow of his uncle David O'Dowda, dated 10th February, 1798, she states "that her late husband, David O'Dowda, lived in the Isle of Man," and she orders "that all the papers and the deeds of mortgage respecting Mac Donnell of Elaghmore shall be given to Captain O'Dowda, whose property it is, together with the copy of the map of his estate, and all other papers belonging to him." Her nephew, James Browne, of Browne Hall, Esq., administered to this will.

In the statistical account of the parish of Kilmactige, in the diocese of Achonry, and county of Sligo, written by the Rev. James Nelligan, Rector and Vicar, and published in Mason's *Parochial Survey*, vol. ii. pp. 349-398, the following curious account is given of the improvements made by this Captain James O'Dowda :

"A valuable improvement was made in this place about twenty years ago, through the exertions of a Captain O'Dowdd [a misprint for O'Dowda], who possessed an estate of many thousand acres of these mountains, which were without inhabitants, except those 'feræ naturæ,' and which were nearly impassable to the active and barefooted native. The immense rocks, steep hills, and deep caverns, which everywhere presented themselves, formed as many insuperable difficulties as the passage of the Alps did in former days ; but this Hannibal by labour and perseverance overcame them all, and has now formed a road, where a coach passes six times a week, conveying passengers to and from Ballina and Castlereagh, and has shortened the line from Ballina to Banada from twenty to twelve miles."

This Captain James O'Dowda, who is said to have been the godchild of the Emperor Joseph, was implicated in the rebellion of 1798, and executed at Killala in September,

ber, 1798. A very curious sketch of his character is given by Sir Richard Musgrave, in his *Memoirs of the different Rebellions in Ireland*, vol. ii. pp. 622, 623, 624, where he says that "considering himself the head of the Clan or family, he despised taking a Christian name, and always subscribed himself O'Doude, Captain, and latterly he had the vanity to assume the title of Baron, perhaps from his uncle Baron Wipler in Germany." Sir Richard says that this family counted twenty-five castles on their extensive estate, many of which are still in existence, and that they "have a burying place appropriated to them in the abbey of Moyne, where may be seen the gigantick bones of some of them, who have been very remarkable for their great stature, as one of them exceeded seven feet in height."—Vol. ii. p. 624.

This Captain James O'Dowda, who was popularly called the Baron O'Dowda, married Temperance Fitz Gerald, daughter of Robert Fitz Gerald, Esq., of Mount Tallant. This marriage took place in the year 1788 or early in 1789, when he was very young, as appears from a German letter in the handwriting of his uncle, the Baron Vippler, dated Wigstätt, the 21st November, 1788, of which the following translation, made for the Editor by that accomplished scholar, George Downes, Esq., author of *Letters from Continental Countries*, &c. &c., is worth preserving :

"MY DEAR NEPHEW,

"I was infinitely delighted to hear that of six letters written to you one had come to hand, and no less that you will be so kind as to admit the sincerity of my letter : you may now quite confidently believe that no one can have more sincere intentions towards you than I. You are then already quite determined to marry ? To tell the truth, I would witness it with more pleasure if it were to happen a couple of years later ; however, you are not to be checked ; and I therefore wish you much joy. May you propitiously take this so great step, which is truly of the last importance ! for every thing which is eternal ought to be undertaken with caution ; and you, my good nephew, have not yet had the opportunity of acquiring sufficient experience of the world. Your future lot will therefore so much the more depend on fortune. And, dear O'Dowda, only keep religion and God constantly before your eyes ; for such must be always kept in view by an honourable man. That you have become so good a manager, I am infinitely delighted to hear. God grant that you may continue in this course, and believe that the best enjoyment is one's own approbation ! You can take myself as an example. How much have good friends cost me, and how little has been purchased !

"That you have received no letter from my brother must not surprise you : you know already with what reluctance he writes. Now concerning your money. To
speak

speaking candidly, it is better for you not to be informed. If you did not get the money . . . and then you must [appear] at our court about permission.

"Mac Kernan is gone on an expedition against the Turks: it is about two months since he left me, but I have not yet received a letter from him. Do not forget to assure your worthy aunt of the very devoted respect I entertain for her. I am delighted that you ride indefatigably: but be on your guard to avoid meeting with an accident. To conclude,

"Your sincere uncle,

"Yours from his heart,

"WM. VIPPLER."

This letter proves beyond a question the connexion of Captain O'Dowda with the family of Vippler; but nothing has been yet discovered to prove that he became the heir of that family, or that he had any right to the title of Baron. The following letter, written by the Honourable Thomas Dillon to him, on the 17th of January, 1795, shows that a relative in Germany had left him a handsome sum of money. This relative was probably his uncle, the Baron Vippler:

"MY DEAR FRIEND,

"It gives me very great Pleasure to inform you that I had a Letter last Post from Lord Dillon, desiring I would send to you to give you the pleasing Intelligence of the following matter, which I give you down in his Lordship's Words.

"Inform O'Dowda directly that there is a handsome Sum of Money left to him by a Relation in Germany; tell him to write immediately to Baron Reiyensfeld, Secretary to the Imperial Minister, No. 6, Bryanton-street, Portman-square, London, or to Count Starhemberg, the Imperial Minister, Portland-place, London; but if he will take my Advice he will set out directly for London. Let him call upon me; I will give him a letter to Count Starhemberg, and that will shorten all proceedings; he may otherwise meet with great delay.'

"Wishing you every prosperity, I remain, My Dear O'Dowda,

"Your very affectionate

"Humble Servant,

"THOS. DILLON.

"*Loughlin House, 17 Jan. 1795.*

"I send this in the care of our friend Mr. Hughes, who will lose no time in forwarding it.

"*O'Dowda, Bunniconilan.*"

He had issue, 1, Thaddæus O'Dowda of Bunnyconnellan, now the O'Dowda, of

whom presently ; 2, James Fiachra O'Dowda of Dublin, solicitor, who married, first, Anne, daughter of William Walker, Recorder of Dublin, and, secondly, Mary, daughter of Joseph Burke of Carrowkeel, county of Mayo, Esq., but had no issue by either, and died in 1843, leaving his property to the family of his eldest brother the O'Dowda ; 3, Robert O'Dowda, now an advocate in the supreme court of Calcutta, who married, in 1828, Catherine Wilhelmina Fulcher of the city of London, by whom he has issue four sons, viz., Robert Charles, James William, William Hickey, Henry Cubitt, and two daughters, Kate Ellen, and Louisa Kenny.

Captain O'Dowda (No. 41) had also two daughters, viz., Antonia Letitia, and Temperance, spinsters, now living.—See *Exshaw's Magazine*, January, 1790, in which is the following entry under BIRTHS :—" At Mount Tallant, near Dublin, the Lady of BARON O'DOWDA, of a daughter."

42. *Thaddæus O'Dowda, Esq.*, son of Captain James O'Dowda. He married, in 1812, Ellen White, daughter of Charles White of Dublin, merchant, and has the following issue, all living at present : Dr. James Vippler O'Dowda, a practising surgeon in Dublin ; 2, Thaddæus O'Dowda, Junior, who is six feet seven inches in height ; 3, John Taaffe O'Dowda ; 4, David ; 5, Robert Francis O'Dowda, and four daughters, namely, Ellen, now Mrs. Kelly, Caroline Victoria, Catherine Wilhelmina, and Elizabeth. He had also another son Francis, and two daughters, Harriet and Louisa, who died young.

ARMS: Or, a saltier sable ; in chief two swords in saltier ; in base an oak leaf, vert.

CREST: Over a coronet, a hand in armour holding a dart, ppr.

SUPPORTERS: Two lions rampant.

MOTTO: VIRTUS IPSA SUIS FIRMISSIMA NITITUR ARMIS.

In a MS. about one hundred and fifty years old, the arms of O'Dowda are described thus: "or, a saltier sable, in chief two swords saltierways, garnished of the first." No supporters are mentioned.

The oldest seal of arms in the possession of the present O'Dowda belonged to the David O'Dowda mentioned by Charles O'Connor, in 1753, as the head of the family. It exhibits the supporters and the coronet in the crest.

B.

PEDIGREE OF O'SHAUGHNESSY.

Of the ancient history of the O'Shaughnessys—who have been so celebrated in Ireland since the reign of Henry VIII.—the Irish annals have preserved but very slight memorials. Since the period alluded to they have been much praised, not only by the Irish bards, but by the more respectable writers of the country, and they had undoubtedly

doubtedly held high rank in Connaught, and have intermarried with the best families of English descent, as the Burkes, Berminghams, Butlers, &c. It appears from a by-law of the Corporation of Galway, passed in 1648, that "Lieutenant Colonel William O'Shaughnessie (in consideration of his alliance in blood to the whole towne, and for good nature and affection that he and his whole family doe bear to it) and his posterity, shall be hereafter freemen of this corporation."—*History of Galway*, p. 216. From their celebrity, high bearing, and character for integrity and honour in Ireland, De Burgo was induced, in his *Hibernia Dominicana*, to write of this family, "cujus nobilitatem, antiquitatem, et integritatem qui non novit, Hiberniam non novit." Notwithstanding all these testimonies, however, the truth of history obliges us to state that the O'Shaughnessys are but rarely mentioned in ancient Irish history, and that no person of the name ever became full chief of Aidhne or the south Hy-Fiachrach, the O'Heynes, O'Clerys, or Mac Gillikellys being in turn the chiefs of that territory; but upon the decay of the family of O'Cathail, or O'Cahill, shortly after the period of the English invasion, the O'Shaughnessys became chiefs of the territory of Cinel Aodha, or Kinelea, which comprised the south-eastern half of the territory of Aidhne, and this was the highest rank they ever attained to.

In a "Description of the Province of Connaught," dated in the month of "January, 1612," published in the twenty-seventh volume of the *Archæologia*, it is stated that the O'Heynes were then utterly banished; but that "the O'Shaughnesses remained a rich and hable family."—p. 126.

4. *Eochaidh Breac*.—He was the third son of the monarch Dathi, according to the Book of Lecan, but we are told no more about him, except that he was the ancestor of the southern Hy-Fiachrach, or the Hy-Fiachrach Aidhne, and of the tribe called Hy-Eathach of the Moy, seated to the west of that river, in the barony of Tirawley, in the county of Mayo, and that he was the father of,

5. *Eoghan Aidhne*, i. e. Owen, or Eugenius of the territory of Aidhne, now comprised in the diocese of Kilmacduagh, in the south-west of the county of Galway; he was so called from his having been fostered in that territory by a tribe called Oga Beathra, who afterwards adopted him as their chief.—*Vide supra*, p. 53. He had four sons, namely, 1, Conall; 2, Cormac; 3, Sedna; 4, Seanach Ceanngamhna, from whom sprung a sept called Cinel Cinngamhna, of whom the O'Duibhghiollas were the chiefs after the establishment of surnames in the eleventh century.

6. *Conall, son of Eoghan Aidhne*.—We are told nothing about him, except that he had one son, namely,

7. *Góibhenn*.—He was chief of Hy-Fiachrach Aidhne, and in the year 531 fought the battle of Claonloch, in the territory of Kinelea, in which was slain Maine, son of Cerbhall,

Cerball, while defending the hostages of the Hy-Maine of Connaught.—(*Ann. Four Mast.*) He had one son,

8. *Cobhthach*.—He had three sons, namely, 1, Aodh, the ancestor of the tribe called Cinel Aodha na h-Echtghe, of whom the O'Cahills and O'Shaughnessys were the chiefs after the establishment of surnames; 2, Colman, the father of the celebrated Guaire Aidhne, King of Connaught, and ancestor of the families of O'Clery, O'Heyne, Mac Giolla Cheallaigh, now Kilkelly, and others; 3, Conall, the great grandfather of St. Colman, patron saint of Kilmacduagh, whose crozier and belt, ornamented with gold and gems, was in the possession of the O'Shaughnessy family in Colgan's time (1645).

9. *Aodh, son of Cobhthach*.—Of the generations from this Aodh down to Gealbhuide (No. 27 in the Genealogical Table) our annalists have preserved no notice.

The first notice of this family which occurs in the Irish annals is at the year 1159, in which it is recorded that Gealbhuide, the son of Seachnasach, was slain in the memorable battle of Ardee, fought between Muirheartach Mac Loughlin, head of the northern Hy-Niall, and Roderic O'Conor, King of Connaught. The following are all the notices of the O'Shaughnessys, O'Cahills, and their territory of Cinel Aodha, or Kinelea, preserved in the Annals of the Four Masters and Clonmacnoise, down to the year 1408.

"A. D. 1154. Toirdhealbhadh O'Conor [King of Ireland] set out on a predatory excursion into Meath, but returned without a single cow, his son Maelseachlainn and Donnchadh O'Cathail [Donogh O'Cahill], lord of Cinel Aodha na h-Echtghe [Kinelea of Slieve Aughty], being killed."—*Four Masters*.

"A. D. 1159. Gealbhuide O'Shaughnessy [*recte* Mac Shaughnessy] was slain in the battle of Ath Fhirdia."—*Four Masters*.

"A. D. 1170. Diarmaid O'Cuinn [Dermot O'Quin], chief of Clann Ifernain [in Thomond], was slain by the Cinel Aodha of Echtghe."—*Four Masters*.

"A. D. 1191. Cinel Aodha na h-Echtghe was given to King Roderic O'Conor."—*Four Masters*.

"A. D. 1197. Maoileachlainn Riabhach O'Shaughnessy, lord of half the territory of Cinel Aodha, was slain by the son of Donnchadh O'Cathail [O'Cahill]."—*Four Masters*.

"A. D. 1221. The sons of Gillenenewe macconn [*recte* Cromm] O'Seaghnessa, took house upon Gille Mochoynne O'Cahall, prince of Kynelagh, who killed him after his coming forth."—*Ann. Clonmacnoise*, translated by Connell Mageoghegan.

"A. D. 1222. Giolla Mochoine O'Cathail, lord of Cinel Aodha, East and West, was slain by Seachnasach, the son of Giolla na Naomh O'Shaughnessy, at the instigation of his own people."—*Four Masters*.

"A. D.

"A. D. 1224. Seachnasach, the son of Giolla na naomh O'Shaughnessy, was slain by the Clann Cuilen [the Mac Namaras] and the bachall mor [large crozier] of St. Colman of Kilmacduagh, was profaned by this deed."—*Four Masters*.

"A. D. 1224. Giolla na naomh Crom O'Shaughnessy, lord of the western half of Cinel Aodha na h-Echtghe, died."—*Four Masters*.

"A. D. 1240. Hugh, the son of Giolla na naomh Crom O'Shaughnessy, was slain by Conchobhar, son of Aodh, son of Cathal Croibhdhearg O'Conor and Fiachra O'Flynn."—*Four Masters*.

"A. D. 1248. Opichen Guer [Hopkin Poer] was slain by Giolla Mochoinne O'Cahill."—*Four Masters*.

"A. D. 1251. Giolla Mochainne, the son of Giolla Mochainne O'Cahill, was slain by Conchobhar, the son of Cathal Croibhdhearg O'Conor."—*Four Masters*.

"A. D. 1403. Mortagh Garve O'Seaghnosy, tanist of Tyre-Fiaghragh Ayne, was killed by those of Imaine."—*Annals of Clonmacnoise*, translated by Mageoghegan.

"A. D. 1408. John Cam O'Shaughnessy was slain by the son of O'Loughlin, in a game on the green of Clonrode."—*Four Masters*.

Seeing from these extracts (and we have no more), that it is now impossible to add dates to the pedigree of O'Shaughnessy given in the Genealogical Table, from Aodh, the ancestor of the Cinel Aodha, down to Sir Dermot, who was knighted in 1533 (No. 36 in the Genealogical Table), we must be content with illustrating this pedigree from this Sir Dermot down to the last acknowledged representative of the name, and adding a few observations to identify the present senior of the name.

36. *Sir Dermot O'Shaughnessy* was the son of William, who was the son of John Buidhe, son of Eoghan, son of William, son of Giolla na naomh, son of Ruaidhri, son of Giolla na naomh Crom, lord of the western half of Kinelea, who died in 1224, son of Raghnaill, or Randal, son of Gealbhuidhe, who was slain at the battle of Ardee in 1159, son of Seachnasach, the progenitor after whom this family took the name of Ui Seachnasigh, i. e. descendants of Seachnasach, now generally anglicised O'Shaughnessy, and pronounced in the original territory O'Shannessy, and by some corruptly anglicised Sandys.

The first notice of this chieftain is found on Patent Roll, 33-35, Henry VIII., from which it appears that the king, on the 9th of July, 1533, wrote to the Lord Deputy and Council of Ireland, saying, "We have made the Lord of Upper Ossory, M^cNemarrowe, O'Shaftnes, Denys Grady and ——— Wise, Knyghtes; and woll that by virtue and warraunt hereof youe shall make out unto M^cNemarrowe, O'Shaftnes and Denys Grady, several patentees of all soche lands as they nowe have."

By Letters Patent, dated 3rd December, 35 Henry VIII., A. D. 1543, the king granted to Sir Dermot Sheaghyn [Sheaghynes], knight, captain of his nation, in consideration

sideration of his submission, and pursuant to the king's letter, dated the 9th of June preceding, "All the manors, lordships, towns and town-lands of Gortynchegory, Dromneyll, Dellyncallan, Ballyhide, Monynean, Ardgossan, Ballyegyn, Kapparell, Clonehaghe, Tollenegan, Lycknegarishe, Crege, Karrynges, Tirrelagh, Rathvilledowne, Ardmylowan, one-third part of Droneskenan and Rath; the moiety of Flyngeston, Ardvillegoghe, Dromleballehue, Cowle, and Beke," which lands, it is recited, the said Sir Dermot and his ancestors had unjustly possessed against the Crown, to hold to him and his heirs male in capite, by the service of one Knight's fee, with a clause of forfeiture in case of confederacy against, or disturbance to the Crown. *Inrolled* on the Patent Roll of the thirty-fifth year of Henry VIII. *Dorso*.

This Sir Dermot married Mor Pheacach, i. e. More the Gaudy, O'Brien, who died in 1569, at an advanced age. Her death is thus recorded in the Annals of the Four Masters:—"A. D. 1569. Mor Pheacach (daughter of Brian, son of Tadhg, son of Toirdhealbhadh, son of Brian of the Battle of Nenagh O'Brian) and wife of O'Shaughnessy (Diarmaid, son of William, son of John Buidhe), a woman celebrated for her beauty and munificence, died. By Mor Pheacach he had two sons, namely, Sir Roger, his successor, and Diarmaid, or Dermot Reagh, who went to England in his youth, and became servant or companion to the Earl of Leicester, as will presently be made appear from original documents.

37. *Sir Roger, son of Sir Dermot*.—This Sir Roger was generally called Giolla dubh, anglice Gilduff, or Gilliduff, i. e. *juvenis niger*, by the Irish, from his black complexion and the colour of his hair. He married the Lady Honora (daughter of Murrogh, first Earl of Thomond) who had been a professed nun and an abbess, by whom he had four sons, namely, 1, John, born four or five years before marriage, as were also two daughters, Joan and Margaret; and, 2, William; 3, Fergananim; and, 4, Dermot, who were all born in marriage. Sir Roger, who was called by the Irish Giolla dubh, died in the year 1569, as we learn from the Annals of the Four Masters, in which the following notice of his death is given:—"A. D. 1569. O'Shaughnessy (Giolla dubh, son of Diarmaid, who was son of William, who was son of John Buidhe), pillar of support to the English and Irish who had sought his assistance, and a man who, though not skilled in Latin or English, had been greatly valued and esteemed by the English, died. His son John assumed his place."

After the death of Sir Roger, his brother, Diarmaid Riabhach, anglice Dermot Reagh, or Darby the Swarthy, O'Shaughnessy, who had been servant or companion to the Earl of Leicester, returned to Ireland, having first procured a letter from Queen Elizabeth to her Deputy, Sir Henry Sidney, of which the following is a faithful copy although, by some unaccountable mistake, he is in it called the son of William.

By

"By the Queene.

“ELIZABETH R.

“Right trusty and welbeloved we grete you well. Wher one Derby O'Shaghnes the youngest sonne, as he saith, of William O'Shaghnes, Lord of Kynally, in that o'. Realme of Ireland, hath by the meanes of his Lord and Master, o'. Coosen, the Erle of Leicester, humbly required us not onely to geve him leave to returne into his contry, but also to recomend his petition unto yow for some order to be taken with hym upon the death of his brother named Roger O'Shaghnes as being next heire unto him, we being duely inforemed of his honest demeanor here and of his earnest desire to Serve us, have been content to accompt him to o' Service, and do require yow to have favorable consideracion of his sute, and as you shall fynd it mete to place and settle him in the foressaid Contry, so the rather to incurrage him to persever in his fidelitie, to shewe him as muche favor as may accord with the good goverment of the same Contry.— Given under our Signet at o' Mannor of Otelande, the xxiiird of June, 1570, in the xiith yere of our Reigne.

*"To o' right trusty and welbeloved Sr Henry Sidney,
Knight, of o' order of the Garter, and Deputy of
our Realme of Ireland."*

It is very extraordinary, that in this letter Dermot Reagh is supposed to have been the son of William O'Shaughnessy, which he most unquestionably was not, for we have the testimony of the Irish Annals, and of his cotemporaries, that he was the brother of Sir Roger, as he states himself, and as such he was not the son but the grandson of a William O'Shaughnessy, for Sir Roger was the son of Sir Dermot, and grandson of William. It would appear from the following entry in the Annals of the Four Masters that this Derby or Dermot was made chief of his name in 1571 :

“A. D. 1571. John, son of Gilla dubh, who was son of Diarmaid O'Shaughnessy, who had been the O'Shaughnessy from the time of the death of his father until this year, was deprived of that title, and also of Gort Insi Guaire, by his paternal uncle Diarmaid Riabhach, the son of Diarmaid, for he was virtually the senior.”

This Dermot Riabhach, or Reagh, as we are informed by the Four Masters, continued to be the chief of the O'Shaughnessys until the year 1573, when he and Ulick, the son of Richard Burke, slew Morogh O'Brien (the son of Dermot, who was son of Morogh), in revenge for which John Burke deprived O'Shaughnessy of Gort Inse Guaire. But he held considerable sway in the territory till the year 1579, when he laid a snare for his nephew William, the second son of Sir Roger, near Ard Maoldubhain, on which occasion a fierce combat took place between them, in which he slew his nephew, but though

1, Elis, daughter of ——— Lynch, by whom he had Sir Dermot, his son and heir, of whom presently, and one daughter, who married Daniel O'Donovan of Castle Donovan, chief of Clancahill in the county of Cork. This daughter of Sir Roger is not mentioned in any pedigree of O'Shaughnessy that the Editor ever saw, but she is mentioned in Mons^r. Laine's Pedigree of the Count Mac Carthy, and in the family papers of the late General Richard O'Donovan of Bawnlahan, near Castletownshend, in the county of Cork, as the daughter of Sir Roger O'Shaughnessy, Knight, and also in an ode addressed, in 1639, to her husband Daniel O'Donovan, by Muldowny O'Morrison, in which he thus praises him and his wife :

“Ua Donna báin na n-óig-beart, tuilliom garma a gnát-oigheact,
Cuinge ceart ó á fíréim noime, a éeact 'ran péim noigheide ;
Uáccar an iarréar Muínan, upra an éire oo cócugad,
Flaíe amra ó áir g-crú Cuirc-ne, capla an élu fá a cómuirce.
Duad n-bealba ó á opeic foraiğ, fuair inğion I Sheachnoraig,
Réide gan cumga g-croide, úmla, féile, ir foirtine.
Pailm coruib oo éreib Dáirí, inğion péib-énoideac Ruairí,
Fuair aingé na n-glún ór' éin, ag enúc le h-oidele an oimig.
Ceiré buan na noigheide noimpe, ní léig uairé ar imirce,
Tug ar ainm Ghuairé ór éin, an gairm ir buaine braitéirí.
Fiu an tpeab ór tuirneac Síle, buaid féile ar a príim léine,
Óa coimíde ag maicne an míob-óil: noighe aicme Eiréamóin.”

“The offspring of Donovan of the good deeds, hereditary deserver of dignity,
A worthy representative of the stock he sprung from, has come into the regal suc-
cession.

Superintendent of the west of Munster, prop for supporting justice,
Illustrious chieftain of our Corenian blood, under whose protection our fame is placed.
The palm for beauty of her sedate aspect O'Shaughnessy's daughter has obtained,
Meekness without narrowness of heart, humility, generosity, firmness.

A fruitful palm-tree of the race of Dathi, the kind-hearted daughter of Rory,
Who inherits the attributes of the sires she sprung from, in longing to indulge the
flame of hospitality.

The undying character of the kings before her she has not suffered to pass away,
But has reflected on the name of Guaire that lasting lustre she had derived from him.
The race from whom Sheela has descended deserved the palm for hospitality,
Of which the drinkers of metheglin boast: they are the choice of Heremon's race.”

Sir Roger married, 2, Julia, the daughter of Cormac Mac Carthy, lord of Mus-
kerry,

kerry, but had no issue by her. He was living in the year 1647, as appears by a curious letter written by him to his daughter Gylles in that year, and now preserved at Bawnlahan, in the possession of Major Powell, who succeeded to the property of the late General O'Donovan in 1832. It is as follows :

"For my verie loveinge Daughter Mrs. Gyles Donovane, at Castledonovane, theise.

"DAUGHTER,

"I have received yours of the eighteenth of februarie last, and as for your troubles you must be patient as well as others, and for my parte I taste enough of that fruite ; God mend it amongst all, and send us a more happie tyme. As for the partie lately comaunded to the countree of Kiery, who may be expected to return that way, they are conducted by my Nephew (your Cuossen) Lieut. Collonell William Bourke, to whom I have written by the bearer in your behalfe. I am most Confident he will not suffer any wrong to be don unto your Dependants, Tenants, or yourself. And If in gase [in case] you should expect the whole Armey, you may certifie me soe much with speed, and I shall take that Course that shal be befittinge. In the meane tyme beseeching God to bless and keepe you and yours,

"I am,

"Youre assured loving ffather,

"R. O'SHAGHNISSEY.

"*Fedan, 14. Martii, 1647.*"

The arms on the seal of this letter are "a tower crenelled in pale between two lions combatant." The crest, "an arm embowed holding a spear."

This Gylles, who was living in May, 1676, had four sons, as appears from the O'Donovan records, namely ; 1, Daniel, who was a colonel in the service of James II. and who was the great grandfather of the late General O'Donovan of Bawnlahan ; 2, Cornelius ; 3, Morogh ; and 4, Richard, all living in 1655, but of whose descendants the Editor has not as yet discovered any satisfactory account, but believes that they are all extinct.

According to the pedigree of O'Shaughnessy given in the O'Clery MS. in the Library of the Royal Irish Academy, this Sir Roger, or Gilla-dubh O'Shaughnessy, died in the year 1650. There is a portrait of him dressed in armour preserved among the muniments of Ormond Castle, Kilkenny.

40. *Sir Dermot O'Shaughnessy*.—He married Joan, daughter of Lord Barrymore, and had by her two sons, Roger, his successor, and Cormac, or Charles. He died in 1673.

The following abstract of his Will, which is preserved in the Prerogative Court, Dublin, is well worthy of a place here, as throwing light not only on this pedigree, but upon the manners and customs of the times :

Abstract

Abstract of Will of Sir Dermot O'Shaughnessy of Gort-Inchigorey.

"I order my bodie to be buryed in the Cathedral Church of Kill M^cDuagh, in the tomb where my ancestors were buryed—I doe order, that my son and heir shall cause fyve hundred and fower skore Masses to be said or celebrated for my soule immediately after my death; and I bequeath £29 to be given to those who shall without delay celebrate those Masses, allowing 1s. for every Masse af^d, and that each of the abbye's and convents ment^d. hereafter do say the office of the dead for my soul and 15 masses besides,—I order 100 of my Ewes for my son Cha^s. O'Shaughnessy, and bequeath to my eldest son and heir Roger O'Shaughnessy all my plate and household stuff, and I do charge my said sonnes to live during their lives in brotherly affection amongst themselves without animosity or contention—I bequeath to my son Charles the £20 mortgage I have from *I. Prendergast*, of the 60 acres he had in Ballinekelly, provided he shall cause 200 masses to be said for my soule—I order and leave my stuffe suite with gold buttons and my rapier for my son Charles—I leave the piece of grey frize to Edmond O'Heyne. I leave the piece of grey broad-cloth to father John Mullowny, he sayinge as many masses, for my soule, as the said cloth is worth—I leave one of my shirts to John Butler, one more to Edmond Heyne, one more to my servant Lawrence Donovan, and another to Edmond M'Hugh—I leave one of my best halfe shirts and my scarlett wastcoate to Dermott Clorane—I order the gold diamond ring I have in pawne from James Devenisse, for himselfe, he saying one hundred rosaryes for my soule—I leave my white gowne to Lawrence Donovan, and the rest of all my clothes to my son and heir Roger—I leave my white horse to my daughter in law Hellean Shaughnessy, I leave three young cowes and three great cowes, with four garrans, to my daughter Gyl's Salean, and my hatt to John Buttler—I order my son Roger to pay Eight pieces of Eight towards James Dowley his ransom—I leave two cowes and a mare to my neice Nell Donovan—In Witness of all which I have hereunto subscribed my hand and fixed my seal the 29th of January, 1671.

"DER. O'SHAUGHNUSSY.

"The Legacies I leave for my soule with some of the clergy, viz.—To the Dominicans of Gallway 20s. To the Augustines of Galway 20s. To the Convent of Inish 20s. To the Vicar General, ffa. Michael Lynch, 20s. To ffa. Teige O'Meere 20s. To ffa. John Mullownee 30s. To ffa. Donogh Nelly 10s. To ffa. Thomas Kenny 10s. To ffa. John Nelly 10s. To ffa. Teige Mac Rory 10s. To ffa. Daniel Conegan 10s. To ffa. Thomas Grady 10s. To ffa. Breen Donnellan 10s. To ffa. Donogh Fahy 10s. To ffa. Daniel Broder 5s. To John Mac Glynn, lay-friar, 3s. To Thomas Burke, lay-frier,

lay-frier, 5s. Memorandum, that I do bequeath to my son and heire, Roger O'Shaughnessy and his heirs, the £500 due unto me from my lo. Viscount of Clare.

" D. O'S.

" Being present at the signing and sealing hereof,

" FFR. JO. MOLOUNY.

LAWRENCE DONOVAN.

DER. CLORANE.

" Proved—8 July 1673, by his son Roger."

41. *Roger O'Shaughnessy, Esq., the son of Sir Dermot.*—He married, in 1688, Helena, the daughter of Conor Mac Donogh O'Brien of Ballynue, by whom he had one son, Colonel William O'Shaughnessy, and one daughter, Helena, who married Theobald Butler, and was the mother of Francis, John, and Theobald Butler, living in 1784. Roger joined King James's forces, and was engaged at the battle of the Boyne, from which he returned home sick, though not wounded, and died in the castle of Gort on the 11th of July, 1690. His property was declared forfeited on the 11th of May, 1697, and King William granted all his estates, *in custodiam*, to Gustavus, the first Baron Hamilton; but he having soon after obtained a grant of other lands, the king, by letters patent, dated 19th June, 1697, granted to Thomas (afterwards Sir Thomas) Prendergast, in consideration of his good and acceptable services (the discovery of the assassination plot, &c.), all the estate, real and personal, of Roger O'Shaughnessy, Esq., deceased, in Gort-Inchigorie, and several other lands in the barony of Kiltartan and county of Galway. By a subsequent patent, dated 20th September, 1698, reciting the foregoing grant, and also that his Majesty was informed that the estates were then annually worth five hundred pounds, but that they had since proved very deficient of that sum; and it being the real intention that five hundred pounds a year should have been granted, several other lands of the clear yearly value of £334 os. 2½d., situate in the several counties of Tipperary, Galway, Roscommon, and Westmeath, were granted accordingly.—*Rot. Pat. 10 William III.*

42. *Colonel William O'Shaughnessy.*—He died in exile in France in 1744, without issue.

41. *Cormac, or Charles O'Shaughnessy, the second son of Sir Dermot.*—The Editor has not been able to discover the name of his wife, but it appears from De Burgo's *Hibernia Dominicana*, p. 505, and a pedigree compiled by Peter Connell in 1784, for a Cornet Butler, that he had three sons, namely, Colman O'Shaughnessy, Titular Bishop of Ossory; Robuck, or Robert O'Shaughnessy, Esq., and Joseph, who had a daughter Mary, the mother of a Cornet Butler, who was living in 1784. He had also a daughter Mary, who, according to Peter Connell, became the wife of Mortogh Cam Mac Mahon, Esq.

After

After the death of his cousin german, Colonel William O'Shaughnessy, in France, in 1744, Bishop Colman instituted proceedings at law against Sir Thomas Prendergast, the son of the patentee, for the recovery of the estate of Gort, and these proceedings were continued after his decease in September, 1748, by his brother Robuck O'Shaughnessy, Esq. and after his death by his (Robuck's) son, Joseph O'Shaughnessy, Esq. living in the time of De Burgo, 1762, who has the following curious notice of this family :

“ F. COLMANUS O'SHAUGHNESSY, S. Theologiæ Magister, Alumnus *Athenriensis* Cænobii, oriundus è præclarissima Familia de *Gort*, in *Galviensi* Agro *Conaciæ*, cujus Nobilitatem, Antiquitatem, et Integritatem, qui non novit, *Hiberniam* non novit. *Lo-vanii* in Ordinem Fratrum Prædicatorum ex Officiali Militari Cooptatus, ibidem Studia confecit, atque docere incepit Anno 1706. Missionibus Apostolicis *Hiberniæ* maturus, eoque profectus, laudabiliter se gessit, Sermone, et peculiari Morum Candore, in plurimis *Conaciæ* Regionibus, ingenti cum Animarum Fructu prædicans. Die 30 Aprilis 1726 in Comitibus *Dublinii* celebratis electus fuit Provincialis in locum *Stephani* nostri *Mac-Egan*, Episcopi tunc *Clonmacnoisensis*, nuperrimè laudati. Anno 1736 à Clemente XII., Pontifice Maximo, renunciatus fuit. Episcopus *Ossoriensis*, vulgò Ossory, in *Lagenia*, sub Metropoli *Dublينيensi* atque *Dublinii* in Monialium nostrarum Aedibus Sacris consecratus à D. *Joanne Linegar*, ejusdem Urbis Archipræsule, assistantibus F. *Stephano Mac-Egan*, mox laudato, *Midensi*, et F. *Michael Mac-Donogh* Kilmorensi Episcopis, ex ordine nostro, ut ex nuper dictis liquet, assumptis. Anno 1744 defuncto Patruæ suo, Tribuno *Gulielmo O Shaghnessy*, in Galliarum Partibus, quò pater ipsius *Rogerus* Regem *Jacobum* secutus fuerat Anno 1691, eam ob Causam Castro suo Allocali *Gortensi*, amplissimisque circumjacentibus Prædiis, ultrà Summam bis Mille, et quinquies centum Librarum *Sterlingarum*, id est, decies Mille Scutorum *Romanorum*, annuatim valentibus, privatus a Principe *Arausicano*, nuncupato *Gulielmo III.*, qui eadem concessit Equiti *Thomæ Prendergast*, durante duntaxat Vitâ laudatorum *Rogerii*, et *Gulielmi O-Shaghnessy*; isto, inquam, *Gulielmo* defuncto, *Colmanus* noster *O-Shaghnessy*, etsi jam Episcopus, Litem inchoavit, quâ Familiæ suæ Primipilus, *Dublinii*, in Curia *Communium Placitorum*, contrà tunc, et adhuc existentem Equitem *Thomam* pariter *Prendergast*, primo dicti filium, ad Bona illa hæreditaria recuperanda; atque Præsule nostro è vivis sublato, in jure successit Germanus ipsius Frater, *Robocus O-Shaghnessy*, Armiger, hujusque nunc succedit Filius *Josephus O-Shaghnessy*, Armiger. Eques autem *Thomas Prendergast* acriter se defendit, non quidem Justitiâ Causæ suæ, sed Pecuniâ, et Potentiâ, unus quippe est è Senatoribus Regni in *Parlamento* sedens, in-superque Regi à Sanctoribus Consiliis, ad Differentiam Domini *O'Shaghnessy*, qui Fidei Catholicæ est Cultor, suisque hæreditariis Bonis exutus.”—pp. 505, 506.

42. *Roebuck, or Robert, son of Charles O'Shaughnessy*.—He had two sons, Joseph, who died in 1783, and William, and four daughters, Mary, Catherine, Ellice, and Eleanor, who were living in 1784, when Peter Connell wrote the pedigree for a Cornet Butler. Tradition states that this Joseph O'Shaughnessy, assisted by his relatives, the gentry of the county of Galway, took forcible possession of the mansion house of Gort, on which occasion they caused the bells of Athenry and Galway to be rung for joy. But O'Shaughnessy was finally defeated.

In Howard's *Treatise on the Rules and Practice of the Equity side of the Exchequer in Ireland*, second edition, Appendix, p. 903, the case of Smyth against O'Shaughnessy is mentioned as one of great importance. Howard says :

"In the case of *Smyth*, guardian of *Prendergast* and others, against *O'Shaughnessy* and others, in the court of *Chancery* here, in *October*, 1760, on a petition to the lords commissioners (the Lord Chancellor being then in *England*) on a possessory bill and affidavits, an injunction was granted to the sheriff to restore the plaintiff, as devisee of the estate in question, to the possession of the mansion-house, out of which, it had been sworn, he had been forced by the defendant *O'Shaughnessy*, who claimed under some old dormant title, not as heir at law ; and an injunction was also granted to the party, as to the demesne, unless cause should be shewn to the contrary, in the time prescribed by the order ; afterwards, in *Michaelmas* term following, the defendant came to shew cause against the injunction to the party, and to set aside the injunction to the sheriff upon a notice for that purpose ; but as to the first point, the court disallowed the cause ; and as to the second point, the court refused to set aside the injunction, for that it is an order of course, and usually granted at the first instance, as the party turned out of his place of residence, and may not have a place to go to ; and on these motions the following points were determined :

"That the defendant should not read any affidavits to contradict the facts in the plaintiff's affidavits, or shew any other cause than appeared on the face of the plaintiff's affidavits," &c. &c.

On this occasion it is said that the Lord Chancellor, Mansfield, lent Sir Thomas Prendergast Smyth eight thousand pounds to sustain him against O'Shaughnessy, which sum was charged on the Gort estate, and which has since been paid to the heirs of Lord Mansfield.

When Joseph O'Shaughnessy had taken forcible possession of the mansion-house of Gort, the whole tribe of the O'Shaughnessys believed that he had defeated Prendergast in the law suit, and a very curious song of exultation was composed on the occasion by a poor man of the family, named James O'Shaughnessy, the first quatrain of which runs as follows :

“Duar na gábaid nár fágaíir-re, a bile gan loct,
 O buaid tú an báire, ir fearrúe an éine tá boct,
 Deid luad ag dáim, a’r epáct ag ollamnaib oir,
 ‘S ó uairib Fáil geabair bárr clú féile ‘ra n-Dort.”

“Mayest thou meet neither peril nor danger, O hero without fault,
 As thou hast won the goal, the tribe that is poor will be the better of it,
 The poets shall spread thy fame, and the ollaves shall speak of thee,
 And from the nobles of Inisfail thou wilt receive at Gort the palm for hospitality.”

This Joseph, the last claimant of the Gort estate, died without issue in 1783, and there is no one now living that has yet traced his pedigree with certainty to the first Sir Dermot, who was knighted by Henry VIII.; some think that his race is totally extinct in the male line; but Captain Tyrrell of Kinvara has attempted to show that Mr. Bartholomew O'Shaughnessy of Galway is now the head of the name.

Captain Edward Tyrrell has compiled a pedigree of the O'Shaughnessys, from old documents which he had from Martin Colman O'Shaughnessy of Galway, in which he states that Colman, Titular Bishop of Ossory, already mentioned, but whom he incorrectly styles Lord Abbot of Cong, had several brothers; namely, Charles, Darby, ancestor of the O'Shaughnessys of the county of Limerick, where he settled, and Roger, ancestor of Dean O'Shaughnessy of Ennis, and of Dr. William O'Shaughnessy of Calcutta, F. R. S. Although this pedigree is, in the early part, full of errors in dates and genealogical facts, still there appears to be much truth contained in it for the last five generations, and the Editor is tempted to give that portion of it in this place, as containing the researches of a very intelligent old gentleman who was born in O'Shaughnessy's country, and who is now nearly a century old. He is, however, entirely wrong in making Dr. Colman the son of Sir Roger II. O'Shaughnessy, for we know from his contemporary De Burgo, already quoted, that he was the cousin german of Colonel William O'Shaughnessy (son of Roger, son of Sir Dermot III.), who died in France in 1744; that is, he was the eldest son of Cormac, or Charles, the second son of Sir Dermot, mentioned in the Will of 1671.

The Editor is of opinion that all the descendants of Sir Roger II. O'Shaughnessy are extinct in the male line, and that the O'Shaughnessys of Galway, Limerick, and Clare are descended from Lieut.-Colonel William O'Shaughnessy, who was made free of the corporation of Galway in 1648, and who was the third son of Sir Dermot II. This William had four sons, namely, William, Edmond, Dermot, and Ruaidhri, or Roger; and it is highly probable, though not yet proved, that his son Dermot is the ancestor of the O'Shaughnessys of the county of Limerick, and Ruaidhri, or Roger, the ancestor of the O'Shaughnessys of the county of Clare.

PEDIGREE OF MR. BARTHOLOMEW O'SHAUGHNESSY OF GALWAY, AS COMPILED BY
CAPTAIN TYRRELL OF KINVARA.

According to this pedigree, which is beautifully drawn out on vellum (and in the possession of Dr. Terence O'Shaughnessy, R. C. Dean of Killaloe, who resides at Ennis, in the county of Clare), Colman O'Shaughnessy, Abbot of Cong, was the son of Sir Roger II.; but this is not true, for we learn from Dr. Colman's cotemporary, De Burgo, and from Peter Connell of Kilrush, who drew up a pedigree of O'Shaughnessy for a Cornet Butler, in 1784, that this Colman was the cousin-german of Colonel William O'Shaughnessy, who died in France in 1744, without issue. Captain Tyrrell writes that this Colman had five brothers, namely, Joseph, the head of the family, Charles, Darby, Roger, and James, the two last being twin brothers; but Captain Tyrrell is here totally mistaken, as we learn from De Burgo that on the death of Colonel William O'Shaughnessy in France, in 1744, Bishop Colman became the head of the O'Shaughnessys, and went to law with Sir Thomas Prendergast for the family estates, and that on the death of Colman, in 1749, his next brother, Roebuck, renewed the suit, as being the next senior representative of the family; and that after his death Joseph, his son, carried it on, and that it remained undecided in his (De Burgo's) time. Peter Connell also, who was born about the year 1740, and who knew all about this law suit between the O'Shaughnessys and Sir Thomas Prendergast, gives Colman but two brothers, namely, Robert (i. e. the Roebuck of De Burgo) and Joseph. From the total omission of Roebuck in Captain Tyrrell's pedigree of the O'Shaughnessys, it is quite clear that he has committed some mistake in enumerating the brothers of Dr. Colman O'Shaughnessy, as well as in making him the son of Sir Roger II.; and although he states that he drew this pedigree from the O'Shaughnessy papers, some of which are still, as he says, in his possession, we cannot receive his compilation as correct while in opposition to the registered records of the country, and to printed books of the highest authority. We must, however, receive this gentleman's testimony as far as it regards those genealogical facts which have come under his own immediate cognizance; and as he is now nearly a century old he must have heard and seen much of this family. The Editor, therefore, feels it his duty to lay before the reader that part of Captain Tyrrell's pedigree of the O'Shaughnessys which may be true in itself, though engrafted on a false stem.

2. *Charles O'Shaughnessy*.—He was the brother of Colman, Abbot of Cong. His other brothers were, 1, Joseph, the head of the Gort family [?]; 2, Darby, who settled in the county of Limerick and had numerous issue, whose descendants are still in that county; and, 3, Roger, who settled in the county of Clare, and is the ancestor
of

of all the O'Shaughnessys of that county ; and, 4, James, of whose descendants no account is preserved. This Charles married Anne, daughter of Major Walcott of Duross, in the county of Galway, and had issue by her three sons, namely, 1, Charles, of whom presently ; 2, Roger, who lived at Russane, which he sold to Oliver Martin, Esq., and died without issue male ; and, 3, Darby, who married Elizabeth, daughter of Thomas Taylor, Esq., of Dungorey, and died s. p. aged thirty-one. He had also four daughters, of whom the eldest married Burke of Meelick, and the second O'Flaherty of Connemara.

3. *Charles O'Shaughnessy, the son of Charles.*—He was born in 1660, and married Isabella French of Galway, called the Phoenix from her beauty, and had three sons, namely, 1, Darby, of whom presently ; 2, John, who was born in 1692, and who resided at Kilmaine, in the county of Mayo, where he married Margery Kirwan, by whom he had issue male and female ; 3, James, born in 1694, who went, it is supposed, to Jamaica, and was never heard of by any of his family. He had also six daughters, of whom the first married Michael French of Abbert ; the second Geoffry Martin of Ross ; the third Thomas French of Moycullen ; the fourth R. Eyre ; and two became nuns. He was an improvident man, and gave large portions to his daughters.

4. *Darby O'Shaughnessy, the son of Charles.*—He was born in the year 1690. He married, first, Cicily O'Brien, by whom he had two sons, William and John, and three daughters ; and, secondly, Anne Gilmore of the county of Mayo, by whom he had Martin and James. He was reared for the Church by the Abbot of Cong, but was reduced to keep an academy in Dublin. He gave fifty pounds towards Joseph's suit with T. Prendergast Smyth, and was buried in the abbey of Galway, where he died. His son William, who was born in 1724, married Honor Lynch, by whom he had no male issue. He had three daughters. This William was barrack-master of Headford, and died at Galway [in 1781], aged fifty-seven. Thus ends the male line in the second branch in the fourth generation from Roger. His second son John, who was born in 1728, married Mary Bodkin, and died in 1779, leaving one daughter. His son James died unmarried.

5. *Martin Colman O'Shaughnessy, the third son of Darby.*—He was born in 1747, and married Mary Mac Donough, by whom he had two sons, Bartholomew and Andrew. Finding little property descend to him, it having gone to the female line, he thought a trade better than be a burden on his friends, or the many relations he might boast of, and was bound to a wig-maker. He died in 1829, aged 82. Thus ends the grandeur of this ancient family !

6. *Bartholomew O'Shaughnessy, son of Martin Colman.*—He was born in the year 1789. He married Deborah Morris of Spiddle, by whom he got £900 fortune. He has

has issue male and female, as has also his brother Andrew, who was born in the year 1796.

Captain Tyrrell, in a letter to the Editor, dated September 15th, 1843, writes the following account of the manner in which he obtained the evidences for compiling this pedigree :

"In respect to the Galway barber, it is rather a long story, yet I will strive to get through it as distinctly as I can, for he is certainly the elder branch of that once great and ancient family, now totally gone to decay. About thirty-five or thirty-six years ago, when I lived in Galway, I had occasion to get my razors set to rights, and went to the father of the present barber, O'Shaughnessy, also a barber, and sitting in his shop ; while he was so employed, his daughter came in, opened a good sized box near where I was sitting, and took out a bundle, or rather an handful of papers, on which I saw indistinct writing. I asked what she was going to do with them. She said to kindle the fire. I asked the father of the young woman what the papers related to ; he replied he did not know, nor could he learn from persons who had examined them, as time had totally obliterated them. The box, he informed me, belonged to his grand-uncle, who was Abbot of Cong. This poor barber was then near seventy years of age, and spelled the name 'O'Shoughnessy' on his sign board, and often said it was the ancient mode of spelling the name. In short, I purchased the box, which I have to this day, and its contents, from the poor barber, and on my going to Dublin, I waited on my friend Mr. Kirwan, the highly celebrated chemist of his day, who showed me a way to enable me to read the whole of the papers."

In another letter, dated Kinvara, November 30th, 1843, Captain Tyrrell writes concerning the law suit between Joseph O'Shaughnessy and Sir Thomas Prendergast :

"This law suit was not finally closed in my memory, as it went before the Lords and Commons of England ; and I remember having seen this Mr. Joseph O'Shaughnessy and his sister often, in the years 1768, 1769, and 1770, in a state nearly allied to beggary, at Gort ; from thence they removed to Dublin, and before 1775 [*recte* 1783] both were dead without issue, by which the present barber's grandfather was, without dispute, the next heir to Sir Roger O'Shaughnessy."

Arms.—A castle triple-towered az.

Supporters.—Two lions or.

Crest.—Over a side helmet a hand in armour holding a spear.

Motto.—FORTIS ET STABILIS.

The arms of O'Shaughnessy are given in a MS. in the British Museum, Clarendon 4815, entitled "Copies of Grants of Arms collected for a Peerage by Aaron Crossley." The crest, however, is not given in this collection, but it is added here from an impression

pression of the seal of Sir Roger O'Shaughnessy, on a letter to his daughter Gylles, the wife of Daniel O'Donovan of Castle Donovan, written in 1647.

C.

PEDIGREE OF O'CLERY.

9. *Colman, son of Cobhthach*.—This Colman was King of Connaught for twenty-one years. He married the mother of St. Caimin of Inis Cealltra, and was the father of Guaire Aidhne, King of Connaught, and Lairgneun, who was also King of Connaught seven years.

10. *Guaire Aidhne*.—He was King of Connaught for thirteen years, during which period he distinguished himself so much for hospitality and bounty that he became almost the god or personification of generosity among the Irish poets, and those of modern times boasted that O'Shaughnessy was his lineal descendant. Thus Muldowny O'Morrison, in an ode, addressed, in 1639, to Daniel O'Donovan of Castle Donovan, who was married to O'Shaughnessy's daughter, boasts that his wife Sheela reflected honour on the name of her illustrious ancestor Guaire; but we have already seen that the Cinel Aodha, of whom O'Shaughnessy was chief, were not of the race of Guaire; but the poet was perfectly pardonable, as he had the authority of MSS. of considerable antiquity for deducing the Pedigree of O'Shaughnessy from Guaire Aidhne, King of Connaught.—See p. 54, Note 1.

In the year 645 Guaire fought the battle of Carn Conaill against King Diarmaid, the son of Aodh Slaine, in which he was defeated. He died in the year 662, and was buried at Clonmacnoise. According to the Book of Lecan, Guaire had three sons, namely, 1, Nar, who had a son Cobhthach, who had a son Flann, the ancestor of the family of O'Maghna, chiefs of the territory of Caenraighe, in Aidhne, and who was the senior of the race of Guaire—see p. 61, *suprà*; 2, Artghal, the ancestor of O'Clery, O'Heyne, and Mac Gilla Kelly; and, 3, Aodh, the ancestor of the tribe called Cinel Enda. It would appear from the Annals of the Four Masters that he had another son, Ceallach, who died in the year 665.

11. *Artghal*.—He was the second son of Guaire, but our annalists or genealogists have preserved no particulars about him, except that he was the father of,

12. *Fearghal Aidhne*.—He was King of Connaught for thirteen years, and died in 694, under which year the Four Masters, in their Annals, erroneously call him the son instead of the grandson of Guaire Aidhne. He had two sons, 1, Torpa, the ancestor of O'Clery, and, 2, Flaithniadh, the father of Art, or Artghal, chief of Aidhne, who was slain, according to the Four Masters, in the year 767.

13. *Torpa, son of King Feargal Aidhne*.—He had two sons, Cathmogh, ancestor of the subsequent chiefs, and Aodh, from whom the celebrated poet Flann Mac Lonain was the fourth in descent.

14. *Cathmogh, son of Torpa*.—He had two sons, 1, Tighernach, lord of Aidhne, who died, according to the Four Masters, in the year 822, and Comuscach, the ancestor of the subsequent chieftains.

15. *Comuscach, son of Cathmogh*.

16. *Ceadadhach, son of Comuscach*.

17. *Cleireach, son of Ceadadhach*.—He is the progenitor after whom the family of O'Cleirigh, or O'Clery, have taken their surname. He had two sons, Maolfabhail, of whom presently, and Eidhin, the progenitor of the family of O'Heyne.

18. *Maolfabhail, son of Cleireach*.—He was lord of Aidhne, and died, according to the Annals of the Four Masters, in the year 887. He was father of Tighearnach O'Clery, lord of Aidhne, who died in 916, and of,

19. *Flann, otherwise called Maolcerarda O'Clery*.—He was slain by the men of Munster in the year 950, under which he is styled, in the Annals of the Four Masters, lord of South Connaught, and rioghdamhna, or heir presumptive, of all Connaught. He was father of,

20. *Comhaltan O'Clery*.—He was lord of Hy-Fiachrach Aidhne, according to the Annals of the Four Masters. This very powerful chieftain, assisted by Maelseachlainn Mac Ardaí, in the year 964, defeated the celebrated Sen Fergal O'Rourke, King of Connaught, and slew seven hundred of his people, and among the rest Taichleach O'Gara, lord of South Leyny. He died in the year 976.

21. *Giolla Cheallaigh, son of Comhaltan O'Clery*.—Comhaltan O'Clery was succeeded in the lordship of Aidhne by Muireadhach O'Clery, who was probably his son, and who died, according to the Four Masters, in the year 988, after which Giolla Cheallaigh, or Kilkelly O'Clery, succeeded to the lordship. In the year 998 he slew Diarmaid Mac Dunadhaigh, lord of Siol Anmchadha, but in 1003 he was himself slain by the celebrated Tadhg O'Kelly, chief of Hy-Many, as we are informed by the Four Masters:—"A. D. 1003. A battle was fought between Tadhg O'Kelly with the Hy-Many, and the Hy-Fiachrach Aidhne with the men of West Connaught, in which were slain Giolla Cheallaigh mac Comhaltain O'Clery, lord of the Hy-Fiachrach Aidhne, Conchobhar Mac Ubbain, and Cennfaoladh Mac Ruaidhri, and many others. Finn, the son of Marcan, Tanist of Hy-Many, was also slain in the heat of the conflict." This Giolla Cheallaigh is the progenitor after whom the family of Mac Giolla Cheallaigh, Kilkelly, or Killikelly, have taken their surname, so that that family are virtually O'Clerys. He had one son,

22. *Cugaela, son of Giolla Cheallaigh O'Clery.*—After the death of Giolla Cheallaigh O'Clery, in 1003, it would appear that Maolruanaidh, or Mulrony na paidre [*of the prayer*] O'Heyne succeeded to the lordship of Aidhne, for he commanded the South Hy-Fiachrach in the battle of Clontarf, A. D. 1014, in which he fell. To whom succeeded Cugaela, the grandson of Comhaltan O'Clery, who seems to have ruled the territory for a period of eleven years, for he died, according to the Four Masters, in the year 1025. According to the genealogical MS. of Peregrine O'Clery, now preserved in the Library of the Royal Irish Academy, this Cugaela O'Clery had three sons, namely, 1, Braon, the ancestor of all the septs who retained the name of O'Clery; 2, Giolla na naomh, or Sanctius, the ancestor of the family who took the name of Mac Giolla Cheallaigh, now Killikelly, a family which was very respectable in the territory of Aidhne in the reign of Queen Elizabeth, and then seated in the castle of Cloghballymore, near Kinvara—see p. 68, Note ^r; but, strange to say, the pedigree of this family is not carried down lower than the twelfth century in any Irish MS. accessible in Dublin; 3, Eidhin, the progenitor, after whom the family of the O'Heynes took their surname; but this Eidhin could not have been a son of Cugaela, who died in 1025, for his grandson Mulrony na paidre O'Heyne was chief of Aidhne, and was slain in the battle of Clontarf in 1014; and we must therefore agree with Duaid Mac Firbis, who makes this Eidhin the son of Cleireach, No. 17 in the Genealogical Table.

23. *Braon, son of Cugaela O'Clery.*—He was slain, in the year 1033, as we learn from the Annals of the Four Masters at that year.—“A. D. 1033. A battle was fought between the men of Eile and the Hy-Fiachrach Aidhne, in which fell Braon O'Clery and Muireadhach, the son of Giolla Padraig, and many others.”

24. *Eoghan, son of Braon O'Clery.*—In the time of this Eoghan the family of O'Heyne became chiefs of Aidhne, but it does not appear that any member of the family who retained the name O'Clery ever after obtained chief sway in the territory; and they were finally driven out by the Burkes. From this Eoghan, who must have died about the year 1063, we are presented with the following generations, of which no dates or other particulars are preserved in the Irish annals.

25. *Domhnall O'Clery.*

26. *Giolla na naomh O'Clery.*

27. *Tighernach O'Clery.*

28. *Muireadhach O'Clery.*

29. *Tadhg O'Clery.*

30. *Giolla Iosa O'Clery.*

31. *Domhnall O'Clery.*

By allowing thirty years to each of these generations we will find that this Domhnall may have flourished towards the close of the thirteenth century, and this seems to have been the period at which the O'Clerys were driven out of the territory of Aidhne by the Burkes. He had four sons, namely ; 1, John Sgiamhach, i. e. the comely, the ancestor of the O'Clerys of Tirconnell; 2, Daniel, from whom are descended the O'Clerys of Tirawley; 3, Thomas, from whom are the O'Clerys of Briefny O'Reilly; and, 4, Cormac, from whom are the O'Clerys of Kilkenny.—See Genealogical Table.

32. *John Sgiamhach* (i. e. *the Comely*) *O'Clery*, fl. circ. 1303.

33. *Diarmaid O'Clery*, fl. circ. 1333.

34. *Cormac O'Clery*.—He was the first of the family who removed to Tirconnell, which he did shortly after the year 1382, when Toirdhealbhadh an fhiona O'Donnell was chief of Tirconnell. He married the only daughter and heiress of Matthew O'Sgingin, who was at the time chief historian to O'Donnell, and had by her,

35. *Giolla Brighde O'Clery*.—He was so called after his maternal uncle, Giolla Brighde O'Sgingin, who had died in 1382, a short time before the birth of O'Clery. This Giolla Brighde O'Clery was educated in the profession of his maternal grandfather, whom he succeeded in the capacity of historical ollav or chief historian to O'Donnell. He had one son, who succeeded him, viz.

36. *Giolla riabhach O'Clery*.—The Four Masters have the following notice of his death :—" A. D. 1421. Giolla riabhach O'Clery, a learned historian, died after having spent a life of virtue." There must be some error, however, in this date, for his father, Giolla Brighde, having been born after 1382, was only 39 years old in 1421, when the death of his son is mentioned as that of a learned historian! The truth would appear to be that Giolla riabhach is here a mistake for Giolla Brighde.

37. *Diarmaid of the three Schools, the son of Giolla riabhach*.—The year of the death of this Diarmaid, strange to say, is not recorded by his descendants, the Four Masters, in their Annals.

38. *Tadhg, or Teige Cam O'Clery*.—His death is thus recorded in the Annals of the Four Masters at the year 1492 :—" A. D. 1492. O'Clery (Tadhg Cam), ollav to O'Donnell in science, poetry, and history, a man who had maintained a house of universal hospitality, for the mighty and the needy, died, after having subdued the world and the devil." This Tadhg Cam had three sons, 1, Diarmaid, of whom presently; 2, Tuathal, who died in 1512, and who was the great grandfather of Michael O'Clery and Conary O'Clery, two of the Four Masters, and of Bernardinus O'Clery, the superior of the convent of Donegal in 1632 and 1636; 3, Giolla riabhach, chief of this family, who died in 1527.

39. *Diarmaid, son of Tadhg Cam O'Clery*.—He had four sons, namely, Cucoigriche,

or

or Peregrine, Giolla Bhrighde, Cormac, a friar of the order of St. Francis, and Muirgheas.

40. *Cucoigcriche, or Peregrine O'Clery*.—He was living in the year 1546, as we learn from a passage in the Annals of the Four Masters under that year. He had six sons, namely, 1, Maccon, of whom presently; 2, Cosnamhach; 3, Dubhthach; 4, Tadhg; 5, Cormac; and, 6, Maurice Ballach, who was hanged in the year 1572 by the Earl of Thomond, who wished to exterminate the Irish poets.

41. *Maccon, son of Cucoigcriche O'Clery*.—He was the chief of the Tirconnell, or literary sept of the O'Clerys, and died in the year 1595, under which year the Four Masters have preserved the following record of him:—"A. D. 1595. Maccon, son of Cucoigcriche, son of Diarmaid, son of Tadhg Cam O'Clery, chief historian to O'Donnell, died at Leitir Maolain, in Thomond [now Lettermoylan, in the parish of Dysart O'Dea, in the barony of Inchiquin]. He was a learned and erudite man, profoundly versed in history and poetry, fluent, eloquent, and gifted with the harmony and splendour of oratory, and withal, pious, devout, religious, and charitable." He had five sons, namely, 1, Lughaidh of the Contention of the Bards, of whom presently; 2, Giolla Brighde; 3, Maccon Meirgeach; 4, Cucoigcriche; and, 5, Duibhgeann, who was slain at Clare in the year 1600.

42. *Lughaidh, or Lewy O'Clery, son of Maccon O'Clery*.—He was the head of the Tirconnell branch of the O'Clerys, and was in possession of all his lands in the year 1609, when he was selected as one of the "good and lawful" men of the county of Donegal, appointed to inquire into the King's title to the several escheated and forfeited lands in Ulster. He was the principal disputant on the part of the northern bards in the contest with Teige Mac Dary and those of the south of Ireland, respecting the claims of the rival dynasties of the northern and southern divisions of Ireland to supremacy and renown, and his poems written during this controversy are very curious, as preserving many historical facts, and for the purity and correctness of their diction. The year of his death is not recorded by the Four Masters, and the probability is that he lived to a later period than that to which their Annals extended, for they have no entry later than the year 1616. He had two sons, Cucoigcriche, or Peregrine, of whom presently, and Cairbre.

43. *Cucoigcriche, or Peregrine O'Clery, the eldest son of Lughaidh*.—He married one of the Mac Sweenys of the county of Donegal, by whom he had two sons, Diarmaid and John. It appears from an inquisition taken at Lifford on the 25th of May, 1632, that he held the half quarter of the lands of Coobeg and Doughill, in the proportion of Monargane, in the barony of Boyleagh and Bannagh, in the county of Donegal, from Hollantide, 1631, until May, 1632, for which he paid eight pounds sterling per annum

to William Farrell, Esq., assignee to the Earl of Annandale, but, as the document states, being "a meere Irishman, and not of English, or British descent or surname," he was dispossessed, and the lands became forfeited to the king. Shortly after this period he removed, with many other families of Tirconnell, to Ballycroy, in the south of the barony of Erris, in the county of Mayo, under the guidance of Rory or Roger O'Donnell, the son of Colonel Manus, who was slain at Benburb in 1646, and the ancestor of the present Sir Richard Annesley O'Donnell of Newport. He carried with him his books, which were his chief treasure, which he bequeathed to his two sons, Diarmaid and John, as we learn from his autograph Will, which was written in Irish at Curr-na-heillte, near Burris-hoole, and which is extant, in rather bad preservation, in his genealogical MS. now in the Library of the Royal Irish Academy. In this Will, which was made shortly before his death in 1664, he writes:—"I bequeath the property most dear to me that ever I possessed in this world, namely, my books, to my two sons Diarmaid and John. Let them copy from them, without injuring them, whatever may be necessary for their purpose, and let them be equally seen and used by the children of my brother Cairbre as by themselves; and let them instruct them according to the And I request the children of Cairbre to teach and instruct their children." The injunctions here solemnly laid by him on his posterity were faithfully fulfilled, and a knowledge of the Irish language, as well as his own honesty of character, has been transmitted in the family to the present day.

44. *Diarmaid, son of Cucoigcriche, or Peregrine O'Clery*.—No memorial of him remains in the MSS. except that he was the son of Peregrine and the father of,

45. *Cairbre O'Clery*.—He married, about the year 1692, ——— Maguire of Arney Bridge, in the county of Fermanagh, by whom he had two sons, namely, Cosnamhach, or Cosney, and Philip, who died without issue male, and one daughter Alice. He removed with his children to the parish of Drung, in the county of Cavan, and was interred in the churchyard of Drung.

46. *Cosnamhach, or Cosney O'Clery, son of Cairbre*.—He was born in the year 1693 at the foot of Nephin mountain, in the county of Mayo. He removed from thence to a place called Knockbinish, in the county of Leitrim, whence he removed accompanied by his father, to the parish of Drung, in the county of Cavan, where he married Mable, daughter of Donnell Ultagh [Donlevy], by whom he had one son, Patrick, and four daughters. He died in the year 1759, in the sixty-sixth year of his age, and was buried in the churchyard of Drung.

47. *Patrick, son of Cosnamhach O'Clery*.—He was born in the year 1738, and in 1759 he married Anne, daughter of Bernard O'Gowan, or Smith, of Lara, in the county of Cavan, and had by her twelve children, six sons and six daughters. He died
in

in the year 1816, aged seventy-eight years, and was interred in the churchyard of Drung.

48. *John, eldest son of Patrick O'Clery*, now living. He was born in the year 1778, and in 1812 married Alice, daughter of Patrick Smith of Ashfield, in the county of Cavan, and had by her five children, of whom only two are now living, namely, John and Anne.

This John, No. 48, removed to the city of Dublin in 1817, where he still lives, like his ancestors, a strictly honest and worthy man, and a good Irish scribe and scholar. His son, John O'Clery, Jun., has written the following remarks on the family manuscripts, in a letter to the Editor, dated 37, Nassau-street, 12th February, 1842, which should not be omitted here :

"Cucogry left his books to his sons Dermot and Shane. Cairbre, son of Dermot, had them in his possession, and left them to his son Cosnamha, who left them to his son Patrick, through whom they came into the possession of his son John, my father. By an accidental fire, which occurred in the house of my grandfather, a great part of Cucogry's manuscripts was materially injured. The only ones which escaped damage were the following :—The Book of Pedigrees, the Book of Invasions, the Life of Red Hugh O'Donnell, the *Ambra Choluim Chille*, and *Triallam timcheall na Fodhla*, which were brought to Dublin by my father in 1817. He *lent* these books to the late Mr. Edward O'Reilly, *but did not bargain for or sell them* to him. He never got them back, however, as he did not know of Mr. O'Reilly's illness until he heard of his death, and saw that he had included these very books in his catalogue, except the Life of Hugh Roe, which, it appears, he had disposed of to Mr. Monck Mason, who resided at that time in Harcourt-street, and this he had done without letting my father know any thing about it. My father, on hearing of his books being thus advertised for sale, made an affidavit that he merely lent, but did not sell them to Mr. O'Reilly. Notwithstanding this, however, his executor, the Rev. Eugene O'Reilly of Navan proceeded with the sale of them, and it was under these circumstances that they came by purchase, at O'Reilly's auction, into the possession of the Royal Irish Academy. But although they could not perhaps be placed in better hands, or any where that they would be taken better care of, as far as their preservation is concerned, yet by all the laws of strict justice, they are as much my father's property, even at this moment, as if the Royal Irish Academy had never paid one farthing for them. Little did Cucogry think that these very books, on which he set so high a value, as is seen by his own Will, would ever, by such means, pass out of the hands of his descendants. My father has still a copy, which he made himself, of the Book of Pedigrees, and he has also some of the very books which belonged to Cucogry."

Mr.

Mr. Martin Clery of Ballycroy, in the county of Mayo, also descends from *this* Cucogry, or Peregrine, who died in 1664, and Mrs. Conway of Doonah castle, in Ballycroy, descends from his brother; but they are unable to add dates to the different generations, having retained no manuscript memoranda.

It does not appear that this family had ever obtained any grant of arms from the Irish College of Heralds, and the Editor has not been able to find that they ever used any armorial bearings in ancient Irish times.

D.

PEDIGREE OF O'HEYNE.

18. *Eidhin, the son of Cleireach*.—We have already seen in the pedigree of O'Clery, No. 22, that Peregrine O'Clery errs in making this Eidhin the son of Cugaela, chief of Aidhne, who died in 1025, and we must therefore follow the authority of Duaid Mac Firbis and of the O'Mulconrys in the *Leabhar Irse*, who make him the second son of Cleireach, the ancestor of the family of O'Clery. He had one son, Flann, of whom presently, and one daughter, Mor, the first wife of the monarch Brian Borumha, and the mother of his sons Murchadh, Conchobhar, and Flann, who were slain in the battle of Clontarf.

19. *Flann*, of whom we know nothing, except that from the pedigrees and the Irish annals we must come to the conclusion that he had two sons, namely, 1, Maol-ruanaidh na Paidre (or Mulrony of the Prayer) O'Heyne, chief of Aidhne, who was slain in the battle of Clontarf in the year 1014, of whose issue, if he left any, no account is preserved; and, 2, Maolfabhaill, or Mulfavill O'Heyne, by whom the line was continued.

20. *Maolfabhaill, son of Flann O'Heyne*.—He became chief of the Hy-Fiachrach Aidhne, or South Hy-Fiachrach, probably after the death of Cugaela O'Clery, in the year 1025, and if so, he was chief for twenty-three years, for his death is recorded in the Annals of the Four Masters at the year 1048.—“A. D. 1048. Maolfabhaill O'Heyne, lord of Hy-Fiachrach Aidhne, died.”

21. *Cugaola, son of Maolfabhaill*.—No notice of him is preserved in the Irish annals unless he be the O'Heyne, lord of the Hy-Fiachrach Aidhne, mentioned in the Annals of the Four Masters as having slain Domhnall Ruadh O'Brien in the year 1055, which he probably was.

22. *Giolla na naomh, surnamed of the Plunder, son of Cugaela O'Heyne*.

23. *Flann, son of Giolla na naomh O'Heyne*.

24. *Conchobhar, or Conor, son of Flann O'Heyne*.

25. *Aodh, or Hugh, son of Conchobhar O'Heyne.*—He was probably the Aodh O'Heyne, lord of Hy-Fiachrach Aidhne, mentioned by the Four Masters at the year 1121, as having been slain in Munster, whither he had gone on a predatory excursion with Turlogh O'Conor, who was then King of Connaught, and presumptive monarch of Ireland.

26. *Giolla Cheallaigh, or Gillikelly, son of Aodh O'Heyne.*—He had two sons, Aodh and Giolla na naomh, and was slain, according to the Annals of the Four Masters, in the year 1153, together with his son Aodh.

27. *Giolla na naomh, son of Giolla Cheallaigh.*—The Irish annals have preserved no memorial of this Giolla na naomh. In his time Roderic O'Conor, monarch of Ireland, was resident in the O'Heyne territory. At the year 1180 the Four Masters mention the death of a Maurice O'Heyne, lord of Hy-Fiachrach Aidhne, and at 1187, the death of Duvesa, daughter of O'Heyne, and wife of Conor Mac Dermot, lord of Moylurg, but nothing remains to show how this Maurice, or Duvesa, stood related to the Giolla na naomh in question; but it is highly probable that the one was the son and the other the daughter of his brother Aodh, who was slain in 1153.

28. *Eoghan, or Owen, son of Giolla na naomh O'Heyne.*—At the year 1201 the Four Masters enter the death of Conchobhar, or Conor O'Heyne, the son of Maurice; at 1211 that of Cugaola O'Heyne, and at 1212 they have the following entry:—“A. D. 1212. Donnchadh O'Heyne had his eyes put out by Aodh, the son of Cathal Croibhdhearg O'Conor, without the permission of O'Conor himself.” These were evidently the grandsons of Aodh, or Hugh O'Heyne, who was slain in 1153, and whose race was now laid aside, when Donnchadh was deprived of his eyes and rendered unfit for the chieftainship. After this Eoghan, the son of Giolla na naomh O'Heyne, became chief of the Hy-Fiachrach Aidhne, and one of the most conspicuous chieftains that ever ruled that territory. In the year 1225 he was one of the chiefs of Connaught who joined the sons of King Roderic O'Conor against Hugh, the son of Charles the Red-handed O'Conor, King of Connaught, who was assisted by the English; on which occasion Hugh O'Conor despatched his brother Felim and others of the chiefs of his people, and a large body of English soldiers, into Hy-Fiachrach Aidhne to plunder Eoghan O'Heyne, and they encamped one night at Ardrahin, for the purpose of plundering the country early the next morning; but when O'Flaherty of Iar-Connaught, and the other enemies of Hugh O'Conor, had heard that the English were here stationed with the intention of plundering Eoghan O'Heyne, they did not neglect their friend, but marched, as the Four Masters state, “with one mind and one accord,” until they came to a place near Ardrahin, where they halted, and having held a consultation, they came to the resolution of sending Tuathal, the son of Muircheartach, and Taithleach O'Dowd,

O'Dowd, with a strong force, to Ardrahin, while O'Flaherty and the son of Muircheartach O'Connor were to remain with their forces outside. The two O'Dowds, with their soldiers, marched courageously and boldly into the town of Ardrahin, and made a vigorous and desperate attack upon the English, whom they put to flight east and west. The party who fled eastwards were pursued by the O'Dowds, and the constable, or captain of the English received two wounds, one from the javelin of Tuathal O'Dowd and the other from that of Taithleach, which left him lifeless; but the party who fled westwards met O'Flaherty and the son of Muircheartach O'Connor, and routed them to their misfortune. After this the sons of Roderic and their supporters made peace with Hugh O'Connor and his friends, which the annalists remark was an unreasonable peace, as there was no church or territory in Connaught at the time that had not been plundered or laid waste!

In ten years after this we find this Eoghan on the warmest terms of friendship with the English. In the year 1235 he joined Richard, the son of William Burke, in his famous expedition into Connaught, on which occasion he rendered the English great services both by his deeds and counsel, as will appear from the following simple narrative, extracted by the Four Masters from the older annals:

"A. D. 1235. Richard, the son of William Burke, assembled the English of Ireland, the most illustrious of whom were the following, viz.—Fitz-Maurice, Lord Deputy of Ireland; Hugo De Lacy, Earl of Ulster; Walter Rittabard [Riddlesford], Chief Baron of Leinster, who commanded the English of Leinster; and the Lord John Cogan, with the English of Munster, together with all the Roothes of Ireland. They crossed the ford of Athlone, and set fire to the town; then going to Elphin they burned the great church there, and proceeded from thence to the monastery of Ath Dalaarg [Boyle], on the River Boyle, on the eve of Trinity Sunday. Parties of their soldiers entered the monastery, broke into the sacristy, and carried away chalices, vestments, and other treasures. But the English nobles were highly incensed at this conduct [*of the soldiery*], and sent back as many of those articles as they found, and made restitution for such as they could not find. On the next day they sent forth parties to Creit, to Cairthe Muilchenn [now Glencar], and to the tower of Glenfarne, marauding, who carried off great spoils from those places to the Lord Deputy's camp at Ardcarne. Here the English held a private consultation at the request of Eoghan O'Heyne (who wished to be revenged on the Momonians, and particularly Donnchadh Cairbreach O'Brien), and determined on returning back through Hy-Many and Moinmoy, and passing thence into Thomond, without giving the Momonians any notice of their intentions. This they accordingly did, and committed great depredations. When Felim, the son of Cathal Croibhdhearg O'Connor, saw that the English had passed out of his territories,

he

he held a council, and it was resolved that he should march with his troops in aid of the Momonians. On their arrival in Munster they had daily skirmishes with the English. At length a pitched battle took place, in which the united forces of the Connacians and Momonians fought bravely against the English, but the English troops, consisting of infantry and cavalry, who were all clad in armour, at length vanquished them, and killed numbers both of the Connacians and Momonians, but especially of the latter, in consequence of the imprudence of Donnchadh Cairbreach O'Brien. The Connacians then returned home, and on the day following O'Brien made peace with the English and gave them hostages. The English then returned to Connaught, and went first to Aodh O'Flaherty, who made peace with them rather than that they should plunder his people and carry off his cattle.

"Felim, the son of Cathal Croibhdhearg, finding himself beset with dangers, then resolved on taking with him to O'Donnell [Domhnall Mor] all the cows belonging to those who should be willing to take his advice in the territories of Conmaicne Mara and Conmaicne Cuile, together with the son of Maghnus and Conchobhar Ruadh, the son of Muircheartach Muimhneach O'Connor, and leaving the whole country desolate to the English. The English, on discovering what he had done, advanced to Dun-Mugdord, whence they despatched messengers to Maghnus, the son of Muircheartach Muimhneach, to demand hostages from him, but Maghnus refused to give them either peace or hostages. The English then sent forth from Dun Mugdord a numerous army against the sons of Roderic O'Connor, which plundered Achill and carried great spoils to Druimni. In the mean time Aodh O'Flaherty and Eoghan O'Heyne came round with their numerous forces, who carried boats with them as far as Lionan Cinn mhara [now Leenaun], and thence to Druimni, to meet the Lord Deputy at the Callow of Inis Aonaigh [Inisheany]. Maghnus at this time was with his ships on the water close to the island, where he and the English had frequent engagements. But the English gave him rest for awhile: they repaired to their camp, where they found the boats which had been carried round by O'Flaherty and O'Heyne*, and carried them

* Roderic O'Flaherty, in his unpublished account of West Connaught, written for Sir William Petty's intended Atlas, says that the boats of Lough Orbsen (now Lough Corrib), were carried by land on this occasion from Bunbonan, on Lough Orbsen, to Iomaire, on Lionsain, a distance of five miles [*recte* six miles and a half]. His words are, "Imaire an linain, anciently Linan Kinn mara, is
IRISH ARCH. SOC. 12.

a long green spot of land by the sea of Coelshalyroe [now Killary], whither the boats of Lough Orbsen were drawn by the forces of West Connaught and Hy-Fiachry Aidhne from Bonbona to the sea for five miles, anno 1235, to invade the sea islands there, upon an expedition into the Owles by Maurice Fitz-Gerald, Lord Justice of Ireland; Richard De Burgo, Lord of Connaught;

them to a large strand near the place where Maghnus was. When Maghnus had perceived the boats, he landed on Inis raithin, and sent a party of his people to the island of Inis Aonaigh. But when the English perceived Maghnus and his people landing on these islands, they launched their boats, and troops of well-armed mail-clad soldiers, and landing on the island on which Maghnus's people were, and also upon Inis raithin, on which Maghnus himself was, they killed all the people they found on them. Maghnus and those who were with him on Inis raithin went into their ships and fled from the island; but had Maghnus been on friendly terms with the O'Malleys they would have sent their fleet against that of the English. There was not a cow upon one of the Insi Modha islands [the islands of Clew Bay] which the English did not carry off to the main land in one day, and those from whom they had been taken would have been obliged to come off their islands in consequence of thirst and hunger had they not been taken prisoners.

"Many of the common people were put to death on that night by the English, who, on the next day, being Friday, landed on the islands north of Umhall, and the chiefs of the army issued orders that no people should be put to death on that day in honour of the crucifixion of Christ. After they had plundered and devastated Umhall, both by sea and land, they marched on with their spoils to Luffertane, thence they advanced to Ballysadare, where they plundered O'Donnell for having afforded refuge to Felim O'Connor after his expulsion. From thence they moved to the Curlious and to Caladh Puirt na Cairge, on Lough Key, to attack a party of the people of Felim O'Connor, who were defending that place. On this occasion the English of Ireland and the Lord Deputy spared and protected Clarus Mac Mailin, herenach of Elphin, and the canons of the island of the Blessed Trinity, and the Lord Deputy himself and the chiefs of the English went to see that place, and to kneel and pray there. The English afterwards, with great art and ingenuity, constructed wonderful engines by means of which they took the fortress called the Rock of Lough Key from the people of Felim and Cormac Mac Dermot, and the Lord Deputy left guards in it with plenty of provisions and beer. On this expedition the English left the Connacians bereft of food, raiment, and cattle, and the country of peace and tranquillity; the Irish themselves plundering and destroying each other. The English, however, did not receive hostages or pledges of submission on this occasion. Felim made peace with the Lord Deputy, and the English gave him the five cantreds belonging to the king, without cattle, but free from tribute."

In

Hugh De Lacy, Earl of Ulster; the Lord Walter Riddlesford, with the English forces of Leinster, and the Lord John Cogan, with the English forces

of Munster, in pursuit of a party of O'Connors, belonging to Felim O'Connor, King of Con-naught."

In the year following, 1236, we find this Eoghan O'Heyne in opposition to Felim O'Connor, and assisting Brian, the son of Turlogh O'Connor, who had been set up as king of the Irish of Connaught by the English. He died, according to the Four Masters, in 1253.

29. *John, son of Eoghan O'Heyne.*

30. *Aodh, or Hugh, son of John O'Heyne.*

31. *Donnchadh, or Donogh, son of Hugh O'Heyne.*—The Irish annalists preserve no historical notice of the three last generations. At the year 1261 the Four Masters state that Maelfabhaill, or Mulfavill O'Heyne, slew Hugh, the son of Maolseachlainn O'Connor; and at 1263, that he was himself slain by the English; and at 1326 they notice the death of Nicholas O'Heyne; but nothing remains to show how these stood related to the generations above given. This Donnchadh had two sons, namely, Eoghan, who became lord of the Hy-Fiachrach Aidhne, and was slain, according to the Annals of the Four Masters, in the year 1340 by his own kinsmen, and Muircheartach O'Heyne, by whom the line was continued.

The Irish annalists preserve but very few notices of this family from the year 1340 to 1578. At the year 1377 Mac Namara and his people of Clann Coilen defeated the people of Clanrickard, and slew Theobald, son of Ulick Burke, the commander of a great body of Kerns, and O'Heyne's three sons, with many others of the chiefs of Clanrickard.—*Ann. Clonmacnoise.*

In the year 1407 O'Heyne joined Mac William Burke of Clanrickard, and Cathal, son of Rory O'Connor, King of Connaught, and fought the battle of Killaghy against O'Connor Roe, but they were defeated and taken prisoners. The annalists do not give us the Christian-name of the O'Heyne here mentioned, but we may conjecture that he was No. 33 in the pedigree, namely, Aodh Buidhe, the son of Muircheartach.

32. *Muircheartach, or Murtoth, son of Donogh O'Heyne.*

33. *Aodh Buidhe, or Hugh the Yellow, son of Muircheartach O'Heyne.*

34. *Brian, son of Hugh the Yellow, O'Heyne.*

35. *Conchobhar, or Conor, son of Brian O'Heyne.*

36. *Flann, son of Conor O'Heyne.*—He had four sons, who became the founders of four distinct septs, namely, 1, Edmond, the ancestor of the succeeding chiefs, except two; 2, Ruaidhri na Coille, i. e. *Rory or Roger of the Wood*, who became chief of the Hy-Fiachrach Aidhne, and died in the year 1578, as we learn from the Four Masters:—“A. D. 1578. O'Heyne (Ruaidhri na Coille, son of Flann, son of Conchobhar) died. He had been distinguished for his hospitality and activity in the use of arms from the beginning of his career until he was summoned from this world. His fraternal nephew, Eoghan Mantach, son of Edmond, was elected to his place.” 3. His third son was

Aodh Buidhe, the ancestor of O'Heyne of the castle of Dunowen ; and, 4, Flann O'Heyne, the ancestor of O'Heyne of the castle of Dun Guaire.

37. *Edmond, son of Flann O'Heyne*.—Nothing is recorded of this O'Heyne except that he was the father of,

38. *Eoghan Mantach O'Heyne*.—He succeeded his uncle, Ruaidhri na Coille, as chief of the Hy-Fiachrach Aidhne, in 1578. The following order of the Council of Connaught in his favour is worth inserting here, as throwing curious light upon the history of property at this period.

“ *Order of Council of Connaught*—1586.

“ WHEREAS, it is given us to understand that Owen Mantagh O'Hein of Lydegane, in the barony of Kiltaraght, within the co^y of Galway, chiefe of his name, is seized amongst other lands of the q^r. of land called Caherkearney, & the q^r. of Cratnagh, w^{ch}. 2 q^{rs}. by a reason they were not presented unto us, are not comprised within the Indentures of her Majt^y. Composition, & for as much as by the said Indentures there was no freedom provided for the said Owen, and that by his own confession & presentment yt is found owte the s^d. twoe q^{rs}. of land to be concealed and not presented as afforesaid, whereby he is the better worthie to engage the same. It is therefore condecended, granted & agreed in considⁿ. of the premises that the s^d. Owen Mantagh O'Hein shall possess s^d. lands discharged of her Mat^{ies}. Composition Rent. Given at Dublin the 13th of May, 1586.

“ RICH^d. BINGHAM.

THOMAS DILLON.

THO^s. C. STRANGE.

GEORGE COMERFORD.”

NICHO. WHITE.

This Eoghan Mantach, or Owen the Toothless O'Heyne, died in the year 1588, as we learn from the Four Masters. “ A. D. 1588. Eoghan Mantach, son of Edmond, son of Flann, son of Conchobhar O'Heyne, lord of Hy-Fiachrach Aidhne, died, and his son Aodh Buidhe [Hugh the Yellow] was elected to his place.”

39. *Aodh Buidhe, or Hugh Boy, the son of Eoghan Mantach O'Heyne*.—Upon the surrender of his property he received a grant of an extensive estate in the original territory, as will appear from the following curious document extracted from the fourth file of Fiants :

“ A Graunte unto Hughe Boy O'Heine, sonne and heire of One [*Owen*] O'Heyne of Ledigan, in the coy. of Gallway, within the province of Conaght, upon his Surrender, bearing date the 22nd of July. in the xxxth yeare of her Ma^{ties}. raigne, of 33^s. 4^d. Sterlinge yerely, chief rent going out of three q^{rs}. of lande in Crannaghe, of one q^r. of lande

lande in Clonchie, of one q^r. of lande in Cahern, one q^r. of lande in Cahircarne, one q^r. of lande in Crossye, and two q^m. of lande in Rahassane; and also 33^s. 4^d. Ster. chiefe rent yerely goinge out of one q^r. of lande in Sisselleidigan, one q^r. of lande in Tuelgon, one q^r. of lande in Corveighe, one q^r. of lande in Kintierleveigh, and one quarter of lande in Dunguoir in th' aforesaid Countie: also 33^s. 4^d. chiefe rent yerely goinge out of one q^r. lande of Cahirkillen, one q^r. of lande in Caherglassane, one q^r. of lande in Keppaghbeg, one q^r. of lande in Cahermadorishe, one q^r. of lande in Powleneveigh, and one q^r. of lande in Rahalben in th' aforesaid Countie; also 33^s. 4^d. Ster. chiefe rent yerely goinge out of one q^r. of lande in Ballibuige, one q^r. of lande in Lawghcoure, one q^r. of lande in Kiltwyne, and one q^r. of lande in Caherscarlie in th' aforesaid countie; also fortie one shillings foure pence Ster. chiefe rent yerely goinge out of one q^r. of lande in Ballevanegrane, one q^r. of lande in Monescrib, one q^r. of lande in le Mey, one q^r. of lande in Fonchenbeg, one q^r. of lande in Keapaghmore, and one q^r. of lande in Clogher in th' aforesaid countie: also 35^s. 8^d. Ster. chiefe rent yerely going out of one q^r. of lande in Knocklegan, one q^r. of lande in Gortevallaile, one q^r. of lande in Dromyn, one q^r. of lande in Trelick, one q^r. of lande in Fonshenmore, one q^r. of lande in Rewe, one q^r. of lande in Dowres, one q^r. of lande in Townaght, one q^r. of lande in Agard, one q^r. of lande in Balliglara, one q^r. of lande in Killily, and one q^r. of lande in Cloneste in th' aforesaid countie—Summa total. x^l. Ster. to the said Hughe O'Heine and his heires and assignes for ever per servicium Militare, viz. per servicium xx^l. partis unius feodi Militis.—Solve jure cujuslibet. Deliberat. in Canc. Hibernie xxiii Julii an. r. R. Eliz. xxx°,—tempore Wil. Fitzwilliams.”

This Aodh Buidhe, or Hugh Boy O'Heyne, died in the year 1594, as we learn from the Four Masters:—"A. D. 1594. O'Heyne (Aodh Buidhe, son of Eoghan Mantach, son of Edmond, son of Flann) died." This is the last notice of the O'Heyne family given in the Annals of the Four Masters; but Duald Mac Firbis gives two generations more of the pedigree of the family of Lydigane, which carry the line down to his own time, A. D. 1645-1666. These generations are,

40. *Aodh Buidhe, son of Aodh Buidhe O'Heyne.*

41. *Eoghan, son of Aodh Buidhe O'Heyne, of Lydigane.*

From the Civil Survey, preserved in the Custom-House, Dublin, it appears that the following persons of the name of O'Heyne were living in the barony of Kiltartan in 1641, principally in the parish of Dawros Kinvara:

Edmond Owen O'Heyne, in Corboy.

Conor O'Heyne, in Kinturly.

Flan Boy O'Heyne, in Kinturly.

Car.

Car. Turlogh and Farro O'Heine, Ibidem.
 Flan Boy O'Hene, in Lissurduffe and Tomareagh.
 Teige and Edmond O'Hene, in Moinskaebo and Moigh.
 Owen O'Hene, in Funchinmore.
 Hugh O'Hene, in Corcarney.
 Flan mac Edmond O'Hene, in Loughcurro.
 Farro O'Hine, in Balligilligagh and Corconnogh.
 Turlo O'Hine, in Cappamore.
 Edmond O'Hine, in Drumon.
 Teige Reagh O'Haine, in Ballimachakill.
 Car. Henry O'Hene,
 Donogh O'Heyne, } in Shragh and
 Owen mac Teige Moyle O'Heine, } Ballinaghan.
 Lawyhewre O'Heine,
 Hugh Boy O'Heine, in Carrocurra and Crannan.

Dominick Darcy of Clonuan, Gent., by his Will (now preserved in the Prerogative Court, Dublin), dated 1st August, 1666, bequeaths to his brother [half brother?] Farragh O'Heyne, during his life, the cartron of Kilboren, and five pounds sterling; to his brother Flan O'Heyne three pounds, and the like to his brother Owen O'Heyne.

John Hynes, Esq., of the New Quay, in the barony of Burren, in the north of the county of Clare, who has acquired a handsome property by honest industry, is descended from Flan Boy O'Heyne of Kinturly, now Kinturlough, mentioned in the above list, from whom the generations to the present day will be seen in the following line:


1. Flan Boy O'Heyne of Kinturlough, living in 1641.
 2. Peter O'H.
 3. Brian O'H.
 4. John Hynes, died 1746.
 5. James Hynes, died 1802.
 6. John Hynes, now living, born 1785.
-
7. James. 7. Dr. Patrick of London. 7. Thomas, died 1841. 7. Michael of Kinvara, merchant. 7. John.

PEDIGREE

E.

PEDIGREE OF MAC FIRBIS.

This family were originally seated in Magh Broin, in Tirawley. They were afterwards removed to Rosserk, on the west side of the Moy, in the same territory, but when the Barretts drove the O'Dowds out of Tirawley, Mac Firbis was fixed at Lecan in Tireragh. They had the privilege of holding the rod over O'Dowd at his inauguration, and of drinking at the banquet even before the acknowledged senior of the race, O'Caomhain.—See pp. 140, 141, 142. The pedigree of this family, as given by Duaid Mac Firbis in 1666, is many generations defective, and cannot be depended upon except for about the last twelve generations. Strange! that this family, who were the hereditary historians to the O'Dowds, while they preserved so much of the history of other families, should have left us so imperfect and uncertain an account of themselves. The following is the part of this pedigree which the Editor believes to be trustworthy :—



Our

Our writers have preserved but few notices of this family. The following are all that the Editor has been able to collect :

"A. D. 1279. Giolla Iosa Mor Mac Firbis, Ollav of Tireragh, died."—*Four Masters*.

"A. D. 1301. Gille Issa Mac Firvissie, chief chronicler of Tyrefiaghach, wonderful well-skilled in histories, poetry, computation, and many other sciences, died."—*Ann. Clonmacnoise*.

"A. D. 1376. Donnchadh Mac Firbis, a good historian, died."—*Four Masters*.

"A. D. 1379. Firbis Mac Firbis, a learned historian, died."—*Four Masters*.

"A. D. 1417. Giolla Iosa Mor Mac Firbis was chief historian to O'Dowd of Tireragh, and composed a long topographical poem on the tribes and districts in the ancient territory of his ancestors."—*Duald Mac Firbis*.

"A. D. 1450. Eugene O'Cormyn and Thady Mac Firbis, Eremites of the order of St. Augustine, received a grant of the lands of Stormor, in Tirawley, from Thady O'Dowd, to erect thereon a monastery under the invocation of the Holy Trinity, and Pope Nicholas the Fifth confirmed the same by a Bull dated 12th December, 1454."—*Archdall, from Meagher*.

"A. D. 1560. Ciothruadh and James, the two sons of Diarmaid Caoch Mac Firbis, and their cousin-german John Og, the son of William Mac Firbis, built the castle of Lecan in Tireragh."—*Duald Mac Firbis*. *Vide supra*, pp. 168, 169.

"A. D. 1672. Duald Mac Firbis, the last of the hereditary antiquaries of Lecan, was murdered at Dunfin."—*Ch. O'Conor of Belanagare*.

The present representative of this family is supposed to be John Forbes, a small farmer living in the parish of Lacken, near Killala, and barony of Tirawley. He descends from one of the brothers of Duald, the last of the antiquaries, and he has lately addressed the following letter to the Royal Irish Academy, which is inserted here for the sake of the particulars it contains of the writer's family, and as a curious assertion of his claim to be the representative of the ancient antiquaries :

"*To the Honourable the President and Associates of the Royal Irish Academy.*

"The Memorial of John Mac Firbis of the parish of Lacken, in the county of Mayo, farmer,

"RESPECTFULLY SHOWETH,

"That Memorialist is descended from the family of Mac Firbis of Lecan—Mac Firbis, in the county of Sligo, hereditary antiquaries of Connaught, being the fifth in descent from the younger and only brother of Duald Mac Firbis, the last of the antiquaries of the family, who was brutally murdered in the county of Sligo.

"That

"That the sisters of said Duaid retired into Spain, where they ended their lives in a convent, whilst his younger brother, the ancestor of memorialist, was dispossessed of the property of Lecan Mac Firbis, since which period memorialist's family have lived in poverty and indigence.

"That memorialist has been informed that a work on Irish antiquities called the Book of Lecan, written by one of memorialist's ancestors, is now in the Library of your honourable Society, together with the copy of another work of like nature, composed by the aforesaid Duaid Mac Firbis, of which his family was deprived at the period of his murder.

"Although the lands of Lecan Mac Firbis have passed away for ever from memorialist's family, yet he humbly hopes, from the honour and humanity of the Noblemen and Gentlemen composing the Royal Irish Academy, that he will be allowed some consideration for these works of his ancestors, which now, as memorialist believes, form a prominent portion of ancient Irish history.

"Memorialist is in a state of humble poverty, and respectfully submits his case, my Lords and Gentlemen, to your humane consideration.

"And will for ever pray.

"*Dublin, 15 Aug., 1842.*"

F.

ST. FIACRE.—THE MUAIDH.

Page 2, Note c.—The proper name Fiachra, making Fiachrach in the genitive case, which occurs so often throughout this volume, is well known on the Continent as that of a celebrated Irish saint, the site of whose hermitage near Meaux was deemed so sacred that to go on a pilgrimage thither was, to a late period, a frequent practice; and we are told of the pious queen Anne of Austria, that when she visited the shrine of this saint in 1641, so great was the humility of her devotion that she went the whole of the way from Monceau to the town of Fiacre on foot.

"L'ermitage de Saint Fiacre est devenu un bourg de la Brie, fameux par les pèlerinages que l'on y faisait; l'église ou chapelle étoit desservie par les Bénédictins; les femmes m'entroient point dans le sanctuaire, et l'on remarque que la Reine Anne d'Autriche, y venant en pèlerinage en 1641, se conforma à cet usage, et qu'elle fit même à pied le chemin depuis Monceau jusqu'à Saint-Fiacre"—*Hist. de Meaux*—quoted by Moore in his *History of Ireland*, vol. i. p. 278, who also quotes from "another work," which he does not name, relating to this saint:—"On a prétendu que le nom de Fiacres avait été donné aux carrosses de place, parcequ'ils furent d'abord destinés à voiturier jusqu'à St. Fiacre (en Brie) les Parisiens qui y allerent en pèlerinage."—See Butler's *Lives of the Saints*, in Aug. 30. Mabillon *Acta SS. Ord. S. Bened.* tom. ii. and the Bollandists.

Ibid.—*The Muaidh, called Moda by Adamnan.*—The learned Dr. Prichard, in his Ethnography of the Celtic race, being misled by the inaccurate work on Ireland by Dr. Wood, states that the Moda of Adamnan is Wexford harbour, and concludes that the Milesian story was written after the seventh century. The following are his words:—“The Milesians arrived in Ireland 1300, B. C., at Inmhear Slainge, or Wexford harbour, the name of which is a *proof* that the Milesian story was written after the seventh century, since in the second that place was called ‘Modoni ostia’ by Ptolemy, and in the seventh Moda by St. Adamnan.”—Sect. XII. Par. 2.

Whatever truth or falsehood there may be in the Milesian story, this argument is too weak and unfounded to destroy it. The words of Adamnan are as follows, and they clearly show that he meant no other than the present River Moadh, or Moy:—“*Alio quoque in tempore de Cormaco nepote Lethani, viro utique sancto, qui tribus non minùs vicibus eremum in Oceano laboriosè quæsivit, nec tamen inuenit, Sanctus Columba ita prophetizans ait: hodie iterum Cormac desertum reperire cupiens, enauigare incipit ab illa regione quæ ultra Modam fluvium sita, Eirros domnonn dicitur: nec tamen etiam hac vice quod quærit inveniet; et non ob aliam eius culpam, nisi quod alicuius religiosi Abbatis Monachum, ipso non permittente, discessorem secum non rectè comitari, navigio suscepit.*”—*Vit. S. Columbæ, Cap. VI. De Sancto Cormaco. (ap. Colgan. Tr. Thaum. p. 340.)*

On the situation of the River Moda Colgan adds the following note, which is an additional authority against the opinion that the Moda of Adamnan was the harbour of Wexford:—“*Fluvius est Connaciæ celebris, vulgo Muaidh, et nobis latinè Moadus, sive Muadus appellatus.*”

On the situation of *Eirros domnon*, which lies beyond the River Moda, Colgan says:—“*Eirros—Est regio Occidentalis Connaciæ vulgò Irros chlann Domnann appellata.*”

Now, as the River Moda of Adamnan is not the harbour of Wexford, where is the argument to prove that Inbher Slainge, the name of the mouth of the River Slaney, is not older than Ptolemy’s time? Where is the proof that the Modoni ostia of Ptolemy is the mouth of the Slaney?—See *Ogygia*, p. 17, where O’Flaherty writes:—“*Nec qui nunc Slanius Modono, aut alio quàm Slanio nomine cognitus à Belgarum ingressu multis seculis ante Ptolemæi natales.*” It is much more likely that the Modonus of Ptolemy is the bay of Bannow, which is said to have been anciently a safer harbour than that of Wexford.

G.

SITH BUDHA.

Page 6, Note 1.—*Sith Budha*, i. e. the hill of Budh. There were three or four celebrated hills of this name in Ireland, which were believed to have been haunted by fairies

fairies or demons; but it would appear from the Life of St. Cormac, as given in the Book of Lecan, and published in a Latin translation, by Colgan in *Acta SS.* that the Sith budha here referred to was in Tirawley. Speaking of Muireadhach, from whom sprung the O'Muireadhaigh of Tirawley, this life has the following words:—"ex cujus semine nobilis familia Muredaciorum in eadem regione olim potens." We find in it also the following curious reference to this hill:—"Ad ejus [sc. Cormaci] etiam Ecclesiam, tanquam ad tutum refugium [seu] asylum, uxor prædicti Aengussii, nomine Saba filii Fieschrii Finni, a quo Fiachrorum familia in regione Amalgadiæ, duxit suum filium Muredacium nomine, læthali contagione percussus, quam contraxit ex quadam pestilenti exhalationi, quæ promanabat ex monte quodam Sith Badha [*recte* Sith Budha] vulgo nuncupato, et dæmonum infestationibus infecto."—*Colgan, Acta SS.* p. 754

H.

THE ANCIENT LEATHA.

Leatha.—See pages 18, 19, *Note* *.—It has been much disputed by modern antiquaries what district the ancient Irish writers designated by the name *Lethu*, or *Leatha*. The translator of Fiech's Hymn on the life of St. Patrick has rendered it *Latium* in the fifth, sixth, and ninth quatrains, but Mr. Patrick Lynch, in his Life of St. Patrick, and after him Lanigan and Declan, have laboured to prove that *Leatha* was never applied to *Latium*, but was a hibernicised form of *Letavia*, the name by which a part, and sometimes the whole of Armoric Gaul was called by the writers of the middle ages. Lynch, after stating that the translator of Fiech's Hymn was in error in understanding *Letha* as designating *Latium*, or Italy, writes as follows, pp. 77, 78:

"The truth is, that the word *Lethu*, in all parts of the Irish hymn where it occurs, should have been translated into *LETAVIA*, the name by which a part, and sometimes the whole country of Armoric Gaul was called by the writers of the middle ages.

"In according to that, the old scholiast on this hymn says, that 'all St. Patrick's family went on commercial business beyond the Iccian sea towards the south to Lethanian Aremorica, or Letheacensian Britain; but at that time the seven sons of Fechtmund being banished from Britain (*Albion*) were committing depredations in *Letha*, a district of Aremoric Gaul'.

"In the life of St. Ailve, Bishop of Emly, in Momonia, or Munster, and not in *Menavia*,

* "Omnes (nempe sancti Patricii consanguinei) simul ex Britannia Alcludensi trans mare Iccium versus austrum negotii causa contulerunt se ad Armoricam Lethanam sive Britanniam Letheacensem. ——— Eo autem tempore septem filii

Fechtmodii regis Britonum erant relegati a Britannis: et fecerunt prædas in Britannia Armorica regione Letha, ubi Patricius cum familia fuit."
—*Scholiast on St. Fiech*, No. 5.

Menavia, or St. David's, as Cambrensis would have it, it is recorded that 'Sampson was Bishop of Dal Omhoir, in the remotest frontiers of Letha,' that is, says Doctor Langhorne, 'the city of Dol, in Bretayne, or *Lethania* Aremorica, for,' continues he, 'Aremorica was also denominated Letha, or Lethania'.

"To the above we shall only add the testimony of Camden, who states that 'this district, previously to the arrival of our countrymen from Britain, was originally called *Aremorica*, that is, *near the sea*, in the British dialect *Llydaw*, importing also its maritime situation, *lying on the coast*; and in Latin *LETAVIA*, among the writers of the middle age; whence its inhabitants, I suppose to be the *LETI*, a people of Gaul mentioned by Zosimus; and, lastly, it was denominated *Britannia Minor*, or Little Britain, from our British compatriots who settled there'."

This reasoning would seem to be borne out by the Irish translation of Nennius, in which "Brittones Armorici" is rendered by the Irish "Óreatain Leata," i. e. the Britons of *Leatha*, as in the following passage:

"Septimus imperator regnavit in Britannia Maximianus. Ipse perrexit cum omnibus militibus Brittonum a Britannia, et occidit Gratianum regem Romanorum, et imperium tenuit totius Europæ, et noluit dimittere milites, qui perexerunt cum eo, ad Britanniam ad uxores suas, et ad filios suos, et ad possessiones suas; sed dedit illis multas regiones, a stagno quod est super verticem Montis Jovis usque ad civitatem quæ vocatur Cantguic, et usque ad Cumulum occidentalem, id est, Cruc Ochidient. Hi sunt Brittones Armorici, et nunquam reversi sunt huc, usque in hodiernum diem."—*Historia Britonum*, Stephenson's edit., pp. 20, 21.

Thus rendered by the Irish translator in the Book of Ballymote and H. 3. 17.

"Maximian po gab riḡ Óreatain, "Maximian succeeded to the govern-
ocur rug plogu Óreatain a Románcaib, ment of Britain; and he led the forces of
co coróair lair ḡreatain in t-imper, Britain into the country of the Romans,
and

^b "Ex hoc tempore, ut obiter id notemus, Sampsonem, cujus antea meminimus (*ex vita Ailbei*) fuisse Episcopum civitatis quæ vocatur Dol omhoir in extremis finibus Letha, id est, Dolensis civitatis in Britannia Armorica Lethana, in ejusdem Ailbei vita legimus; nam Aremorica etiam Letha et Letavia nuncupata est."—*Chronica Reg. Angl.* p. 22, a Dan Langhornio, Lond. ed. 1679.

^c "Ante Britannorum nostrorum adventum, hæc regio primum *Aremorica* dicta erat .i. ad mare

sita; deinde Britannicè *Llydaw* .i. Litoralis, latine *LETAVIA* apud nostros mediis statibus scriptores, unde Letos fuisse suspicor quos in Gallia nominat Zosimus, postremo *Britannia Minor* a Britannis nostris, qui, ut est apud Nennium, tenuerunt regiones a stagno quod est super montem Jovis usque ad civitatem quæ vocatur Cantguic, et ad cumulum occidentalem .i. Cru Ochidient, ut ex Rutilio Claudio et Ægidio Masserio colligi possit."—*Cambd. Brit.* 66.

ocur po gab féin nigi na h-Eorpa; ocur ní po léig uao na pluais nuz leir do cum a m-ban, ocur a mac, nacha fearann, áct do pas fearanna imoa doib ó tha in loch fíl immullach Sleibí loib co Canacuic bu deap, ocur riar co Duma Oichiden, aic a fuil in Chpor earigna. Ocur if iao rin dheatain Leata, ocur taparair tear do ghear.”

and Gratian, the Emperor, was slain by him, and he himself assumed the government of Europe, and he did not permit the forces which he had brought with him to return to their wives, sons, or lands, but he gave them many lands [in the region extending] from the lake which is on the summit of Mount Jove, southwards, to Canacuic, and westwards to the mound of Oichiden, where the grand cross is situated. And these are the Britons of Leatha, and they remained always in the south.”

It looks strange that the Irish translator here seems to take the Welsh word *cruc*, a hill or mound, for the Latin word *cruz*, a cross, and understands *Cruc Ochidient*, which Nennius intended as a Welsh translation of *cumulum occidentalem*, to signify “where the grand cross is situated !”

But it must nevertheless be confessed that in the *Felire Aenguis*, at the 27th of June, the city of Rome is styled “*Ruaim Leata*” in the original text, and *Leata* is explained in the Gloss by the Latin *Latium*, “*Leata, a nomine Latium.*” Also in a very ancient Irish stanza quoted in the same work, Pope Gregory the Great is styled “*Abb Róma Lecha*,” i. e. Abbot of Rome of Letha. These authorities are sufficient to defend the translator of *Fiech’s Hymn* against the criticism of Lynch and his followers Lanigan and Declan. The following authorities are also submitted to the reader on this very curious question :

“If ann rin do cuais Patruic do fogluim eacna agur crabus 1 n-oir-theap vercepte Eatale co German eppcop. iap rin po fucc in e-aingeal e 1 n-Abporic Lecha cur in caepaig dianao ainim Capua 1 Sleib Armoim, rupeir nupam mapir Teppeini.”
— *Vit. Patricii*, in *Leabhar Breac*, fol. 13, b.

“Then Patrick went to learn wisdom and religion in the south-east of Italy, to German the Bishop. Afterwards an angel conducted him to Armoric Letha to the city named Capua, at the mountain of Armoim *super ripam maris Tyrrheni.*”

Duald Mac Firbis has the following notices of this name :

“Focan daoine Phatruig, .i. Patruig

“The cause of Patrick’s slavery was this.

αγυρ α ατάιρ, αγυρ α μάταίρ, αγυρ α όύιγ
ρεατέρα, .i. λυπαίτ, Τιγριρ, Ραϊκέλλ, Οε-
ρερκα, Cinnenum, αγυρ α βραταίρ, .i.
δεόχυν Samian, οο έυασορ υίλε α
δρεαένυις Αίλ Κλυαίτε ταρ Μυιρ η-λέτ
φο οεφ φορ τυρρυρ γο δρεαένυις Αρ-
μυιρς Λεατά, .i. γο δρεαένυις Λεθεός,
άρ πο βάταρ βράιτερ οόις ανν αν ταν
ρην. Αγυρ Ρα οο Φρανγκοίς μάτοιρ
να κλαρμε, .i. Coinceρ, αγυρ βα ριυρριθε
κοιβεαρφα οο Μαρταιν. Αγυρ αρ ι ρην
αιμυιρ πο βάταρ ρεττ μεις Σεττμαίτε,
.i. ριγ δρεταν φορ longg ó δηρεατναίτ.
Οο ρονρσος τρα κρετ μοιρ ι η-δρεα-
ένυις Αρμυιρς Λεατά, βαίλε α η-βοί
Ρατραιγ κο η-α μινναιρ, γc.”

“Τειτ Ρατραις ιαρυμ γο ραίβε λα
Γερμαν ab, α η-οεαρ ι η-οεργερε
Λεατά (ην αυτρηλί ραρτε Gallorum
ιuxta Mare Tennenum). Λεατά, .i.
Italia, Λεατά α λατετυοινε. Γερμαν,
abb ηα καέροτ οαρ ab αιημ Αλτι-
οορρυρ, αρ αιγε πο λέξ Ράτραιγ, αγυρ
δυργυνια αιημ ηα κεανναίτε ρ ο-τά ην
οαταίρ ρην ην γαλλιρ ; γοματ ι η-ηννις
Μαρη Τοιρρην ρην μαρ αρρερε Ριαγ
Σλεδτε,

“In-ηννις μαρη τοιρρην,
Αιηιρ ηννις αο ριμε,
Λευγαίρ κανοιη λα Γερμάν,
Αρεατ αο ριαδασ ιινε.

“Ocyρ Alanenριρ αιημ ηα καέροτ πο
ηα ηιηνρι ρην αρ Μυιρ Τοιρρην.”

this. Patrick, with his father, mother,
and five sisters, Lupait, Tigris, Raichell,
Dererca, and Cinnenum, and his brother
Deochuin Samian, all went from Britain
of Ail Cluath, southwards, across the Iccian
sea, to the Britons of Armuiric Leatha,
that is, to the Britons of Letheoc, who
were their kinsmen at that time, and the
mother of these children was of the Franks,
namely, Coinces, a near relative to St.
Martin. This was the time that the seven
sons of Sechtmad, King of Britain, were
in exile from Britain. They committed
a great depredation on the Britons of Ar-
muiric Leatha, where Patrick and his
people were, &c.” — *Duald Mac Firbis*,
MS. Geneal., p. 692.

“Patrick afterwards went southwards
to German, in the south of Leatha (in
australi parte Gallorum juxta Mare Ter-
renum). Leatha, i. e. Italia; leatha a la-
titudine. German was abbot of the city
named Altiodorus; it is with him St.
Patrick read; and Burgunia is the name
of the principality in Gaul, in which this
city is situated; and this is in the islands
of the Tyrrhenian sea, as Fiag of Sletty
says,

“In the islands of the Tyrrhenian sea
He resided, as is related,
He reads his canons with German,
As is certified by us.

“And Alanensis is the name of the city or
island in the Tyrrhenian sea.” — *Id.* p. 693.

It should be also remarked that in the Book of Lismore, and in the Book of Fenagh
the city of Rome is called Róim Λεατά, i. e. Rome of Leatha, from which it is quite
clear

clear that by *Leatha* the writers of these works meant *Latium*, which was the ancient name of that district of Italy, in which the city of Rome is situated.

I.

SAINT CEALLACH.

Pages 33-35.—This Ceallach, who was the eldest son of Eoghan Bel, King of Connaught, was educated by St. Kieran of Clonmacnoise, and became a bishop at Kilmore-Moy, in Tirawley; but he afterwards resigned his bishopric and retired as a hermit to *Oilen Edghair*, in Loch Con, from fear of Guaire Aidhne, King of Connaught, who had conceived a mortal hatred towards him, as he was the true heir to the kingdom of Connaught. Guaire bribed four ecclesiastical students who were under Cellach's tuition in the hermitage, to murder him, namely, Mac Deoraidh, Maelcroin, Maeldalua, and Maelseanaigh. According to the life of Bishop Ceallach, of which there is a copy in the collection of Messrs. Hodges and Smith, this murder was committed in a wood situated between Loch Con and Loch Cuillinn, in the south of the territory of Tirawley, and after its perpetration King Guaire granted the territory of Tirawley to these four students as a reward for their services in despatching Ceallach, who thereupon erected a fort for themselves at Dun Fine. Soon after this occurrence Muireadhach, who was otherwise called Cucoingilt, the second son of King Eoghan Bel, came to visit his brother Oilen Edghair, but not finding him there, and learning that certain negotiations had passed between his pupils and King Guaire, he at once suspected that the bishop, his brother, had been murdered; after some inquiries and searches he found the body in the hollow trunk of an oak tree, torn by the ravens, scald crows, and wolves. Cucoingilt carried the mangled body to the church of Turloch for interment, but the clergy of that establishment, dreading the vengeance of King Guaire, would not permit it to be buried there; upon which he carried it to the church of Lis Callain, but the clergy refused to admit it; it was next brought to the church of *Eiscreacha*, where it was interred with due honours. Cucoingilt, after having chanted a short dirge over the grave of his brother, in which he vowed vengeance against the murderers, assembled an armed band of three hundred of his relatives and adherents, with whom, after having lived one year in Hy-Many, and some time in Meath, where he married Aifi, the daughter of Blathmac, King of Ireland, he at length returned to Tirawley, his own *Fleasc lamha*, or patrimonial inheritance, where, by the assistance of a swine-herd, he procured admittance to the fort of Dun Fine, in which the murderers of his brother were banquetting. Here he remained at the banquet in the disguise of a swine-herd until he observed that the four murderers, and all their guests and attendants, were
stupid

stupid with intoxication, upon which he sent his friend, the swine-herd, for his armed band, who were concealed in the neighbourhood, who, rushing into the fort, slew all the guards and attendants, and seized upon the four murderers of Bishop Ceallach. The guests in general, on learning that it was Cucoingilt, the second son of King Eoghan Bel, and the brother of the murdered bishop, that had thus disturbed their festivities, were more pleased than grieved at the occurrence, and finished their potations in honour of the rightful heir.

On the next day Cuncoingilt carried the four murderers, in chains, southwards, through the territory from Dun Finè to a place called Durlus Muaidhe, and across Lec Durluis, until he arrived at a place near the River Moy, since called *Ard na riadh* [now Ardnarea], i. e. the hill of executions, where he executed the four, cutting off all their limbs while they were living.

After this Cucoingilt obtained the hostages of Tir Fiachrach and Tir Amhalgaidh, and compelled Guaire to live in Tir Fiachrach Aidhne, in the south of the province.

J.

Cnoc na Maille.

Page 96, Note 4, and page 267, Note 1.—It should be here added that the district lying round the Red Hill of Skreen was originally called Cnoc na Maili, and afterwards Mullach Ruadha, which is now, strange to say, applied not to the hill itself, but to a small townland lying to the east of it. But the name was never so applied until the original Ballybetagh was subdivided into half quarters, which constitute the present townlands, when the names were very strangely confounded. Thus the half quarter on which the church stands received the appellation of Skreen from the church, the division to the south of it was called Lecarrow, i. e. *Λεϊτ-ῥεατράμια*, the half quarter, from its quantity; the hill itself, which originally gave name to the whole district, or Ballybetagh, was called *Cnoc Ruadha*, i. e. Rufina's hill, now incorrectly translated Red Hill, while *Mullach Ruadha*, the more ancient appellation, was transferred to a subdivision to which it is by no means applicable, inasmuch as it is not a *mullach*, or summit, in relation to the other subdivisions, and contains no monument of the Lady Rufina with whose name it is compounded. In this manner, however, have ancient names, in many instances, been transferred and corrupted. The cairn erected over the body of *Ruadh*, or Rufina, the wife of Dathi, still remains on this hill, but it is not on its very summit, as Duaid Mac Firbis writes. It is thus described by Robert Jones, Esq., in a letter to R. C. Walker, Esq., of Rathcarrick, barrister-at-law, who has kindly forwarded it to the Editor:

“Being here for the Christmas holidays I made a search for the cairn of Knockroe,
or

or Mullaghroe, and have discovered it. I enclose a sketch from the Ordnance Map, sheet 19. On the townland of Mullaroe there is nothing of the sort, but the district up the hill is all called Crockroe, or the Red Hill, and there is a large stone fort shown in the Ordnance Survey, called the Red Hill. This, however, is not the cairn, but lower down the hill I discovered the cairn, which had been opened, and contained several small chambers; the principal one has still the covering stones on it, but filled with smaller stones underneath. The cairn is of an oval form, ninety-six paces round. The entire hill is a light soil on lime-stone rock, which every where protrudes. The cairn is formed of these stones; the first chamber has a double covering of large lime-stone flags, the sides being formed of upright flags of the same material, like a small cromlech, and is about six feet square. There appear to be several other smaller ones which have been opened and the rubbish thrown back again. From the stone fort higher up the hill there is a magnificent view: it stands just over the dark lake under Knockacrea, from whence the mountain rises at once, and the view of Knocknarea, Glencarr, and the mountains beyond the Union wood is splendid. It is a very considerable fort and has chambers underneath it.

“ROBERT JONES.

“*Skreen, 27th December, 1843.*”

K.

PEDIGREE OF THE CLANN DONNCHADHA O'DOWD.

Page 116, Note v.—The following document is taken from the Book of Lecan, fol. 85, b, where it has been inserted in a more recent hand:

“Clann aobal mor la Maolpuanaig, mac Donnchaig, meic Aodha, meic Tailteig, meic Aodha, meic Muircheartaig, .i. Tailtech Muaidhe, agur Donnchaib agur in Cornumoirg, .i. Aipio E-

“Maolruanaidh, son of Donnchadh, son of Aodh, son of Taithleach, son of Aodh, son of Muircheartach, had a very great family, namely, Taithleach Muaidhe [of the Moy], Donnchadh^a and Cosnamhach^b,

Archbishop

^a *Donnchadh.* — This materially differs from the text of the Book of Lecan and from the pedigree of the O'Dowds given by Duaid Mac Firbis, as already printed at p. 116, and no doubt can be entertained that the present notices are incorrect, and were inserted into the Book of Lecan from the memory of some local romancer, who had but a confused knowledge of the pedigree of the O'Dowd at this period. This Donnchadh was certainly not the elder brother of

Taithleach Muaidhe, for we have the authority of the original text of the Book of Lecan and of Duaid Mac Firbis to prove that Donnchadh Mor, the ancestor of the Clandonogh O'Dowd, was the second son and not the brother of this Taithleach.

^b *Cosnamhach.*—He was the only brother of Taithleach Muaidhe, according to the original text of the Book of Lecan, in which he is called Archdeacon of Tuam, and intended archbishop.

por Tuama, agus ar é in Taitleac Muaidhe rin do marbhad a m-bel Atha Taitligh ar Coillte Lughna Meic Firtir, ne Gallaid. Agus no eirgeas ar clann imda ag Donnchadh Mor O'Dubha ne h-Onorunn, ingen Meic Dairein Daireo, .i. Donnchadh Og, agus Muirheartach, agus Taitleac, .i. cnam-fhiach na clainni ar a méo, agus ar a milidheacht agus onogh eli o'a paba gur ab mac tabairtar é, agus go b-firé o'a ithe fa riachaid é, no go b-tuc O'Luachan o'a eirg féin o'a oileamoin é; agus Lochlainn agus Aodh in Chopainn, agus Cormac, .i. Eppoc Cilli h-Éalao, agus Aodh Ruadh, agus Conchobhar na Ceitherne.

“Do gab Taitleac Muaidhe in eirgear-nur o'aimeoin Donnchadh agus na rinniréct. Ro gab Donnchadh Mór agus

Archbishop of Tuam. This is the Taithleach Muaidhe who was slain at Bel Atha Taitligh, in Coillte Lughna Mac Firtir, by the English^c. And Donnchadh Mor O'Dubha had numerous issue by Honora, the daughter of Mac Wattin Barrett^d, namely, Donnchadh Og, Muirheartach^e, and Taithleach (*called* the cnaim-fhiach of his children, for his size and warlike character, *though* others say he was a natural son^f, and that he was found under the ravens, which were devouring him, until O'Luachain took him into his house to nurse him); Lochlainn, Aodh an Chorrainn, Cormac^g, Bishop of Killala, Aodh Ruadh^h, and Conchobhar na Ceitherneⁱ.

Taithleach Muaidhe took the chieftainship in despite of Donnchadh and his seniority^j. Donnchadh Mor and his sons proceeded

^c *By the English*.—See p. 115, Note ^u, and pp. 303, 304, Note ^m, and also *Addenda*, pp. 354, 355.

^d *Honora, the daughter of Mac Wattin Barrett*.—This is utterly false, for she was the wife of Donnchadh Og, his son.—See p. 118. This Donnchadh Mor had only three sons, namely, Donnchadh Og, Conchobhar, and William, Bishop of Killala.—See p. 116.

^e *Muirheartach*.—He was the grandson, not the son of Donnchadh Mor.

^f *Natural son*.—Cnamhfhiach na clainni, i. e. the bony-raven of the children. The Rev. P. Mac Loughlin, in his abstract of the Book of Lecan, gives an absurdly false translation of this passage as follows:—“This Donogh Mor had by Onora Barrett Donogh Og and Mortogh, and Taithleach, otherwise called Cnamfiach, whom

some say was a natural son, and got by the father at a hunt, or, as others say, was educated in his own house.”

^g *Taithleach, Lochlainn, Aodh an Chorrainn, and Cormac* were all the grandsons, not the sons of Donnchadh Mor.

^h *Aodh Ruadh*.—He is not given in the original text of the Book of Lecan, nor by Duaid Mac Firbis.

ⁱ *Conchobhar na Ceitherne*.—He was actually the son of Donnchadh Mor and the brother of William, Bishop of Killala, who is not set down in this corrupt pedigree at all.

^j *In despite of Donnchadh and his seniority*.—This is utterly false, and a barefaced fabrication by some local romancer, for Taithleach Muaidhe was the father not the brother of Donnchadh.

a clann ag fogail, agus ag uibear, agus ag fip-milleo fonn O b-Fiachrach agus O n-Amalgaid, no go n-becharo oie ar dainib, agus earbaid ar aic-measuib eorpa, no go n-becharo luc leannanna na n-aon comairli eorpa fein in tip oo poinn, agus comatha comora agus fearonn fairring oo tabairt oo na clannoib rin Donncharo Moir, agus in Tigearnur oo beo ag Tailtec Muaidi agus ag a t-rioc ina oearaid. Agus ar i po in poinn, .i. Sin-eagalacht agus reirbir in peeta nio oo tabairt oo Donncao Og, mac Donncharo Moir, agus ceannur ceirern agus congbal oo Conchabar na ceirerni, agus tigeannur ceall oo Uilliam Eppoc, agus cir agus oligeao ar in g-ceatnamao cuio oo'n tip oo Donncharo Moir fein, agus mir murra ar a cinn fuar oo Donncharo Moir, .i. fecht m-baile Cuile Cearnada, peata agus cath-igce agus cornam in tip o' fiacharb ar Donncao agus ar a clann maicni i n-a

proceeded to plunder, rebel, and destroy the land of Hy-Fiachrach and Hy-Amalgaidh, so that destruction was brought on men and want on tribes [*during the contention*] between them, until their followers consulted together and agreed to divide the country, and to give those sons of Donnchadh Mor large considerations and extensive territory, and to cede the chieftainship to Taithleach Muaidhe and his descendants after him. This *was* the division: To cede the seneschalship and the service [administration] of the regal law to Donnchadh Og^k, the son of Donnchadh Mor, and the superintendence of the kerns and the houses to Conchobhar na Ceithirne, and the lordship of the churches to William the Bishop^l, and the rent and law of the fourth part of the territory *were ceded* to Donnchadh Mor himself, and a mir murra^m was also ceded to him (Donnchadh Mor) for his seniority, viz., the seven townlands of Cuil Cearnadaⁿ; and Donnchadh Mor, and his sons after him, were

^k *Donnchadh Og, the son of Donnchadh Mor.*—He died in the year 1384, that is, 102 years after the death of Taithleach Muaidhe—see p. 117—so that it is very clear this compact was not made in the time of the latter. It is quite evident from all the circumstances, that if this compact were ever made, it was made between Sen Brian O'Dowd and his brother Donnchadh Mor.

^l *William the Bishop.*—He was Bishop of Killala, and died in 1350.—See p. 117, Note ^b. It is strange that the author of this interpolation

does not tell us who he was. According to the original text of the Book of Lecan and the work of Duaid Mac Firbis, he was the third son of Donnchadh Mor.

^m *Mir murra.*—The meaning of this term is not given in any Irish dictionary. It seems clear from the context that it is used here to denote a freehold property, which was to descend to the posterity of Donnchadh Mor for ever.

ⁿ *Cuil Cearnada.*—For the exact extent of this district see pp. 166, 167, and 246, 257.

beaḡaḡo ácc nama in mīr murra o'fear-
ann c-ḡaor fuaip Donnchaḡ Mor.

"Do ḡeanam eolur ar ḡaḡ ceatpa-
moin oibh foleit ar eḡla in outhcōir
oo bol i m-bachao, .i. Baile cairthi in
chuile, mar ata, ceatpaimi in Cairḡi fēin,
aḡur ceatpaimi Aingilin, aḡur Ceat-
paimi na ḡ-cloch, aḡur ceatpaimi Cill
ḡriḡoi, oir i rī cuio ponna pleacca Aḡoa
Ruait, mic Donnchaḡ Oig, in baile
rīn. Ceatpaimi bec Muini Conallain,
Ceatpaimi mor Muini Conallain, aḡur
Ceatpaimi in labain, aḡ rīn baile
fearainn pleacca Muirceartach, mic
Donnchaḡ Oig, mic Donnchaḡ Mōir.
Ceatpaimi Cill na n-ḡarḡan, in Ceat-

were obliged to sustain the battles and
defence of the territory, though they have
nothing for it but the *mir murra* of free
land, which Donnchadh Mor had obtained.

"To preserve a knowledge of every
quarter of these separately lest their pa-
trimony might be consigned to oblivion.
They are as follows, viz., Baile Cairthi in
chuile^o, viz., the quarter of the chairthi
itself^p, and Ceathramh Aingilin^q, Ceath-
ramh na ḡ-cloch^r, the quarter of Cill-
Brighde^s, for this townland was the divi-
dend of Aodh Ruadh, the son of Donnchadh
Og. The quarter of Rath Raodain^t, the
small quarter of Muine Conallain, the
large quarter of Muine Conallain^u and
Ceathramha an labain^v; this was the town-
land of the posterity of Muirheartach,
the

^o *Baile Cairthi in chuile* was the ancient
name of a large townland or ballybetagh, com-
prising the present townland of Corha and other
subdivisions in the north-west of the parish of
Kilgarvan, in the district of Coolcarney, barony
of Gallen, and county of Mayo.

^p *Cairthi*, now the townland of Carha, or Car-
rownacarha, in the same parish. It is but a sub-
division of Baile Cairthi an Chuile.

^q *Ceathramha Aingilin*, now unknown.

^r *Ceathramha na ḡ-cloch*, i. e. the quarter of
the stones, now well known, and anglicised Car-
rownaglogh, a townland in the north of the parish
of Kilgarvan.

^s *Cill Brighde*, now the townland of Kilbride,
otherwise called Carrowcleagh, in the north of
the same parish. It derives the name of Cill
Brighde from an ancient church dedicated to St.
Bridget, the ruins of which are still visible.—See

Map.

^t *Rath Raodain*, now anglice Rathreedaun, a
townland in the west of the same parish, the pro-
perty of Thaddæus O'Dowda of Bunnyconnellan,
Esq., the present chief of his name. There is in
this townland a holy well dedicated to St. Fechin,
the patron saint of this parish.

^u *Muine Chonallain*, i. e. the hill or shrubbery
of Conallan, the proper name of a man, not of a
family, as some suppose. The name of this place
is now corrupted to Bunnyconnellan, but it is
correctly written Moneyconnilane in some of the
more ancient of the O'Dowd records, and even
in one document of so late a date as 1705. Both
divisions of this townland are the property of the
present O'Dowda, whose house stands upon the
western division.

^v *Ceathramha an labain*, now anglicised Carrow-
labaun, a townland in the west of the same parish.

paími Riabac, Ceátpaími mic Coinín
Ceátpaími na h-Oiliḡ, Baile fearpaínn
pleaceta Aíosa in Chopaíno. Ceátpaími
Lir aró mor, Ceátpaími Meic Carra,
Ceátpaími na Dnelliḡ, Ceátpaími I
Dubagáin, ag rin baile Concobair na
Ceitherni .i. Baile na Droelaḡ, Ceá-
tpaími mor Cairleim, Ceátpaími Deac
Cairleim, agus leir Baile Gleanna da
ghub, agus Baile Taitleḡ Moir .i. cnaim
Fhiac na Cloinne; Leir Baile Rúrḡaḡi,
.i. Ceátpaími na Cairḡi, Ceátpaími na
Corra Driḡi, Ceátpaími Droima Sgu-
abaiḡ, Ceátpaími Meic Driḡbli agus
sa ceátpaíme ele nach aipmíobḡ ronn;
agus aipmíobḡ Taitleḡ do ben rin

the son of Donnchadh Og, who was the
son of Donnchadh Mor. The quarter of Cill
na n-garbhan^w, Ceathramha riabhach^x,
Ceathramha Mic Coinin^y, the quarter of
Oileach^z, constituting the townland of the
posterity of Aodh an Chorainn. The
quarter of Lis ard mor^a, Ceathramha Meic
Carra^b, the quarter of Grellach^c, Ceath-
ramha Ui Dhubhagain^d, that is, the town-
land of Conchobhar na Ceithirne. Baile
na Brothlaighe^e, the great Castlequarter
and the less Castlequarter^f, and the half
townland of Gleann da ghubb^g, this is
the townland of Taitheach Mor, Cnaimh-
fhiach na Cloinne. The half townland of
Rusgach^h, the quarter of Carraigⁱ, the
quarter

^w Cill na n-garbhan, now Kilgarvan, a town-
land in the east of the parish of the same name,
containing the grave-yard and some slight ruins of
the ancient church, erected by St. Fechin in the
seventh century.—See Colgan's *Acta Sanctorum*,
p. 134, c. 8.

^x Ceathramha riabhach, i. e. grey quarter, now
anglicised Carrowreagh, a townland in the west
of the same parish.

^y Ceathramha Mhic Coinin, i. e. Mac Coinin's
quarter, now Carrowconeen, in the west of the
same parish.

^z Oileach, now the townland of Ellagh, in the
south of the same parish: it is now divided into
two parts, of which the larger is called Ellagh-
more, and the smaller Ellaghbeg.—See p. 369,
where Ellaghmore is mentioned as the property
of Captain O'Dowda.

^a Lis ard mor, i. e. the fort of Ardmor, or the
great height, now anglicised Lissardmore, and
sometimes corruptly Lissermore. It is situated
in the west of the same parish.

^b Ceathramha Mhic Carra, i. e. Mac Carra's
quarter. This name is now obsolete and cannot
be identified.

^c Grellach, now Grallach, near Graffy, in the
same parish.

^d Ceathramha Ui Dhubhagain, i. e. O'Dugan's
quarter, now Carrowmagooan, in the north-east
of the parish of Attymas, in the district of Cool-
carney, and barony of Gallen.

^e Baile na Brothlaighi.—This name is not in
use at present, but it was the original name of
the denomination of land on which is situated the
small lough called Lough Brohly, lying westwards
of Ellagh, in the parish of Kilgarvan.

^f The great Castlequarter and the less Castle-
quarter.—These subdivisions are now called Car-
rowcastle, and are situated in the west of the
parish of Kilgarvan.

^g Gleann da ghubb, now Glendawoo, a town-
land in the east of the parish of Attymas.

^h Rusgach, now anglicised Roosky, a townland
in the east of the parish of Attymas.

amaç o' airmoein na cloinni oili agur
ba ceaéromoin oile map aon riu .i.
Ceaéromi i Sgorra agur a Ceaéromi
Caol.

"Agro cor agur cunnrað Tailte
Muaidi, .i. ní O b-Fiachraç ne Donn-
chað Mor, .i. beé umal upramach oo
Tailleç Muaidi ap ron in ceaéromi
pann oo'n eir oo thabairt oo Donnchað
agur o'a rliçt; Eirgi i mach umal,
upramach oo éabairt oo Tailleç Mu-
aidi, ap ron in ceaéromi pann oo'n eir
oo tabairt oo Donnchað agur o'a rliçt
Eirgi imac umal innuic oo thabairt
oo Tailleç Muaidi ap uairli a anma
agur a innu, agur gac uair o'a m-beið
éigea-báil ap O'n-Dubha, Donnchað
agur a clann o'a ppearaol fa n-oith-
cell. Ácuio cuain agur calað ag Donn-
chað Mor féin agur aga rliçt. O'a
m-beað Goill no Gaoibil a n-oibthaig
i Dubha Donnchað Mór agur a clann

quarter of Corra drisighi, the quarter of
Drom Sguabach^k, Ceathramha Meic Geir-
bli^l, and two other quarters not mentioned
here; and the posterity of Taithleach got
possession of these in despite of the other
children, besides two other quarters,
namely, Ceathramha Ui Sgorra^m and Ceath-
ramh Caolⁿ.

"The following is the compact and cove-
nant of Taithleach Muaidhe, King of Hy-
Fiachrach, with Donnchadh Mor, viz., that
Donnchadh and his descendants should be
obedient and submissive to Taithleach
Muaidhe, in consideration of their having
received the fourth part of the territory,
also to furnish an obedient, submissive,
and sincere Rising-out to Taithleach Mu-
aidhe for the same consideration, and also
for the nobility of his name and wealth;
and whensoever the O'Dubhda should
happen to be in jeopardy that they should
assist him to the best of their ability. That
Donnchadh Mor himself and his descen-
dants should have their own portion of the
harbours^o. If the English or Irish should
be in the country of O'Dubhda, Donn-
chadh

ⁱ *Carraig*, now anglicised Carrick, a townland
in the east side of the same parish.

^j *Corra Drisighi*, now Corradrishy, a townland
in the centre of the same parish.

^k *Drom Sguabhach*, now anglicised Drumacoba,
a townland in the south of the same parish.

^l *Ceathramha Meic Geirbli*, i. e. Mac Geirbli's
quarter, now Carrowkeribla, a townland in the
west of the same parish.

^m *Ceathramha I Sgorra*, i. e. O'Sgorra's quarter.

This name is now obsolete.

ⁿ *Ceathramh Chaol*, i. e. the narrow quarter.
There is no division of land in the district of
Coolcarney at present bearing this name, though
the name is common in other districts.

^o *Their own portion of the harbours*, that is to
say, that they should have the profits of such
harbours and fisheries as were in their own por-
tion of the territory, without paying any royalty
to the chief in consideration of them.

do chabairt uireas níú fein do Taithleac
Muaidhe agus dá cloinn agus a leitheo
oilí rin uatha-ran agus aobert in
Seancha annro :

“Callraighi Cuilí na g-cneao
pachat innce dá h-aiem,
Cuil Chearnuga na g-call g-car,
neam-bona in onong dán dúthcar.

Ceitéirí cairig ar tír e-ruar
ag Callraighi na g-caom énuar,
coinnmí vocaib par g-caire-ní,
cairí fíoinní na raor-maicní.

O’Cuinn ír O’Rochlan peir,
ó h-lannan na n-arm n-aiméil,
gan uigbail do’n gleri Gall,
O’Finain in meine Mor Clann.

O Del Easa na n-eas n-glan,
feas na tuaithe ní nár tubao
go Brognach pa teno teni
do chopain ceann Callraighi.

chadh Mor and his descendants should
give as many as themselves^p to Taith-
leach Muaidhe and his descendants, and
the like from them to him. On which sub-
ject the historian has the following lines :

“Into Callraighi Cuile^q na g-cneadh
I shall proceed to describe it,
Cuil Cearnadha of the knotty hazles,
Not unhappy the tribe in whom it is
hereditary.

Four chieftains are in the upper country,
In Callraighi of beautiful fruit trees,
A festive party who have entered into
our catalogue,

It is proper to name the noble party.

O’Cuinn and O’Rothlainn the ready,
O’h-Iarnan of dreadful arms,
Without injury to the choice of the
foreigners,

And O’Finain a prop of great descendants.

From Bel easa of the clear cataracts,
The extent of the country which was
not oppressed

To the Brosnach of impetuous current,
Which defends the head of Calraighi.

From

^p Should give as many as themselves.—This is very lamely expressed by the writer, but his meaning is this :—“Should the country of the O’Dowd happen to be invaded by English or Irish enemies, the Clann Donogh O’Dowd are bound by this compact to furnish as many men and arms to oppose them as the O’Dowd himself; and, on the other hand, in case the country of the Clann Donogh O’Dowd only were attacked the O’Dowd is bound by this compact to supply as many men, arms, &c., to check the invaders as the Clann Donogh O’Dowd had themselves, be

that number great or small.

^q Into Callraighe Cuile, &c.—The four first quatrains of this poem are quoted from the large poem of Giolla Iosa Mor Mac Firbis already printed.—See pp. 244, 245. The remaining part is from a different source, but the whole is garbled by the interpolator, who evidently wished to uphold the dignity of the Clann Donogh O’Dowd by making them descend from the elder brother of Taithleach Muaidhe, contrary to the evidence furnished by the original text of the Book of Lecan.

Ο δέλ Αἶα in þheadha anall
 ar e þairring na b-þearann
 map cam ba o-þaroll uile,
 go Tpaig alaino Eothuili.
 Donnchað Mor rug map roga
 Cuil Cnama Cuil chearnuma
 amarc rúl ir ráime lino
 in cúil ir áille o' Eirino.

 Ο δορραϊγ na rpeað rolar,—
 na bíð aon 'na amopar,—
 Cúil cnáma in þearann ar þao
 co epáig nað oleagam oo þearmao.

 Οο δέν oo'n þoirino éolur
 in ba cúil a g-comópeur
 cúil ar gac ceann oo'n tþp
 an geall ó gac cúil cluimeí.

 Ταϊτεῖ Μυαῖο, πα μόρ παῖ,
 τigeapna ar þonn Ο δ-Þιάραῖ,
 αῖαο α ἐλανν ό þoin alle
 a g-ceann Donnchað 'pa éloinni.

From Bel atha an fheadha^r, thither
 Is the breadth of the lands,
 As I am describing them all
 To the beautiful strand of Eothuili^s.
 Donnchadh Mor took as choice
 Cuil Cnama, Cuil Cearnadha,
 A prospect to the eye the most delight-
 ful we deem
 The most beautiful cuil [angle] of Erin.
 From Borrach^t of the bright streams,—
 Let no one be in doubt of it,—
 Cuil Cnama embraces all the land,
 As far as the strand, which we should
 not forget.
 I shall afford intelligence to the tribe
 Respecting the two cuils which are in
 competition,
 A cuil at each extremity of the territory,
 The *palm* wager being won by each cuil
 was heard of^u.
 Taithleach Muaidhe^v of great success
 Became lord of the land of Hy-Fiach-
 rach,
 And his descendants have been ever since
 Over Donnchadh and his lineage.

The

^r *Beal atha an fheadha*, i. e. *Os vadi sylva*, now Ballina, a well known market-town on the River Moy, in the barony of Tirawley.

^s *Eothuili*, the name of a great strand near Ballysadare, often already referred to.

^t *From Borrach*, &c.—From this it appears that *Cuil Cnama* was co-extensive with the district of the Strand, already described at p. 265. The name *Cuil Cnama* is still remembered in the country, but supposed to comprise only the parish of Dromard, where there is a small lough

called *Lochan Chuile Cnama*.

^u *Each Cuil was heard of*.—The meaning of this quatrain, which is couched in such obscure words, is, that the two districts, *Cuil Cnama* and *Cuil Cearnadha*, situated, the one at the east and the other at the western extremity of Tireragh, rivalled each other in romantic beauty and fertility, and that each claimed the palm in turn.

^v *Taithleach Muaidhe*, &c.—This quatrain is undoubtedly a fabrication, for *Taithleach Muaidhe* was many years dead at the time.

Ceasároumí cuio do'n éir ear
 fuaip Donnchaó ó Dún Durlair,
 gac laoi a g-ceill sa g-cuirí
 map saoi ra peim riagraoi.
 Mile bliadan, nochá bréig,
 annála Críste ne coiméo
 trí céo do bliadnaib bhara,
 map do filao in peancara,
 agur a dó ne dearbao sam,
 ra lo rap ceanglaó cunnasó."

The fourth part of the irriguous land
 Donnchadh of Dun Durlais obtained,
 Which every poem makes known,
 As he is in the regal catalogue.
 A thousand years^w, it is no falsehood,
 The era of Christ to be preserved
 Three hundred of fleeting years,
 As the history sets forth,
 And two to be certified by me,
 On the day the treaty was ratified."

L.

INAUGURATION OF IRISH CHIEFS.

See page 143.—The inauguration of the ancient Irish kings and chieftains, has been so imperfectly described by modern Irish writers that the Editor is for this reason tempted to treat of it more fully in this place, in the hope that some readers may feel interested in the subject. We have unfortunately no minute or authentic account of the manner in which the pagan monarchs or chieftains were inaugurated or installed, the sum of what we are told on the subject being that the pagan Irish monarchs were made at Tara on a certain magical stone called the Lia Fail, which was wont to emit a sound when the person about to be elected was legitimate. For some account of this stone, and the inauguration of Conaire Mor, at Tara, the reader is referred to *Petrie's History and Antiquities of Tara Hill*, pp. 154, 155. (*Trans. R. Irish Acad.* vol. xviii.)

The oldest account of the inauguration of a king of the Irish race is that given by Cumin, who became Abbot of Iona in the year 657, who says (*Vit. S. Columbæ*; apud Colgan, *Tr. Th.* p. 321,) that St. Columba ordained Aidan King of Scotland, by imposition of hands. Adamnan also has the same statement (*Vit. S. Col. lib. iii. c. 5*). "Ibidemque Aidanum iisdem adventantem diebus, in regem, sicut erat jussus, ordinavit,

^w *One thousand years, &c.*—The whole quatrain tells us that this compact was made between Taithleach Muaidhe and Donnchadh Mor, in the year 1302, that is, twenty years after the death of Taithleach Muaidhe! Every fabrication recoils on itself, and nothing but the truth will stand the test of true criticism. As already re-

marked, it is highly probable, however, that a compact of this nature was entered into in this year, 1302, between Sen Bhrian O'Dowd, who succeeded to the chieftainship about this year (see p. 356), and his next brother, Donnchadh Mor O'Dowd, who died in the year 1337.—See p. 116.

navit, et inter ordinationis verba, de filiis et nepotibus, pronepotibusque ejus futura prophetizavit, imponensque manum super caput ejus, ordinans benedixit."

From a notice in an ancient Life of St. Patrick, quoted by Keating, it would appear that twelve coarbs and twelve chieftains were always present at the inauguration of the King of Connaught, on Carn Fraoigh, near Tulsk; and this notice is corroborated by a passage in the Annals of Clonmacnoise, as translated by Connell Mageoghegan, which states that in the year 1316 Rory O'Connor, who attempted to wrest the kingdom of Connaught from Felim O'Connor, the rightful heir, "went to Carne Fraoigh, where he was invested King of Connaught by the twelve chieftains of Silemorrie, twelve coworbs, and other spirituais that were accustomed to use the ceremonies usual at the time of the investiture of the king."

From such respectable authorities, it is manifest, that since the introduction of Christianity into the country, the Irish kings and chieftains were inaugurated by the clergy, and that the ceremony was strongly marked with a religious character. But Giraldus Cambrensis, who came to Ireland about the year 1202, as tutor to prince John, has left on record the following very opposite account of the matter:—"Est in Boreali ac ulteriori Ultoniæ parte apud Kenelconil gens quædam quæ barbaro nimis et abominabili ritu sic sibi regem creare solet. Collecto in unum universo populo terræ illius, in medium producit jumentum candidum, ad quod sublimandus ille non in principem sed in belluam, non in Regem, sed exlegem, coram omnibus bestialiter accedens, non minus impudenter quam imprudenter se quoque bestiam profitetur, et statim jumento interfecto, et frustratim in aqua decocto, in eadem aqua balneum ei paratur, cui insidens, de carnibus illis sibi allatis, circumstante populo suo, et vescente, comedit ipse. De jure quo lavatur, non vase aliquo, non manu, sed ore tantum circumquaque haurit, et bibit. Quibus ita ritè non rectè completia, regnum illius et Dominum est confirmatum."—*Top. Hib. Dist.* 3, c. 25.

This account of the mode of inaugurating the chief, or prince of Tirconnell, was probably never heard of in Ireland until after the publication of the works of Giraldus. The first who refuted it was Keating, who writes as follows in the Preface to his History:*

"Α οειρ απίρ ιρ ιν 25 καίτοι οο'η
λεαθορ ευαυργβαλα ευγ αρ Ειρινν, γυρ
αβ αmlαο οο πfεί Rí Chineil γ-Conaill,

"Ab eodem pingitur, seu potius fingitur, O'Donnelli Kinelconelliæ Reguli inaugurandi ritus. Omnes (inquit) Regionis

* The original is here given from O'Mulconry's MS. copy of Keating's History, in the Library of

Trinity College, Dublin, together with the Latin translation of Dr. Lynch.

Α. Ο'Ομόναιλλ : Κυρηνουγαθὸς ὁ ὅρῳ ἀρ
 λυτὴ α ἐπὶ ἀρ ἐνὸς ἀρὸς 'να οὐέαιγ;
 λάρ βάν ὁ ἡαῖαθ; α κυρ ο'ά βρυε
 α γ-κοιρὴ ἡόρ ἀρ λάρ ἀν ἡαῖαιρ; αἱρ
 κᾶρ η-α βρυε, α βειε αἱ ὅλ α η-ανδρυε
 ἀναιλ γαῖα ἀρ ὁ ὁμ λὲ η-α βέλ, αἱρ
 βειε αἱ ἡε ἡα ρεολα ἀρ α λάραιβ γαν
 ργῖν, γαν ἀρῃ ο'ά γεαῖαθ αἱρ; αἱρ
 γο ἡανῖα ἀν αἱρ οἱε ὁο'η ρεοἱ ἀρ ἀν
 γ-κομῖαἱ, αἱρ γο β-ρῶεργῖοθ ἑ ρέιν
 'ῖαν ἀνδρυε.

Αἱρ ρολλυρ γυρ βρευγὰς ἀν ἡί ρι α
 βειρ Cambreny ὁ ρέιν ρεανῶρα ἡα
 η-Θῖρῖον, ὅρ ἀρ ἀναιλ βοἱλλῖγῶρ
 γυρ ἀβ ἀναιλ ὁ γαιρὶ Ο'Ομόναιλλ,
 maille ἡε ρυῖε ὁ ἀμεαγ υαῖολ αἱρ
 οἱρῖοῦ α ἐρῖε ρέιν, αἱρ παοῖρῖο
 ο'υαῖρῖβ α ἐρῖε ὁ ρεαῖν 'να ρῖα-
 ναιρ, γο ρλαῖ η-οἱρῖγ, η-βάν 'η-α λάρ,
 αἱρ ἀν ἡαν ὁ ὁάῖοθ ὁ ρῖγ Chinél
 γ-Conaill ἑ, ἀρεῖ α βειρῖοθ, ceannur
 α ἐρῖε ρέιν ὁ γαῖαἱ, ceap αἱρ
 κοῖρῖον ὁ κοῖρῖαἱ ἡορ γὰς ὁα ἡαν
 ο'ά οὐέαιγ; αἱρ γυρ ἀβ υἱε ὁ η-ὁρ-
 οἱρῖαθ ἀν τ-ρλατ ὁ βειε οἱρῖοθ, βάν,
 ὁ ὅρ α γ-κυῖνῃ ὁ, γυρ ἀβ εἰα ὁ
 ὁἱρῖοθ βειε οἱρῖοθ 'η-α βρειεῖοἱνῃρ,
 αἱρ γλᾶν, ἡοῖαἱ 'η-α γῖοῖαἱβ.

Αἱρ ἡοῖαθ ἡομ Cambreny ὁ ἡαῖ
 ἡα βρεῖγῇ ρι, αἱρ μεαῖαἱ γορ ἀβ λὲ

onis Incolæ in editum quemdam collum
 primo convocabantur, tum equâ candidâ
 mactatâ, amplissimæque ollæ in latè pa-
 tente campo collocatæ injectâ, et luculento
 subjecto igne assatâ, Regulus denunciatus,
 admotis ollæ labris jusculum instar canis
 absorbebat; carnes nullo addito cultro
 dente discerpebat, et tandem devorabat, et
 reliquiis ad adstantes projectis, ipse jus-
 culo instar balnei usus, totum corpus eo
 perfundebat, et proluibat.

Sed quis hoc splendidum esse menda-
 cium inficiabitur, cum non solum nullus
 ejusmodi ritus ab accuratis rerum enarra-
 tionibus literis traditus deprehendatur,
 verùm etiam disertis verbis renunciandi
 O'Donnelli Kinelconelliæ Reguli ab iis me-
 moriæ prodatur in hunc modum : Quando
 quis O'Donnelli titulum insigniendus erat
 Kinelconelliæ Nobiles et aliorum ordinum
 homines ad statum collum confuebant;
 tum e proceribus unus assurgens, peractis
 reverentiæ debitæ officiis, candidam vir-
 gam omninò directam, ac detorsionis omnis
 expertem, quam manu gestabat, denunci-
 ato Regulo porrigens, 'accipe, ait, auspi-
 catum dignitatis insigne; hujusce virgæ
 candorem, rectitudinemque, moribus re-
 ferre memento, ut nulla maledicendi libido
 factorum candorem notâ ullâ maculare,
 aut studium in amicos animum a justitiæ
 rectitudine cuique præstandæ flectere pos-
 sit : Imperium tibi debitum bonis avibus
 ini, et hujus Reipublicæ fasces, securæ-
 que capesce.'

Hæc cum ita se habeant faciliè adduci pos-
 sum ut credam rumusculum hunc ab aliquo

Hibernis

meabail do cúip ríor 'n-a éiríoch f; óir ar pollur gur óaoine cráibéiochá, caon-
 oúépaécaá íao, ó aimir gur h-aimir,
 agur gur éréigíochor morán síob an
 rasgól, agur gur ériochnuigíoch a
 m-beaéa go raéimor, ríagáta; agur
 for go o-táinig íomao do naomái
 síob, mar atá Colam Cille, Daoiéin
 agur Aoamhán, et peliqui. Ní h-in-
 éirette fóir go o-éioépaíoch uairle E-
 peann fulong do níg Chinéil g-Conaill
 ar an nóir m-barbaróa úo luaidíoch
 Cambrení do beir ar aéaige aige, agur
 an éreioim caeoilíoch ar maréain aca
 ó aimir Pháoruiú go gabátaur Gall.

Hibernis infenso leviter enarratum a Cam-
 brensi, homine nimirum ab Hibernis alieni-
 ore, avidè captatum, et posteritati commen-
 datum ad majorem infamiam Genti concii-
 landam fuisse. Certè compertum est. Natio-
 nem plagam illam incolentem, humanitate,
 benignitate, atque adeo pietate, per singu-
 lorum vicissitudines sæculorum sic splen-
 duisse, ut illinc quam plurimi prodierint,
 qui fluxis terræ rebus desertis vitam con-
 tinuato per asperiora pietatis exercitia
 cursu ductam sælici exitu terminaverunt;
 ejusmodi fuere SS. Columba, seu Colum-
 kille, Baitinus, Adamnanus, compluresque
 alii; quorum a texendâ hic nomenclaturâ
 modo supersedemus. Huc accedit quod
 nullus æquus rerum æstimator judicabit
 cæteros Hiberniæ procures fidei præsertim
 Catholicæ apprime colentes, tam barbarum
 morem ullo pacto tolleraturos."

And again, in the reign of Brian Borumha, he has the following more circumstan-
 tial account of the inauguration of the Irish chieftains (p. 223 of O'Mulconry's MS.):

"Ag po ríor ar in Senéur in móo ar
 a n-beintí ríoga o'óruéaó a n-Éiríoch,
 agur créo fá n-óruéigéí íao, íoir áir-
 níg agur níg coigíó, agur phríomplaié
 fearpáinn. Tuig naé síob do gairm a
 n-Éiríoch anallóo acé gairm níg ag na
 flaéaib fearpáinn, amuil fá nóir do'n
 éineao Iuduíóíoch, acé amáin go m-bíoch
 síuicíóe ag in g-cinne Iuduíóíoch, agur
 do mórán do éineaoíoch síle, amuil do
 síob éaoiríoch a n-Albam ag Dal Riada,
 no gur níogaó feargúr Mórí mac Éarca
 orro. Ar é fáé íomorra fá níogéor
 aon ouine amáin ór cionn na b-puiblióíoch,

"Ex vetustis historiárum monumen-
 tis excerpí, quos hic subjicio, ritus in
 Regum inaugurationibus adhiberi consue-
 tos, sive ii totius Hiberniæ Monarchæ
 fuerint, sive provinciarum Reges, aut di-
 tionum Toparchæ. Nec alio quam Regum
 Titulo, quandam apud Hibernos pro-
 vinciarum et minorum regionum do-
 mini insigniebantur; de aliarum gen-
 tium, et præsertim Judæorum more, qui
 primo ducibus, deinde regibus, ute-
 bantur, sicut in Albania Dalriadi ante
 Fergusium, Ercæ filium, Regem renun-
 ciatum Dynastis parebant. Causa verò cur

unus

αγυρ να γ-κριός, ιοννυρ γο m-βιάς γαέ
 αον 'να φλατιορ φέιν υμάλ οό, αγυρ γαν
 αρ βρειε βο νεαέ οιοβ φρεαπαβηρα, να
 κορ 'να αχαιο φεαό α φλατιρ φέιν, αγυρ
 α ετιγριν γυρ 'b ó Όηια, αρ κοόναέ, αγυρ
 αρ κυμαάταέ όρ cionn cáιγ, βο h-ορουι-
 γεαό 'να ριγ όρ cionn na b-puiblió é,
 ο'ά b-pollamnuγaó, αγυρ ο'ά ρέιρ ριν
 γο n-oleaγair οόib υμλα βο εαβαιρ
 οό, αγυρ α ετιγριν γυρ b'έ an ε-αοιν Δια
 cέona, αρ κοόναέ αρ neam, αρ calmian,
 αγυρ αρ ιφριονn, τυγ in κυμαέ ροιν
 οό, αγυρ γυρ'b υαιό φυαιρ φλατιορ.
 Αγυρ αρ meinic γυρ ab iao na oaoine
 αρ γλιοα, αγυρ αρ φογλαμέο βο βίοό α
 n-Ειρινn, βο τογέαοι α b-φλατιορ βο
 ριναάτυγαό in uile, αγυρ βο cómícean-
 gal na cópa, αγυρ βο ε-ρναόμαό na
 ριόέάana, map α τα Slange mac Deala,
 mic Lóic, φα h-áipo-βρειεioín α n-Ειρινn
 'να αιμριρ φέιν; Ollam Fóbla, βο bί
 φογλαμέα, αγυρ Τιγεαρημυρ, α mác,
 βο bί φεαρραέ map in γ-ceono, αγυρ
 Κορμαc mac' Aipe βο bί eolaé 'pan
 βρειεioínnyρ ευαιε, αγυρ po ργρiob an
 Ceaype ριογ, αγυρ map ριν α túρ na
 n-aiμpior, αρ iao lucé in φεαpa, αγυρ
 in oream ba mó ρonn βο'n maitioρ
 puiblyge βο meubuyáó βο τογέαοι le
 φeapuib Eneann op cionn na γ-κριό, γο
 o-εáiniγ Páopuiz, αγυρ neape na h-ea-
 guilri, αγυρ ó εáiniγ Páopuiz αγυρ
 neape na h-eaγailre αρ ag na h-eap-
 γaió, ag na h-uairlib, αγυρ ag na cpoi-
 nicib, βο βίοό toγa na ρiόγ, αγυρ na
 o-εigeapmaó γο γabáιeap γall: αγυρ na
 γapma cleáétop anoip, map atá Úapún,

unus Regiá dignitate insignitus populis
 et regionibus præficitur, est, ut quilibet
 in ejus Ditione constitutus illius jussa
 audiat, et impugnare non audeat. Nemi-
 nem enim fugere debet supremam illam
 potestatem populum gubernandi Regibus
 a Deo, Regum Rege et Domino dominan-
 tium, conferri; ac proinde mandatis regis
 morem non gerere, perinde esse ac divinæ
 ordinationi resistere. Hiberni olim quos
 prudentiá et eruditione præ cæteris in-
 structiores depræhendebant, eos plerumque
 ad dignitatem Regiam evehebant, ut gra-
 vioribus suppliciis scelera plecterentur,
 legum observatio securius vigeret, et pax
 firmitus effloraret. Quibus præcipuè de
 causis, Slangius Delæ filius, Luighi nepos,
 supremi judicii officio per ea tempora
 functus; Ollamus Follus, vir etiam erudi-
 tione clarus; et Cormacus Arturi filius
 jurium scientissimus, qui et opus egregi-
 um de principis institutione scriptum re-
 liquit, Reges salutati sunt. Consuetudo
 itaque optima illa erat quæ apud Hibernos
 primitus invaluit, ut quo quisque litera-
 tior et ad provehendam Rempublicam ap-
 tior et propensior videbatur, eo expeditius
 Regni gubernaculis admoveretur. Post
 autem Hiberniam fidei splendore Divi Pa-
 tricii operá illustratam, et Ecclesiam suum
 fulgorem adeptam, ad Anglos Hiberniá
 potitos, penes episcopos et antiquarios
 Regum et Dynastarum electio fuit; nec
 usurpati nunc honorum tituli Baronum,
 Vicecomitum, Comitum, Marchionum et
 Ducum tum erant in usu: sed similes
 honores adepti appellabantur *triath*, id est
 Dynastæ

ὀθιοcont, Ιαπλα, Μαρquéιρ, νο Διυice, νιορ cleacacō a n-Θιρινν ιαο, acē επιαέ, τιγεαρνα, πλαίε νο Rí, αγυρ a πlonnacō ó na cpiócuiōb vo bíocō 'n-a pailb.

Re linn iomoppa γαρμα vo γlacacō vóib cιγιocō in cpoινice, αγυρ an leaδap v'á nγοιπέap in Teagypc pιoγ leiρ, map a m-biocō pum cumap nór αγυρ peaéc na cpiéc, αγυρ map a m-biocō poillpυγacō in luaibioéc bíop ó Θia, αγυρ o'n pobal epé maie vo óenanān, αγυρ an oíogaltyp bíop ór a cionn féin, αγυρ ór cionn a t-pleacacō epé neamcōmall céipe, αγυρ cópac, amuil opouyγiop Zeaδap na pιoγ, αγυρ an Teagypc Rιoγ vo óeunam.

“Ar meinic fóp vo beancacoi uppuide v'a γ-cáipuib vo ópuing óiocb, pa com-lionacō peaécac na cpiéc vo péip an Teagypc pιoγ, no in píge vo léigion vóiocb, gan impiopán, amuil vo beanpac Tuaeá De Θhanonn vo Θhpeap Móp mac Ealaécān, a namypip pιoγacécā Θipionn vo éaδapc vó.

“Ar e an cpoινice vo βειπιocō pλαε a láim γac cιγεapna pe linn γαρμα vo γaδáil, αγυρ o'είρ na pλαice vo óáil óó, vo cúipiocō a γ-céill vo na tuaeáuib nac pιγiocō in τιγεapna, no in Rí, a leap apm vo γlacacō ó joim amacō vo pmaccty-γacō a éipe, acē βειé umol v'á tπλαic, amuil pγoláipe v'á maigypcip. Oip amuil vo βειp an pγoláipe cpionna γpáó, αγυρ umlaéc, αγυρ buibioécup v'á maigypcip, ap map pin vliγéiop vo na h-ioc-topánuib βειé v'á pιoγuib, epé map ap le pλαic cópa, αγυρ céipe pειupyp na

Dynastæ seu Toparchæ ; *tighearna*, id est Domini ; *flaith*, id est Satrapæ ; aut *righ*, id est Reges ; adjecto locò nomine cui dominabantur.

“Cum autem quispiam Regis aut Toparchæ dignitatem inibat, Antiquarius aderat librum gestans Institutionem Regis inscriptum ; Leges et Instituta Regionis illius, quam candidatus ille Regni vel Toparchiæ administraturus erat, et præmia illi a Deo et populo conferenda, si Republicam benè gesserit, sin autem malè supplicia illum et posteros manentia, complexum. In his enim rebus tractandis Liber Regum et Institutio Regis versantur.

“Sæpius etiam ejus amici, prædes effecti, obstringebantur illum vel instituta Regionis, ex præscripto Institutionis Regum ad amussim impleturum, vel Regno se ultrò, citra litem, abdicaturum. Nec Tuadedanani Bressum Magnum, Eleathani filium, Regio titulo potiri ante passi sunt, quam ejus amici simili se pacto devincerint.

“Regi designato virgam antiquarius porrigebat, ac deinde conversus ad adstantes, arma Regi ad suos in officio continendos in posterum minimè necessaria pronuntiat : populum enim ei non secus ac discipulorum magistro morem gerere debere adultiores discipulos et sui commodi intelligentes, semper præceptoribus suis amorem, obsequium, et gratias deferre solere, et subditos ad similia officia Regi suo præstanda obligari, utpote qui jus iis justitiæ virgæ, non ferri acie administrat. Virga Regi per antiquarium tradita tota erat

h-íocópáin bíor aige, agus nac lé faobas airm na h-éagópa. Ar amluio bíor an t-plateo do beiran t-ollam a láim in pioḡ, geal go h-íomlán, do cómápea na pírinne lé o-tuigéior in ḡile bíor 'ran plait, do brioḡ go ramluigéior in geal nír in b-pírinne, agus an oub nír in m-bréig. Ar í cúir fa m-bí in t-plateo oírioc o'á cor a ḡ-céill do na puiblic-uis, agus do na tuasúib, gur ab oírioc, ḡlan, oligiuir an t-geapna beie 'n-a ḡníom-uis, 'n-a briaéruib, agus 'na breaéruib, ior coruio agus námuio, amúil do beie impiorán ior a o'á láim. Ar uime do ópuiḡiuoir in t-plateo roin gan faob gan cnopán uirre, acé coimpreio uile, o'á cor a ḡ-céill do na tuasúib, gur ab amluio oligie na t-geapnuioe beie gan aníocpaé, gan gaipbéio, acé coimpreio uile.

"A o-Teamruig do gaipéi gaé Rí do pioḡuib Eirionn riam, ag a mbíoc pioḡ-acé Eirionn uile, do éoil na n-uapoi, agus na n-ollam pé ḡ-cneioiom, agus do éoil eagalri, uairle, agus Ollamán ó roin anuap.

Ar leic na pioḡ a o-Tularḡ Oḡ do

erat candida, ut veritatem et candorem illi mordicus observandum esse in regimine indicaret; uti enim nigredo mendacium, ita candor denotat veritatem. Illa etiam virga recta fuit, ut omnibus innotesceret Regem semper æquum et rectum spectare debere, nec verbum ullum aut iudicium præferre, quod injuriam sapere possit. Eum nimirum teneri amicis et inimicis, summis et infimis, æquitatem juxta exhibere, non secus ac si lite inter ambas manus ortâ, æqualem se utrique præstaret. Eadem etiam teres erat et nodi omnis expers, ut meminerit Rex iræ se tubere [aut] asperie subditis minimè præbere, sed composito sedatoque animo ac vultu, legibus sancita suis pariter et alienis prout jus postulat, administrare.

"Totius Hiberniæ Reges Teamoriæ^x inaugurabantur, primoribus et antiquariis ante Christianismum huc illatum, assensum præbentibus: sed post Hibernos Christianismo imbutos Episcopis, proceribus et antiquariis suffragia ferentibus.

"Super lapidem Regium in Tulchoga^y O'Nelli

^x *Teamoria*, at Tara, in Meath. The stone on which the pagan kings were inaugurated at Tara was called the *Lia Fail*, and Mr. Petrie has shown that it is still preserved there, though it was fabled by Hector Boece, and believed by the credulous Keating to have been carried to Scotland, and thence to Westminster.

^y *Tulchoga*, now Tullaghoge, a small village in

the parish of Desertoreaght, barony of Dunganon, and county of Tyrone. The Lord Deputy Mountjoy remained here for some time in 1602, and broke in pieces the stone on which the "O'Neale was made," but it is said that pieces of it were to be seen in the orchard belonging to the glebe house till the year 1776, when the last fragment of it was carried away.

ḡairéí O'Néill, ḡur O'Catáin, ḡur O'h-Aḡáin oo ḡairéas é, O'Donnḡaile a marḡḡal ḡluarḡ, ḡur Muineior ḡhḡir-leín, ḡur Clann ḡhiorḡaḡḡo bḡeizíomuin ḡeiniócuir Ulaó uile.

“A ḡ-Cill Miceḡenain oo ḡairéí O'Domnaill, ḡur O'ḡiorḡail oo ḡairíob é, ḡur O'ḡallcuḡair a marḡḡal ḡluarḡ.

“Ar Mhaḡ n-Aḡair oo ḡairéí O'ḡriain; Mac Conmaḡa oo ḡoiríob é. O'Duibḡoir Choille na manaḡ a marḡur-

O'Nelli nunciabantur ab O'Cathano^a et O'Hagano^a, O'Dongholius^b autem militiæ ab O'Nello; Breslani^c vero, et Clanbirthagri^d rei judiciaræ præficiabantur.

“O'Donnelli, Kilmacnenanæ^e, ab O'Farghil^f inaugurabantur, et O'Galchurum^g militiæ præfectum habebat.

“In Magh Adhor^h O'Briano dignitas conferebatur a Macconmaraⁱ: O'Duibhir de Coilnamanagh^j et O'Gorman^k erant O'Briano

^a *O' Cathano*, by O'Cahan, or O'Kane, chief of Oireacht Uí Chathair, comprising the baronies Tirkeerlin, Keenaght, and Coleraine, in the county of Londonderry.

^a *O'Hagano*, now O'Hagan. The site of the ancient residence of O'Hagan is to be seen on a gentle eminence a short distance to the east of the village of Tullaghoge. It is a large circular encampment surrounded by deep trenches and earthen work. Within these stood the residence of O'Hagan the Rechteraire, or lawgiver of Tullaghog, and here too was placed the stone on which the “O'Neale was made,” till it was destroyed as above mentioned.—See *Annals of the Four Masters* at the year 1455. According to the tradition in the country, O'Hagan inaugurated O'Neill by putting on his golden slipper or sandal, and hence the sandal always appears in the armorial bearings of the O'Hagana.

^b *O'Dongholius*, now O'Donnelly. The chief of this name lived at Ballydonnelly, now called Castle Caulfield, in the parish of Donaghmore and barony of Dungannon, and about three miles west of the town of Dungannon, in the county of Tyrone.

^c *Breslani*, i. e. the O'Breslens.

^d *Clanbirthagri*.—This name is unknown to

the Editor.

^e *Kilmacnenana*, now Kilmacrenan, in the county of Donegal. It is said that the chief of Tirconnell was originally inaugurated on the hill of Doon, near the village of Kilmacrenan, but afterwards at the church. It is also said that the stone on which O'Donnell was installed King of Tirconnell was preserved in the old church at this village, but the Editor could not find it in the year 1835.

^f *O'Farghil*, called O'Firghil by the Four Masters, who state that he was the comharba, or hereditary warden of the church of Kilmacrenan. The name is now corrupted to Friesle.

^g *O'Galchurum*, now O'Gallagher, or Gallagher.

^h *Magh Adhor*, so called at this day, and situated in the townland of Toonagh, parish of Clooney, and barony of Upper Tulla, and county of Clare.—See *Circuit of Muircheartach Mac Neill*, p. 47.

ⁱ *Mac Conmara*, now Mac Namara.

^j *O'Duibhir de Coilnamanagh*, i. e. Dwyre of Kilnamannagh, in the now county of Tipperary.

^k *O'Gorman*, recte Mac Gorman, chief of the territory of Ibricken, in the west of the county of Clare.

gail rluaiḡ; Siol Flanncaḡa a bpeir-
iomain peimioḡair, Clann Crair a olla-
muin pe oan, agur Clann ḡruaiḡbeaḡa,
no Clann Cruirḡin a ollaḡmuin pḡ peanḡur.

“Ar ḡior ḡeannḡair no ḡairḡi Maḡ
Carrḡhaiḡ; O’Suillioḡain Mḡr, agur
O’Donnchaḡa Mḡr no ḡairioḡ é; Muin-
tir Ruairḡ a mairḡḡair rluaiḡ; Clann
Aḡḡaḡain a bpeirioḡmuin, Muinḡir Dá-
luirḡ a ollaḡmuin pḡ oan, agur Muinḡir
Duinin a ollaḡmuin pḡ peanḡur.

O’Brian a militiḡ prḡfecturá; Mac Glan-
chius¹ a jure dicendo; Clanchraith^m a
Poesi; et Clanchrutin^a et Clanbruadein^o a
re antiquariá.

“Mac Cartho Magno^p in Lisbanchor^a
insignia dignitatis porrigebat O’Sulevanus
Magnus^r, et O’Donnchus Magnus^s mili-
taribus ejus copiis, et Ruarkus^t suḡ diti-
onis imperabant; ad judicia exercenda
Clanegani^u; ad carmina pangenda Muin-
tir Dhali^v; Historias scribendas Muntir
Dhunnin^w, ab eodem designabantur.

“In

¹ *Mac Glanchius*, now Clancy. They were seated at Tulach Finn, near Sliabh Eilbhe, in the north-west of the county of Clare; Boethius Clancy, one of this family, was high sheriff of the county of Clare in the reign of Elizabeth. His death is thus entered in the Annals of the Four Masters: “A. D. 1598. Baothghalach, son of Aodh, who was son of Baothghalach, son of Muirchertach Mac Flannchadha of Cnoc Fionn, in the county of Clare, died in the month of April this year. He was well skilled in the Latin, Irish, and English languages.” According to the tradition in the country he murdered a number of Spaniards belonging to the great Armada, who were shipwrecked on the coast of Clare, and is cursed every seventh year in a church in Spain.

^m *Clanchraith*, i. e. the family of Magrath. The celebrated Irish work called *Caithreim Thoir-dhealbhaigh*, or Wars of Turlogh O’Brien, was written by the head of this family.—See *Battle of Magh Rath, introductory Remarks*.

^a *Clanchrutin*, i. e. the Mac Cruitins, or Mac Curtins, the last literary man of whom was Hugh Boy Mac Curtin, author of the Irish Grammar, English Irish Dictionary, and the Short Discourse on the Antiquities of Ireland.

^o *Clanbruadein*, i. e. the family of Mac Brody,

who were otherwise called Mac Dary. The last poet of this family was Tadhg, or Teige Mac Brody, who commenced the Contention of the Bards, already referred to.—See p. 82, Note v, and p. 320, Note v.

^p *Mac Cartho Magno*, i. e. the Mac Carthy More.

^a *Lisbanchor*, now Lisbanagher, in Kerry.

^r *O’Sulevanus Magnus*, i. e. O’Sullivan Mor of Dunkerrin, in the south of the county of Kerry.

^s *O’Donnchus Magnus*, i. e. O’Donohoe More of Ross, near Killarney, chief of Eoghanacht Locha Lein.

^t *Ruarkus*, i. e. O’Rourke, or Mag Ruairc.—See Hardiman’s Irish Deeds, published in the fifteenth volume of the Transactions of the Royal Irish Academy.

^u *Clanegani*, i. e. the family of Mac Egan.—See the notices of this family in the volume on Hy-Many.

^v *Muintir Dhali*, i. e. the family of O’Daly. There were various distinct branches of this family in Ireland, all following the poetical profession.

^w *Muintir Dhunnin*, i. e. the family of O’Duinnin. The name is still numerous in the county of Cork, where it is now anglicised Dinneen.

“Αἱρ Ḥnoc an Ḥoga vo γαιρέι Mac Murchaḥo, αγυρ O’Nuallān vo γαιριού έ ; α each, αγυρ α eppaḥ vo O’Nuallān; O’Deopaiḥān α Ḥreitioḥ, αγυρ Mac Eochado α ollam pé vān.

Αἱρ Zeic mīc Eochado vo γαιρέι eḡ-eapna Cinnriolaḥ, αγυρ Mac Eocaḥa vo γαιριού έ.

“Α η-Ḥún Caillige Ḥéirre vo γαιρέι O’Ḥroin αγυρ Mac Eochado vo γαιριού e.”

The next of the Irish writers who replied to Cambrensis, and attempted formally to refute him, was the celebrated Dr. Lynch, author of the translation of Keating’s History of Ireland, which has just been quoted; his observations on Giraldus’s account of the inauguration of the prince of Tiroconnell in his *Cambrensis Eversus*, are as follows :

* *Mac Murchuus*, i. e. Mac Murrough, now Kavanagh, of whom Kavanagh of Borris, in Carlow, is the chief, and next to him was the family represented in 1691 by Brian na Stroice, and in 1760 by Morgan Mor, a captain in the French service.

† *O’Nuclano*, now O’Nolan. He was chief of Fotharta Fea, now the barony of Forth, in the county of Carlow, where the family is still respectable.

‡ *O’Doran*, now Doran, a name very numerous in Leinster. According to the Irish annals the heads of this family were Brehons of Leinster, whence one of the name, emigrating to the United States of America, became a brehon or judge in our own time.

It is strange that the two last items are left untranslated by Dr. Lynch. The copies of Keating differ materially, and it is highly probable that Keating himself had inserted many passages into his work from the year 1629, when he finished it, till 1650, when he died, and that this may, in

“In colle Anbhogaidh Mac Morchuus^{*} honoris sui titulum inibat; O’Nuclano[†] dignitatis eum ornamentis insigniente, et equum ejus atque paludamentum pro præstiti officii salario referente: O’Doran[‡] Mac Murchuo fuit ab Historiis.” — *Dr. Lynch’s translation*, pp. 252, 253, 254.

[“Apud Lec Mic Eochadho nominabatur Dominus de Hy-Kinselaigh, et Mac Keogh nominabat eum.

“Apud Dun Caillighe Beirre O’Byrne nominabatur et Mac Keogh nominabat eum.”]

“Vides

some measure, account for the difference of the copies. The two passages left untranslated by Dr. Lynch sound thus in English :

“On Leac Mhic Eochadha, the Lord of Hy-Kinsellagh, was nominated, and Mac Eochadha [now Keogh, or Kehoe] used to nominate him.

“At Dun Caillighe Beirre O’Broin [O’Byrne] was nominated, and Mac Eochadha used to nominate him.”

To this list Keating might have added several other localities, as Carnfraigh, near Tulak, where the poet O’Mulconry, Mac Dermot, and others inaugurated the O’Conor; the Rock of Cashel, where the King of Munster was inaugurated; Sgiath Ghabhra, now Lisnaskea, near Enniskillen, in the county of Fermanagh, where Maguire was installed; Cruachan O’Cuproin, in the county of Leitrim, where O’Rourke was inaugurated prince of Breifny Tullyvea, where the Mac Mahon was made, Carn Amhalgaidh, where the O’Dowd was made, &c.

“ Vides vt in huius tam fædi ritus delineatione omnes eloquentiæ suæ, non historice, sed oratoriæ thesauros non segniter effundit. Sicut enim oratores quem laudibus exornandum susceperunt, eulogijs ultrà veri metas attollunt; sic Giraldus limites veri transiliens, omnes eloquentiæ caninæ machinas adhibet, vt istarum sordium infamia legentium animis altius infigatur. Nam *historicæ seueritas* (inquit) *nec veritati parcere novit, nec verecundiæ*. Nimirum homo (si Diis placet) fidissimus verecundiæ potius quam fidei jacturam facere maluit. Vt ille quem sæpius infidum deprehendimus, inuerecundum etiam se hic agnoscat. Qui proindè illam Ciceronis objurgationem declinare non potest dicentis, *Qui semel verecundiæ fines transierit, eum benè et grauiter oportet esse impudentem*. Itaque cuius impudentiam vidimus, jactantiam etiam eiusdem videamus, *Rem hanc inhonestam venusta verborum vermilitate* (vt ipse loquitur) *depromere* pollicentis. Promissam quidem orationis *vermilitatem*, siue venustatem in superiori spurcæ inaugurationis delineatione iam exeruit. Vt ex hac Giraldi ostentatione illam Stanihursti censuram prodiisse censeam dicentis : *Giraldum scriptorem meo sanè indicio non ferreum suo planè aureum fuisse*.

“ Sed qua veritate prolata inaugurationis narratio fulciatur dispiciamus. Domestici certè scriptores eam disertis verbis funditus evertunt. Hac enim quam subijcio ratione Tirconelliæ Regulos initiatos fuisse tradunt. Quando quis Odonelli titulo insigniendus erat, Tirconelliæ proceres et aliorum ordinum homines ad statum collem confluebant. Tum è proceribus vnus assurgens, peractis reverentiæ consuetæ officijs, candidam virgam, et omnino rectam, distortionisque omnis expertem quam manu gestabat, denunciato Regulo porrigens: accipe (ait) auspicatum dignitatis insigne, huius virgæ candorem, rectitudinemque moribus referre memento, vt nulla maledicendi libido factorum candorem notâ illâ maculare, aut studium in amicos animum à justitiæ rectitudine cuique præstandâ flectere possit. Imperium igitur tibi debitum bonis auibis ini, et huius Reipublicæ fasces securesque secure capesse. Nunc igitur in eo controversiæ cardo vertitur vninè neganti, an pluribus affirmantibus illi rem auditione tantum, his aspectu comperientibus fides adhibenda sit? dispiciendum etiam si a domesticis scriptoribus veriora, quam ab vno aduenâ producantur, et ab ijs qui pro suo munere res gestas scriptis tradunt, quam peregrino falcem in alienam messem immittententi tabulis, et monumentis publicis, quam privati cuiusuis narrationi, quæ non magis temerè agyrtæ alicui excidit, quam auidè à scriptore inuido excepta, et posteritati commissa est. Certè Scriptores patrii non studio, sed officij sui adimplendi causâ scriptis ista consignarunt, Giraldus res Hibernicas magis ex libidine, quam ex vero celebrat, obscuratque.

“ Quis credat Diuum Patricium, qui ditionem hanc accuratè perlustrans, illius incolas in fidei documentis apprimè instruxit, terræ principem Conallum Gulbanum

virtute sic informauit, vt laicum habitu, monachum vita egerit commissurum vt reliquorum scelerum surculis penitus euulsis, hanc vnam spurcitiam tanquam pristinae superstitionis fœcem non in obscuris aliquibus hominibus, sed in ipsis patriæ luminibus inhærere pateretur? Quod si S. Patricij vel notitiam, vel sollicitudinem tam obvia, et in tam clarâ luce collocata fœditas (quod credibile non est) subterfugeret; cognitionem profecto et reprehensionem plurimorum sanctorum in Tirconallia longo post temporum decursu commorantium declinare non potuit. Amplius quam quinquaginta sancti ex uno Conallo Gulbano prodiisse memorantur, quorum plurimi sedes in Tirconallia fixerunt, et cænobia plusquam viginti condiderunt. Duæ præterea sedes Episcopales Rapothensis, et Dorensis in eadem ditione constitutæ sunt; in quibus quot Episcopi et monachi morabantur, tot in ijs tanquam in speculis erant vigiles longè latèque prospicientes collocati, quos adeo perspicua macula tam diuturno temporis curriculo latere non potuit, Nec enim in latebris, sed in propatulo, nec inter plebejorum vltimos, sed in optimatum cœtu sordes istæ frequentabantur. Vt tam perspicacium virorum cognitionem, et purioris vitæ sectatorem animadversionem effugere non potuerint.

“Pluribus è Dorensium Rapothensiumque Episcoporum, Abbatumque serie non solum summa consuetudo ac familiaritas cum Tirconallia Regulis, sed etiam cognationis contiguitas intercessit. Ita vt si Principum reverentia præsules ab ijs objurgandis deterrebat; certè præsulum ergà cognatis studium ad eos è feritate tantâ eruendos attraheret. Putabimus nè SS. Columbam, Baithenum, Laarenum, Fergnaum, Suibhneum, Adamnanum, aliosque viros sanctissimos, in his partibus natos et pietatis informationem nactos, et impertitos acerrimos vitiorum proculcatores hos sentes, et tribulos increpationis falce non demessuisse? Quos si potestas istius mali abigendi defecisset, certè SS. Moelbridius et Malachias Hiberniæ Primates hinc oriundi ritum adeò peruersum latius serpere non paterentur. Nec ipsi principes crebra in alios liberalitate, in Deum pietate insignes, qui se multis humanissimos pluries exhibuerunt, Principatus initium ab inhumanitate tam execrabili ducerent. Qui si hanc impudentiam non vltro ponerent, eam supremi Reges Hiberniæ, seueris legibus proculdubio coercerent.

“Nullibi certè tam fœdâ alibi ludicrâ initiatione aliqui principatum auspicantur. *In Carinthia quoties nouus princeps Reipublicæ gubernationem inît, solemnitatem nusquam alibi auditam obseruant. In patentibus pratis erectis lapis marmoreus est, quem cum dux creandus est rusticus quidem, cui per stirpis suæ successionem hæreditario id officium debetur, ascendit, ad dextram bouem habens fœtam nigri coloris, ad leuam equa illi sistitur strigosa macieque insigni, frequens circa populus agrestiumque turba ingens. Dux indè futurus ex aduerso mouet purpuratorum multitudine sceptus procedunt Principatus signa, omnesque*

omnesque in toto comitatu egregiè culti præter futurum ducem. Is agresti habitu, pileo tectus, calceos et pastorem baculum gerens pastorem agit, magis quam principem. Hunc venientem intuitus qui lapidem obtinet Illirica voce quis est hic exclamat, qui tam superbè incedit? Respondet circumfusa multitudo Principem regionis adventare. Tum ille iustusne iudex? Salutem patriæ quærens? liberæ conditionis? Dignusne honore est? Christianæ pietatis cultor, ac defensor? Clamatur: est quidem et erit. Rursus idem, quæro quo me jure hac à sede dimovebit? Respondet Ducalis aulæ magister, sexaginta denariis hic à te locus emitur, iumenta hæc tua erunt, ad bouem et equam manum intendens, vestimenta quæ Dux exuet habebis; erisque tu cum domo tuâ tota liber à tributo. Quibus dictis rusticus malam percutit alapâ leuiter incussâ, iubetque æquum iudicem esse, præmioque abducta loco cedit. Tum lapidem Dux occupat, nudum gladium vibrans ad omnem se partem vertit, populum affatur, polliceturque se æquum iudicem futurum, Ferunt et aquam agresti pileo oblatam potare, in futuræ sobrietatis argumentum, &c., imperium Austriæ Principes obtinent, et Archiducem appellant. (Joannes Auban de Moribus gent. l. 3, c. 18).

"Nec mirum est in Principum inferioris ordinis inauguratione ludicros gestus adhiberi; quando Imperator ipse Romanus post coronam auream a Pontifice receptam in montis Martij bis mille passus Româ dissiti vertice manu elatâ se gyrat dicens: *Omnia quæ videmus nostra sunt,*" &c.—*Cambrensis Eversus*, pp. 315, 316, 317.

To the foregoing observations of Keating and Lynch the Editor has to add, that most probably Giraldus never himself saw the ceremony of the inauguration of the prince of Tirconnell; and that he, therefore, repeated it from the report given him by some enemy of the Irish, as he did many other silly stories, such as the legend of the eruption of Lough Neagh, the legend of the speaking wolf, which predicted that the English would subdue the Irish, the story of the men who were wont to turn stones into red pigs and sell them at fairs, &c. &c. That he was never in Tirconnell, and therefore could not have been an eye-witness to the ceremony of the inauguration of the prince of Tirconnell, is pretty clear from his own words, in his *Hibernia Expugnata*, from which it can be inferred that he never dared to travel beyond the limits of the English power in Ireland, for, speaking of the English who had ventured into the territories of the Irish, he says, "*Ubi capti decapitati, non redempti sed interrepti.*"

That Giraldus's account of the inauguration of the prince of Tirconnell is a fabricated falsehood, and of a similar character with many others of his stories, is clear from the fact, that the Irish writers themselves, who often allude to Irish customs barbarous enough to modern ideas, never make any allusion to such a form of inauguration, and it is not for a moment to be supposed that the form used in inaugurating the prince of the Cinel Conaill tribe was different in any material point from that adopted by the prince

prince of the Cinel Eoghain, or any other of the ancient Irish septs. But happily for the character of the ancient Irish, the form of inaugurating their chieftains continued in full force, to its utmost acme of barbarity, till the reign of James I. of England, and we have on this subject the testimony of Spenser, who does not appear to have read a word of Cambrensis's great work on Ireland, and who, though pretty well primed with prejudices against the native Irish, still lived so near the age of historical veracity that we may safely believe him, particularly on this point, whereon he does not materially differ from the account left us by the native Irish writers of the usual form of the inauguration of their chieftains. Spenser lived many years in Ireland in the reign of Queen Elizabeth, and in his curious work, entitled "View of the State of Ireland" (which is written in the shape of a dialogue between Irenæus and Eudoxus), he gives the following account of the inauguration of the Irish chieftains :

"*Eudox.* What is this which you call Tanist and Tanistry ? they be names and terms never heard of nor known to us.

"*Iren.* It is a custome amongst all the Irish, that presently after the death of one of their chief lords or captaines, they doe presently assemble themselves to a place generally appointed and knowne unto them, to choose another in his steed, where they do nominate and elect, for the most part, not the eldest sonne, nor any of the children of the lord deceased, but the next to him of blood, that is, the eldest and worthiest, as commonly the next brother unto him, if he have any, or the next cousin, or so forth, as any is elder in that kindred or sept ; and then next to him do they choose the next of the blood to be Tanist, who shall next succeed him in the said captainry, if he live thereunto.

"*Eudox.* Do they not use any ceremony in this election ? for all barbarous nations are commonly great observers of ceremonies and superstitious rites ?

"*Iren.* They use to place him that shalbe their Captaine upon a stone, alwayes reserved for that purpose, and placed commonly upon a hill ; in some of which I have seen formed and ingraven a foot, which they say was the measure of their first captaine's foot, whereon hee standing receives an oath to preserve all the auncient former customes of the countrey inviolable, and to deliver up the succession peaceably to his Tanist, and then hath a wand delivered unto him by some whose proper office that is ; after which, descending from the stone, he turneth himself round, thrice forward and thrice backward.

"*Eudox.* But how is the Tanist chosen ?

"*Iren.* They say he setteth but one foot upon the stone, and receiveth the like oath that the captaine did."—Dub. edit. p. 11, printed from the first edition, 1596.

Another writer who appears to have seen the ceremony of inaugurating an Irish chief with his own eyes, Philip O'Sullivan Beare, being born about the year 1588, and who

who had never read a word of Cambrensis's work, thus describes the ceremony in his *Historiæ Catholicæ Ibernæ Compendium*, tom. i. lib. 3, fol. 33, p. b.

“CAPUT III.

“Ibënorum magnatum inauguratio, et apud eos esse novos aliarum gentium titulos.

“Inaugurantur verò Ibernî optimates, vel alij ab aliis, vel ab illis, quibus more maiorum est consecrandi facultas data. Ad quod in locum inaugurationi constitutum conveniunt, longis hominum agminibus, et solemnî pompa comitati. Ibi intersunt iudices, qui, cui candidatorum principatus debeatur, ex jure, legibusq; pronuncient. Mox consecrandi jurare coguntur, nunquam se contra fidem Catholicam aliquid machinatos, aut permissuros, ut clientes, oberati et suse dictioni subjecti moliantur. Quin etiam, si necesse habeant, sanguinem pro ea effusuros, et mortem oppetituros: subjectos sibi in officio contenturos, et inter eos justitiam exercituros. Inde a sacerdote sacrum Missæ peragitur, et virga consecratur, quæ in sceptrum novo principi traditur, qui certis et conceptis verbis, ab eo, qui inaugurat, prolatis, vel Osullivanus, vel Orellus, vel alius creatur et appellatur, et a circumstantibus renunciatur, nec amplius proprio baptismatis nomine solet vocari. Sic vetustati placuit nec hodiè etiam displicet, etai Marchionis, Comitis, Vicecomitis et Baronis dignitates quas Ibernia diu respuit, his antiquissimis titulis posthabitis, jam sint in magno usu et honore.”

This account of the inauguration of the Irish chieftains, by Philip O'Sullivan Beare, may be objected to, on the grounds that as there was no difference of religion among the Irish until shortly before the discontinuance of the custom of electing Irish chieftains, so there could have been no necessity of swearing to defend the Catholic faith. But it is highly probable that such Irish chieftains as were inaugurated in Munster during the rebellion of the Earl of Desmond, were obliged to swear that they would defend the Catholic faith to the utmost of their ability. In this view O'Sullivan's account may be regarded as correct, but it seems improbable that before the reign of Elizabeth, the chief to be elected was required to swear that he would defend the Catholic faith. This was a notion that sprang up in O'Sullivan's time, which then told very well among the Spaniards, who patronized the Irish; and it will be remembered that O'Sullivan's book was chiefly intended to rouse the Spaniards to sympathy with the Irish. It is highly probable, however, that the chief to be inaugurated was made to swear to the coarbs of the Church in his territory that he would preserve the rights and immunities of their churches, and to the utmost of his ability prevent the neighbouring chieftains from plundering their sanctuaries and termon lands. The next point which looks suspicious in P. O'Sullivan Beare's account is the consecration of the rod by a priest. No mention is made of such a consecration by Keating, who was
coeval

coeval with Philip O'Sullivan Beare, and who must have seen the ceremony as well as he, and no reference to such is found in any native Irish account; and indeed it looks very strange that if the wand were consecrated by a priest, it should not have been presented to the chief by the bishop, or one of the coarbs of the churches, rather than by the bard or lay chieftain. The fact seems to be, that the rod was not consecrated by any religious ceremony, but it is highly probable that when Dr. Sanders was sent to Ireland to instruct the Geraldines, he suggested to the Earl of Desmond that such Irish chieftains as were to be inaugurated in Desmond should be called upon to swear to defend the Catholic faith, and that the wand should be consecrated to render the ceremony more solemn and sacred. That the rod, however, was handed to the chief by the ollamh or chief poet, or by the historian or chronicler of the district, or by another chieftain, will be sufficiently obvious from the following authorities:

1. In a tract entitled *Teagusc Rígh*, preserved in the Library of Trinity College Dublin, H. 1, 17, it is stated, that the Bard read the heads of this work to the chief to be inaugurated, and asked him if he were willing to preserve inviolable the laws written in this book, which when the chieftain had answered in the affirmative, he was presented by the bard with a rod.

2. The following account of the inauguration of the O'Dowd, inserted in the Book of Lecan in a beautiful hand, very nearly as ancient as the original, and which is undoubtedly authentic, will show that although bishops and the coarbs of churches were present at the ceremony, still the rod was handed to the O'Dowd by Mac Firbis, the chief poet and historian of the district, which would hardly have been the case if the rod had been consecrated.

“Αἰγυρ τῦρ σῖγῖ σ'Ο'Caomhain ó Ua
n-Dubha; αἰγυρ γαν Ο'Caomhain σ'α
h-íðí no go τῦγα ρέ σσ'ñ φίλῖσ h-í, .i. σσ
Mac Fírbíurí, αἰγυρ αρμ αἰγυρ εαρρσάσ,
αἰγυρ εἰch h-l Duðba ταρ εἰρ anma σσ
γαιρμ σσ σ'Ο'Caomhain, αἰγυρ αρμ αἰγυρ
εαρρσάσ h-l Chaomhain αἰ Mac Fírbíurí;
αἰγυρ ní σῖngmála Ο'Duðba σσ γαιρμ
co bpat, no go n-γοῖrῖσ Ο'Caomhain

“And the privilege of first drinking
[at the banquet] was given to O'Caomhain
by O'Dubhda, and O'Caomhain was not
to drink until he first presented it* [the
drink] to the poet, that is, to Mac Firbis;
also the weapons, battle dress, and steed
of O'Dubhda, after his nomination, were
given to O'Caomhain, and the weapons
and battle-dress of O'Caomhain, to Mac
Firbis;

* First presented it, &c.—From this prerogative it would appear that Mac Firbis was the senior of the race of Fiachra, and that he was really descended from Amhalgaidh, the son of

Fiachra Ealgaidh, who constructed Carn Amhalgaidh. For an account of a similar honour shown by O'Conor of Connaught to O'Finaghty, in token of seniority, see page 108, Note ^b.

agur Mac Fírbíorgh an t-annm, agur nó
go n-abra Mac Fírbíorgh corp na rlaite
or cinn h-l Dubha; agur gac cléiríech,
agur gac comarba cillí, agur gac
Érboc, agur gac taoiréac fepoino so
raða an annma a n-oiag h-l Chaomhain
agur Meic Fírbíorgh; agur ata ní cena,
oa tégmas a Tíri Amalgais O'Dubha

Firbis, and it is not lawful ever to nomi-
nate the O'Dubha until O'Caomhain and
Mac Firbis [first] pronounce the name,
and until Mac Firbis brings the body of
the rod over the head of O'Dubha; and
after O'Caomhain and Mac Firbis every
clergyman and comharba of a church, and
every bishop^b, and every chief of a district
pronounce

^b *Every bishop*.—This account of the inaugu-
ration of O'Dowd was certainly written while
the custom was in full force, and there can be no
doubt that it is perfectly correct. It will be cu-
rious here to notice, and compare with it the
modern traditional account of the ceremony, in
order to show how facts are obscured and exag-
gerated by oral tradition. The modern tradi-
tional account of this ceremony, which was pub-
lished in the *Rainbow, or Western Magazine*,
No. III., July, 1840, pp. 144, 145, erroneously
states that the O'Dowda was inaugurated on the
hill of Ardnarea, which is incorrectly interpreted
as denoting *Eminence of Kings*.—See p. 34,
Note * of this volume. It runs as follows, being
given in the shape of a traditional story told to
the writer by a native of the district:—"After
having directed my attention to the various
places, he at length said, 'The mound on which
you stand is the most interesting spot in the ex-
tensive district now before you. It is connected
with the ancient history of this country, and as-
sociated with many of those wild and beautiful
legends which are handed down by tradition
among the people. This hill is called *Ardnarea*,
which means the *Eminence of Kings*, and the
name was given to it from the fact that it was
the place on which the ancient rulers of this
country were inaugurated. Before the introduc-
tion of Christianity the ceremony was performed

by the archdruid, whose altar you may perceive
to be still standing on the hill to the west (and
he pointed out the spot)" [but all false, for that
is the monument of the murderers of Bishop Cel-
lach.—See p. 34, Note *.—Ed.] "But when the
light of the Gospel succeeded to the superstitions
of the ancient Irish, a Christian bishop presided
at the coronation of the ruler of the district. He
was assisted by a numerous assembly of inferior
clergy, and by all the chiefs of the surrounding
country, who had a voice in the selection of the
prince who was to govern them: for though the
sovereignty was hereditary in the family of the
O'Dowda, the eldest son did not always succeed—
but that prince was chosen, whose physical pow-
ers and mental qualifications were best adapted
to command respect and maintain the dignity of
his high station. On the day of election the bards
and heralds took possession of the summit of this
mound, and prepared the seats for the ceremony.
The multitude remained below, but sufficiently
near to take such part as their leaders would di-
rect them, and it sometimes happened that violent
contests arose between the followers of the re-
spective candidates, and that blood was spilt to
maintain their pretensions to the crown. In ge-
neral, however, the bishop and his clergy suc-
ceeded in allaying the animosity of the contending
parties, and the election concluded in peace, and
with all the rude festivity of the times. On this

oo bu uolta oo co Capnn Amalgau oo
 garpm anma oe, ach go m-beie na taol-
 rið farir: agur no oa tegmao a Capnn

pronounce the name. And there is one thing, should O'Dubhda happen to be in Tir Amhalgaidh [Tirawley] he may re-pair

spot the bishop's throne was placed, and on either side there were seats for the clergy, according to their dignity and gradations; and on that other spot directly opposite the prelate was placed a low stool for the candidates for sovereignty. The lay chiefs formed a circle on the outside, and behind each were his bard, herald, and guards to preserve order and direct the movement of the multitude below. Previous to the ceremonies on the mount high mass was celebrated in the church with all the pomp and splendour of the Catholic ritual. The prelate addressed the assembly, and pointed out to all the parties concerned their respective duties, and he seldom failed to have such an understanding with the candidates and their adherents as to prevent confusion afterwards. The order of procession was as follows:—First, a clergyman in his surplice, bearing aloft the cross with an image of the crucified Redeemer, and on each side of him a trumpeter, who announced the approach of the procession. Then came the candidates, each attended by a bard and aged counsellor—those were followed by the chiefs, bearing wands, according to their seniority, the youngest being foremost, and after each his train of bards, counsellors, and body-guards. To those succeeded the inferior clergy, followed by the dignitaries, and last of all, by the bishop himself, crowned with a mitre, and bearing in his hand a crozier, or pastoral staff, to indicate his office. The respective parties on their arrival took up the positions assigned to them; and, after a brief prayer by the bishop, he called each of the electors by name, beginning with the youngest, and asked whom he would have as his ruler; and if two-

thirds of the electors were found to agree upon any one of the candidates he was proclaimed forthwith. The bishop administered the usual oaths to him, anointed him with oil, and, having set the crown on his head, led him to the throne which himself had occupied before, and then did him homage as his subject. The chiefs followed, and, as each did homage, he broke his wand, to indicate that the sovereign authority was now vested in the prince they had chosen. After this ceremony was concluded the procession returned to the church in the same order as it had gone out, except that the sovereign came in the last place as most entitled to honour. Here another exhortation was made by the bishop, the object of which was chiefly to impress on the new king the necessity of governing with justice and mercy, and of promoting to the utmost of his power the happiness of his subjects. The multitudes then dispersed, and the evening concluded with festivities and rejoicings. Three centuries at least have passed away" [the last election of an O'Dowda was in 1595.—Ed.] "since the last election took place on this mount, and though there is still an O'Dowda, the lineal descendant of the last sovereign of this territory, his present title to any preeminence consists in a large tract of hereditary estate, and the many virtues which adorn his amiable character. He hopes not for any other sovereignty, for it has been decreed by unerring fate that no O'Dowda will be ever inaugurated on the hill of Ardnaree. The hopelessness of their case has passed into a proverb, which is continually quoted to express a forlorn hope that can never be realized. The proverb is *Suil ee*

ingine Bhriain h-é, nír dólta do anonn do
 gairm an anma, agus nír éigé do anall
 ó Capann Amalgaidh, áir ip é Amalgaidh
 mac Fiacra Algaio, do tocuil an capann

pair to Carn Amhalgaidh^c to be nominated,
 so as that all the chiefs are about him :
 but should he happen to be at Carn in-
 ghine Bhriain^d [in Tireragh] it is not ne-
 cessary

Ghlooda [*Dhlooda*] *le Ardnaria*. '—See pp. 307,
 308, Note 9.

This account is curious, as containing some
 glimmerings of truth, but the writer has added so
 much from his own imagination to the simple
 tradition, that he has rendered it of little or no
 historical value.

^c *Carn Amhalgaidh*. — The situation of this
 place has not been pointed out by any of our to-
 pographical writers, nor is there any monument
 in the barony of Tirawley now bearing the name.
 But from the description of the place given in the
 Dinnsenchus, Lib. Lec. fol. 247, a, a, it would
 appear that it was situated on the summit of Mul-
 laghcarn, i. e. *hill of the carn*, situated about half
 a mile from the town of Killala. The carn itself,
 which gave name to this hill, has been nearly
 destroyed, but there is still a very curious monu-
 ment on the hill a short distance to the north of
 the road. It resembles an earthen fort with
 round stones of great size placed in a circle on
 its border. The internal diameter of this circle
 is about seventy-eight feet, and its external di-
 ameter is two hundred and forty feet. Some of
 the large stones, which were removed from this,
 and also from an adjacent monument, are still to
 be seen in a field not far distant. Mullaghcarn
 stone circle commands a most extensive view of
 the country in every direction, also of Killala
 bay and of a great extent of the sea, and cor-
 responds in every particular with the references
 to Carn Amhalgaidh, which is said to have been
 constructed by Amhalgaidh, the son of Fiachra
 Ealgaidh, the ancestor of the Mac Fimbises,
 among other things, to command a view of his

fleet going out and coming in.

^d *Carn inghine Bhriain*, i. e. the carn of the
 daughter of Brian. This carn has not yet been
 identified with any satisfaction. It is not the
 carn on the red hill of Skreen already described,
 for that was the carn of Rufina, the daughter of
 Airtiri Uchtleathan. The Editor is of opinion that
 the Carn inghine Bhriain was the grand one called
 Miosgan Meidhbhe, situated on the conspicuous
 hill of Ardnarea in Cuil Irra; for Meadhbh, after
 whom that carn was called, might have been the
 daughter of Brian, the eldest son of King Eochaidh
 Muighmheadhoin, and thus it might be appropri-
 ately called Carn inghine Bhriain, or the carn
 of the daughter of Brian. But the Venerable
 Charles O'Connor was of opinion that this carn on
 Knocknarea was called from Meava, the daughter
 of Eochy Feylogh, King of Ireland, and the cele-
 brated Queen of Connaught, who raised so much
 disturbance in the kingdom during the times of
 Tiberius, Caligula, Nero, and Claudius.—*Letter*
to Dr. Curry, Aug. 27th, 1761. But we have
 the direct evidence of the most authentic Irish
 MSS. that Meadhbh, or Meave, the daughter
 of King Eochy Feylogh, was killed on the
 island of Inis Clothrann, in Lough Ree, in the
 Shannon, and buried at Cruachan (see p. 28,
 Note 7); so that we cannot for a moment believe
 that the carn on Knocknarea, called Miosgan
 Meidhbhe, was called after Meadhbh, the daugh-
 ter of Eochy Feylogh, as O'Connor asserts, evi-
 dently without having sufficiently considered the
 subject. But it may be objected to this con-
 jecture that Ardnarea lies to the east of the strand
 of Traigh Eothuille, and that, therefore, it is out-

oo féin oo cum ainn tigeapna oo gairm
 oe fein agur oa gac ouine oá n-gebaó
 flaiter na diaig, agur ir ann aca Amal-
 gais fein aóluic, agur ir uada ainn-
 nigeer an capnna; agur gac níg oo
 clanoaib Fiachra ná gairfead ainn
 map rin biaó gair feicle oo, agur ní
 ba h-oirpnaic a iúl ná a reimeao agur
 ní faicfe flaitiur De co bnae. Finit
 Amen."

cessary for him to go over [the Moy] to
 have the title given to him, and it is not
 necessary for him to come across [to Carn
 inghine Bhriain] from Carn Amhalgaidh,
 for it was Amhalgaidh, the son of Fiachra
 Ealgach, that raised that carn for himself,
 in order that he himself, and all those
 who should obtain the lordship after him,
 might receive the style of lord upon it.
 And it is in this carn that Amhalgaidh
 himself is interred, and it is from him it
 is named. And every king of the race of
 Fiachra that shall not be thus nominated,
 he shall have shortness of life, and his
 race or generations shall not be illustrious,
 and he shall never see the kingdom of
 God*. Finit. Amen."

3. We are informed by Philip O'Sullivan Beare that one chief was often inaugurated by another. Of this we have a good example on record in the Court of Chancery in Ireland, namely, an abstract of a law suit which took place in 1592, before the Lord Chancellor, Adam Loftus, between Donell O'Donovan of Castle Donovan, chief of his name, and his brother Teige O'Donovan, who attempted to depose him, but failed. This document is of great importance to this inquiry, as the case was decided according to the Irish custom of Tanistry, and as it is perhaps the only registered law document in which the custom of inauguration of the Irish chieftains is distinctly recognized. The Editor is therefore tempted to present the reader with extracts from it.

"To His Honorable Lordship the LORD CHANCELLOR,

"SHEWETH,

"Your poore Supplicant Teige O'Donovane of Castledonovane, in the county of Corke, Genta.—That whereas he was seised in his demesne as of fee of the Manors, Castells,

side the limit of O'Dowd's legitimate territory, and the Editor is willing to grant the weight of this objection to its fullest extent, though it will appear from the poem of Giolla Iosa Mor Mac Firbis, written in 1417, that O'Dowd claimed

jurisdiction over the entire country as far as the River Cowney, which falls into the sea at Drumcliff.

** The kingdom of God.—This shows clearly that the ceremony was considered a religious one.*

Castells, Townships, Lands, &c., of the Lordshipp of Clancabell, was wrongfullie disseised by Donell O'Donovane, comonlie called O'Donovane of Castle Donovan ; and as the said Donell is a man of greater wealth and alliance in those parts your Supplieant may not have indifferent tryall at common lawe, and that the premises doe alsoe lie in a remote countrey, that therefore it may please your Lordshipp to cause the said Donell to appeare before your Lordshipp to answer to the premises.

“Donell O'Donovane in answer saith, that the O'Donovan for the time being hath bene tyme beyonde the Memorie of Man seised of the said Lordshipp and hereditaments of Clancabell, and that the Custom of Carebry, where the said Lordshipp lies, is, and hath bene tyme beyond Memory, that the chieftaine of the said contrie of Cairbrie, called Mac Cartie Reough, and the moste parte of the gentlemen of the said contrie have and had the ellection, nomynatinge, and appointinge of the O'Donovan, for the tyme beinge, of one of the best and worthiest of the said Name, and whosoever the said Mac Cartie Reough and the greatest part of the said Gentlemen should nominate, appoint, and ellect for O'Donovan, and signifie the same by delivering a Rodd to the person so chosen, by the hands of the said Mac Cartie Reoughe, he should have and enjoye, during his lyfe, the said Castells, Lordships, and other hereditaments.—By virtue whereof one Dermot O'Donovan^f, Great Grandfather to this defendant, being ellected and having received a Rodd of the said Mac Carthie Reough, enjoied the same, and after his decease one Dermond mac Conogher O'Donovan^g beinge ellected, enjoied the

^f *One Dermot O'Donovan*.—The pedigree of this Dermot, who flourished about the year 1492, is given as follows by Duaid Mac Firis, in his smaller compilation of 1666 :—“Diarmaid, son of Ragnall, son of Conchobhar, son of Murchadh, son of Tadhg, son of Cathal, son of Crom, son of Maolruanaidh, son of Ragnall, son of Anelis, son of Murchadh, son of Amhlaoibh, son of Cathal, son of Donnabhan, the progenitor of the O'Donovans.” In the margin of p. 632 of his larger work, begun in 1645, and continued, with various interruptions, till the year 1664, he has inserted, evidently long after the original compilation, from some Munster genealogical work, the pedigree of Donell O'Donovan, the defendant, as follows :—“Domhnall, son of Domhnall, son of Tadhg, son of Diarmaid, son of Ragnall,” &c., which perfectly agrees with this law docu-

ment, which was registered in the year 1592, and which has scarcely been opened ever since, for, according to this document, Donell, the defendant, who was inaugurated in 1584, was the son of another Donell, who was Mac Teige, or son of Teige, and a Dermot O'Donovan, chief of Clancabell, was the great grandfather of Donell, the defendant. This confirmation of the correctness and trustworthiness of Mac Firis's compilation is highly worthy of notice in this place.

^g *Dermond mac Conogher O'Donovan*.—He is not mentioned in the pedigree of O'Donovan given by Mac Firis, nor even in the elaborate one compiled by John Collins of Myroes. He was probably the uncle of his predecessor, that is, Diarmaid, son of Conchobhar, son of Murchadh, son of Tadhg, son of Cathal, son of Crom, son of Maolruanaidh, &c.

the same during his life, and after his death one Donell Mac Dermott^b being elected, O'Donovan was also seised during his life, and after his death one Teige mac Dermondⁱ O'Donovan being elected was likewise seised of the said Contrie, and after his death one Daniel Mac Teige^j O'Donovan, father to the Defendant, being elected, was likewise seised of the said Lordship during his life. And after his said Father's death, Sir Owen Mac Cartie, Knight, being Mac Cartie Reough, and chieftain of Carebrie, and the greatest part of the gentlemen of the said Countrie of Carebrie, have elected, chosen, and nominated the defendant [as] O'Donovan, as best and worthiest of the said seapt of O'Donovans, and Mac Cartie delivered him a Rodd wherefore he entered to all the Lordshipp and Lands, and was seised without interruption these eight years past, as was and is for him lawful.

"Where to Teige O'Donovan replied, that he admitted that Mac Cartie Reough being lawfullie Mac Cartie, and no intruder, by assent of most of the freeholders, did use to invest and instal the worthiest of the O'Donovans in the chieftainrie, before which installacion the right of the chieftainrie, with the freehold and inheritance, was cast upon the said Worthiest of the O'Donovans, so as the investinge or installment did yield unto him but the name of Chieftane having the freehold and inheritance cast upon him theretofore; and, therewithall, by the usage and custom of the said contrie, an illegitimate, or base sonne, was to be secluded and put besides the Chieftainrie, Signorie, and inheritance, so that he that was lawfullie borne was ever interested by Custome in them and no bastard: and Donell mac Teige O'Donovan, father to this complainant, and supposed father to Donell, was seised of all those lands, and so died, having yssue this Complainant lawfullie borne, and after espousalls with Ellen Ny-Learie, and the Defendant Donell was borne by the said Ellen before the said intermarriage, so as the said Donell is base borne, and by the said Custome to be secluded. And howbeit Sir Owen Mac Cartie hath invested Donell in the said Chieftainrie, yet as this Complainant at that tyme was, and is yet within twenty-one years of adge, therefore

^b *Donell mac Dermott*.—He was the son of the Dermott, the first chief mentioned in this document.

ⁱ *Teige mac Dermond*.—He was the brother of the last mentioned, notwithstanding the difference of spelling of the name of their father, Dermond, Dermott. Collins says that this Teige was murdered by one of his freeholders, Denis Donovan of Meeny, or Moyny, while his son Donell was an infant, but we cannot believe this to be

true, as we have the authority of this document to prove that his son succeeded him, which he could not have done if he were an infant at the time of his father's death.

^j *Daniell mac Teige*.—This was the celebrated character called Domhnall *na g-Croiccana*, i. e. *Danielis pellium*, in the traditions of the country. He died in the year 1584, when his son Donell, the defendant, was elected to his place by Sir Owen Mac Carthy Reagh.

therefore Donell being base-born, was not nor is yet capable. Besides that one Donell Mac Cartie is intituled to be Mac Cartie Reough, whereunto he had right by Her Highnes' Pattents, so as Sir Owen is an intruder, and the installment of Donell O'Donovan by said Sir Owen, who is an intruder, is avoyded, who is mightilie supported by Sir Owen by his potency and greatnes, for that Donell O'Donovane matched in marriage with a daughter of said Sir Owen : Werefore the Complainant prayeth humblie release from your Honorable Lordship.

"Whereto Donell O'Donovane rejoineth—that Sir Owen Mac Cartie, now Mac Cartie Reough, was lawfullie intituled to the Chieftainrie of the Contrie of Carbrie, and lawfully seised as best and worthieste of the Mac Carties of Carbrie at the tyme of delivering the Rodd to this rejoinant, whoe mainteyneth himself to be best and worthiest of the blood of the O'Donovans, and saith he was borne after espousalls betwixt Donell mac Teige, his father, and father to the Complainant, and the said Ellen Ny-Learie, their mother, and not before. He also saith that the custom of the Countrie warranteth that Bastards, especiallie Muliers, by the Civill Law, might be O'Donovans : that the last Chieftain claymed the said Contrie but durynge his lyfe by the said custome, and not as his inheritance, so as nothinge could descend from him ; and therefore forasmoche as this defendant is lawfullie intituled and seised of the said contre as 'O'DONOVAN,' being best and worthiest of the bloud of the O'Donovans, and lawfullie is vested 'O'DONOVAN,' according the Custome tyme beyond the Memorie of Man, all which he is readie to averr.

"Teige O'Donovan to this further replies, that Sir Owen Mac Cartie is an intruder and the Ceremony of giving a Rodd by him is not by the usadge of the said Lordshipp warrantable ; further, if it fall out that Donell is illegitimate, as indeed he is, then is the averrment untrue, alledging him to be beste and worthiest of the O'Donovans, &c. &c.

"Uppon all which matters Commissioners were chosen of both parties to examine their wytnesses—whereupon it was directlie proved by diverse good witnesses, and especiallie by Sir Ffynen O'Driscoill, Knight, and diverse good gentlemen, that Donell was born many years after the marriadge solempnised at Dromale, in the county of Corke, betwixt Donell mac Teige and the said Ellen Ny-Learie, his mother, who had other sons elder than Donell^k, the Defendant, by reason whereof the complainant being
his

^k *Who had other sons elder than Donell.*—One of these was Diarmaid O'Donovan, who was slain by Daniel O'Sullivan Beare in 1581, and the oak tree, *cujus stipes adhuc manet*, out of which he

was hanged by O'Sullivan, is still called Dairi-heen Diarmada. The ancient Irish did not regard children thus born as illegitimate, for, according to the civil and canon law then used by

his younger brother, he had no title against the said Donell, the said Lordship being customarie, and Donell having proved the custome and his ellection as O'DONOVAN;— and for that it was proved that the father of both was made O'Donovan, and died seised of the Lordship and hereditaments of Clancabell, and the said Sir Owen Mac Cartie was Chieftain of Carbrie, by right, and not by usurpation, when he delivered a Rodd to Donell, now 'O'DONOVAN;' and Donell being the elder brother of Teige, the Complainant, being bothe born of one father and mother after marriage duly celebrated betwixte them accordinge to the rites and ceremonies of the holie church, he had beste right to inherit or succede their said father, and to be O'DONOVAN, and to have and enioie the Lordship, lands, tenements, and hereditaments of Clancabell.— And it is soe adjudged and Decreed, and the said Donell shall recover his charges and costs sustayned in this cause against the said Teige.—Yeoven at Dublin the 12th daie of Ffebruarie Anno Domini, 1592.

AD. LOFTUS, Canc.”

The form of the inauguration of the O'Donovan is more circumstantially described by John Collins of Myross, in his pedigree of the late General Richard O'Donovan of Bawnlahan. It is to be feared that he has supplied some things from his own imagination, which we know was sufficiently creative, for he was a poet, and though but a rude English scholar, he was the author of the beautiful Irish poem entitled “Soliloquy in Timoleague Abbey,” published, with an admirable translation by Furlong, in Hardiman's Irish Minstrelsy, vol. ii. p. 235. But he is entitled to some credit, as he was well acquainted with Irish history, and knew the traditions of the mountains of Carbery better than any person living in his time. The following is the account which he has given of the inauguration of Donell mac Teige O'Donovan, the father of Donell and Teige mentioned in the foregoing document; an account which, if true, presents a dreadful picture of the lawless ferocity of the times. After giving an account of the escape of Donell mac Teige in his infancy from
being

the Irish, the after marriage of the parents rendered them legitimate. But Sir Owen Mac Carthy Reagh, fearing the interference of the English law, then fast encroaching upon the ancient Irish customs, in this case took care to inaugurate as O'Donovan the eldest son of Ellen Ny-Learie, born after the celebration of her marriage with Donell mac Teige. Collins, who gives this part of the history of the O'Donovans from oral tradition and, as he says, from Irish MSS., suppresses the

fact of Ellen Ny-Learie having had children by Donell na g-Croiceann before their marriage. This he did from fear of the vengeance of the late General O'Donovan, who was very proud of his pedigree, though he never did anything to illustrate it, or reflect honour on his ancestors, except by running away from a battle in the Netherlands, accompanied by His Royal Highness the late Duke of York, whom he is said to have carried across a river in their flight.

being murdered by his relatives, the friends of his father and enemies of his mother, he proceeds as follows :

"Immediately after this had happened, his mother [Helena Ny-Donovan] took him away privately out of the reach of his enemies, and with him took refuge in Ibh Leary, at O'Leary's mansion castle Carrignacurra, where they remained in a state of concealment under borrowed names, until he came to a proper age and was well educated, as Denis na Meeny always supplied his daughter and grandson privately with money and every other necessary wanting to them. When he came to the age of twenty-one years his mother divulged his name and parentage, and consequently that he was the lawful heir to the title and lordship of O'Donovan. O'Leary gave him his daughter Helena O'Leary in marriage with a great fortune, and soon after a splendid retinue and well appointed body of his friends attended him to Carbery, there to take possession of his ancient lands and royalties. He was received with joy and congratulation by his grandfather Denis na Meeny the elder and his son Denis na Meeny the younger, and by their party, as also by Mac Conolly, who had served as captain under his father and grandfather, and whose ancestors, for a long time prior to that period, had been a kind of hereditary life guard to the O'Donovan family, and on that account had seven ploughlands assigned to them by O'Donovan in the parish of Drinagh. At the same time a Jeremiah Donovan of a collateral branch was laying in a claim for the property, and was candidate for the name. This Jeremiah, who was called *Diarmuid a Bhairc*, or of the Bark, from having been bred at sea, had a large party to espouse his claim, and amongst which was Ire Donovan of Castle Ire," [*recte*, Castle Ivor] "with his relations and followers, and the Sliocht Tioboit, or posterity of Tioboid, of which we have spoken before.

"The election was to be held in the town of Ross Carbery, under the superintendence of Mac Carthy Reagh, Prince of Carbery, who then dwelt at Binduff Castle, now Castle Salem, and who had the hereditary power of inaugurating the O'Donovan. The form of the inauguration was to give the chosen candidate a straight white wand in his right hand, as an emblem of unbiassed rectitude, and to cause him to swear solemnly to rule with strict justice and equity, as in those times every representative, or head of a family, was absolute in his own principality, and had a gallows and fosse, the former for the punishment of male criminals and the latter for that of the female ones.

"When the appointed day for the election came, Denis na Meeny and his party fell off to the south and met Ire with a division of his party at Ballaghalow, in the parish of Kilmackabea, to the west of Ross, slew himself, and cut off his party to a man. Captain Conolly, in company with Donell na g-Croiceann O'Donovan, O'Leary, and their party,

took the near way from Dromaleague to Ross, through the parish of Drinagh, and on his arrival found Diarmuid a Bhairc inaugurated, with the rod of justice in his hand, in the presence of Mac Carthy; wherefore he sternly demanded of Mac Carthy the reason, and, without waiting for a reply of any kind, ran Diarmaid a Bhairc through the body, who instantly expired. On which Donell na g-Croiceann was inaugurated and saluted O'Donovan! As many of the party and supporters of Diarmuid a Bhairc as were found in the streets of Ross were slaughtered and slain. The castle of Ire" [Ivor], "in the parish of Myross, was partly broken down and his lands taken and possessed by O'Donovan, and what survived of that branch were forced to quit that part of the country. The castle of Gortnaclough was also stormed, taken, and partly destroyed, and its lands taken by O'Donovan," &c. &c.

This, however, cannot have been the original form of the inauguration of O'Donovan, neither was Ross Carbery the original locality at which the ceremony was performed, for, previously to the beginning of the thirteenth century, the sept were seated along the River Maigue, in the present county of Limerick, and the chief resided at Croom, or Bruree, and the probability is, that he was inaugurated on the moat at Bruree, not by Mac Carthy, but by his own people of Hy-Figinte. When the O'Donovans were driven out of the plains of Hy-Figinte, they encroached on O'Driscol and others, and taking their tribe name with them, transferred it to the territory over which they had acquired dominion, and which had been previously called Corca Luighe¹; and we find that in the year 1200 Auliff, or Amlaff, More O'Donovan, who was slain at Kinneigh in that year, is mentioned in the Annals of Innisfallen as chief of the territory of Carbery, a name then recently transferred to Corca Luighe. But the descendants of Donell God [the stammering], the son of Donell More na Curra Mac Carthy, who died in 1185, increasing mightily in numbers and power, elected a chieftain for themselves distinct

¹ *Corca Luighe*.—Nothing is more certain than that the extensive district in the county of Cork now called Carbery, and subdivided into various parts, was originally called Corca Luighe, and belonged to O'Driscol and his correlatives. None of our writers have pointed out when or why this celebrated district was called Cairbre, or Carbery. But the Editor hopes to prove in a future work that this whole district was called Corca Luighe, at least until the year 1178, when the Cairbre Aobhdha were first driven out of the plains along the Maigue in the now county of Limerick, and

that shortly after this period the tribe of Cairbre Aobhdha, namely, the O'Donovans, O'Coileans, or Collins, and other families, being forcibly driven out of their own territory by the Fitz Gerald's, fled into Corca Luighe, which they subdued, and to which they transferred their own tribe name, which, in course of a few centuries, became so firmly established that when the territory was re-conquered by the Mac Carthys they did not attempt to sink the tribe name of those who had sunk its more original appellation.

distinct from Mac Carthy More, and triumphantly obtained dominion over the whole barony of Carbery, in the county of Cork, and compelled O'Driscoll, O'Donovan, O'Mahony the Western, and other septs, to pay them tribute as conquerors of the territory.

Another part of the ceremony of inauguration not mentioned by any of the writers already quoted, is noticed in the Annals of the Four Masters, namely, that in many cases when a superior chief was inaugurated by an inferior chief, the latter put on his shoe or slipper.—See these Annals at the years 1461 and 1488, where it is stated that at the inauguration of the chiefs of the O'Conors, Mac Dermot, chief of Moylurg, put on his shoe. It is also stated that in inaugurating the chief of the O'Neill family, O'Kane threw a shoe or slipper over the head of the prince. It is rather strange that Keating should not have noticed this ceremony.

From the foregoing authorities we may infer that the following conditions were generally requisite to constitute a legitimate instalment or inauguration of an Irish chieftain :

1. That he should be of the blood of the original conqueror or acquirer of the territory, and free from all personal blemishes, deformities, and defects, and be of fit age to lead the clan to the field.
2. That the greater part of his sub-chiefs and freeholders should declare in his favour.
3. That the inauguration should be celebrated at a remarkable place in the territory appointed of old for the purpose, where there was a stone with the impression of two feet, believed to be the size of the feet of the first captain, chieftain, or acquirer of the territory.
4. That the hereditary historian or chronicler of the territory should be present to read to the chief about to be installed the heads of the law relating to the conduct of the chieftain, and that the latter should swear to observe those laws and to maintain the customs of the territory inviolable.
5. That after taking this oath, the chief laid aside his sword and other weapons, upon which the historian of the district, or some other person whose proper office it was, handed him a straight white wand as a sceptre and an emblem of purity and rectitude, to indicate that his people were to be so obedient to him that he required no other weapon to command them.
6. That after receiving this straight white wand, one of his sub-chiefs put on his shoe or sandal in token of obedience, or threw a slipper over his head in token of good luck and prosperity.
7. That after the foregoing ceremonies were performed, one of his sub-chiefs pro-

nounced his surname without the christian-name in a loud voice, after whom it was pronounced in succession by the clergy according to their dignity, and by his sub-chiefs and freeholders according to their respective ranks. After this the chieftain turned round thrice forwards and thrice backwards, in honour of the most holy Trinity, as the Irish still do all good things, and to view his people and his territory in every direction ; which being done he was the legitimate chief of his name.

On the subject of the inauguration of Christian kings, the evidence given by Cummin and Adamnan, as above noticed, is the oldest on record. The most ancient authorities given by Selden for the coronation of Christian emperors, and for that of the Kings of France and England, are subsequent to the time of Adamnan, who died on the 21st of September, 704, in the seventy-seventh year of his age. The sacred cruet of Rheims, used in anointing the Kings of France, is not mentioned previously to the ninth century. In the *Notitia Episcopatum*, printed at Rome in 1533, we are told that the ancient kings usually consecrated, according to the ceremony of the Roman Ritual, were those of Castile, Arragon, Ireland, Scotland, Poland, and Hungary. It is highly probable that the monarchs of Ireland, since the introduction of Christianity, were inaugurated by the Archbishop of Armagh, attended by the four provincial kings, who took a conspicuous part in the ceremony, and there is every reason to believe that the clergy were employed in the inauguration of the chiefs of large districts, such as were called *righa*, or kings by the ancient Irish, but that the lords of single baronies, or Triucha cheds, were appointed by the head chieftain, by consent of his tribe, with the simple ceremony of delivering him a rod. This is evident from various passages throughout the Annals of the Four Masters, which it would be too tedious to quote in the present work.

L.

DEATH OF ST. GERALD OF MAYO.

*See page 145, Note *.*—Dr. O'Connor, in his *Rerum Hibernicarum Scriptores*, denies that the Annals of Ulster and Tighernach record the death of St. Gerald at 732 ; he says that at this year they record the death of Muireadhach, one of his successors, and that St. Gerald himself died long before. See his notes on the Annals of Ulster at the year 731, of Tighernach at 732, and of the Four Masters at 726. It is true that Dr. O'Connor is borne out in this opinion by the Annals of the Four Masters, in which it is expressly stated that Muireadhach was Bishop of Mayo ; but the Editor is of opinion that the Four Masters have mistaken the original Annals of Tighernach, in which the passage stands as follows, without any punctuation :—" A. D. 732. Cath Connach

in quo cecidit Muirebach Mac Inopachtaig Pontifex Muige h-Go Saxonum Garalt obit."

Now it is quite clear from the two verbs *cecidit* and *obit*, that two distinct persons are referred to in the entry, and that the passage should be thus punctuated :— "A. D. 732. Cath Connacht, in quo cecidit Muirebach Mac Inopachtaig. Pontifex Muige h-Go Saxonum, Garalt, obit," i. e. "A. D. 732. The battle of Connaught, in which fell Muiredhach, son of Indrachtach. The Pontiff of Mayo of the Saxons, Gerald, dies," i. e. "Gerald, Pontiff of Mayo of the Saxons, dies." It is quite clear that Muiredhach was a chieftain, not a bishop, and it is more than probable that he was the son of the Indrachtach, King of Connaught, who is said to have been slain in the year 718.—*Vide supra*, p. 315, Note ^h.

Colgan also, at Mart. xiii. seems to think that St. Gerald of Mayo died earlier than 732; and Ussher thinks that he must have died before the year 697; but Dr. Lanigan clearly proves that both these opinions are groundless. The Four Masters enter the death of St. Gerald under the year 726, and in Mageoghegan's translation of the Annals of Clonmacnoise it is entered under the year 729; but as these Annals are antedated by a few years it is obvious that the same date is intended as in Tighernach. But it should be confessed here that even Mageoghegan has mistaken the construction of his original, which he renders thus :—"A. D. 729. The battle of Connaught was fought, wherein Moriegh Mac Inreaghty, Bushop of Moyoe of the English, was slain. Garalt died." It should be, "The battle of Connaught was fought, wherein Moriegh Mac Inreaghty was slain. The Bushop of Moyoe of the English, Garalt, died."

M.

OF THE ANCIENT DIVISIONS OF LANDS CALLED BALLYBETAGHS.

See page 204.—The following notices of the ancient Irish townlands, given by the Rev. John Keogh, author of the Irish Herbal, in a short account of the county of Roscommon, written by him for Sir William Petty's intended Atlas, are here presented to the reader in confirmation of what has been advanced by the Editor at p. 204, on the difference between the ancient and modern Irish townlands. This tract is preserved in MS. in the Library of Trinity College, Dublin, and is dated Strokestown, March 14th, 1683 :

"Connaught (and, I suppose, other provinces) was anciently distinguished into countries called Doohie, or Tyre, named from such and such families, or nations inhabiting them, as in the barony of Athlone, Doohie Keogh, the country or nation of the Keoghs. In the barony of Ballintobber, Doohie Hanly, the country of the Hanleys,

leys, and betwixt Elphin and Jamestown, that sweet country Teer O'Ruin [Tir Briuin] and Teer O'Byrne, the country of the Beirns.

"These countries were subdivided into townlands (in some other parts of Ireland known by the denomination of plough-lands) which were called Ballys, as in Doohie Hanly, Bally nengulluh, [or] Gyllstown, Ballygillecline, the town of the Chlinnes, Ballyfeeny, &c., and each townland was divided again into quarters, which are generally known and distinguished by certain meares and bounds, and for that reason the name of quarter is used as though it signified a certain measure; and now the lands here are generally set and let, not by the measure of acres, but by the name of quarters, cartrons, and gnieves, a quarter being the fourth part of a townland, and a gnieve the sixth part of a quarter, and a cartron also the fourth part of a quarter (although in other parts of Ireland a quarter is the same part that a cartron is here, and a gnieve the fourth part of a cartron). I have been sometimes perplexed to know how many acres a quarter contains, but I have learned it is an uncertain measure, and anciently proportioned only by guess, or according to the bigness of the townland whereof it was a parcel. I have also busied myself with my own concerns to inquire what town, or general denomination of townland, each quarter belonged to, for the more convenient setting of tithes in main parcels by those general names of ballys, but therein I could not meet with satisfaction, it being a thing forgotten since the days of yore, and unknown to the most who yet still retain the names of quarters. And these ancient names of townlands have lost part of their general signification, being now applied only to some small parcells, as quarters or less pieces, and each other parcell of the ancient townland hath another name, according as the inhabitants were pleased to settle their habitations and little villages here and there sparsedly fixed and variously named. I have observed that most names of dwelling places in the beginning of them (before what other addition or surname they are distinguished by) have the following words: Bally, the town; Leghbally, the half town; Carhu, the quarter; Kill, the church; Liss, or Rath, the fort of earth; Cassel, the fort of stone; Carrig, the rock; Ath, the ford; Bealawh, the ford's mouth; Gleann, the valley; Knock, the hill; Ross, Cluain. What Ross and Cluain signify I have not yet learned, they being words not commonly used (but as parts of the proper names of towns) except in ancient times, only I take it Cluain is applied generally to a place enclosed with bog and river or the like, which is commonly the pleasantest and most commodious for habitations, but Ross, being of affinity to the Latin Rus, is applied to places of wider extent, as wildernesses and forests, places overspread with underwood, &c."

CATHAL DUBH O'DUBHDA.

See page 309, Note ¹, and pages 316, 317, Note ².—It is stated in the *Historia familiae De Burgo*, a curious MS. preserved in the Library of Trinity College, Dublin (F. 4. 13.), that every Mac William is entitled to a tribute of five marks yearly out of the country of O'Dowd, and that the then O'Dowd, namely, Cathal Dubh, consented to the payment of this tribute, which is called a *cios cosanta*, i. e. tribute for protection. No date appears to this document, but it states that O'Dowd was present at the writing of it, who subscribes his name to it, and it is also attested by Cosny Oge Mac an Brehon, who was Brehon to Mac Maurice of Clanmorris. It is probable, however, that this tribute was not of long standing; but the power of the O'Dowds was very much crippled at this period by the O'Conors and others, so that Cathal Dubh found it his interest to pay the lower Mac William five marks a year for assisting him against them. Notwithstanding this security of the protection of O'Dowd by the lower Mac William De Burgo, the power of O'Connor Sligo continued to increase, for in the year 1581 he was lord of that tract of country extending from the River Drowes to Ceis Corainn, and from the River Moy, eastwards, to Lough Gill.

O.

THE LOWER MAC WILLIAM DE BURGO'S POSSESSIONS IN TIRAWLEY.

See pages 338, 339, Notes ¹ and ².—The following list of the Lower Mac William's townlands, tributes, &c., in Tirawley, is taken from the *Historia familiae De Burgo*, already quoted:

“*Αἰς το βαρύνταρ Τίπε Αἰμαλγαῖο:*
locum comitatus an tír féin .i. inaò an
iapa; agus do fuair Mac Uilliam po
innce, oót fício déz o'éirge amac innce,
mar atá tís fício marcaí gléicta, agus
ré fício ceépnac, agus naoi ð-fício
giolla capoll, pa n-a lóntuib féin, agus
tí fício marz cíora agus cóma.

“*Αἰς το na fearoinn a ð-fuil rin; an*
túr ann pa ðhuacc thoip, re baile coméa;
agus annr a ðhuacc éiar cúig baile
cómea; ceápanna agus cúig baile

“This is the barony of Tirawley: the territory itself is a *locus comitis*, i. e. the place of the Earl. And Mac William obtained in it eighteen score of a rising-out [i. e. forces], to wit, three score accoutred horse and six score kerns, and nine score horse gillys [horseboys], all to subsist on their own provisions, and three score marks as rent and reward.

“The following are the lands on which these are paid:—first in the eastern Bac, six townlands of reward, and in the western Bac five townlands of reward; a quarter

coméa a n-Gleann Nemhthinn, agus ag
ro a n-anmána rin, .i. Baile in chop-
ráin, agus Baile na Craoibhidhe, agus
leat-Baile Maidheag, agus leat-Baile
Matha, agus leat-Baile Caorthannán,
agus ceatpána Dairbhín, agus ceat-
pána Dhaile mhic Rémag, agus ceat-
pána Dhaile na Laighneach, agus ceatpá-
na Dhaile an Bhrúithneoguigh, agus leat-
Baile Mhaol-átha, agus in Cheatpána
clócaic, agus leat-Baile Trintach, agus
leat-Baile Ráta Ruaidhín, agus Baile
Easa Caoirigh, agus an Cheatpána
riabhac, agus an Cheatpána cúigea-
dác, agus leat-Baile Ráta Toma, agus
Ceatpána an Charbuid, agus ceatpána
Chille h-Achaidh, agus an Ceatpána
mór. agus ceatpána Baile Hostin, agus
cúig leat-ceatpánna ann a Ros ó
t-Sailin ar teach, agus leat-Baile na Lagb-
huile; dá uinge ceatpána dá cúig marg a
n-Inis Cuad, do cíor agus do comá; dá
marg óg do cíor agus do comá a dá
Baile Croir Mhuiréilín; Ocht pinginne
agus fiche ríillinn a m-Baile an Chorr-
baile; ocht pinginne agus fiche ríillinn
ann a Dhaile meadonac; ocht pinginne
agus fiche ríillinn a m-Baile Locha
Bron; ocht pinginne agus fiche ríillinn
a m-Baile Chille h-Aodáin; ocht pin-
ginne agus fiche ríillinn a m-Baile na
Cobhruide; bonn agus uinge d'ór a
g-ceatpánain an Cháirín; dá phin-
ginn agus trí h-uinge ann a Cheat-
pánain móir; dá phinginn agus trí
h-uinge a g-ceatpánain Baile na leice;
dá phinginn agus trí h-uinge ann a'
ceatpánain Siallach; ocht pinginne

quarter and five townlands of reward in
Gleann Nemhthinn, named as follows, viz.,
Baile an Chorrain, Baile na Craoibhidhe,
the half townland of Maidheag, the half
townland of Matha, the half townland of
Caorthannan, the quarter of Dairbhín, the
quarter of Baile mhic Remag, the quarter
of Baile na Laighneach, the quarter of
Baile an Bhrúithneoguigh, the half town-
land of Maol-atha, Ceathramha chlochach
[i. e. the stony quarter], the half townland
of Trintach, the half townland of Rath
Ruaidhín, Baile Easa Caoirigh, Ceath-
ramha riabhach, Ceathramha chuigeadh-
ach, the half townland of Rath Toma,
Ceathramha an charbuid, the quarter of
Cill Achaidh, Ceathramha mhor, the quar-
ter of Baile Hostin; five half quarters in
Ros from Sailin inwards, the half townland
of Lagbhuile; two ounces wanting of five
marks in Inis Cuadh, as rent and reward;
twelve marks as rent and reward in the
two townlands of Cros Muidhelina; twenty
shillings and eight-pence in the townland
of Corrbhaile; twenty shillings and eight-
pence in Baile meadhonach; twenty shillings
and eight-pence in the townland of Loch
Bron; twenty shillings and eight-pence
in the townland of Cill Aodhain; twenty
shillings and eight-pence in the town-
land of Cobhruide; a groat and an
ounce of gold in the quarter of Carn;
two-pence and three ounces in Ceathramha
mhor; two-pence and three ounces in the
quarter of Baile na leice; two-pence and
three ounces in Ceathramha Sdiallach;
twenty shillings and eight-pence in Baile
an Oireacht; twenty shillings and eight-
pence

agur píce rḡillinn a m-ḡaile an Oipeáct; oét pinginne agur píce rḡillinn a m-ḡaile Ráta Leacain; uinge o'óp a n-oueáio Chloinne Philip; oét b-pinginne agur naoi n-uinge a m-ḡaile Chille ḡriḡoe; oét b-pinginne agur píce rḡillinn a m-ḡaile an Chairill; ceáepa h-uinge óég a m-ḡaile Áca liag; bonn agur uinge o'óp a m-ḡaile an ḡleanna; epí h-uinge a m-ḡaile Chapna; bonn agur uinge o'óp a leaḡbaile in Tobair; ceáepa h-uinge óég a m-ḡaile papaió; bono agur éuig uinge a leaḡbaile Locha Deala; oá phinginn agur epí h-uinge a ḡ-ceaḡpaḡmáin Chairle; rḡillinn agur uinge a m-ḡaile I Duḡéaiḡ; naoi m-boinn a ḡ-ceaḡpaḡmáin ḡhpeḡmáioe; oá mḡarḡ am-ḡaile O'ḡ-Comáin; oá phinginn agur epí h-uinge a ḡ-ceaḡpaḡmáin ḡairín; oá phingino agur epí h-uinge a ḡ-Ceaḡpaḡmáin Chuam Néill; uinge a m-ḡaile Mic Cithol. Ácáio na maóir o'á óé-naín o'ḡiaḡnuiri ann ro oo péir mḡar fuapaoar ó na rínnḡearuiḡ éáinicc rompa, ḡac feapann naḡ tiucpa o'á oḡne féin a óíol, an feapann o'ḡuaḡpa oo Mḡac Uilliam; agur fórhoamáio lúḡa éíor Mḡic Uilliam annḡ a ḡ-feapann iná éíor na o-tḡeapnaíḡ eile ḡan ap breicḡ oo na tḡeapnuíḡíḡ rín a ḡ-éíor féin o'ḡáḡáil no ḡo ḡ-ḡaḡaió Mac Uilliam a éíor ap éúr. Áḡur ní eile fóḡḡur ab air an ḡ-feapann aca éíon Mḡic Uilliam, agur ní ḡ-fuail luḡḡ air an éúr oo éḡḡna leir."

pence in the townland of Rath leacain; an ounce of gold in the territory of the Clann-Philip; eight-pence and nine ounces in the townland of Cill Bhrighde; twenty shillings and eight-pence in Baile an Chaisill; fourteen ounces in the townland of Acha liag; a groat and an ounce of gold in Baile an Ghleanna; three ounces in Baile Charna; a groat and an ounce of gold in the half townland of Tobar; fourteen ounces in Baile Faraidh; a groat and five ounces in the half townland of Loch Deala; two-pence and three ounces in the quarter of Caisle; a shilling and an ounce in Baile I Dhubhthaigh; nine groats in the quarter of Breachmhaidh; two marks in Baile O'g-Comain; two-pence and three ounces in the quarter of Cuan Neill; an ounce in Baile Mic Cithol. The stewards bear testimony to this accordingly as they received it from their ancestors, that every land of which its own inheritor cannot pay this tribute is to be declared escheated to Mac William; and should Mac William's rent be less than that of the other lords, these lords cannot raise their rents until Mac William shall first receive his own rent. And moreover that Mac William's tribute is due of the land, and that there is no power of disputing it with him."

The two documents which follow, taken from the *Historia familiæ De Burgo*, will
 IRISH ARCH. SOC. 12. 3 N show

show how the Barretts and Burkes stood in the years 1580 and 1584. The first is given in Irish, with an original Latin translation, and the second is in Latin only."

“ In Dei Nomine Amen.

[illegible]

“Universis et Singulis pateat per presentes, quod Manerium de Bel lecce pervenit ad Johannem [filium] Oliveri De Burgo ejusque filium Vaterum De Burgo, sed vere heredes ipsius manerii seu Castri, viz., Thomas Cathenarum Bared et ejus filii et fratres, viz., Johannes Bared ejusque filius Edmundus fitz Mayw Gullialmus fitz Mayw ruffi longo tempore in judicio et extra judicium convocato auxiliis tam Anglorum quam Hibernicorum contendebant de recuperatione ejusdem manerii; sel non obtinebant, tandem pacem concordiam et favorem prefati Vateri eligentes amicabiliter concordarunt sub forma quæ sequitur, viz., quod ipse habeat supremam partem dicti manerii et dimediam partem solerii et domus medie ad eorum usum et dimediam partem Muniminis seu propugnaculi et terrarum piscariorum vectigaliumque. Item dimediam partem omnium tenementorum terrarum ubicunque in baronia de Tyramhalay jacent seu situantur ad eos de jure pertinentium prefato Vatro concesserunt, sub conditione quod eos in judicio et extra judicium legitime defenderet, et ipsi similiter se prefato Vatro in omnibus consilio auxilio et favore contra omnes assistant et hoc fedus et hunc contractum ad suos heredes assignatosque extendi voluerunt. Hee sunt terre et tenementa de quibus supradictum contractum inierunt secundum ultimam

Ḑaitep map in g-céona oo nor map in
cóiṛ oóib ḑéit aige an-aghaidḑ gac aoin.
Ar í an oúthaidḑ ar a n-bernasar ḑai-
péuwig agur ḑhaitep a ḑúpc an conpaḑ
ṛin, oo péir umácta Thomair na geimle,
map fuaramar ṛgriobḑa í, .i. leatḑ baile
ḑel leice ar túr, agur a ṛócar éirg
agur inḑir agur coiceio, agur naoi
b-ṛinginne agur naoi n-uinge ar leatḑ
ḑaile na cuirce, agur ceatḑamḑa Tulairḑ
cléib, agur leitḑ ceatḑamḑa na n-ḑuir-
tine, agur oo ṛáguibḑ Comár na geimlḑ le
h-umácta naḑ ṛaibe acḑ ba cnoc ṛa geall
oo'n leatḑ ceatḑamuin ṛin, .i. in Réirḑ,
agur an Cnoc leiteac a n-geall ṛe x
n-uinge, agur naḑ ṛaibe acḑ leiteacḑ-
ṛamḑa annṛ na ḑuirceinib agur annṛ a'
Réirḑ agur annṛa Cnoc leiteac. Agur
leatḑ baile Loḑa Muige ḑron, .i. Trian
na ṛgólóg, agur Trian na ṛáirce, agur
Trian an oilean, agur leatḑ ceatḑamḑa
Chluana Alcúin agur leatḑ ceatḑamḑa
ḑhaile na leice, agur leatḑ Ceatḑamḑa
in Tuairín, agur ṛe buin oéḑ a cíor'ṛan
m-bliaduin, agur an ceatḑamḑa ḑoiallacḑ,
agur leatḑ an Chapbuio brḑ, agur leatḑ
ṛeapuin an tige moir, agur Cnocán
Muirḑ, agur Tobar Tigearnán, agur
ḑroioṛneacán agur ḑarḑa Longan, agur
leatḑ coiceio Raḑa ḑpannuim, acḑ a
ṛian ṛin ag ṛliocḑ Roibeapḑ ḑaipo,
agur ṛeacḑ n-galuin oo ṛhíopa na ṛoil-
eog ar coiceio Inṛṛ na n-gall agur x
n-galuin eilḑ oo ḑean Riocarḑ mac Co-
marḑ Chaioḑ amac oo ṛéin agur o'á
ṛliocḑ, agur leatḑ baile na Riṛnige, agur
ceatḑamḑa moṛ ḑhel ṛraḑa agur ḑaile

ultimam voluntatem predicti Thome Ba-
red et antiquas Scripturas, viz., dimedium
villate de Bellece cum omnibus supra-
dictis emolumentis Piscariorum et Vecti-
galium, et ix unxie cum ix denariis pro
dimedio villate na Cuirte. Item quarta
nuncupata twla cleyw, dimedia quarta na
ngwrtyne. Sed predictus Thomas in su-
prema voluntate attestatus est quod solum
duo colles predictae quarte, viz., an Resy et
Cnoc Leytheach erant in pignore x unx-
iorum, et quod non erat in predictis parti-
culis de Gurtyne, Resy, Cnocleytheagh nisi
dimedia quarta. Item dimedia villata
Loghabron, viz., Tryan na Scolog et Tryan
na Parke, et Tryan anoylen et dimediam
quarte Clwyn Alchwyn. Item dimediam
Bayle na lecce, dimedium quarte in Two-
ryn et xvi. grotti annui census. Item
quarta quod vocatur Styallagh, dimediam
Carbayd byg. Dimidium predii in Tyghe
mor, et Cnocan Murys, Tobar Tyarnayn,
Droynchan, Ortus Longayn, dimedium
vectigalis in Rathbranna, preter terciam
partem que debetur genelogie Roberti
Bared, et septem galones ex Pipa na Soleog
ex vectigali Insule na ngall, et x galones
quos Richardus filius Thome Ceci sibi no-
mine vectigalis exegit ac sue posteritati.
Et dimedia villa na Rathny, et quarta
magna Bel tragha, item Bayle Achalyag;
item tertia villa na Cabray Rway; item
tota Villa vallis. Et prefatus Vaterus
Burk hanc concessionem et donacionem
cum benedictionibus heredum premissor-
um tam sibi quam sue posteritate recepit.
Et si nullus ex antedictis donatoribus
supervixisse

Άχα λιαξ αγυρ επεαρ μιν δαίλε na Cab-
puidé Ruaidé, αγυρ δαίλε an Thleanna
uile. Αρ é cor ap a b-puair δαιτερ a'
δυrc in tabairtur po maille pe beannaét
na n-oirgead, αγυρ oo βελé αιγε fein
αγυρ αγ a ρλιοét 'n-a διαίξ. Αγυρ oá
n-eir-gead báchaó fine oo na δαιρεoa-
éuib, ρin a g-cuio ouicéce αγυρ ρineaáuir
oo βελé αγ δαιτερ αγυρ αγ a ρλιοét 'n-a
διαίξ, oo ρéir an éeo connaréta. Αρ í
aoir in eigeapna in ean ra, .i. mile blia-
óain, αγυρ ccccc αγυρ ceirí bliaóna
αγυρ ceirpe xx. an Chéaoain ρoim
n-Obluig, αγυρ ar é Sir Seoín Píorpoio
oo ba Thuiróir a n-Eirinn o'n bainrígáin
Saxan .i. Elirabet, αγυρ Ριρoεapnó δινγ-
gam 'na uacéapán ar cuige Connacht,
αγυρ Ριρoεapnó mac Oilbepur a δυrc 'na
Mac Uilliam an bliaóuin éona ρin.

“Αρ iao ρiaónuiriξ an connaréta ρo,
.i. Mac Philip, map aca Emann Og,
mac mic Pilib, αγυρ hibepo Meiric.
Ριρoεpno Meiric ρazar na ρaircé αγυρ
Uilliam Mac in Chleiriξ, in ρazar eile;
αγυρ γaba na ρaircé, Ρicairn O'Mu-
rain; αγυρ an Dubalcac mac Ρicairn
Duib mic Ribirn, αγυρ Comulcac Og,
mac Macéamína I Uigin, αγυρ Aongur
mac Aóda Ruaid I Uigin in ρgrióneoir,
αγυρ Maolmuirpe mac Aíapopuinn, mic
Aóda dhuidé.

Meiri Aongur O'hugin.

Meiri Maolmuirpe Mac Aíapopuinn.

Meiri Uilliam O'Cleiriξh, Sacerdos.

Meiri An Duballcach Mac Ρicairn
Duibh.

Meiri Ρicairn O'Muráin.

supervixisse act est quod hiis Vaterus jure
hereditario succedat. Scriptum in Bellece
1584, feria iii. ante festum Nativitatis,
Regnante Serenissimo principe Elizabetha
et Johanne Perotho Deputato in Hibernia
existente—Risterdo Byngam Provincias
Thomondie et Connachie gubernante—
Risterdo Olivero De Burgo creato Mac
William.

“Hiis testibus presentibus, viz., Mac
Philipp, cujus proprium nomen est Ed-
mundus, et Risterdo Meric presbitero.

“Ejusque Patre Hyberto et Willielmo
Clery presbitero, et Richardo O Mwayn
fabro ferrario. Et Dualdo filio Richardi
nigri Mac Roberd. Thomulteo filio Ma-
thai y Hwyyinn et Enea filio Odonis Ruffi
y Hwyyynn, ac Mylero filio Alexandri filii
Odonis aliisque clericis et laycia.

Meiri Mac Pilib.

Meiri Comulcach Og.

Meiri hibepo Meiric.

Per me Richardum Merick, Sacerdotem
Parochialem.

Meiri Seaan δαιρεo.

Meiri

Meiri Robag δαιρεο.

Meiri Emonn Mc Maigiu.

Meiri Ulliam δαιρεο.

Meiri Uilleag Mc Maigiu Cuagh.

Meiri Maoilepe δαιρεο.

Meiri Artur δαιρεο.

Meiri Ripoearo Mc Ribepo an Co-
cain."

The second document is as follows:

"Omnibus has literas visuris et audituris innotescat, quod filii Risterdi Baired, eodem modo et eisdem condicionibus, contraherent et convenerunt cum Waltero Kytach a Burk, sicut ceteri alii eorum consanguinei, viz., quod Vaterus habebit dimediam partem omnium prediorum suorum, quocunque loco sita essent, sub condicione hac, ut Waterus eos in justitia sua defenderet pro viribus, et ipsi similiter cum fidelitate omni Vatero assistant, et presertim quod omnes qui eum erga predicta predia molestarent. Et tam Vaterus quam prefati filii Risterdi volunt extendi hunc contractum et obligacionem ad suos heredes et assignatos. Prediorum nomina sunt hec, semiquarta Clwyn Crayn, et semiquarta Clwyn na hatha, et semiquarta an Corrayncaym: Semiquarta vero na Cnoc est apud Vaterum ipsum in pignore 6 vaccarum fetosandarum, et septem vaccarum quas minores vocant, et quinque marcharum cum duabus unxiis: Item quarta de Cwan Neyll, sed ejus dimidia pars est in pignore v. Marcharum Ster. apud filios Mauritiu hy Cernay, et alia dimedia pars apud eosdem in pignore unius Marche. Item sciendum est quod hec est pars que debetur predictis filiis Risterdi a suis consanguineis, viz., octava pars ejus partis quam a Vatero habent in Bellecce cum omnibus suis emolumentis et obventionibus. Insuper utraque pars contrahentium se obligat ut altera alteri pro viribus benefaciat, sive pauperes sint sive divites, sive fortes, sive debiles. Scriptum in Bellecce, A° Domini M^{mo}. ccccc. lxxxiiii. Januarii xiii°. Hiis Testibus presentibus, viz., Risterdo Meric ac Johanne Roday Sacerdotibus, Johanne Bared, Heberto Meric, Tomultheo Juveni O'Hwyginn, ac Enea filio Odonis Ruffi y Hugynn, aliisque quamplurimis clericis et laicis.

"Miri Ripoearo Meiric.

Miri Sean O'Roaroh.

Miri Tomulcach Og O'h-Uiginn.

Miri Congur O'hugino."

P.

ST. PATRICK'S TRAVELS AND ACTS IN TIRAWLEY, ETC.

See page 311, Note *.—"LXXVI. Peragratu varijs Connacæ partibus ad austrum, trajectoque Muadio flumine, venit Patricius ad regionem de *Tir-Amhalgaidh*; ubi tunc erant duodecim filij Regis Connacæ, Amalgadij nempe, filij Fiachrii, de regno contententes. Nomina horum filiorum erant Ængussius, Fergussius, Fethlemius;
Enda

Enda Crom, Enda Cullom, Corbmacus, Carbreus, Eochadius Diainimh, Eochadius alter, Eugenius Corr, Dubchonallus et Alillus Ainech. Ængussius autem alijs astutior, et in spem regni magis erectus, reliquos fratres, præsertim quos magis metuebat ut regni æmulos, curavit per suos conspiratores despicabilibus insigniri cognomentis, ut sic populi ab eis averterentur animi. Vnde his moti viginti quatuor seniores, qui erant viginti quatuor veterum tribuum patriæ præfecti, statuerunt neminem in suum Regem admittere, cuius honori aliquod despicabile cognomentum inferret notam. Lis ergo inter fratres orta eo usque incrementum sumpsit, ut Temoriam ducta sit, Regis Laogarij et Eugenij eius fratris arbitrio decidenda.

“LXXVII. Filij igitur Amalgadij in duodecim curribus profecti sunt Temoriam : *Sed in libris Patricij inuenitur quod exierint in iudicium tantum septem fratres ex eis.* Inter Temoriam venientes erat quidam spectatæ indolis, et multæ gratiæ juvenis, nomine Conallus, Endæ Cromio inter fratres primogenito, natus, causam patris acturus, eiusque loco litem prosequuturus. Hunc iuuenem ob singularem gratiam, præclarasque animi dotes, ante alios metuebat Ængussius. Vnde cum ipse esset janitoribus aulae, et ministris Regis notus (erat enim olim apud Regem Laogarium in aula Temoriensi inter Ephesos educatus) hoc ab eis obtinuit, ut Conallo introitum et accessum ad Regem intercluderent. Cum ergo alij essent in aulam admissi, et ad Regis præsentiam ducti, solus Conallus domo patris sui mansit exclusus : qui nesciens quid ageret, quovè se verteret, audiuit pulsum cymbali S. Patricij pro celebrandis diuinis mysterijs in loco *Tiprad Phadric* dicto symbolum dantis. Accedens ergo Conallus perhumaniter virum sanctum salutavit, et in memoriam refricavit, quomodo ante dies multos infantes suæ patriæ^a, in vtero matrum existentes, clamaverint ad novæ doctrinæ quendam advenam,

^a This is much more pointedly, though briefly, told in Tirechan's Annotations on the Life of St. Patrick, preserved in the Book of Armagh, fol. 10 :—“ Cumque aperuisset librum atque baptizasset virum *Hercum* audivit viros post tergum suum se inidentes ad invicem, de rei illius consideratione, quia nescierunt quid fecerat, et baptizaret tot millia hominum in die illa, et inter cæteras baptismatis sententias audivit. Ecce duo namque viri nobiles confabulantur post tergum sibi et dixit alter alteri, verum est quod dixisti a circulo anni qui præteriiit ut veniasses huc in illis diebus.

“ Dic mihi nomen tuum, quæso, et patris tui, et agri tui, et campi tui, et ubi est domus tua ?

Respondit Endeus, filius Amolngid sum ego, filii *Fechrach*, filii *Echack* ab occidentalibus plagis, de campo Domnon et de silva *Fochlotk*. Cumque audiisset Patricius nomen silvæ *Fochloti* gavius est valde et dixit Endeo Amolngid filio, et ego tecum exibo si vivus fuero quia dixit mihi Dominus exire ; et dixit Endeus non exibis mecum ne occidamur ad invicem. Sanctus quoque dixit, verum tamen numquam vivus ad tuam regionem pervenies, et tu nisi venero tecum, et vitam æternam non habebis quia propter me venisti huc quasi Joseph ante filios Israel. Endeus autem dixit Patricio, tu filio meo baptismum da, quia tener est ; ego autem et fratres mei non possumus tibi credere usque dum ad nostrum plebem per-

aduenam, ignotæ linguæ verbis dicentes; *Hibernienses omnes clamant ad te pueri*^b, Patricius autem hæc læto animo audiens et excipiens, ait: ego sum ad quem illa directa sunt, et in maris Tyrrheni insulis existens ea audiui; *et nesciui utrū in me, an extra me, prolata sunt verba. Et ibo tecum in regionem tuam baptizare, docere, euangelizare.*

“LXXVIII. Post hæc autem interrogabat Patricius, qua causa venerit Conallus Temoriam.

venerimus ne inrideant nos. Conallus autem baptizatus est et dedit Patricius benedictionem super illum et tenuit manum illius et dedit *Cethiacho* episcopo et nutritv illum et docuit eum *Cethiacus* et *Mucneus* frater *Cethiaci* episcopi, cujus sunt reliquæ *Ecclēsia Magna Patricii* in silva *Fochlithi* propter hoc mandavit Conallo insulam suam *Cethiacus*; et generis illius est usque in præsentem diem quia laicus fuit post mortem *Cethichi* sancti.

“Venerunt autem filii *Amolngid* sex ad iudicandum ante faciem *Loiguri*, et *Endeus* contra eos unus, et filius ejus tener et Patricius ante illos et investigaverunt causam hereditatis illorum, et iudicavit illis *Loiguire* et Patricius ut dividerent inter se hereditatem in septem partes, et dixit *Endeus* filium meum et partem hereditatis meæ ego immolo Deo Patricii et Patricio, per hoc dicunt alii quia servi sumus Patricii usque in præsentem diem foedus pepigerunt per manus *Loiguri* filii *Neill*. Patricius et filii *Amolngid* cum exercitu laicorum, episcoporum, sanctorum, et inierunt iter facere ad montem *Egli*, et extendit Patricius etiam pretium duodecem animarum hominum ut inscriptione sua adfirmat de argento et auro ut nullum malorum hominum impederet eos in via recta transeuntes totam Hiberniam. Quia necessitas poscit illos ut pervenirent silvam *Fochlithi* ante caput anni pasce secunda causa filiorum clamantium clamore magno voces audivit in utero matrum suarum dicentium: *Veni Sancte Patrici, salvos nos facere.*”—*Fol. 11, p. a, col. 1.*

^b This vision of St. Patrick, which has rendered the wood of Fochlut so celebrated in Irish history, is thus referred to by the saint himself in

his Confessio, as given in the Book of Armagh, *fol. 23, b, 2*:—“Et iterum post paucos annos in Britannis eram cum parentibus meis qui me ut filium susceperunt et ex fide rogaverunt me ut vel modo ego,—post tantas tribulationes quas ego pertuli,—nusquam ab illis discederem. Et ibi scilicet in sinu noctis virum venientem quasi de *Hiberione* cui nomen *Victoricus* cum æpistolis innumerabilibus vidi, et dedit mihi unam ex his et legi principium æpistolæ continentem vox *Hyberionacum*. Et dum recitabam principium æpistolæ putabam enim ipse in mente audire vocem ipsorum qui erant juxta silvam *Fochluti*, quæ est prope mare occidentale. Et sic exclamaverunt: Rogamus te, sancte puer, ut venias, et adhuc ambulas inter nos. Et valde compunctus sum corde, et amplius non potui legere, et sic expertus [expergefactus] sum. Deo gratias quia post plurimos annos præstitit illis Dominus secundum clamorem illorum.”—See also Usher, *De Primordiis*, p. 632.

The situation of this wood, or woody district, has never been accurately pointed out by any of our writers; Usher indeed says loosely (ubi sup.) that it is in Mayo; but its exact position is evident from the places said to be in it which retain their names to this day, as the church of Crosspatrick, which is still the name of a townland and graveyard situated to the right of the road as you go from Ballina to Killala, and within one mile of the latter; also the church of Domhnach mor, which has long since disappeared, but the name remains which determines its locality, being that of a townland situated in the parish of Killala, in the barony of Tirawley.—See Colgan's *Acta Sanctorum*, p. 457, col. 1, and Lanigan's *Ecclesiastical History of Ireland*, vol. i. pp. 253, 254.

Temoriam. Causam autem sui aduentus exposuit Conallus, addiditque ea non obstante sibi Temoriensis aulæ ingressum esse præclusum. *Cui dixit Patricius, ingredi nunc ianuis apertis, et ad Eugenium filium Neill amicum meum fidelem, qui te adiunabit; capiesque occultè annularem eius digitum, quod signum est inter nos semper; et factum est sic.* Eugenius autem hæc advertens, petijt quid placeat S. Patricio. Respondit Conallus, ei placere, vt Eugenius in præsentī lite sibi assistat. Post hæc Conallus causam dixit coram Rege; et perorando dixit, si iuventutis floridæque ætatis, quæ patriam viribus tueri posset, spectande sit ratio, sibi, qui in hoc genere omnes adspirantes superaret, regimen esse conferendum: si verò senectutis et justitiæ, patrem eius, omnibus esse præferendum, qui reliquos fratres titulo primogenituræ et maturitate iudicij superaret. Vnde motus eius rationibus Laogarius Rex, licet prope inuitus, adiudicauit patri eius paternum solum et solium modo jura suffragantibus persolui consueta, prius persoluat.

“LXXIX. Decisâ sic lite filii Amalgadij, ne omnes benè contenti, reuertuntur in patriam, quos, et præcipuè dilectum suum Conallum, patriæ isti fidem prædicaturus comitatur S. Patricius. Sed Ængussius pessimè cum Conallo, ejusque fantore Patricio contentus, instigatus ad hoc à perfido Laogario Rege, statuit vtrumque è medio tollere; impiumque conceptum fratribus suis Fergusio et Fedlimio, eorum animos ad idem facinus sollicitando, communicauit. Locus sceleri committendo conductus erat *Corann* regio Connaciæ. Sed fratres eius recusarunt in tam impium facinus consentire, dicentes nolle se crimen sacrilegii in innocentem, sanctumque Dei Patricium, nec parricidij in Conallum nepotem admittere. Sed nec sic ad sanio rem mentem redijt Ængussius, sed in concepta perseverans impietate, sceleris consiliarios et consortes admisit duos Magos *Roen* et *Rechet* de progenie Foelani militis: et cum duabus malefactorum turmis progrediens, in via per quam transibant, ante eos statuit insidias, laqueosque mortis: ubi et *Roen* Magus criminis socios animabat, promittens, si ipse primus illum prodigiorum conclamatum patrato rem Patricium aspiceret, eum sui visus maleficio, illicò fore extinguendum. Quæ impia malignantium insidiatorum consilia, diabolicaque proposita cùm vir Dei in spiritu recognosceret, adhuc vno iusto milliari distans (erat enim ipse tunc in loco, vbi nunc est *Cruz Patricij*^c dicta; et insidiatores in loco,

^c *Cruz Patricij*.—The situation of these two places can be determined with sufficient accuracy at the present day; for *Cruz Patricij*, or *Cros Phadruic*, still retains its original name, and is that of a townland containing an ancient church yard and some traces of the ruins of a church, situated to the right of the road as you go from Ballina to Killala, and about one mile south of the latter place. The name *Kill-shorclann* is now ob-

solete, and all traces of the church are removed, but the natives of the district state that parts of the walls of a church originally so called, but then Killybrone, were extant in 1831, when they were totally levelled. The site is pointed out on a rising ground about half a mile from Killala, and about sixty perches to the left of the road leading from Killala to Palmerstown.

in quo jacet Ecclesia de *Kill-shoirclann*) à Domino suo instigatus, ad Magum dixit; non ita fiet, fili Belial; sed ego te prius videbo, teque terra, quam me minaris absorpturam, prius deglutiet viuentem, nisi resipiscas. Cùm autem primum in eius conspectum veniret Patricius, cœpit terra dehiscere, et meatu facto magum *Roan* deglutire. Ad hæc Magus timore perculsus, petensque veniam, et promittens pœnitentiam à terra euomente in æra inter ventos rejicitur, et mox semimortuus deorsum demittitur. Similiter etiam et socius eius impœnitens Rechet à respuente terra proiectus in altum, denuò præceps recidens in terram, ad saxum allisit caput, et mox fulmine percussit interiit. Saxum illud, ad quod allisit caput, vulgò vocatur *ail an druadh*, id est lapis Druydis. Estque Ecclesia in illo loco iuxta *Coill Fochladh* ad Orientem extracta, quæ *Cros phadruic* appellatur. Locus etiam in quo tunc erant insidiatores vulgo *Tulach na n-Druadh*, id est collis Druydum, nominatur, adiacetque prædictæ Ecclesiæ ad occidentem.

“LXXX. Ængussius autem tam terribili spectaculo præmonitus valdè timuit petijtque, et impetrauit veniam, fidemque Christi tantis probatam prodigijs amplexus est: qui et enixè rogauit virum Dei, cui nihil putabit impossibile, vt suam sororem nomine *Felimiam* vitæ dignetur restituere. Annuit Patricius et oratione ad Deum fusa, defunctam vita redonatam fratri præsentauit.

“LXXXI. Quidam oculorum lumine orbatus audiens mirabilia, quæ per mirificum Dei seruum Patricium fiebant, transeunti Patricia occursurus accelerauit gressus: et qui, visu viæ monstratore carebat currens per inuia cadebat, et gressum mox resumens, denuo recidebat. Cernens eum quidam de clericis S. Antistitis risit, et sine misericordia derisit cœci cespitationes. Quod indignè ferens vir sanctus, indignatione commotus ait; Tu dignus es qui beneficio oculorum, quibus malè vides, orberis; et cæcus ille fide plenus, suo infortunio remedium sedulò postulans, dignus quem sol iustitiæ amissi luminis redonet usurâ. Et vix verba finivit, cùm ecce ex tempore clericus cœcitate percussus, oculorum lumen amisit: et cæcus abstersâ caligine luminibus restitutus, cœpit obuia clarè videre, diuinamque bonitatem summis laudibus exaltare. Cœco nomen erat *Roan* filius Conchnamha, fuitque seruus olim Amalgadij Regis; et locus in quo sanatus est *Rœ Roain* abinde vocatus, donatus est postea S. Patricio. Clericus autem vocabatur *Midgna* et ipse et alter Patricij discipulus nomine *Donnmalius* relictis sunt in quodam eremitorio, quod *desertum Patricii* nominatur, iacetque iuxta fontem prope Ecclesiam, *Cros-Phadruic* nuncupatam.

“LXXXII. In loco *Huachtar Charthuinn* appellato venerunt duo claudi ad Patricium; coram quo, vt viscera eius ad misericordiam commouerent, prolixè conuesti sunt se facultate gradiendi, propter claudicantes pedes, destitutos; debere tamen propter rei familiaris curam per loca aspera, et inuia inter montem et planitiem sæpius iter

agere. Quorum miserijs vir misericors ex corde compatiens eos diuinâ virtute erexit, et facultate expedite gradiendi donatos dimisit.

“LXXXIII. Post istos claudos sic officio gradiendi restitutos, venit Patricius ad Ecclesiam de *Domnach-mor*^d, ubi est *episcopus Mucna*^e, et inde ad Ecclesiam de *Cros-phadruic*^f, vbi venit ad eum quidam alius claudus genere nobilis, nomine *Aidus*, cognomento *Longus*, *Ængussii* ex Eochadio filio nepos, similemque imploraturus, et expectaturus gratiam. Quem et iuxta expectationem, fideique meritum, vir sanctus officio pedum et facultate gradiendi restituit iuxta prædictam fontem, qui Ecclesiæ de *Cros-Phadruic* ad occidentem adiacet. *Aidus* autem beneficio gratus dedit tunc Patricio quoddam prædium in quo fundauit Ecclesiam; è qua quietis locum duobus è discipulis Teloco et Domnaldo designauit.

“LXXXIV. Post tot magorum suprâ memoratos congressus, singulosque in publicis certaminibus victos, partimque extinctos, et partim ad penitentiam conuersos; nondum destiterunt reliqui magi, suâ malitiâ excæcati, eius prædicationi resistere, et vitam insidiari. Et cum viderent ipsum in publicis certaminibus continuò victorem non audentes amplius cum eo publicè congredi, statuerunt eum stratis insidiis occultè è medio tollere. Vnde nouem ex eis in vnum conuenientes, in regione de *Tir-amhál-guidh* occultas ei struxerunt mortis insidias. Quod cum videret vir illustris Amalgadii filius *Enda* volentes occidere Patricium, dixit filio suo *Conallo*; *vade et custodi Patricium, ne magi occidant illum. Ipse etiam Patricius sensit eos.* Pro quo pugnans, tanti sceleris ultor ignis æthereus eos in numero nouem combussit, et illicò extinxit.

“Peragrans postea vir Sanctus eandem regionem, venit ad locum amœnum vbi *Muadius* fluuius piscosus exoneratur in oceanum. In eo autem loco, piâ terræ Principum liberalitate donato, ad ripam fluminis australem construxit nobilem Ecclesiam, sedemque postea Episcopalem *Killaladh*^g nuncupatam: cui et vnum è discipulis *Muredachum* nomine, primum præfecit Episcopum.

“LXXXVI. Ibi etiam vir sanctus baptizauit, Deoque consecrauit duas celebratæ sanctitatis virgines *Crebream* et *Lassaram*, *Gleranno* viro nobili *Cuminei* filio, natas. Hæ sunt, quæ incluse in vtero materno in regione de *Caille Fochladh* referuntur dudum ante in persona infantium Hiberniæ clamasse ad S. Patricium, dum esset in insulis maris Tyrrheni efflagitando vt sepositâ morâ ad Hibernos conuertendos acceleraret:

^d *Domhnach mor*, now the townland of Donaghmore, in the parish of Killala, and barony of Tirawley.

^e *Episcopus Mucna*. — He is also the patron saint of Malghin, or Moyne, near Killala, where

a great abbey was afterwards erected.

^f *Cros Phadruic*.—This is the *Cruz Patricij* mentioned in cap. 79.

^g *Killaladh*, now Killala.

raret: earumque sacræ exuviæ vt patronarum loci, in summa veneratione in Ecclesia de *Kill-fhordann*, iuxta Muadium versus Occidentem asseruantur.

“LXXXVII. Inde progressus venit ad locum, qui à concessu publico, in quo cum subiectis populis congregati erant filij Amalgadij Regis, vocatur *Forrach mhac namhalgaidh*^b. Ingentem ibi populi multitudinem cum suis principibus collectam reperiens, vir Apostolicus in medium cœtum se contulit, et ad succisionem idolatriæ gladium spiritus auaginavit, et verbo Dei velut romphæa bis acutâ, totius multitudinis corda penetravit, et in Christianæ fidei ac doctrinæ amplexum voluntarios perduxit. Eo die septem Amalgadij filios cum ipso Rege et duodecim millibus hominum, Christo lucrificavit, et in fonte qui *Tobur enadharc* nuncupatur, omnes baptizavit. Populoque nouiter conuerso *Manchenum* cognomento *Magistrum*, virum Sanctum, et in Scripturis egregie versatum, fidei et doctrinæ præfecit magistrum.

“LXXXVIII. In eodem agro S. Patricius duo magna operatus est signa. Fœminam vnâ defunctam vitæ restituit, et alteram cum sua prole in vtero gestatâ, vitâ et mortali et æternâ, donauit. Hanc autem fœminam cum suo fœtu mortuam resuscitauit vir Dei infra Ecclesiam de *Kill-aladh*. Et cùm ad eam resuscitandam pergeret, eum comitati sunt Felimius, Amalgadij filius, et Conallus eius ex Enda fratre nepos; et *Ængussius* etiam Felimij frater, qui alia via superiori ad sepulchrum defunctæ mulieris iter suscepit. Matrem autem cum prole iam resuscitatam sacrâ vndâ intinxit in fonte iam supra memorato: *Et illa suscitata prædicaui turbis de pœnis Inferni, de præmijs cœlestibus: et per lachrymas regauit fratrem suum, et Deo per Patricium crederet: quod factum est; et baptizatus. Et in illo die duodecim millia baptizati sunt in fonte Oenadharc ut jam supra retulimus.*

“LXXXIX. Retro flectens versus austrum, venit inde Patricius ad vadum quoddam iuxta lacum *Loch Deala*ⁱ vocatum, vbi statuit ædem sacram excitare: sed fundus erat versipellis *Ængussij*, qui viro Dei se opponens, animique duplicis, verbo et facto ostendens prauitatem; dixit se non ex sincera, sed fictâ et turbatâ mente credidisse et baptismum suscepisse. Patricius hæc audiens in peruersum hominem, eiusque semen fulminavit maledictionis sententiam, precans et prædicens, nec ipsius nec seminis eius domicilium futurum nisi humile, eiusque posteritatem malis seditionum et homicidiorum notis fore notandam.

“XC. Inde versus Orientem reflectens venit ad locum *Leac-fionnbaile* vocatum, qui est supra Ecclesiam de *Kill-mor*^j ad ripam superiorem Muadij fluminis: ibique nostræ

^b *Forrach mhac n-Amhalgaidh*.—This was the parish of Ballysokeery, in the barony of Tirawley.—See p. 281, Note ¹.

ⁱ *Loch Deala*, now Bally-Loughdalla, in the ^j *Kill-mor*, now Kilmore-Moy, near Ballina.

nostræ religionis vexillum triumphale Christi crucem erexit. Sed locus iste à Monachis postea possidentibus, cepit *Lia na manach*^k, id est petra Monachorum appellari.

“XCI. Ibi etiam baptizavit virum Principem, Eochadium Dathia, sive Dauide Fiachrij filio natum : cuius et vxorem Ectram nomine, paulò antè è viris excedentem, vitæ restituit ad vadum ante fores Ecclesiæ Kill-morensis iacens ; quod ex eius nomine *Ath-Echtra*, id est vadum Ectræ nuncupatur. Cui vado et adiacet eiusdem fœminæ sepulchrum, quod et similiter ab ea denominationem retinens, *Feart echtra*^l, id est, tumulus Ectræ, vulgò appellatur, vt periti antiquitatum istius patriæ ex continua traditione referunt.

“XCII. Progressus inde Patricius ad alias Connaciæ partes, S. Olcano discipulo suo mandauit, vt post multos labores in prædicatione Euangelij exantlatos, se ad locum quietis, et cellam construendam conferret, reliquam vitæ partem in quiete et cœlestium contemplatione transacturus : et ut singularis obedientiæ virtus in discipulo præcellens, et magistro probè nota, mundo etiam manifestaretur, iniunxit ei Ecclesiam ædificare, vbicumque Deus dignaretur ipsi de loco prouidere idoneo. Filius obedientiæ de sui veracissimi Patris præcepti, alias incerti, seu indeterminati, certitudine nihil hæsitans, absque morâ, gestans in humero securim, arripit itineris initium, cuius et lineam et finem nesciebat. Cerneus pater tantam filij resignationem, voce et consolatoriâ et propheticâ ait ; Olcane fili, cum benedictione perge, et ubi securis ceciderit, securus reside et ædificia. His auditis pergit S. Olcanus, et nescius quo pergeret, vel pedem figeret, cum venisset ad locum postea *Kill-mor uachtair mhuaidhe* appellatum, securis inopinato è scapulis cecidit, velati cœlitus proiecta. Aduertens autem vir Dei locum illum esse sibi à Domino designatum, cepit ædificare : et cum sudore multo ædificauit Monasterium, vbi factus est in gentem magnam.

“XCIII. In cultu et irrigatione dominicæ vineæ indefesso studio, de die in diem progrediens vir Apostolicus, et singulos patriæ non solùm tractus, sed et angulos circumeundo, deflexit versus Boream, venitque ad locum *Leac Bailbene*, id est, petram Balbenij, vocatam. Vbi denuò filios Amalgadij suâ benedictione muniuit. Deinde per vtrosque Bertlacios transiens, ab Occidentalibus ad Orientales Bertlacios profectus, venit ad Muadij fluvij ostia, ubi in Oceanum soluitur. Postquam vna filia esset ibi submersa, fertur vir sanctus ita portum illum benedixisse, et de eo pronunciasse nullum

^k *Lia na manach*, now called *Liag*. This place is situated on a hill a short distance to the south of the old church of Kilmore Moy, near Ballina. The name is applied to a rock on which a cross is sculptured within a circle, and to an ancient churchyard. All traces of a church, if such ex-

isted, have disappeared.

^l *Feart Echtra*.—This grave is still to be seen in a field lying a short distance to the east of the old church of Kilmore-Moy, and nearly opposite a holy well called Toberpatrick.

nullum in posterum in eo fore submergendum. Prædixit et Bertlacios Orientales ad iura Ecclesiarum suarum olim spectaturos: qui et in continua habent traditione Dominum regionis illius in periculis semper S. Patricij inuocatione et patrocino fore protegendum.

“XCIV. Vterius progredienti viro Dei occurrit in finibus istis, et truculentè occursat ei populus Gregragiorum; qui non tantum sunt conati ipsum à suis finibus excludere; sed et tantâ mentis insolentiâ in ipsum insurrexerunt, vt ipsum et socios saxis et lapidibus impetierunt. Tunc justæ indignationis spiritu motus vir Dei, fertur insolenti populo condignam factis mercedem apprecari, et sic apprecando maledictionis sententiâ prædixisse eos in omni conflictu cædendos, et ubique fore iugo seruitutis et contemptui subiectos. Progrediens autem versus Septemtrionem, cum Muado flumine traiecto veniret in regionem Gregragiorum occurrerunt ei duo ex illa gente Magi, qui statuerunt eum è medio tollere. Sed seruus Dei virtute Domini sui instructas ab eis euadens insidias, prædixit ex eorum progenie magos et maleficos nunquam defecturos.

“XCV. Adjit postea vir Sanctus Conallum charissimum suum; cuius probaturus, et remuneraturus mentis pietatem et resignationem ait; Placetne mi Conalle, monasticam a me suscipere tonsuram? Conallus autem respondit se cor habere paratum ad faciendum quod viro Dei placeret. Gaius Patricius de tanta principis resignatione, eamque largâ mercede remunerans, ait; Non fiet quod dixi, sed ego tuis defendar armis; tuque de semine tuo successores habebis condignos: et multi sæcularis militiæ gloria famosi, multique Christianâ cœlestis militiæ professione conspicui athletæ, de eodem prodibunt semine. Et mox cum baculo suo, qui baculus Jesu dicebatur, crucis signum eius scuto impressit, asserens neminem de stirpe eius in bello vincendum, qui signum illud in suo scuto impressum gestaret; ipsumque proinde Conallum *Sciath Bachlach*, .i. scuti baculati, appellandum. Nec mirum sanè quod stirpe illa minime foret imbecillis, quæ baculi Jesu, omne robur quantumcumque debile fulcientis, impressum signum in suis insignibus, vt symbolum promissæ victoriæ, iure hæreditario gestaret.

“XCVI. Inde progressus peragrando oram maritimam regionis de *Hui Fiachrach*, venit S. Antistes ad fluvium quendam; quem, cum ob magnam aquarum illuviem traicere non posset, sterilitatis maledicto subiectum pronunciauit. Moram tamen iuxta eius marginem contraxit in loco, *Buaille Phadruic* appellato, in quo crux iuxta tumulum posita conspicitur. Ad ipsum in illo loco commorantem venerunt. *S. Bronius* Episcopus de *Cassel-irra* et *S. Mac-rime* Tutelaris Ecclesiæ de *Corca Raoidhe*; et ibi eis scripsit alphabetum. Et audiui (inquit vetustus author) ab alio quod in illo loco dedit dentem ex ore suo Episcopo Bronio, propterea quod charus esset Patricio^m.

“XCVII.

^m *Patricio*.—The annotations of Tirechan, in from Forrach mac n-Amhalgaldh to Ros Mliorum the Book of Armagh, state that Patrick passed Caitni, where he built a church, and crossing the

"XCVII. Baptizavit vir Dei in istis partibus septem Drogenii filios vnumque ex eis sibi elegit in alumnum, nomine *Mackercam* : quem videns parentibus prædilectum, quia eum in partes longinquas secum ferre non audebat, commisit S. Bronio Episcopo educandum. Et ipse est, qui præfectus est Ecclesiæ de *Kill-roe-mor*^a in regione Amalgadiæ. Tunc etiam, vir sanctus iecit fundamenta Ecclesiæ de *Cassel-irra*^o; in cuius atrio est saxum, super quem cecidit dens eius suprâ memoratus.

"XCVIII. Susceptum iter prosequutus per oram maritimam Borealis Connaciæ, venit Patricius ad fluvium *Sligeach*^p appellatum : vbi exhaustum corpusculum volens reficere, petit a piscatoribus quatenus velint retia tendere, et suæ piscationis beneficio de aliquâ piscium refectione providere, qua præsentem releuet naturæ necessitatem. Illi responderunt, licet res illa videretur difficilis tempore illo hyemali, se tamen velle eam in gratiam tanti hospitis attentare. Attentarunt, magnumque cœperunt salmonem, quem viro Dei læti obtulerunt. Quorum benignum obsequium remunerans vir Dei, ipsis bene precatus est, flumenque benedixit, apprecans, et apprecando prædicens, nullo anni tempore pisces in eo defecturos. Quod veridicum oraculum rei continuò probat eventus : nam fluuius ille ita exindè abundat salmonibus, vt nullum sit anni tempus, in quo recentes in eo non reperiantur salmones.

"XCIX. Erat inter Patricij discipulos vnus, nomine *Rodanus* vir profundæ humilitatis et observantiæ singularis. Hic vt erat obedientiæ singulare specimen, quia omnia ad Magistri nutum faciebat ; ita bruta animantia eius nutui per omnia parebant. Præfectus enim a Magistro armentis fratrum pascendis et custodiendis, ita hanc curam obibat vt vituli ad vbera matrum sugenda non accederent, nec ab eis recederent, nisi ad eius, licentiam dantis, vel reuocantis, nutum. Hunc Patricius postea iuxta virtutum

Muaidh at Bertriga, now Beartrach, he raised a cross there, and proceeded thence to *Fossa Riabairt*, (the Rath Righbhaird of the Irish lives of this saint) near which he built a church for his disciple Bishop Bronus, the son of Ienus, now Killaspugbrone.

^a *Kill-roe mor*, now Kilroe, a very ancient church in ruins, situated in a townland of the same name, in the parish of Killala and barony of Tirawley. It stands on a rocky hillock about one mile to the east of the town of Killala. This hillock commands a beautiful view of the sandy island of Beartrach, of the bay of Killala, and of the Cloigthesach, or Round Tower and steeple of the church of Killala. This church is built of very large stones, in the primitive Irish style, and is

only twenty-four feet in length and eighteen feet in breadth. Its west gable and south wall are nearly destroyed, but the north wall and east gable, with its small round-headed window, are in good preservation.

^o *Cassel-irra*.—This was the ancient name of a stone fort situated in the district of *Cuil-irra*, near, or within which the church of Killaspugbrone, near the town of Sligo, now nearly overwhelmed with sand, was erected.

^p *Fluvium Sligeach*.—This was the ancient name of the River Gitly, which flows through the town of Sligo, to which it has given its ancient name, Gitly being a corruption of Gilly, a name given to the river because it flows from Lough Gill.

tum et meritorum exigentiam Episcopum ordinavit, et Ecclesiæ de *Kill-rodain* in regione de *Muiresch-aigle*¹ præfecit.

"C. Patricio Connaciæ circuitum ad exitum propè ducenti et transeunti, constructis insidiis occurrerunt viri *Calregiæ de Culechernadan*², armorumque ac clypeorum strepitu, clangoribus, et clamoribus excitatis satagerunt sanctum Dei, ejusque socios terrere, ac de suis finibus fugatos propellere. Ad quos vir sanctus quod in spiritu vidit, dixit; quia contra inermes armati insurrexistis; et pacis et salutis nuncios è finibus vestris effugare contendistis; vos ipsi vestrique posteri in die belli, velut oves, in fugam acti, hostibus terga dabit. Hæc illi audientes, valdè consternati sunt, et super temeritate suâ pœnitentiam agentes, omnes præter quinque in genua prouoluti veniam humiliter postularunt. Vir misericors paululum, velut deliberans, tacuit, et mox alio præsago et consolatorio oraculo ad eos ait; stabit fixum quod Dominus per os meum loquutus est: attamen quia erroris veniam humiliter postulatis, in nullo conflictu, etiamsi omnes Cunnacij vos insequantur vltra quinarium numerum ex vobis occumbent. Et hoc oraculum impleri continuò probat euentus."—*Septima Vita S. Patricij*, lib. ii.—*Colgan Trias Thaum.*, p. 140.

Q.

EOGHAN BEUL, KING OF CONNAUGHT.

See page 312, Note 1.—In the Life of St. Ceallach, Bishop of Kilmore Moy, who was the son of this Eoghan Beul, there is a curious account of the battle of Sligeach (Sligo), in which his father, Eoghan, fell. It makes distinct mention of this king's *onchu*, or banner, and of the *meirgeadh*, or standards, which his chieftains carried on their plundering excursions into the other provinces. It goes on to state that Eoghan lived three days, or, according to others, a week, after being mortally wounded in the battle, in which time he advised the Hy-Fiachrach to elect his son Ceallach King of Connaught, and requested of them to go to Clonmacnoise, where he was under the tuition of St. Kieran, and intreat of him to come home with them and accept of the kingdom,
for

¹ *Muiresch Aigle*, now Murreak, an abbey at the foot of *Cruachan Aigle*, now Croaghpatrick, about four miles from Westport. The name *Muirisc* was originally applied to the level district lying between the mountain and the sea. There is another *Muirisc* in the barony of Tireragh,

but this is not the one here referred to.

² *Calregiæ de Culechernadan*, now Coolcarney, a district in the barony of Gallen, and county of Mayo, comprising the parishes of Attymass and Kilgarvan.—*Vide supra*, pp. 166, 167, 246, 247.

for that his second son Muireadhach, otherwise Cuchoingeilt, was not of age to succeed him. They did so, and Ceallach was induced to go with them, contrary to the wish, and without the knowledge of his saintly tutor, who thereupon pronounced a curse against him which finally wrought his destruction; for though he was afterwards reconciled to St. Kieran, and raised to the episcopal dignity, the curse could not be revoked, and he was afterwards driven from his bishopric, and, as already stated in Addenda G, murdered by his own four pupils, at the instigation of Guaire Aidhne, King of Connaught. King Eoghan ordered himself to be interred in a standing position, with his red javelin in his hand, and with his face turned towards Ulster, as if fighting with his enemies. This was accordingly done, and the talismanic result was, that as long as the body was left in that position the Connacians could not be defeated by the Ultonians, but whenever they came in collision the Ultonians were defeated by the Connacians. The Ultonians, on learning the cause of this, disinterred the body of Eoghan Beul, and carrying it north of the River Sligo, buried it with the face under, at the cemetery of Aonach Locha Gile near Lough Gill, in the present county of Sligo. This superstition is so curious, that the Editor hopes to be excused for giving the original account of it, word for word, with a literal translation.

"Ar beir fof Eoghan a aonacul ocup a ga beapz ana lámh in in uaó. Ocup tobair m'airgi ar in tuaircirt, ar taeó na tulóa i ngebaio in tuaircepe ne cat cuigeó Connacht, agur airgeó m'uaigi-rí fofpo, agur mé féin innce ar in cop-ugeo rin.' Ocup do coimleao co fip an rgel rin; uair gaó inaó a tegmaó Clanna Neill u'a céile ocup Connacht-aó, do muigeao maóim do gnúirib ar Clannaib Néill ocup ar in tuaircirt ann; conao h-i comaple do pinni Clanna Neill agur tuaircirt Epenn uime rin, teact pluairgeao mór co Ráit O Fiachrach, ocup Eoghan do cógbáil ar in aó-nacul, ocup a éairi do bneich leo cap Sligeach po chuairh; ocup po h-aónaiceao tall h-é, a n-aenach Locha Gile, agur a bél ne lám, co nach beir doib

"Eoghan also told them to bury himself with his red javelin in his hand in the grave. 'Place my face towards the north, on the side of the hill by which the northerns pass when flying before the army of Connaught; let my grave face them, and place myself in it after this manner. And this order was strictly complied with; and in every place where the Clanna Neill and the Connacians met in conflict, the Clanna Neill and the northerns were routed, being panic stricken by the countenances of their foes; so that the Clanna Neill and the people of the north of Ireland therefore resolved to come with a numerous host to Raith O'bh-Fiachrach and raise *the body of* Eoghan from the grave and carry his remains northwards across the Sligo. This

was

rin 'na conaig ceriúite do cinnu pe was done, and the body was buried at the
 Connachtaib." other side of the river, at Aenach Locha
 Gile, with the mouth down, that it might
 not be the means of causing them to fly
 before the Connacians."

The custom of thus interring Irish kings and chieftains in a standing position is often referred to in Irish historical tales. It is stated, for example, in *Leabhar na h-Uidhri*, a compilation made at Clonmacnoise in the twelfth century, that the monarch Loeghaire, who was cotemporary with St. Patrick, but who had never been converted to Christianity, was interred in the external rampart of *Rath Loeghaire*, at Tara, in a standing position, with his military weapons upon him, and having his face turned southwards upon his enemies, the Lagenians, as if fighting with them, or bidding them defiance.

The following very curious allusion to the same King Loeghaire, and to the custom of the interment of kings in a standing position, with their arms, is found in the Book of Armagh, which contains perhaps all the old fragments of Irish literature now remaining to us :

"Perrexitque ad civitatem *Temro*, ad Loigarium, filium Neill, iterum quia apud illum fœdus pepigit ut non occideretur in regno illius, sed non potuit credere, dicens : Nam Neel pater meus non sinivit mihi credere, sed ut sepeliar in cacuminibus *Temro* quasi viris consistentibus in bello : quia utuntur gentiles in sepulchris armati prumptis armis facie ad faciem usque ad diem *Erdathe* apud Magos, id est iudicii diem Domini. Ego filius Neill et filius Dunlinge in *Maistin* in Campo Lippi, pro duritate odivi," &c.—*Annotations of Tirechan, Book of Armagh*, fol. 10, a, 2.

There is a curious little poem quoted by Duald Mac Firbis in his large genealogical work, describing the residence of King Eoghan Beul, but the Addenda to this volume having been already extended to too great a length, the Editor thinks it better to reserve it for some future work. It was situated on the island of Inis Eoghain, in Lough Mask, on which the Editor saw distinct traces of its earthen ramparts in the year 1838.

R.

ADDENDA ET CORRIGENDA.

Page 2, note ^b, for "1645" read "1650."

Page 15, line 3, for "Cnaimghiollan" read Cnaimghiolla.

Page 22, line 5, for "Naoníallac" read "Naoníallac."

Page 25, line 12, after "Cruachan" insert "and was interred in Roilig na Riogh, or Cemetery of the Kings, at Cruachan."

Page 33, line 20, *for* "foster brothers" *read* "foster sons, or pupils."

Page 34, line 12, *for* "Muolparéce" *read* "Maolparéce."

Page 35, line 3, *for* "foster brothers" *read* "foster sons."

Page 35, line 7, *for* "Ard na riogh," *read* "Ard na riagh."

Page 41, line 11, *for* "Glasano Triallaigh" *read* "Glasan Ui Triallaigh."

Page 61, line 10, *for* "Baill-derg" *read* "Aodh Baill-derg."

Page 67, Note °, *for* "in the parish and barony of Kiltartan" *read* "in the parish of Kilmacduagh and barony of Kiltartan.—See Ordnance Survey of the County of Galway, sheet 122."

Page 80, Note °, *for* "called g-cedne" *read* "called Magh g-Cedne."

Page 89, Note °, *for* "of the Leinster Clearys of Leinster" *read* "of the Clearys of Leinster."

Page 101, Note °, *for* "1645" *read* "1650."

Page 104, line 2, *for* "mic Diarmada Cnoic" *read* "mic Diarmada Caoic."

Page 124, Note °, lines 6 and 16, *for* "1452" *read* "1458," and same note, line 7, *for* "eight years" *read* "about three years."

Page 138, Note °, *for* "this Ceallach was King of north Connaught" *read* "this Aodh, son of Ceallach," &c.

Page 144, Note °, *for* "paid by an Englishman" *read* "paid by one of the Anglo-Irish inhabitants of the English pale."

Page 168, Note °, col. 2, lines 3, 4, *for* "This castle is still standing" *read* "This castle is now a heap of crumbled ruins."

Page 179, line 3, *for* "No sept is great in comparison of them," *read* "No sept has arrived at their happiness."

Page 183, Note °, *for* "conraín" *read* "coraín."

Page 223, line 12, *for* "Is the Hy-Muireadhaigh of banners" *read* "are of the Hy-Muireadhaigh of banners."

Page 247, line 1, *for* "Carllaidhe" *read* "Callraidhe."

Page 247, line 10, *for* "O'h-Iarmain" *read* "O'h-Iarnain."

Page 258, Note °, *for* "Maolruanaidg" *read* "Maolruanaidh."

Page 262, Note °, *for* "O'Luidhlearga" *read* "O'Suidhlearga."

Page 265, Note °, col. 2, line 7, *after* "district of the Strand" *insert* "otherwise called Cuil Cnamha."

Page 277, line 1, *for* "A small land" *read* "A smooth land."

Page 277, Note °. At the end of this note add: "In addition to the above evidences we have the testimony of Connell Mageoghegan, that the Cairbre of which O'Ciardha was chieftain is the present barony of Carbury, in the county of Kildare, which,

which, after the subjection of O'Ciardha, became the country of a branch of the Berminghams. In his translation of the Annals of Clonmacnoise, made in 1627, he states, under the year 1076, that it was called Bremyngham's country in his own time. 'A. D. 1076, Gillepatrick O'Kiergie, Prince of Carbrej, now Bremyngham's country, died.' "

Page 279, line 7, *for* "Rodha" *read* "Rodhba."

Page 279, Note ¹, page 284, Note ^b, and page 291, Note ^c. The Editor must here acknowledge that he has been hypercritical and over sceptical in these Notes, for it appears from a MS. Life of St. Ceallach, formerly in the possession of Mr. Hardiman, that there was a place called Durlus Muaidhe, or Durlus Guaire, in the territory of Tirawley, and situated between Dun Fine, now Doonfeeny, and Ard na riagh, now Ardnarea, and not far from Kilmore-Moy. This Durlus Guaire, though the name is no longer extant, must doubtlessly be the place alluded to in his poem by Giolla Iosa Mor Mac Firbis, and not the Durlus Guaire, or Dun Guaire, in the country of the southern Hy-Fiachrach, as the Editor has rather too hastily assumed in the notes above referred to. In all antiquarian and historical researches we must draw our inferences, not from our own imaginations, but from the recorded facts before us, and when these facts are not sufficiently numerous or definite, they may often lead us to very erroneous conclusions.

Page 293, line 12, *for* "east of the old Alps" *read* "eastwards to the old Alps."

Page 298, line 3, *for* "ap plait-ni" *read* "pap plait-ni," or "pap plait-ni."

Page 299, line 3, *for* "under chieftains" *read* "under our chieftain."

Page 300, Note ¹. At the end of this note add: "The death of this Aodh is entered in the Annals of Clonmacnoise, at the year 978, where he is called Hugh O'Dowdie, King of Lower Connaught, in Macgeoghegan's translation."

Page 306, line 2, *for* "mḡcain" *read* "mátcain."

Page 313, Note ^c, *for* "reign of Conall and Ceallach" *read* "reign of Diarmaid, son of Fergus Ceirbheoil, and also of Conall and Ceallach."

Page 314, line 7, *for* "ḡuine" *read* "ḡuaine."

Page 315, lines 3 and 9, *for* "Tiobraidhe" *read* "Tiobraide."

Page 337, line 23, *for* "had inhabited the south of the mountain" *read* "had inhabited to the south of the mountain, or were seated in the territory lying southwards of the mountain."

Page 366, line 32, at end of paragraph insert, "In 1705, this David and his fourth son, Dominic, then the only son surviving, sold several denominations of land to a Mr. Wingfield, as appears from the original deed of sale, in the possession of the present O'Dowda."

Page 405, line 28, *for* "A. D. 1645-1666" *read* "A. D. 1650-1666."

Page 408, line 21, *for* "1672" *read* "1670."

Page 414, line 19, *for* "German" *read* "German, the Abbot."

Page 440, line 21, *after* "was handed to the O'Dowd," *insert* "or rather, as we are told by the writer in the Book of Lecan, was raised over his head by Mac Fírbis, in token, no doubt, of the influence which the latter exercised over him by his advice and writings; and it is scarcely credible that the rod would have been so raised by the poet, if it had been previously consecrated by a priest, as Philip O'Sullivan Beare asserts."

Page 458, line 16, *for* "sel non" *read* "sed non."

Page 459, line 36, *for* "na Ríénige" *read* "na Ríénige."

Page 462, Note ^a, lines 7, 8, *for* "baptizavet" *read* "baptizavit."

Page 467, line 21, *for* "regavit" *read* "rogavit."

Do eiríochuigeas an obair nua, iad mór íasóir agur úinéir, a n-Ách cliaith
Duiblinne, an t-ócáid la déag ve mí Iúin, 'ran m-bliadain d'aoir ar o-Tig-
earna 1844, le Seán, mac Eamonn Oig, mhic Shéan Eamonn, mhic Uilliam, mhic
Choncuibair Uí Dhonnabáin; agur má geibean an léigéoir ní inéime innse,
cruiseas ré gur ear déicéall an fíor fíorúil do éirí; agur cuimnígeas luí a
h-innéiréas na b-fíor obair éirí na fá'n ngráin íar ó loctas, agur gur mion
do h-innéiréas deag-íasóir do h-éirí na b-fíor agur mioníar n-eirí-
na, agur fíor éirí a n-áineolur.

EXPLANATORY

30. Maolrua
ina
143

31. Diarmaid

32. Conchobair
C.
yes

33. Eoghan
of
fl.

24. Tadhg
d

35. Dathi


36. Dathi

37. James

38. Dathi

39. Davi

SHOWING THE DESCENT OF



EXPLANATORY INDEX TO THE MAP.

A

Αβαυνν αργνε, the Arigna river, on the boundary between the barony of Tirerrill, in the county of Sligo, and that of Drumahaire, in the county of Leitrim.

Αβαυνν αλλα Γρεκ, now the Aille river, in the east of the parish of Aghagower, in the territory of Umhall.

Αβαυνν μόν, i. e. the great river, now Owenmore, a river in the county of Sligo, flowing into Ballysadare bay.

Αβαυνν να μλλακταν, a stream which formed the south boundary of the territory of Partry, in Carra.

Αβασ Chonaυπε, Achonry, a parish church and Bishop's See in the barony of Leyny.

Αβασ Φοβαυ, i. e. the field of the spring, now Aghagower, the name of a celebrated church and parish, situated in the east of the barony of Murriak.

Αβασ μόν, i. e. the great field, now Aghamore, a townland containing the ruins of a church, situated in a parish of the same name, in the barony of Costello.

Αβασ πργ, now Aghacree, a townland near Ballymoghany, in the parish of

Castleconor, in Tireragh.

Αιρτευχ, a territory in the north-west of the county of Roscommon, adjoining Lough Gara, and between the rivers Lung and Breedoge.

Αιρτεγε αν μερραγ (incorrectly engraved Αχ τεγε αν μερραγ), now Attymas, a parish forming the southern part of the district of Coolcarney, in the barony of Gallen.

Αιρ τεγε Γυαυριμ, the site of an ancient house on the island of Inishbofin, q. v.

Αν οά bhac, a territory in the south-east of the barony of Tirawley, for the extent of which see pp. 232, 233, note ^k.

Αν φοο ουβ, i. e. the Black Sod, the name of a point of land in the south-eastern extremity of the parish of Kilmore, barony of Erris.

Αν Ζαγάν, a district in the north of the barony of Tirawley.—See pp. 222, 223, Note ^l.

Αιοναχ μόν, Enaghmore, a castle in ruins in the parish of Crossmolina, in the barony of Tirawley.

Απο ααα, i. e. high field, Ardagh, near

- Ballina, in the barony of Tirawley.—See p. 11, Note ^t.
- Αἶρο ἀάρο, Ardagh, in the barony of Tirerrill, in the county of Sligo.
- Αἶρο ἀν τεαρμωῖνν, Ardatermon, a townland in the west of the barony of Carbury, in the county of Sligo.
- Αἶρο νὰ νḡλαρ, now Ardnaglass, otherwise Ardabrone, a townland containing the extensive ruins of a castle, in the parish of Skreen, in Tireragh.—See p. 270, Note ^s.
- Αἶρο νὰ νḡαḡ, now Ardnarea.—See p. 34, Note ^w.
- Αἶρο Οḡ-Ceallaḡ, now Ardokelly, in the parish of Templeboy, in Tireragh.—See p. 264, Note ^f.
- Αἶε κḡαε ἀν Chopainn, i. e. the hurdle-ford of Corran, the ancient name of Ballymote, in the barony of Corran, county of Sligo.
- Αἶε εḡαα, Ahena, a castle in ruins, situated in a townland of the same name, in the parish of Tagheen and barony of Clanmorris.
- ḡ.
- ḡaile ἀν Chapḡl, i. e. town of the Cashel, or stone fort, now Ballycastle, a small town in the parish of Doonfeeny, in the north of the barony of Tirawley.
- ḡaile ἀν chapḡlḡn, or Imleac ḡeal, now Castletown, in the parish of Easkey, in Tireragh.—See pp. 256, 257, Note ^a.
- ḡaile ἀν εḡαα, Ballinchalla, a parish in the barony of Kilmaine, bordering on Lough Mask.
- ḡaile ἀν οḡḡn, now Ballindoon, an abbey in ruins, in the barony of Tirerrill and county of Sligo.
- ḡaile ἀν ḡleanna, now Ballinglen, in the parish of Doonfeeny, in Tirawley.—See pp. 7, 220, 221.
- ḡaile ἀν μḡḡα, now Ballymote, in the barony of Corran.—See Αἶε κḡαε ἀν Chopainn.
- ḡaile ἀν Roḡba (incorrectly engraved ḡaile νὰ Roḡba), Ballinrobe, a well known town in the barony of Kilmaine.
- ḡaile ἀν τ-ḡḡḡḡḡn, Ballinteean, a castle in ruins, in the parish of Ballysokeery, in the barony of Tirawley.
- ḡaile ἀν τḡḡḡḡ, i. e. the town of the causeway, now Ballintogher, in the north of the barony of Tirerrill, in the county of Sligo.
- ḡaile εḡα leaḡḡn, Ballylahan, in the barony of Gallen, formerly the seat of Mac Jordan De Exeter.
- ḡaile εḡḡḡḡ, now Caggaula, a townland in the parish of Ballintober, barony of Carra.—See p. 191, Note ^o.
- ḡaile εḡḡḡ cḡḡḡḡ, now Ballysokeery (incorrectly engraved ḡaile εḡḡḡ cḡḡ), a townland in which stood a church and castle, in a parish of the same name, in the barony of Tirawley.
- ḡaile εḡḡḡ ḡḡḡḡ, now Ballysadare, a little town in the N. E. of the barony of Leyny.
- ḡaile loḡḡ Meḡḡḡḡ, Ballyloughmask, now Loughmask Castle, in the parish of Ballinchalla and barony of Kilmaine.
- ḡaile Mḡḡḡ Conleḡḡḡḡ, now Ballykinlettragh, in the parish of Kilfian and barony of Tirawley.—See pp. 7, 221, 222.

Ḑaile Mhic Ḑiolla cāip, now Ballykil-cash, in the parish of Kilmacshalgan, in Tireragh.—See p. 260, Note ^a.

Ḑaile na Ḑpoēlaigi, the ancient name of the townland containing the lake of Loch Brothlaighi, now Lough Brohly, in the parish of Kilgarvan.—See p. 421, Note ^a.

Ḑaile na cille, i. e. the town of the church, now Ballynakill, a parish in the barony of Tirerrill, in the county of Sligo.

Ḑaile O'Ḑ-Fiacháin, i. e. the bally, townland, or residence of the family of O'Fiachain, the ancient name of Newport, in the parish and barony of Burishoole, in the county of Mayo.

Ḑaile Tobair Phátopuig, now Ballintober, a townland containing the ruins of a splendid abbey, in a parish of the same name in the barony of Carra.

Ḑaile Uí Ḑhánáin, Ballybanaun, a townland in the parish of Ballyovey and barony of Carra.—See p. 189, Note ^b.

Ḑaile Uí Chioḑagáin, O'Kerrigan's town, now Ballykerrigan, a townland in the parish of Balla and barony of Carra.—See p. 155, Note ^c.

Ḑaile Uí Choicil, now Cottlestown, in the parish of Castleconor, in the barony of Tireragh.—See p. 249, Note ^c.

Ḑaile Uí Ḑhírcáin, now Ballyeeskeen, in the parish of Templeboy, in Tireragh.—See p. 261, Note ^c.

Ḑaile Uí Doite, Ballyduffy, a townland containing the ruins of a castle in the north of the parish of Addergoole.

Ḑaile Uí Eāḑra, i. e. O'Hara's town, now

Ballyhara, near the village of Tobercurry, in the barony of Leyny.

Ḑaile Uí Ruāipc, now Ballyrourke, a townland in the parish of Balla, in the barony of Carra.—See p. 155, Note ^b.

Ḑaile Uí Mhoḑaine, now Ballymoghany, in the parish of Castleconor, in Tireragh.—See p. 249, Note ^c.

Ḑalla, now Balla, or Ball, a village containing the ruins of an ancient church and round tower, in a parish of the same name, in the barony of Carra.

Ḑealaḑ Dúin iapáin, a road extending across the strand from Doonieren, in Ros Ceide, northwards to Finned in Machaire Eabha, in the barony of Carbury, and county of Sligo.

Ḑéal an áca pāoa, now Ballinafad, a well known village, in the south of the barony of Tirerrill, in the county of Sligo.

Ḑéal an cláip, now Aclare, a townland in the parish of Kilmacteige, in the south-west of the barony of Leyny, where there is an old castle in ruins.

Ḑéal an cōmpaic, i. e. *os confluentia*, now Belacorick, near the conterraneous boundary of Erris and Tirawley, on the road from Ballina to Belmullet.

Ḑéal an cāipḑ, i. e. the Bull's mouth, a strong current between Inishbiggle and Achil Island, barony of Burishoole.

Ḑéal áca h-amnāip, now Ballyhaunis, a village celebrated for its abbey, situated on the boundary between the parishes of Began and Annagh, in the barony of Costello, in the county of Mayo.

Θéal áca h-én, now Ballyhean, a village in a parish of the same name in the barony of Carra.

Θéal áca na níceas, a well known ford on the Owenboy river, about a mile and a half from Foxford, in the barony of Gallen.—See pp. 166, 167, Note ^d.

Θéal eapa, now Foxford, a small town in the barony of Gallen.

Θéal muileac, Belmullet, the name of a neck of land on which a little town now stands, between Broad Haven and Blacksod Bay, in the barony of Erris.

Θéal epága, now Beltraw, on the west side of the strand of Traigh Eothuile, in the eastern extremity of the barony of Tireragh.

Θeann gorm, i. e. the blue *ben* or peak, a mountain in the south of the barony of Murrisk. It is also the name of another mountain in the parish and barony of Burrishoole, or Lower Umhall.

Θeannoqa, now Banada village, near which is an abbey in ruins, situated westwards of the village of Tobercurry, in the barony of Leyny.

Θeápna na gaioie, now Windy Gap, on the south-east boundary of the parish of Addergoole, in the barony of Tirawley.

Θeápnar Cocha Talt, now Barnislough-Talt, in the west of the barony of Leyny, adjoining the barony of Gallen.

Θeápnar mór Típe Oilíolla (incorrectly engraved Oeápnar mór Típe Oilíolla), the ancient name of the valley between Slieve Daén and the eastern extremity

of Slieve Gamh, in the barony of Tirerrill, county of Sligo.

Θeapnanach, Barranagh Castle, situated in the southern portion of the parish of Kilmore, in the barony of Erris.

Θeaptrapach, now Bartragh, a sandy island at the mouth of the River Moy, in Tireragh.—See p. 250, Note ^z.

Θélna leice, Ballynalecka, in the parish of Ballintober and barony of Carra.—See p. 155, Note ^c.

Θél áca na lúb, now Newbrook, the seat of Lord Clanmorris, in the barony of Carra.—See p. 156, Note ^k.

Θél lice, now Belleek, in the parish of Kilmore, in the barony of Tirawley.

Θinn Gulban, or Θeann Gulban, now Binbulbin, a remarkable mountain in the parish of Drumcliff, in the barony of Carbury, county of Sligo.

Θoppach, a district in Tireragh, for the extent of which see p. 262, Note ^v.

Θot Thóla, i. e. St. Tola's booth, or tent, now Bohola, an old church in ruins, in a parish of the same name, in the barony of Gallen.

Θráioíliab, now Braulieve, a mountain on the frontiers of the counties of Sligo and Leitrim, forming for some miles the eastern boundary of the barony of Tirerrill.

Θpeaímaz, Breaghwy, or Breaffy, an old church in ruins in a parish of the same name, in the barony of Carra.

Θpéaoach, a territory in the west of the barony of Tirawley. See p. 229, note ^b.

Θpocach, Brockagh, a townland contain-

ing the ruins of a castle situated in the parish of Kilmaglasser, in the barony of Burrishoole.

Ἰπρεκλιὰς, now Brecklieve, or Brecliff, in the barony of Tirerrill, west of Lough Arrow, county of Sligo.

Ἰρροναχ. Brosnagh, a mountain stream, flowing through the south-west part of the barony of Tireragh.—See p. 247, Note ¹.

Ἰνριγγέιρ Ceara, i. e. the Burgage of Ceara, now Burriscarra, an abbey in ruins, situated in a parish of the same name in the barony of Carra.—See p. 202, Note ^c.

Ἰνριγγέιρ Umhall, i. e. the Burgage of Umhall, anglicè Burrishoole, the name of an abbey and castle from which the parish and barony of Burrishoole received their name.

Ἰν αἰῶνα, i. e. river-mouth, the name of the mouth of the river which flows through the little town of Louisburgh, in the north-west of the barony of Murriak, or Upper Umhall.

Ἰν οὐίθε, i. e. the mouth of the River Duff, now Bunduff, at the northern extremity of the county of Sligo.

Ἰν φεωε, now Bunnafeidia, a townland in the parish of Dromard, in Tireragh.—See p. 271, Note ^m.

Ἰν φιννε, now Buninna, a townland in the parish of Dromard, in Tireragh.—See p. 121, Note ^m.

C.

Cabpach, now Cabragh, a townland in
IRISH ARCH. SOC. 12.

the parish of Easkey, in Tireragh.—See p. 253, Note ¹.

Caipbre, now the barony of Carbury, forming the northern part of the county of Sligo.

Caipri, now Corha, or Carha, in the parish of Kilgarvan, in the district of Coolcarney, now a part of the barony of Gallen.

Caipéal, a stone fort in the eastern side of the Island of Achil.

Caipéal Caírne, Castlelaffy, a castle built on the site of an ancient cashel, or stone fort, situated in the parish of Kilmeena, in the barony of Burrishoole.

Caipéal mór, i. e. the great cashel, or stone fort, a townland in the parish of Killaraght, in the barony of Coolavin.

Caipleán an Ḫhappauḡ, i. e. Barry's castle, now the town of Castlebar, in the barony of Carra.—See pp. 160, 161, Note ^v.

Caipleán an Ḫhúpcawḡ, Castle Burke, a castle in ruins in the east extremity of the parish of Ballintober, in the barony of Carra.

Caipleán an Inḡir, Inver Castle, on the margin of Invermore, or Broad Haven.

Caipleán ḡ Chlocám, Cloghan Castle, situated in the parish of Kilbelfad, in the south-east of the barony of Tirawley.

Caipleán Caoch, Castlekeagh, a castle in ruins in the parish of Killedan, near the southern extremity of the barony of Gallen.

Caipleán Concoḡar, now Castleconor,

- situated on the margin of the River Moy, in a parish of the same name in the barony of Tireragh.
- Caipleán Leacain, now Castlelackan, in the parish of Lackan and barony of Tirawley.
- Caipleán na m-Brí, anglicè Brees, or Brize Castle, a castle in ruins in the parish of Mayo and barony of Clanmorris.
- Caipleán na caillege, the Hag's Castle, in Lough Mask, near Ballinrobe.
- Caipleán na cipse, Castlekirk, a very ancient castle in Lough Carra, in the barony of Carra.—See p. 331, Note ^c.
- Caipleán na Daoile, Deel Castle, near the little town of Crossmolina, in the barony of Tirawley.
- Caipleán na Daoite, now Castlenageeha, a castle in ruins in the parish of Kilcummin and barony of Tirawley. Daoite in this name means a fresh water stream into which the tide flows.
- Caipleán Mannann, Mannin Castle, a castle in ruins on a small island in Loch na n-airneadh, in the parish of Aghamore, and barony of Costello.
- Caipleán mór, i. e. the great castle, now Castlemore, in the barony of Costello.
- Caipleán Uí Cheallairg, Castlekelly, on the margin of Lough Conn, in the parish of Kilbelfad, barony of Tirawley.
- Caipleán Uí Mhánille, O'Malley's Castle, on the east side of Clare Island, in Clew Bay.
- Calpange Caichim, a district in the barony of Carbury, in the county of Sligo, nearly coextensive with the present parish of Calry.—See p. 276, Note ^c.
- Calpange Mairge h-Eleag, a territory in the west of the barony of Tirawley.—See p. 238, Note ^f.
- Caoille Conaill, a district in the north-east of the barony of Tirawley.—See p. 225.
- Caol, Keel, a small village in the western portion of the island of Achil.
- Caol, now Keel Bridge, near Ballinrobe.—See p. 201, Note ^a.
- Caol-íáile puao, i. e. the narrow reddish brine, now the Killary harbour, forming the southern boundary of the barony of Murrisk.
- Caopéannán, now Castle Hill, a townland on the west side of Lough Conn, in the barony of Tirawley.—See p. 233, Note ^m.
- Capn, now Carns, in the parish of Castleconor, in Tireragh.—See p. 249, Note ^a.
- Capna, Carns, a castle in ruins in the east of the parish of Moygawnagh, in the barony of Tirawley.
- Capn Amalgao, near Killala, in the barony of Tirawley.—See p. 441.
- Capn Oilholla, i. e. Oilíoll's carn, a remarkable carn giving name to a ruined village on the west side of Lough Arrow, in the barony of Tirerrill.
- Capraig, now Carrick, a townland in the parish of Attymas, district of Coolcarney, and barony of Gallen.—See p. 422, Note ⁱ.
- Capraig an eapa, i. e. the rock of the cataract (*torrentirupes*), now Carrick-

- anass Castle, in the south of the parish of Lackan, in the barony of Tirawley.
- Cappary Aodha, i. e. Aodh's rock, a celebrated rock in the sea off the coast of Erris, a short distance to the north of Inishkea.
- Cacaur, a stone fort near Slievemore, in the island of Achil.
- Cacaur, the name of an ancient stone fort, now nearly destroyed, situated in the north-east extremity of Achil Island, in the barony of Burrishoole, or Lower Umhall.
- Cacaur Mhic Tuirc, a large Cyclopean fort, lately destroyed, near Cong, in the barony of Kilmaine.
- Cacaur na map, i. e. the stone fort of the beeves, the name of a very ancient fort, and also of an old castle built by O'Malley, on the margin of the bay of Westport, and which gave origin to the town of Westport, which is still universally called Cacaur na map in Irish.
- Cacaur na peanna, Cahernaran, a stone fort, now nearly destroyed, situated on a point of land northwards of Croaghpatrick, and on the margin of Westport Bay.
- Ceann Eacla, i. e. Achil Head, the name of the western extremity of the island of Achil.
- Ceann Tuirc, Kinturk, a castle in ruins in the parish of Ballyhean, in the barony of Carra.
- Cearra, now Carra, a celebrated territory, now a barony in the county of Mayo.
- Cearra na an Cábáin, now Carrowlabau, or Carrowlabane, a townland in the parish of Kilgarvan, district of Coolcarney, and barony of Gallen.—See pp. 420, 421, Note ^v.
- Cearra na carláin, now Carrowcastle, in the parish of Kilgarvan, district of Coolcarney, and barony of Gallen.—See p. 421, Note ^f.
- Cearra na Lochán, now Carrowloughaun, a townland in the north-east of the parish of Skreen, in Tireragh.—See p. 120, Note ⁿ.
- Cearra na Mhic Coin'n, now Carrowconeen, in the parish of Kilgarvan, in the district of Coolcarney, and barony of Gallen.—See p. 422, Note ^v.
- Cearra na Mhic Geirbla, now Carrowkeribla, a townland in the parish of Attymas, district of Coolcarney, and barony of Gallen.—See p. 422, Note ^l.
- Cearra na g-cloč, now Carrowmaglogh, a townland in the parish of Kilgarvan, in the district of Coolcarney, and barony of Gallen.
- Cearra na Gneilligí, i. e. the quarter of Greallach, now Grallagh, in the parish of Kilgarvan, district of Coolcarney, and barony of Gallen.—See p. 421, Note ^e.
- Cearra na maddoo, now Carrownamaddoo, a townland near Binbulbin, in the barony of Carbury, in the north of the county of Sligo.
- Cearra na Uí Dhubháin, now corruptly anglicised Carrowmagooaun, a townland in the parish of Attymas, district of Coolcarney, and barony of Gallen.—See p. 421, Note ^d.

Clappaige Uachtair, i. e. Upper Kerry, a territory in the county of Mayo, comprising the entire of the barony of Clanmorris, except the termon of Balla, which was a part of Ceara originally.

Clappaige Locha na n-áinneas, a territory in the county of Mayo, comprising the parishes of Aghamore, Knock, Bekan, and Annagh, that is, that portion of the barony of Costello belonging to the archdiocese of Tuam.

Cill a' Ghaoibair, Kilgeever, an old church in the barony of Murrisk, or Upper Umhall, situated nearly due west of Croaghpatrick.

Cill alais, now Killala, a town and bishop's see in the barony of Tirawley.

Cill anoub, now Killarduff, in the parish of Doonfeeny, barony of Tirawley.

Cill Beacán, i. e. the church of St. Beacan, now Bekan, an old church in a parish of the same name, in the barony of Costello.

Cill beag, i. e. the small church, the name of the site of an ancient church in the southern portion of the parish of Kilmore, barony of Erris.

Cill Béalbada, Kilbelfad, a parish in the south-east of the barony of Tirawley.— See p. 233, Note °.

Cill Beiteach, now Kilbeagh, a parish in the north of the barony of Costello.

Cill Bhríge, i. e. the church of St. Bridget, anglicè Kilbride, an old church in a parish of the same name, in the north of the barony of Tirawley.

Cill Bhríge, Kilbride, an old graveyard

in which formerly stood a small church, situated in the north of the parish of Kilgarvan, in the district of Coolcarney, now in the barony of Gallen.

Cill Bhríge, Kilbride, an ancient church in ruins near the north-west extremity of the barony of Murrisk, or Upper Umhall.

Cill Duamne, now Kilboyne, in the parish of Ballyhean and barony of Carra.

Cill Cheallair, Kilkelly, an old church situated in a village and parish of the same name, in the barony of Costello.

Cill Cinn Iubair, an old church in ruins, in the parish of Killedan and barony of Gallen.

Cill Chalmáin, Kilcolman, an old church in ruins, in a parish of the same name, in the barony of Clanmorris.

Cill Chomáin, Kilcommon, an old church in ruins in the north of Erris, giving name to the parish of Kilcommon.

Cill Chomáin, Kilcommon, an old church in ruins, in a parish of the same name, in the barony of Kilmaine.

Cill Conoub, Kilconduff, an old church in ruins, in a parish of the same name, in the barony of Gallen.

Cillín Chopmac, i. e. the little church of St. Cormac, the name of an ancient graveyard in which formerly stood a small church, situated in the parish of Kilbelfad, in the south-east of the barony of Tirawley.

Cill Chopnán, Kilcurnan, an old church in ruins, in the parish of Crossboyne and barony of Clanmorris.

Cill Chuimín, Kilcummin, an ancient

church, in a parish of the same name, in the north-east of the barony of Tirawley.

Cill Cuimne, Kilkevna, an old church in ruins, in the parish of Killedan and barony of Gallen.

Cill na Chamóig, Kildacommoge, an ancient church in ruins, in a parish of the same name, in the barony of Carra.

Cill Damnait, i. e. the church of St. Dymphna, or Devnet, an old church in the southern portion of the island of Achil.

Cill Diarmata, i. e. St. Diarmaid's church, in the north-west of the parish of Attymas, district of Coolcarney, and barony of Gallen.

Cill Dubhóin, now Killadoon, a parish in the barony of Tirerrill, in the county of Sligo.

Cill Ena, a small church in ruins near the confluence of the Abainn mór and Muinín rivers, in the parish of Kilcommon, barony of Erris.

Cill Eapbuig óróin, i. e. the church of Bishop Bronus, now Killaspugbrone, near Knocknarea, in the south-west of the barony of Carbury.

Cill Fhainle, now Killanley, in Tireragh.—See p. 252, Note ^b.

Cill Fionnainne, i. e. St. Fintan's church, now destroyed; it was situated on the margin of the strand, in the south of the parish of Kilcommon, in the barony of Erris.

Cill Fhopclann, the name of an ancient church in the woody district of Coill Fochloth, near Killala, in the barony of

Tirawley.—See pp. 465, 467.

Cill Glar, Kilglass, an old church in a parish of the same name, in Tireragh.

Cill Iapnach, i. e. the church of St. Lassera, now Killasser, an old church in ruins, in a parish of the same name, in the barony of Gallen.

Cill Iacóin, Killedan, an ancient church in ruins, in a parish of the same name, and barony of Gallen.

Cill Meaboin, i. e. the middle church, now Kilmaine, a village and parish in the barony of Kilmaine.

Cill Mhic Iairpe, an old church in ruins, in the parish of Kilmaglasser, in the barony of Burrishoole.

Cill Mhic Tpeana, now Kilnactranny, a parish in the south of the barony of Tirerrill, in the county of Sligo.

Cill Mhídeán, now Kilvine, a parish forming the extreme southern portion of the barony of Clanmorris.

Cill Mioóna, i. e. St. Meena's church, an old church in ruins, situated in a parish of the same name, in the barony of Burrishoole.

Cill Moí, i. e. the church of St. Mobhi, now Kilmovee, an old church in ruins, in a parish of the same name, in the barony of Costello.

Cill Molápa, the name of an old church and parish in the barony of Kilmaine.

Cill mór, Kilmore, an old grave yard, formerly covered with sands, in which stood the original church of Kilmore, barony of Erris.

Cill mór Muarbe, Kilmore-Moy, an an-

- cient church near Ballina, in the barony of Tirawley.
- Cillín ouſ, an ancient church yard, in which stood a small church, in the townland of Killeenduff in the parish of Easkey, in Tireragh.
- Cillín na n-ſarſ, now Killeen, in the parish of Robeen, in the barony of Kilmaine, but anciently in the territory of Ceara or Carra.
- Cill na ngarſán, now Kilgarvan, a parish in the district of Coolcarney, barony of Gallen.
- Cill Oirſ, now Killerry, an old church, giving name to a parish in the north of the barony of Tirerrill, in the county of Sligo.
- Cill Phian, now Kilfian, the name of the original church of the parish of Kilfian, in the barony of Tirawley.
- Cill Reo, an ancient church in the parish of Killala, and barony of Tirawley.—See p. 470.
- Cill Ronán, i. e., St. Ronan's Church, Kilronan, a church in ruins, in the parish of Aghamore, and barony of Costello.
- Cill ruir, now Kilross, a parish in the barony of Tirerrill, in the county of Sligo.
- Cill Sealbhag, i. e., the church of St. Sealbhach, now Kilshalvy, a parish in the barony of Corran, in the county of Sligo.
- Cill Seapſnán, Anglice Kilaheshnan, an old church in ruins, in a townland of the same name, in the parish of Killasser, and barony of Gallen.
- Clann Cuain, a territory comprising the northern part of the barony of Carra.—See p. 205, Note ¹.
- Clara, Clare Island, situated in Clew Bay, lying due west of Westport.
- Clocán, the name of a castle which stood in the townland of Cloghans, in the parish of Kilmainemore, in the barony of Kilmaine.
- Cloc ſara, i. e., the Long Stone, a remarkable stone near the Neale, on the boundary of the parishes of Kilmolara, Ballinchalla and Cong, in the barony of Kilmaine.
- Cluan caſa, now Battlefield, in the south of the barony of Corran, in the county of Sligo.
- Cluan Eocaille, now Cloonoghill, an old church giving name to a parish in the west of the barony of Corran, county of Sligo.—See p. 36, Note ⁴.
- Cluan mſ, Cloonmore, an old church in ruins, in the parish of Crossboyne, and barony of Clanmorris.
- Cluan na g-cliabac, now Cloonagleavragh, a townland in the parish of Easkey, in Tireragh.—See p. 258, Note ⁶.
- Cnoc (An cnoc), Knock, a townland containing the ruins of a church, in a parish of the same name, in the barony of Costello.
- Cnocán an coill, i. e., hillock of the hazel, now Knockaunacuill, a castle situated in a townland of the same name, in the parish of Mayo, and barony of Clanmorris.

Cnoc an cailleán, i. e., hill of the castle, the name of a hill, on which formerly stood a castle, situated in the south of the parish of Kilcommon, in the barony of Erris.

Cnoc Doite, i. e. hill of the booth or tent, now Knockboha, a famous hill in the parish of Lackan, and barony of Tirawley.

Cnoc móp, Knockmore, a townland containing the ruins of an abbey, in the north of the barony of Coolavin.

Cnoc na líona, Knocknalina Castle, in the north-east of the parish of Kilmore, in the barony of Erris.

Cnoc na píag, or Cnoc na píag, i. e. the hill of executions, now Knocknarea, a remarkable hill in the parish of Killaspugbrone, in the south-west of the barony of Carbury in the county of Sligo.

Coónach, Cownagh, the ancient name of the river of Drumcliff, in the barony of Carbury and county of Sligo.

Coillte Cúighne, i. e. the woods of Leyny, a small district in the north of the barony of Leyny, verging on the great strand of Traigh Eothuille.—See pp. 115, 303, 304, 354, 355, 418.

Cofm, Keem, a townland now containing a small village in the western portion of the island of Achil.

Conga, a village containing the ruins of a large abbey, in a parish of the same name, on the boundary of the counties of Mayo and Galway.

Conmaicne Cúile Tolaó, a territory in the south of the county of Mayo, and

extending from the River Robe to the Black River at Shrule. It comprises a considerable part of the barony of Kilmaine.

Copann, now the barony of Corran, in the south of the county of Sligo.

Copacá, now Corcachs, two townlands in the parish of Templeboy in Tire-
ragh.—See p. 264, Note ^b.

Coppa Driúig, now Corradrishy, a townland in the parish of Attymas, district of Coolcarney, and barony of Gallen.

Coppóloé, Corclogh Castle, in the northern portion of the parish of Kilmore, barony of Erris.

Copp-ílaó, a mountain in the southern part of the parish of Kilcommon, in the barony of Erris.

Craoipán cille, an old church in ruins, in the North-west of Ros Ceide, now the Rosses, in the barony of Carbury, a short distance to the North-west of the town of Sligo.

Croí Doicín, St. Baithen's cross, now Crossboyne parish, in the south of the barony of Clanmorris.

Croí Phádpúig, St. Patrick's cross, an ancient grave yard near Killala, in Tirawley.—See pp. 464, 465.

Croí Uí Mhaolríona, i. e. O'Molina's cross, now Crossmolina, a small town in a parish of the same name, in the barony of Tirawley.

Cruacán Gaileang, a district in the parish of Killasser, in the barony of Gallen.

Cruacán Oiglé, or Cruacán Aiglé, the

ancient name of the celebrated mountain of Croaghpatrick, or St. Patrick's *Reek* [rick], in the barony of Murrisk, or Upper Umhall, in the south-west of the county of Mayo.

Cuan an íóio ouib, i. e. Blacksod Bay.

Cuan Inbhr mór, Broad Haven.

Cuan Móo, now Clew Bay.

Cúil Dheinnne, a place in the barony of Carbury, near the foot of Binbulbin, where St. Columbkille fought a battle, for which he was sent on a pilgrimage to Scotland by St. Molaise of Inishmurry.

Cúil Cille Dhicín, now Carrowbrickeen, a townland in the parish of Dromard, in Tireragh.—See p. 271, Note °.

Cúil Ceapnaóga, anglicè Coolcarney, a district now forming the northern part of the barony of Gallen, and including the parishes of Kilgarvan and Attymas, but anciently a part of the principality of Hy-Fiachrach, and the patrimonial inheritance of the Clandonogh O'Dowd.—See pp. 166, 167, 246, 247, 419.

Cúil cnáma, a district in the east of Tireragh, for the extent of which see p. 265, Note ¹, and p. 424, Note ¹.

Cúil ioppa, a district in the south-west of the barony of Carbury, comprising, according to the deed of partition of the Sligo estate, the parishes of Kilmacnawen and Killaspugbrone.

Cúil maóile, now Colooney, a small town in the barony of Tirerrill, county of Sligo.

Cúil na g-caireal, i. e. *angulum muro-*

rum, now corruptly Cloonagashel, an old castle in ruins, in the parish of Ballinrobe and barony of Kilmaine.

Cúil O b-Finn, now Coolavin, a barony in the south of the county of Sligo.

O.

Oaim-inir, i. e. Ox-island, one of the islands in Clew Bay.

Oungean mór, i. e. the great fastness, or fortress, a large fort near Ballindine, in the parish of Crossboyne and barony of Clanmorris.

Oaoil, anglicè Deel, a river flowing through the parish of Crossmolina, in Tirawley.

Opaigneac, now Drynaghans, in the parish of Kilglass, in Tireragh.

Opuim éliaó, now Drumcliff, a celebrated village, containing the ruins of a round tower, in the barony of Carbury and county of Sligo.

Opuim Coluim, i. e. Columb's hill, now Drumcolumb, a parish in the barony of Tirerrill, in the county of Sligo.

Opuim paice, now Drumrat, a parish in the barony of Corran, county of Sligo.

Opuim scuaba, or Opuim rguabach, now Drumscoaba, a townland in the parish of Attymas, district of Coolcarney, and barony of Gallen.

Oub, i. e. the Black River, a small river at the northern extremity of the barony of Carbury, in the county of Sligo.

Oub ác, i. e. Blackford, now Doonah, a castle in ruins, in the south of the parish of Kilcommon, in the barony of Erris.

Dubglas, i. e. the black stream, now Douglas, near Ballynakill, in the barony of Tirerrill, in the county of Sligo.

Dubloic, i. e. Black Lake, a beautiful lake in the south of the parish of Kilgeever, in the barony of Murrisk.

Dub-oileán, i. e. Black Island, an island off the coast of Erris, lying southwards of Inishkea.

Dúic Enna, Doohana, a castle in ruins in the parish of Kildacommoge, in the barony of Gallen.

Dúma Chaocháin, now Dunkeeghan, in the north of Erris.

Dúma Chinn aille, i. e. the sand-bank at the head of the cliff, a remarkable sand-bank, near the little village of Keel, in the island of Achil.

Dúmac mór, Doaghmore, remarkable sand hills in the west of the barony of Murrisk, or Upper Umnall.

Dúmn, Dooneen, a fort on the east side of the River Moy, near its mouth, in Tireragh.

Dún, the name of a fort on Inishturk, q. v.

Dún aille, now Dunally, a short distance to the north of the town of Sligo, in the barony of Carbury.

Dún Décin, now Dunbeakin, a townland in the parish of Kilmacshalgan, in Tireragh.—See pp. 260, 261, Note °.

Dún Sinnealla, Doonvinnalla, on the northern coast of Erris.

Dún Capcáin, Dooncarton, a fort in the north of the parish of Kilcommon in Erris.

Dun Cinnepeacáin, now Donaghintraine,
IRISH ARCH. SOC. 12.

a townland in the parish of Templeboy, in Tireragh.—See p. 283, Note 7.

Dún Deópuric, a remarkable lofty rock in the sea, off Downpatrick head, in the parish of Kilbride and barony of Tirrawley. On this rock stood an ancient fortress which has not yet been explored.

Dún Doimnainn, or **Dún Doimnaill**, an ancient fort situated on a small round hill in the valley of Gleann an Chairil, or Glencastle, in the parish of Kilcommon and barony of Erris.

Dún Fíne, now Doonfeeny.—See p. 6, Note 2.

Dún Floinn, now Dunflin, a townland in the parish of Skreen, in Tireragh.—See p. 264, Note 1.

Dún rapamn, Doonierin, an earthen fort near the margin of the strand, in Ros Ceide, in the barony of Carbury and county of Sligo.

Dún Mugóro, an old castle built by Mac Philbin, situated in the barony of Murrisk, about four miles due east of Westport.

Dún na m-bó, Dunnamoe, an ancient fortress, built of stones without cement, in the northern portion of the parish of Kilmore, in the barony of Erris.

Dún na móna, Doonamona, an old castle built by the O'Kellys, situated near the boundary of the parishes of Rosslee and Drum, in the barony of Carra.

Dún Néill, now Dunneill, a townland in the parish of Kilmacshalgan, in Tireragh.—See p. 262, Note 1.

Dún na b-Fiaíacá, or **Dún Ua b-Fiaíacá**,

a celebrated townland in the parish of Aughanagh, in the south of the barony of Tirerrill, in the county of Sligo.

Dún Uí Choibéir, now Doonycoy, a townland in the parish of Templeboy, in Tireragh.—See p. 263, Note ^a.

Dún Ultaín, anglicè Dunulton, or Doon-alton, a townland in the parish of Templeboy, in Tireragh.—See p. 260, Note ¹.

E.

Eacánach, Aughanagh, a church built by St. Patrick on the West side of Lough Arrow, in the south of the barony of Tirerrill, in the county of Sligo.

Eacnop, now Aughris, a townland in which formerly stood an abbey, situated in the north of the parish of Templeboy, in Tireragh.

Eacuil, Achil, a celebrated island in the county of Mayo, forming the north-west portion of the barony of Burrishoole, or Lower Umhall.

Eacuil Beag, i. e. little Achil, a small island near the southern extremity of the great Achil.

Eaglaip Ruac, the ancient name of the original church of the parish of Bally-naheglis, situated near the River Moy, in the south-east of the barony of Tirawley.

Eanach Duáin, now Annagh, an island in Lough Conn.—See p. 282, Note ^v.

Eanurige, now Annies, in the north of the parish of Robeen, now in the barony of

Kilmaine, but anciently in the territory of Ceara, or Carra.

Eúneach, now Oweniny, **abann Eúniúge**, a river in Tirawley, flowing through the parishes of Doonfeeny, Kilfian, and Moygawnagh, and paying its tribute to the Owenmore, in Erris, at Beal an chomhraic.

Eileacthann, Ellistrin, a castle in ruins in the north of the parish of Kilmaine-more, in the barony of Kilmaine.

F.

Fearpat Reanna an Uagáin, the ancient name of a ford on the River Gitly, or Sligeach, near its mouth.

Fearpat Treirí, i. e. trajectus Tresia, in the parish of Killala and barony of Tirawley.—See p. 9, Note ¹.

Fepc Echra, a pagan grave, near the church of Kilmore-Moy, in the barony of Tirawley.

Fingio, now Finned, a townland in the parish of Easkey, in Tireragh.—See p. 256, Note ².

Fingio, now Finned, a townland near Drumcliff, in the barony of Carbury, county of Sligo.

Finn (**abann Finne**), a small stream in the east of Tireragh, which falls into the bay of Ballysadare at Buninna, q. v.

Fionnabair, now Finnure, a townland in the parish of Skreen, in Tireragh.—See p. 270, Note ¹.

Fionnglaip, a stream which formed the ancient boundary of the territory of Ceara.—See p. 150, Note ^f.

Fionnloch, or Fionnloch Ceara, now Lough Carra, near Ballinrobe.

Fionnloch Ioppuir, the fair, or white lake of Erris, now Carrowmore Lough, in the parish of Kilcommon, in the barony of Erris.

5.

Gaileanga, a territory in the county of Mayo, originally belonging to O'Gara and his correlatives, comprising the whole of the present barony of Gallen, except Coolcarney, which was a part of the principality of Hy-Fiachrach.

Gaoirneac, now Gweeshadan, a castle in ruins, in the parish of Drum and barony of Carra.

Garrán áro, Garranard, a castle in ruins in the parish of Moygawnagh, in the barony of Tirawley.—See p. 336.

Glasir gurt, now Glasgort, a townland in the parish of Ballintober, in the barony of Carra.—See p. 152, Note ^m.

Gleann an Charál, i. e. the glen or valley of the cashel, or stone fort, situated in the parish of Kilcommon and barony of Erris.

Gleann dá fuð, or Gleann dá búð, now Glendawoo, a townland in the parish of Attymas, district of Coolcarney, and barony of Gallen.

Gleann na Muaoib, a valley in the north of Erris.

Gleann Némchinne, a valley district, in the parish of Addergoole, in the south of the barony of Tirawley.—See p. 233, Note ^m.

Gleann Oirpeog, now Glenhest, a valley district, situated partly in the barony of Burrishoole, and partly in that of Tirawley.—See pp. 331, 332.

Gleóir, a river in Tireragh, discharging itself into Killala Bay at Pollacheeny.—See p. 109, Note ^e.

Gpáinreach, now Grange, a small village in the barony of Carbury, in the north of the county of Sligo.

Gpáinreach beag, now Grangebeg, a townland in the parish of Templeboy, in Tireragh.—See p. 263.

Gpáinreach mór, now Grangemore, a townland in the parish of Templeboy, in Tireragh.—See p. 263, Note ^e.

1.

Iarcanó, now the Easkey, a river in Tireragh.—See p. 255, Note ^e.

Imleac íreat.—See Gaile an cárléin.

Imleac Mopáin, now Emlaghmore, in the south-west of the barony of Tireragh.—See p. 243, Note ^v.

Inir Ámalgaoib, now Inishlee, in Lough Conn.—See p. 99.

Inir aonairg, now Inisheeny, a celebrated island in Westport Bay.

Inir áro, i. e. high island, anglicè Inishard, an island in Lough Mask, on the east side.

Inir bó finne, i. e. *insula vaccae albæ*, an island in the ocean opposite the Killary harbour.

Inir Cua, Inishcoe, in the parish of Crossmolina, in the barony of Tirawley.—See pp. 281, 282, Note ^u.

INIR Eapco, now Inishark, near Inishbofin, off the coast of Connamara.

INIR EOġAIN, i. e. the island of Eoghan Beul, King of Connaught, now Inishowen, a small island in Lough Mask, on the east side.

INIR FPAOIĠ, i. e. the heathy island, a small island near the south-east extremity of Lough Gill, in the county of Sligo.

INIR ĠEIOE, i. e. insulæ Sanctæ Geisæ, now Inishkea, an island off the coast of Erris, southwards of Inis Gluaire.

INIR ĠLUAIPE, Inishglory, a celebrated island off the coast of Erris, on which are churches dedicated to St. Brendan.

INIR MEÁDOIN, i. e. middle island, now Inishmaine, an island containing the ruins of an abbey, situated in Lough Mask, on the east side.

INIR MÓP, i. e. the great island, an island in Lough Gill, q. v.

INIR MUINEADAIĠ, anglicè Inishmurry, an island off the coast of Sligo, in the bay of Donegal, on which are the ruins of several churches dedicated to St. Molaisi.

INIR PAŪIN, now Inishraher, a celebrated island in Westport Bay.

INIR RÓÓBA, Inishrobe, a small island opposite the mouth of the River Robe, in Lough Mask.

INIR PCNEADANN, or EIPCIP AĠANN, now Inishcrone, in the parish of Kilglass and barony of Tireragh.—See p. 254, Note ^q.

INIR TUIPC, Inishturk, an island in the

ocean off the western coast of the barony of Murrisk.

INIR UH MHAOILÉLUIE, now Inishmulclohy, an island close to the land in the bay of Sligo.—See p. 275, Note ^b.

INIR MOO, Inishymoe, a general name of the islands in Clew Bay.

IOPPUR DOMHNANN, i. e. Iorrus of the Damnonii, the ancient name of the present barony of Erris, forming the north-west portion of the county of Mayo.

Ł.

ŁÁEPAC, now Laragh, a townland in the parish of Skreen, in Tireragh.—See p. 266, Note ^q.

ŁEACAN, now Lacken, or Lecan, a townland in the parish of Kilglass, in Tireragh, containing the ruins of a castle built by the Mac Fimbises.—See pp. 168, 251, 474.

ŁEACĠ ÁIP IOPPUR, i. e. the monument of the slaughter of Erris, a large cairn of stones situated near Binghamstown, in the parish of Kilmore-Erris.

ŁEACĠ NA MAOL, the ancient name of a remarkable cromlech near Ballina, in the barony of Tirawley.—See p. 34, Note ^r.

ŁEAMACH, now Lavagh, a townland in the parish of Dromard, in Tireragh.—See p. 269, Note ^d.

ŁEITINIR, now Lehinch, a castle in ruins, in the parish of Kilcommon and barony of Kilmaine.

ŁIA NA MANACH, now Liag churchyard,

- near the old church of Kilmore-Moy, in the barony of Tirawley.
- Λιαέμυνη, now Leafoney, near Lacken, in Tireragh.
- Λιορ αν ποιλλ, now Lissadill, a well known place in the west of the barony of Carbury, in the county of Sligo.
- Λιορ να πεαμωρ (incorrectly engraved λιορ να πεαμωρ), now Lisnarawer, a townland in the parish of Dromard, in Tireragh.—See p. 272, Note 1.
- Λοacán Cúile cnámha, a small pool in the district of Cuil Cnamha, in the parish of Dromard, in Tireragh.
- Λοχ Αρβαχ, Lough Arrow, a large lake in the south of the barony of Tirerrill, county of Sligo.
- Λοχ bó fínne, a small lake on the island of Inishbofin, q. v.
- Λοc Coppα, Loughcorra, a small lake, situated to the south of the mountain of Croaghpatrick, in the parish of Oughaval, and barony of Murrisk.
- Λοc Cuillinn, Lough Cullin, a lake in the south of the barony of Tirawley, into which Lough Conn discharges its superabundant waters.
- Λοc Oeula, a small lake in the townland of Ballyloughdalla, in the parish of Ballysokeery, and barony of Tirawley.—See p. 281, Note 1.
- Λοc Oeapγάν, anglicè Lough Dargan, a small lake in the townland of Castle-dargan, in the parish of Kilross, barony of Tirerrill, and county of Sligo.
- Λοχ Γίλε, now Lough Gill, near the town of Sligo.
- Λοχ Ιαρκανò, anglicè Lough Easkey, a remarkable lake on the confines of Tireragh and Leyny.—See p. 255, Note 1.
- Λοχ Μεαρχα, Lough Mask, a large and beautiful lake in the south of the county of Mayo, and adjoining that of Galway.
- Λοc να n-áinneαò, i. e. lake of the sloes, now Mannin lake, in the parish of Aghamore, and barony of Costello.
- Λοχ να cille, i. e. lake of the church, a small lake on the boundary of the parishes of Shrute and Moorgagagh in the barony of Kilmaine.
- Λοc Ναοίμ Χαcαpαγ, i. e. St. Cathasach's lake, a small lake dedicated to this saint, in the north-west of the barony of Murrisk, or Upper Umhall.
- Λοχ Οιpβεα, now Lough Corrib, which forms the southern boundary of the county of Mayo, from the village of Cong to the Black River.
- Λοχ Tαlt, now Lough Talt, a remarkable lake in the south-west of Leyny, and close to the boundary of that of Gallen.
- Λοc Tecer, now Lough Gara, on the frontiers of the counties of Mayo, Sligo, and Roscommon.
- Λongpore Uí DhúBoa, now Longford, in the parish of Dromard, in Tireragh.—See p. 123, Note 7.
- Λυβγονcán, now Luffertaun, in the parish of Ballintober, in the barony of Carra.—See p. 153, Note 1.
- Λυigne, now Leyny, a barony in the county of Sligo, formerly the patrimonial inheritance of the family of O'Hara.

m.

Μαξ Καρέα, a castle in ruins, in the parish of Shrute, in the barony of Kilmaine.

Μαξ Εαβα, now Machaire Eabha, Anglicè Magherow, a level plain lying between Binbulbin and the sea, in the barony of Carbury, in the north of the county of Sligo.

Μαξ Εννα, Moyhenna, a castle in ruins near Turlough, in the barony of Carra.

Μαξ Γαμναχ, Moygawnagh, the site of an old churchyard, in a parish of the same name, in the barony of Tirawley.—See p. 231.

Μαξ Λυινγε, now Lung, near Ballaghadereen, in the barony of Costello.

Μαξ Οβαρη, Moyour, a castle built by the family of Burk, in the parish of Kilmeena, and barony of Burrishoole.

Μαξ Τυπεαδ Conga, Moyturey, a battle field containing extremely ancient monuments, situated in the parish of Cong, in the barony of Kilmaine.

Μαξ Τυπεαδ Τυαδ, i. e. the northern Magh Tuireadh, now Moterra, a townland in the parish of Kilmastranny, in the barony of Tirerrill, where a great battle was fought between the Fomorians and Firbolgs, in the primitive ages of Irish history, and where remarkable monuments of a battle are still visible.

Μαξ Υι Γηαδρα, i. e. O'Gara's plain, now Moyogara, a castle in ruins, situated near the margin of Loch Techet, or Lough Gara, in the barony of Coolavin.

Μαξ Εο, i. e. the plain of the yews, or plain of the oaks, as Colgan renders it, now Mayo, a village in ruins, famous for its monastery, situated in the barony of Clanmorris.

Μαξην, now Moyne, famous for its beautiful abbey, in the parish of Killala and barony of Tirawley.—See p. 328.

Μαξην, Moyne, a townland containing the ruins of a church and castle, situated in the south of the parish of Shrute, in the barony of Kilmaine.

Μαννιρεν an uplari, now Urlare abbey, in the parish of Kilmovee, and barony of Costello.

Μαννιρεν na Cpoipe, Cross Abbey, a small abbey church in ruins, near Binghamstown, in the parish of Kilmore, barony of Erris.

Μαννιρεν na rpaue, Strade Abbey, in the parish of Templemore and barony of Gallen.

Μάιτεος, a place on the boundary of ancient Ceara, situated near the church of Aghagower, in the barony of Murrisk.

Μαοιλπέδ, a lofty mountain in the south of the barony of Murrisk or Upper Umhall.

Μιλιuc, Meelick, an ancient church, near which stands a round tower, in a parish of the same name, in the barony of Gallen.

Μιλιuc an Λοα, i. e. Meelick of the lake, a townland in the parish of Killala, in the barony of Tirawley.

Μιορσάν Μείοδε, a remarkable cairn of

stones on the summit of Knocknarea, to the west of the town of Sligo.—See p. 441.

Muc òub, now Muckduff, a townland in the parish of Castleconor on the Moy, in Tireragh.—See p. 250, Note ^w.

Muicinn, i. e. Hog Island, an island in Lough Conn, in Tirawley.

Muincinn, Munhin, a small river flowing out of Carrowmore Lough, and paying its tribute to the Abhainn iníor, or great river, in the parish of Kilcommon, barony of Erris.

Mune, now Carrowmoney, in the parish of Ballyovey, and barony of Carra.—See p. 190, Note ⁱ.

Mune Chonalláin, now anglicised Bunnyconnellan, but Moneyconillane in a deed of sale, dated 1705. It is the seat of the O'Dowda, and is situated in the parish of Kilgarvan, and barony of Gallen, but was formerly in the territory of Hy-Fiachrach, and a part of the patrimonial inheritance of the Clann Donogh O'Dowd.—See p. 420, Note ^u.

Muiric, a small plain lying between the mountain of Croaghpatrick and Westport Bay. It is also the name of a small abbey situated in the same plain, on the margin of the bay, from which the barony of Murrisk was named.

Muiric, a district in Tireragh, for the extent of which, see p. 257, Note ^b.

Mullaó Ruaoá, now Knockroe, a celebrated hill near the old church of Skreen, in Tireragh.—See pp. 96, Notes ^d, ^e, and p. 416, ^j.

Múrógac, Moorgagagh, a parish in the barony of Kilmaine.

N.

Nuáchongbail, now Oughaval, an ancient church dedicated to St. Columbkille, near Croaghpatrick, in the barony of Murrisk.

Néiméinn, a mountain in the parish of Addergoole, in the south of the barony of Tirawley.—See p. 233, Note ^m.

Néiméinn dheag, i. e. little Nephin, a mountain in the south of the parish of Kilcommon, in the barony of Erris.

O.

Oileach, Ellagh, the name of a stone fort which formerly stood near Bingham's Castle, in the southern portion of the parish of Kilmore, barony of Erris.

Oileach, now Ellagh, a townland in the parish of Kilgarvan, district of Coolcarney, and barony of Gallen.—See p. 421, Note ^z.

Oileán na caírac, i. e. the the island of the caher or stone fort, now Caher Island, off the coast of the barony of Murrisk.

Oileán na Glaise, Illannaglashy, an island in the south-east of Lough Conn, in Tirawley.

Oipeam, now Errew, a townland in the parish of Crossmolina, on Lough Conn, in the barony of Tirawley.—See p. 239, Note ⁱ.

Oipeam, Errew, a townland in the parish of Ballyhean, in the barony of Carra.—See p. 196, Note ^f.

p.

Poll a caonairg, Pollacheeny, the name of a place where formerly stood a castle, near Rathlee, on the margin of the bay of Killala in Tireragh. The River Gleoir falls into the bay at this place.

Port na h-aille, now Portnahallia, in the parish of Kilbride, in the north of the barony of Tirawley.

R.

Raenín, Rahens, a townland in the parish of Islandeady in the barony of Carra.—See p. 150, Note ^a.

Ráth, Rath, a castle in ruins, in the parish of Aghamore and barony of Costello.

Raé dhonouib, now Rafran, a townland containing an abbey in ruins, in the parish of Killala, and barony of Tirawley.—See p. 224, Note ^b.

Raé Laoig, now Rathlee, in the parish of Easkey, in Tireragh.—See p. 251, Note ^b.

Raé Maolcaé, Rathmulcah, a remarkable fort containing subterraneous chambers, situated near Castleconor, on the west side of the River Moy.

Raé Maol ouib, now Rathmaol, in the parish of Easkey, in Tireragh.—See p. 259, Note ^b.

Raé maol, now Rathmoyle, a townland containing an ancient fort in that part of the parish of Kilmore-Moy lying on the east side of the River Moy.

Raé Muirceagán, an earthen fort near

Ballycastle, in the north of the barony of Tirawley.

Raé Raodáin, now Rathreedaun, an earthen fort and townland in the parish of Kilgarvan, in the district of Coolcarney and barony of Gallen.

Raé piabaic, now Rathreagh church, in a parish of the same name in the barony of Tirawley.

Raé Rígbáino, the ancient name of a fort, near the old church of Killaspugbrone, in the south-west of the barony of Carbury, in the county of Sligo.

Reaclann, Raghlin, the name of the southern point of Machaire Eabba, in the west of the barony of Carbury, in the county of Sligo.

Róobca, the River Robe, which flows through the baronies of Clanmorris and Kilmaine, in the county of Mayo.

Róibín, now Robeen church, in the parish of the same name, which is now in the barony of Kilmaine, though it anciently belonged to the territory of Ceara or Carra.

Rop Ceive, a point of land lying between the river of Sligo and that of Drumcliff, in the barony of Carbury. It is separated from the plain of Machaire Eabha by the creek and river of Drumcliff.

Rop Ceipse, or Rop Seipse, now Rosserk, in the parish of Ballysokeery, in the barony of Tirawley.—See p. 51, Note ¹.

Rop Laoig, now Roslee, a townland in the parish of Easkey, in Tireragh.—See p. 258, Note ^d.

Rop Laoġ, now Rosslee, a parish in the barony of Carra.—See p. 198, Note ^a.

Rop mac Caŕni, now Ross point, in the parish of Killala, and barony of Tirrawley. See p. 469, Note ^a.

Ruirín, now Rusheen, a townland lying between Clogher and Lisrobert, in the barony of Carra.

Rúrgaċ, now Roosky, a townland in the parish of Attymas, district of Coolcarney, and barony of Gallen. See p. 421.

S.

Scop mór, now Scurmore, on the east side of the Moy, near the island of Bartragh, in Tireragh.

Scpín, now Skreen, a celebrated church dedicated to St. Adamnan, in a parish of the same name, in Tireragh.—See p. 267, Note ^t.

Seanċuac, Shancoagh, an ancient church in the barony of Tirerrill, situated to the west of the mountain called Braidshliabh.

Sfó Muirbġe, an island in Clew Bay, lying due west of the abbey of Burrishoole.

Sġin Chiapáin, now Baile an t-Sigheain, in the parish of Ballinrobe and barony of Kilmaine.

Siúip (an t-Siúip), the ancient name of the Castlebar river, in the barony of Carra.—See p. 205, Note ^a.

Sliaċ Alp, Slieve Alp, a mountain in the southern part of the parish of Kilcommon, in the barony of Erris.

Sliaċ Cápn, Slieve Carna, a mountain in

the parish of Killedan, in the south of the barony of Gallen.

Sliaċ dá én, now Slieve Daën, a mountain in the north of the barony of Tirerrill, in the county of Sligo.

Sliaċ Ğam, anglicè Slieve Gamph, a chain of mountains in the county of Sligo, separating the barony of Leyny from that of Tireragh.

Sliaċ Ğuġa, a territory anciently belonging to O'Gara, comprising that part of the barony of Costello which belongs to the diocese of Achonry, namely, the parishes of Kilkelly, Kilmovee, Killeagh, Kilcolman, and Castlemore-Costello.

Sliaċ mór, i. e. the great mountain, now Slievemore, in the north of the island of Achil.

Smotán, now Smuttanagh, a townland in the parish of Manulla, barony of Carra.

Spútair, now Shrule, a famous village, containing the ruins of a castle, situated on the boundary of the counties of Mayo and Galway.

T.

Tamnac, an old church and parish, in the barony of Tirerrill, in the county of Sligo.

Teac Chaoin, Tagheen, a church in ruins, in a parish of the same name, in the barony of Clanmorris.

Teac Teampla, now Templehouse, in the barony of Leyny.

Teampull Chaillín, i. e. St. Caillin's church, an old church in ruins, in the southern extremity of the parish of

Kilmastranny, in the barony of Tirerrill, and county of Sligo.

Teampull Cholmáin, i. e. St. Colman's church, an ancient church on the island of Inishbofin, q. v.

Teampull Cholmáin, i. e. St. Colman's church, an old church in ruins, situated a short distance to the south of Slievemore, in the island of Achil.

Teampull Choluum Cille, i. e. St. Columbkille's church, an old church in ruins, situated on the island of Inishkea, off the coast of Erris.

Teampull Choluum Cille, an ancient church on Inishturk, q. v.

Teapmonn Dairbhile, i. e. the termon, or sanctuary of St. Dairbhile, a curious old church in ruins, in the southern extremity of the parish of Kilmore, barony of Erris.

Teampull Enda, i. e. the church of St. Enda, a very ancient church, situated in the south of the parish of Kilcommon, in the barony of Erris.

Teampull Marcáin, i. e. St. Marcan's church, the site of an old church in the south-west extremity of the parish and barony of Burrishoole.

Teampull Pháoruis, an ancient church dedicated to St. Patrick, situated on Caher island, off the coast of the barony of Murrisk.

Teapmonn Cappac, Termoncarragh, an old church in ruins, in the northern portion of the parish of Kilmore, barony of Erris.

Tír Amalgaid, now the barony of Ti-

rawley, forming the north-east part of the county of Mayo.

Tír an áir, or **Tír Náir**, a district in the parish and barony of Burrishoole, lying westwards of Lough Feeagh.

Tír Fhiachpach Muaidé, now Tireragh, a famous territory in the county of Sligo, to which originally belonged the district of Coolcarney, now a part of the barony of Gallen.

Tír Oiliolla, now Tirerrill, a barony in the south-east of the county of Sligo.

Tobar Aépacta, i. e. St. Athracha's well, a holy well in the parish of Kilaraght, in the barony of Coolavin.—See p. 41, Note ^q.

Tobar Chomáin, St. Coman's well, a holy well near the old church of Kilcommon, in the north of the barony of Erris.

Tobar Zugna, Toberloona, in the parish of Robeen, now in the barony of Kilmaine, but anciently in the territory of Ceara, or Carra.—See p. 200, Note ^w.

Tobar Pháoruis, i. e. St. Patrick's well, Toberpatrick, an old church, near which is a holy well of the same name, in the parish of Annagh and barony of Costello.

Tóin pé gó, now Tonrego, in the parish of Dromard, in Tireragh.—See p. 273, Note ^u.

Tócan Pháoruis, i. e. St. Patrick's causeway, the name of an ancient road, still traceable, in many places, from the abbey of Ballintober, in the barony of Carra, to Croaghpatrick, in the barony of Murrisk, or Upper Umhall.

Ṭpáig Capáin, a strand on the east side of Broadhaven, in the parish of Kilcommon and barony of Erris.

Ṭpáig ceall, now Lackan Strand, in the parish of Lackan, in Tirawley.

Ṭpáig Eochnile, now Trawohelly, a famous strand near Tonregu, on the east boundary of the barony of Tireragh.

Ṭuam óa Boóap, now Toomore, in the barony of Gallen.—See p. 242, Note °.

Ṭuam óa Boóap, now Toomour, an old church in ruins, in the parish of Kilturra, in the northern extremity of the barony of Costello, and adjoining the county of Sligo. This name has been incorrectly engraved Ṭuam óa Boó.

Ṭuam óa Boóap, now Toomour, a parish in the barony of Corran, in the county of Sligo.—See p. 242, Note °.

Ṭuapín, now Turin, a castle in ruins, in the parish of Kilmainemore, in the barony of Kilmaine.

Ṭuath Aiteacáta, now Touaghty, a parish in the barony of Carra.—See p. 157, Note °.

Ṭuat Maige Fionnalba, now Manulla, a parish in the barony of Carra.—See pp. 192, 193, Note °.

Ṭupán, Turan, the name of an old castle,

now nearly destroyed, in the southern portion of the parish of Kilmore, barony of Erris.

Ṭuplac, Turlough, a parish containing the ruins of an ancient church and round tower, in the barony of Carra.

U.

Uí Eoach, a tribe and territory in the east of the barony of Tirawley.—See pp. 226, 227.

Uí Mac Caoáin, a district in the north of Erris.

Umhall lochepach, i.e. Lower Umhall, the ancient name of the barony of Burris-hoole, in the west of the county of Mayo.

Umhall Uachepach, i.e. the Upper Umhall, the ancient name of the barony of Murrisk, in the south-west of the county of Mayo. Both these territories are called the OWLES by English writers, and sometimes incorrectly latinized *Pomum*, as in the State Papers, "O'Maley *De Pomo*," which is intended to denote O'Malley of Umhall. This error originated in the resemblance of *Umhall*, the name of this territory, to *Ubbhall*, an apple!

GENERAL INDEX.

	<i>Page.</i>		<i>Page.</i>
A.		Arann, in Scotland,	352
A Bhainn na mallachtan,	151	Ardachadh, in Tirawley,	11
Achadh Fobhair, now Aghagower, 150,	151	———, O'Maoilruaidh of, 165, 232, 233	
Achadh gabhair, <i>recte</i> Achadh fobhair, <i>q. v.</i>		Ard an fhenneadh,	33
Achill, island of,	401	Ard Carna, O'Sgingin originally seated at, 77	
Adam Cusack, slew Taithleach Muaidhe		———, situation of,	76, 77
O'Dubhda,	115	Ardgabhair, O'h-Arain of,	167
Adamnan, Abbot of Iona, his account of		Ard Maoldubhain, in O'Shaughnessy's	
the inauguration of Aidan, King of		country,	377
Scotland, by St. Columbkille,	425	Ard na maol monument, situation of, 34, 35	
———, his reference to the River Moda, 410		Ard na n-glas,	173, 270, 271
———, the patron saint of Skreen, 266, 267		———, seat of Edmond O'Dubh-	
Aenach,	200, 201	da,	306, 307
———, a regal seat in Ceara,	204, 205	Ardnarea abbey, when built,	359
Aengus, son of Nadfraoch, K. M.	5	———, castle of, taken by the sons of	
Aghagower, Vallancey's visionary deri-		Conor O'Dowd,	360
vation of,	151	Ard na riagh, derivation of the name, 34, 416	
Aidhne, pronounced Ina, territory, extent of, 52		———, castle of, built by the	
———, ancient tribes of,	53	English,	123, 125
Ail an druadh,	465	———, O'Morain of,	167
Alt Fharannain,	171, 258, 259	———, the seat of Maghnus, son	
Alps, Dathi the last Pagan monarch of Ire-		of Tadhg Buidhe O'Dubhda,	307
land killed at, by a flash of lightning, 21, 311		Ard O'n-Aodha, in Caille Conaill, 167, 224,	
Aonach, one of the three chief seats in		225	
Ceara,	155	Ard O'g-Ceallaigh,	171, 264, 265
Aonach Locha Gile,	472	Ardrain,	399
Ara,	288, 289	Ath Cliath Duibhlinne, now Dublin,	127
		Ath Cliath Muirge,	171

	<i>Page.</i>
Ath Cunga, situation of, . . .	242, 243
Ath Dalaarg, monastery of, . . .	400
Ath Echtra,	468
Athenry, battle of,	356, 357, 358
———, baron of,	358
Ath Fen,	100, 101
Ath na lub, now Newbrook, . . .	198, 199
Athrachta, St., of Killaraght, . . .	41
Ath seisidh, in Ceara,	198, 199
Ath Talmaide,	19
Anghris. <i>See</i> Eachros.	

B.

Bac, cantred of, divided in two parts, 11, 165	232, 233
Bacs, the two, the Lower Mac William	
De Burgo's tributes from,	456
———, given to Sir Maigiu Bar-	
rett,	333
Baile, meaning of the word,	210
Baile an bhealaigh,	194
Baile an chaislen, situation of, . . .	123
Beile an Chriochain bhuidhe,	155
Baile an ghleanna, in Dun Fine, . . .	220, 221
Baile an ghleanna,	165
Baile an Riagain,	193
Baile an Regles,	157
Baile an smotain,	155
Baile an Tobair,	ib.
Baile Cagail, in Ceara,	ib.
Baile Cairthi in chuile,	420
Baile Carnan tornaidhe,	155
Baile Cille Buainne,	ib.
Baile crannain,	195
Baile Craoibhe, <i>alias</i> Baile an Tobair, . .	155
Baile Lis aiche,	157
Baile Mec Conletreach, in Dun Fine, . .	165, 220, 221
Baile na Brothlaighi, in Coolcarney, . .	421

	<i>Page.</i>
Baile na craibhi, or Baile na craoibhe, . .	191
Baile na Grealcha,	154
Baile na leacan, a part of the territory	
of Caille Conaill,	167
Baile na leargan moire,	155
Baile Riagain,	ib.
Baile Tobair Padruig, situation of, . . .	159
Baile Ui Bhanain, in Partry,	153, 189
Baile Ui Choitil,	167, 248, 249
———, the seat of Domhnall	
O'Dubhda,	309
Baile Ui Dhiscein,	171
Baile Ui Eineachain, or Baile Ui Ei-	
meachain,	165, 234, 235
Baile Ui Mhochaine, 122, 123, 167, 248, 249	
Baile Ui Ruairc,	155
Balla, termon of,	157, 197
Ballina, ancient Irish form of the name, 424	
Ballybetaghs, ancient divisions of land so	
called, notices of, by the Rev. John	
Keogh,	453, 454
Ballycrooy, in Mayo, O'Clerys and other	
families removed to, with Roger	
O'Donnell,	396
Ballymoghany. <i>See</i> Baile Ui Mhochaine.	
Ballysadare,	355
Barretts of Tirawley of Welsh descent, 325	
——— subdue the Lynotts, 337	
Barretts, compact between the family of,	
and the Lower Mac William De Burgo, 460	
Barrett, Captain Dominic, descent of, . .	122
Barrott, Robert,	335
Barrotts of Munster, of Welsh descent, . .	325
Barry seated in Connaught at an early	
period,	161
Bawnlahan, seat of General Richard	
O'Donovan,	361
Beal atha an fheadha, now Ballina, . . .	424
Beal Atha na muice,	173
Beal Easa,	423

	Page.		Page.
Bearna baoghail, meaning of,	211	Buaille Phadruic,	469
Bearna Domhnail, in Magh Eleog,	113	Buill river,	286, 287
Beartrach, O'Floinn of,	167, 250, 251	Bun Fede,	173
Beinn Gulban,	276, 277	Bun Finne,	175, 284, 285
Bel Atha Cunga, situation of,	244, 245	———, situation of,	120
Bel Atha Tailtigh,	355, 418	———, O'Dowds of,	121
Bel easa, or Beal easa, now Foxford, 246, 247		Bunnyconnellan, the seat of the O'Dowda, 362,	
Bel na lece,	155		420
Beo Aodh, St. of Roscam,	344	Bunreamhar, situation of,	151
Bertlaci tribe,	468	Burke, Remond, his deposition in 1458,	
Beul atha na g-carr, one of the bounda-		in favour of Hugh O'Dowde of Sta-	
ries of Ros laogh,	157	linge, in Meath,	124
Beul atha na lub, one of the ancient		Burke, Teaboid Maol,	339
boundaries of Ros laogh,	ib.	Burkes, their first settlement in Tirawley, 337	
Beul atha na n-idheadh,	167		
Beul atha na sesidh, in Ceara,	159		
Bodaighe, battle of,	19		
Boirinn, in Thomond,	33		
Book of Lecan, when compiled,	359		
Borrach,	173, 262, 260, 424		
———, situation of,	265		
Borumean tribute,	32		
Bourke, Lieut.-Col. William, the nephew			
of Sir Roger II. O'Shaughnessy,	381		
Boyle, pilgrimage to the abbey of,	353		
Braenros, or Braonros,	196, 197		
Braonros,	157		
Breachmhagh,	167		
———, road of,	ib.		
———, families of,	244, 245		
Breadach, half cantred of, 10, 11, 165, 228,			
	229		
———, families of,	11, 230, 231		
Breaghmhagh, plain of,	33		
Breifny O'Reilly, extent of,	73		
Brosnach river,	423		
———, course of,	247		
Brugh na Boinne, a pagan cemetery			
near the River Boyne,	303		
Brunachs, or Browns, invade Tirawley, 329			

	<i>Page.</i>
Calraighe Laithim,	276, 277
Calraighe Muighe h-Eleag, a district of Tirawley,	13
Calregia de Culechernadan,	471
Caol, now Keel Bridge, one of the bound- aries of Partraighe,	152, 153
Caol Partraighe, one of the boundaries of O'Goirmghiolla's estate in Ceara, 159, 200, 201	201
Caonraighe Aidhne, descent of tribe so called,	35
Caonraighe, now Kenry, in the county of Limerick,	53
Caonraighe, battle of,	309
Carinthia, mode of inaugurating the Archduke of,	436, 437
Carns Castle in Tirawley,	337
Carn,	248, 249
Carn on Knockroe, described,	417
Carn Amhalgaidh, by whom erected, 100, 101, 347	101, 347
———, O'Dowd inaugurated on,	434, 442
———, situation of,	443
Carn Conaill, battle of,	391
Carn Fearadhaigh, near Limerick,	344
Carn Fraoigh, near Tulske, the place where the Kings of Connaught were inaugurated,	426
Carn inghine Bhriain, in Tireragh, on which the O'Dubhda was sometimes inaugurated,	443
Carn, Mac Cailleachain of,	167
Carra, barony. <i>See</i> Ceara.	
Carraig, quarter of, in Coolcarney,	421
Carrignacurra, O'Leary's seat,	449
Carrun, or Carew, Sir William,	335
Carrunachs, or Carews,	335
Cashel, rock of, Kings of Munster inau- gurated on,	434

	<i>Page.</i>
Cashen river in Kerry, ancient name of,	38
Casan Ciarraighe river, situation of,	38
Castlebar, derivation of the name, 160, 161	160, 161
Castleconnor, William May of,	362
Castlequarter, or Carrowcastle,	421
Castletown, Teige Reagh O'Dowd of,	363
Castletown. <i>See</i> Baile an chaislein.	
Cathair mhor, O'Caomhain's fort,	141
Cathaoir Mor, monarch of Ireland, Ca- rews said to descend from,	335
Ceallach, St., extracts from life of, 33, 415, 416, 471, 472	33, 415, 416, 471, 472
Ceann Bugha, situation of,	313
Ceara, now Carra, extent of,	449
———, rent of,	286, 287
———, men of, their descent,	15, 185
———, seats of, the chiefs of,	204, 205
———, hereditary chiefs and freeholders of,	149, 187
———, last king of,	159
———, when castellated by the English barons,	189
———, Staunton or Mac Aveely of,	189
Ceathramha Aingilin,	420
Ceathramha an chaisil, Bawn of,	175
Ceathramha an labain,	420
Ceathramha an tighe cloiche, held by O'Clery in right of his profession,	81
Ceathramha chaol in Coolcarney,	422
Ceathramha I sgorra in Coolcarney,	422
Ceathramha Lochain, O'Dowds of,	121
Ceathramha Mhic Carra,	421
Ceathramha Mhic Coinin, situation of,	421
Ceathramha Mhic Geirbli, situation of,	422
Ceathramha na cuchtrach, one of O'Cle- ry's townlands,	81
Ceathramha na g-cloch,	420
Ceathramha riabhach, situation of,	421
Ceathra Ui Dhubhagain in Coolcarney,	421
Cenannus, now Kells,	181

	<i>Page.</i>		<i>Page.</i>
Ciarraghe Aidhne,	53	Cinel Conaill, extent of,	73
Ciarraghe Luachra, extent of,	39	Cinel Fechin, situation of,	33
Cill. <i>See</i> Kill.		Cinge, battle of,	23
Cill Achaidh duibh, where situated,	8	Cionn Saile, now Kinsale,	37
Cill Aindi,	192, 193	Clann an Fhailghe, a Welsh tribe in Ire-	
Cill Ainne,	167	land,	325
Cill Ardubh, herenachs of,	165, 222, 223	Clann Birthagro, O'Neill's Brehones,	432
Cill Athracht, situation of,	41	Clann Cele of Killala,	51
Cill Barrainn, now Kilbarron, situation		Clann Coilen, the tribe name of the Mac	
of,	79	Namaras of Thomond,	403
Cill Bealad,	165, 232, 233	Clann Conaill, descent of,	224, 225
Cill Brighde, quarter of,	420	Clann Conchobhair O'Dubhda, descent	
Cill Comain, William Fionn Barrett of,	325	of,	115
Cill Cuimin, church of, on the northern		Clann Conchobhair or O'Conors of Cru-	
boundary of Caille Conaill,	9, 45, 167	achan,	292, 293
Cill Dairbhile in Erris,	353	Clann Cuain, descent of,	161, 204, 205
Cill Domhnaigh, the property of O'Cle-		———, separated from the Hy-	
ry,	81	Fiachrach, and why,	163
Cill Ealaigh, now Killala,	51	———, place themselves under the	
Cill Fainne,	167, 252, 253	protection of Mac Dermot,	212, 213
Cill Ichtair. <i>See</i> Grainseach,	167	Clann Domhnaill Ui Dhubhda of Loch	
Cillin na m-buidhean,	159, 202, 203	Con, descent of,	113
Cillin na n-garg, causeway of,	159, 198, 199	Clann Domhnaill O'Dubhda,	350
Cill na n-garbhan, now Kilgarvan,	421	Clann Donnchada O'Dubhda, descent of,	117
Cill Mhic Duach, now Kilmacduagh,	31	Clann Donnchadha O'Dowd, compact be-	
Cill Mor Muaidhe,	234, 235	tween them and the O'Dowd,	419, 425
———, Mac Conlena of,	165	———, pedigree of,	
Cineal Airmeadhaigh, descent of,	13	as inserted in a modern hand in the	
Cineal Aodha, descent of,	55	Book of Lecan,	417, 425
Cineal Aodha na h-Echtghe,	3	Clann Heil, a Welsh tribe in Connaught,	325
Cineal Cearnaigh, descent of,	55	Clann Hosty of Welsh descent,	327
Cineal Cinngamhna, descent of,	55	Clann Misdal Ui Dhubhda,	139
Cineal Cuaiche, descent of,	55	Clann Maoilruanaidh, who,	214
Cineal Enda, descent of,	15, 63	Clann Mec n-Earca,	95
Cineal Eoghain, lord of,	315	Clann Neill Ui Dubhda,	113
Cineal Guaire,	3	———, attempted to dis-	
———, descent of,	55, 63	possess O'Caomhain,	169, 252, 253
Cineal Ianna, chief of,	63	Clann Philip, the Lower Mac William	
Cineal Seudna, descent of,	55	De Burgo's tribute from,	457
Cinel Becon in Bregia, descent of,	33	Clann Ricin, a Welsh tribe,	327

	<i>Page.</i>		<i>Page.</i>
Clann Robert, descent of,	333	Coirte, battle of,	23
Clann Taithligh Ui Dubhda,	137	Collins, John of Myross, his account of the inauguration of Donell na g-croi- ceann O'Donovan,	448
Clann Taithligh Oig Ui Dubhda, pedi- gree of,	113	Colom, battle of,	23
Clanna Temin,	107	Compacts, between the Barretts and the Lower Mac William De Burgo,	458, 459, 460, 461
Clann Toimin of Erris, a Welsh tribe,	325	Conaire, fort of,	290, 291
Clann Toimilin, a Welsh tribe,	327	Conn, race of, who,	177, 179
Claonloch, battle of,	373	Connaught, North, Aodh O'Dubhda, King of,	349
Clare, Duigan O'Clery slain at,	395	Contention of the Bards,	83
Clochan na n-dall,	337	Coolcarney. <i>See</i> Cuil Cearnadha.	
Cloigtheach Achaidh fhobhair,	151	Corann, battle of,	315
Clonmacnoise, Guaire Aidhne, King of Connaught, buried at,	315	Corcachs, families of,	171, 264, 265
Clontarf, battle of,	393	Corca Luighe, the ancient inheritance of O'Driscoll,	450
Clothra, daughter of King Eochaidh Feidhleach,	28	Clann Domhnail Ui Dubhda of Loch Con, descent of,	113
Cluain Eochaille, situation of,	36	Corca Raoidhe,	469
Cluain Lis Nellin, one of the boundaries of Ross laogh,	157	Cormac, St., blesses the Hy-Muireadh- aigh of Tirawley,	7
Cluain na g-cliabhadh,	171, 258, 259	Cornasack, in Tirawley, Teaboid Maol Burke murdered at, by the Barretts,	339
Cluain Ui Chosgraigh,	173, 268, 269	Corpar, battle of,	23
Cnaimh-fhiach, meaning of,	418	Corra Drisighi, situation of,	422
Cnamhchoill, where,	73	Cosnamhach O'Dubhda, archdeacon of Tuam,	115
Cnocan, three townlands of,	193	Craebh tinne, battle of,	352
Cnoc an Bhogha, Mac Murrrough inau- gurated at,	434	Crannan Tornaighe, one of the bounda- ries of Magh Fhiondalbha,	153
Cnoc na n-Druadh, now Knockroe,	99	Criathrach in Ceara, extent of,	159
Cnoc na Maili, where,	416	Criathrach, three townlands of,	202, 203
Cnoc na n-os,	134	Criochan,	173, 270, 271
Cnoc Ruadha, 416,—carn on, described,	417	Cromwell, Oliver, his followers in posses- sion of Tirawley in Duaid Mac Fir- bis's time,	339
Codhnach, river at Drumcliff,	143	Cros Phadruic, near the district of Caill Fochladh to the east,	463, 464, 465, 466
———, formed the boundary of O'Dowd's country,	278, 279, 301, 303		
Codhnach, fort of,	296, 297		
Coill Fochladh. <i>See</i> Fochloth Wood,			
Coillin Aodha, situation of,	250, 251		
Coillin, great rath of, by whom erected,	169		
Coillte Lughna,	418		
Coillte Luighne,	173		
Coill Ua bh-Fiachrach	3		

	<i>Page.</i>		<i>Page.</i>
Crossmolina, derivation of the name,	12, 13	Dathi, his sons,	33
Cruachan O'Cuiproin, O'Rourke inaugu- rated at,	434	—, his descendants,	17, 18, 19
Cruachan, plain of,	200, 291	—, his battles,	19
Cruachan Fele,	99	De Burgo, author of <i>Hibernia Domini-</i> <i>cana</i> , his account of the O'Shaugh-	
Cruces of Fingal,	107	nessys,	373, 384
Cuil Chearnadha, chiefs of,	167	Deel, river in Tirawley, course of,	8
—, extent of,	167, 246, 247	Derry, O'Donnell of,	298, 299
—, seven townlands of,	419, 421	Dichlethe O'Triallaigh, story of,	38, 39
Cuil Chernadan,	471	Dillon, Honourable Thomas, his letter to O'Dowda,	371
Cuil Cille Bricin,	173, 270, 271	Disert Ui Triallaigh church, situation of,	38, 39
Cuil Cnamha district, extent of,	424	Doire na n-ath,	173, 272, 273
Cuil Fabhair, where,	33	Domnach mor, situated in the wood of Fochloth in Tirawley,	463, 466
Cuil remuir, the property of O'Clery,	81	Domhnall Dual-bhuidhe, historical notice of,	97
Cuimin Fota, St., descent of,	9, 45	Dowdalls, believed by Duald Mac Firbis to be O'Dowds,	127, 128
Cul an daingin,	157	Dowds, or O'Dowds of Dublin, their de- scent,	359
Cul Daingin,	196, 197	Dower, curious reference to,	207
Cumin, abbot of Iona, his account of the inauguration of Aidan, King of Scot- land, by St. Columbkille,	425	Draighneacha, the two,	175, 282, 283
Cusack, Adam,	115, 355	Drogheda. <i>See</i> Droichead Atha.	
—, Collin,	355	Droichead Atha, now Drogheda,	124
Cusacks, invade Tirawley,	329	Drom sguabach, situation of,	422
Cutemhen, a celebrated prophet,	40	Druim an chroinn, the property of O'Clery,	81
Curr na h-eillte, near Burrishoole, Pe- regrine O'Clery lived at, and made his will there,	396	Druimni,	401
		Dubhda, anglicised Dowda, meaning of the name,	347
		Dubhros, now Duross, near Kinvara,	53
		Duddy. <i>See</i> O'Dubhda.	
		Duirtheach, meaning of the word,	52
		Dumb Book of James Mac Firbis refer- red to. (<i>See</i> Mac Firbis).	141
		Dumha Chaochain in Iorrus,	173, 280, 281
		Durlus Muaidhe in Tirawley,	416
		Durlus,	284, 285, 290, 291

D.

Dal Araidhe, King of,	311
Dambchluain, battle of,	94, 95, 344
Daoill, now the Deel River, course of,	8
—, river, Amhgaigh O'Dowd of,	129
—, river, the Clann Robert seated along the,	335
Darcy of Galway. <i>See</i> O'Dorchaidhe.	
Dathi, last pagan monarch of Ireland, death of,	21
—, meaning of the name,	20, 21

	<i>Page.</i>
Dulpin, Sir David,	335
Dun Becin, families of,	171, 260, 261
Dun Caillighe Beirre,	434
Dun Cinntréathain, one of the chief seats of the kings of Hy-Fiachrach,	175, 282, 283
Dundonnell in Erris,	97
Dun Durlais,	425
Dun Eoghain, now Dunowen, O'Heyne of,	67, 404
Dunfeeny in Tirawley,	6
Dun Fine, families of,	6, 165, 218, 219, 221, 222, 280, 281, 415
Dun Floinn,	264, 265
Dun Gaillmhe, or Galway fort, fleet of,	352
Dun Guaire,	386, 387
———, castle, O'Heyne of,	67, 404
Dun Maoilduibh,	99, 169, 258, 259
Dun mich Conchobhair,	173, 282, 283
Dun Mugdord,	401
Dun Neill, situation of,	134
———, O'Dubhda of, his pedigree,	135
———, from whom called,	171, 262
———, chief seat of O'Conbhuidhe,	175
———, the seat of Ruaidhri, son of Domhnall Cleireach O'Dubhda,	305
———, the seat of Domhnall Ballach O'Dubhda,	306
Dunowen castle, O'Heyne of,	404
Dun Ui Chobhthaigh, families of,	171, 262, 263
Dun Ulltain,	171, 260, 261
Duthchasach, meaning of,	149

E.

Eachros, O'Flannghaile of,	171
———, situation of,	138
Ealla, now Duhallow in the county of Cork,	52

	<i>Page.</i>
Eanach Dubhain, one of the chief seats of the chiefs of Hy-Fiachrach,	173, 282, 283
Earc Culbhuidhe, descendants of,	204, 205
Eas Ruaidh, abbey of,	76
Ecclesia Magna in the wood of Fochloth, now Donaghmore, near Killala,	462
Egli Mountain, or Cruachan Oigli, now Croaghpatrick,	463
Eidhneach River, where,	43
Eisceacha, church of,	415
Eisgir Abhann, now Inishcrone,	152
———, the seat of Tadhg Riabh- ach O'Dubhda,	305
Elphin, great church of,	400
Eochaidh Feidhleach, monarch of Ire- land; his daughters buried at Rath- croghan,	27, 28, 29
Eochaidh Muighmheadhoin, king of Ire- land,	3
Eoghan Aidhne, descendants of,	53, 55
Eoghan Beul, king of Connaught, his pe- digree and descendants,	33
———, by whom fostered,	53
———, his death,	471
———, his body interred in a stand- ing position,	472
Eric, meaning of the word,	4
Eric, curious one obtained by Lynott of Tirawley,	339
Ernaans of Munster,	309
Errew in Carra,	196, 197
Errew on Lough Conn,	12, 13, 239
Erris. <i>See</i> Iorrua.	

F.

Faile, battle of,	23
Fal, one of the boundaries of the territory of Partraighe,	153
Feargna, race of, who,	179
Fearsad Tresí, situation of,	9, 51, 165, 333

	<i>Page.</i>
Fearsad Tresí, one of the boundaries of	
Hy-Eathach Muaidhe, 165, 167, 226, 227	
Feart Echtra, situation of,	468
Feart Lothair, one of the three chief	
seats in Ceara,	156, 204, 205
Ferfeasa Mac Fírbis,	296, 297
Fiacra, St., some notices of,	409
Fídh Cruaichi, position of,	194, 195
Fídhmuine Ua Suanáigh, St., of Rathain,	
and his brothers,	37
Finghid,	169, 256, 257
Fíodh Cruaiche,	155
Fíonnabhair,	173, 270, 271
Fíonnchalamb, O'Fíonnagain of, . 7, 51, 165	
Fíonnghlais, one of the boundaries of	
Ceara,	149
Fírbolga, seated in Ceara,	350
Fíir Siuire, location of,	161, 163
Fíir Thire, descent of,	204, 205
———, situation of,	161, 163
Fitz-Robert, Walter,	335
Flann Mac Lonan, the poet,	70
Fleasc lamha, meaning of the term,	415
Fleming, Adam,	355
Fochloth wood, St. Patrick's vision con-	
cerning people of,	462, 463, 466
———, situation of,	463
Forbes of Drominoir in Scotland,	107
Forrach mac n-Amhalgaidh,	345, 467
Foxford. <i>See</i> Beal easa and Bel easa.	

G.

Gailian, fort of,	290, 291
Gaillimh, now Galway,	47
Gall-Gadelians,	352
Gamanradii,	291
Gamanradii of Erris,	97
Gannon, family of. <i>See</i> Mag Fhionain.	
Gaughan. <i>See</i> O'Gaibhtheachain.	
Gerald, St., of Mayo, said to have been	

	<i>Page.</i>
cotemporary with Dubhda, the ances-	
tor of the O'Dowds,	145
———, the true period of	
his death considered,	452, 453
Ghest, Lady Ellenor, the mother of	
David O'Dowd,	361
Giraldus Cambrensis, his account of the	
inauguration of the prince of Tírcon-	
nell,	426
Glaísi Guirt na Iainni, one of the boun-	
daries of Partraighe,	153
Glasán O'Triallaigh, a relic,	40
Glascharraig, situation of,	37, 38
Gleann an chairn, where,	7
Gleann da ghubb, situation of, in Cool-	
carney,	421
Gleann Maoilduin at the Eidhneach,	
where,	42, 43
Gleann Neimhthinne, district of,	10
———, chief of, 165, 232, 233	
——— given to Ricin Bar-	
rett,	333
———, the Lower Mac	
William De Burgo's tributes from,	456
Gleann Osdegh, now Glenhest,	331
Glenfarne, tower of,	400
Glenn Neimhthinne, situation of,	236, 237
Gleoir, river of, 109, 167, 169, 248, 249, 254,	
255	
Grainseach,	167, 242, 243
Grainseach Bheag,	171
Grainseach Mhor,	171, 262, 263
Gregragii, people,	469
Grellach, situation of,	421
Grenius, battle of,	25
Grianan, meaning of the word,	209
Guairé Aidhne, King of Connaught,	
procures the murder of St. Ceallach,	35
———, his pedigree and	
descendants,	61

	<i>Page.</i>		<i>Page.</i>
H.			
Herberts of the county of Limerick, . . .	335	Imairi, near Errew, in Carra, . . .	196, 197
Huachtar Charthuinn,	465	Imleach iseal,	169, 175, 257
H-Ui. <i>See</i> Ui and Hy.		Imleach loisge,	167, 242, 243
H-Ui Fiachrach, St. Patrick's acts in, . .	469	Inauguration of the Irish chiefs, account of, by Philip O'Sullivan Beare, . . .	439
Hy-Airmeadhaigh of Caille Conaill, de- scend of,	9	_____, summary of conditions requisite to constitute a legitimate one,	451
Hy-Amhalgaidh,	3	Inis Amhalgaidh, in Loch Con, . . .	99
Hy-Aodha of Burren, descent of, . . .	33	Inis Aonaigh,	401, 402
Hy-Becon of Meath, descent of, . . .	13	Inis Awley, in Loch Con,	347
Hy-Columbkille, or Iona Island, pilgri- mage to,	317	Iniscrone. <i>See</i> Inis Sgrebhainn and Eiscir abhann.	
Hy-Conaill of the River Daoil, descent of, .	9	Inis Cua, the seat of Cosnamhach Mor O'Dubhda,	115
Hy-Eachach of the Moy, descent of, . . .	33	Inis Dornglas, a small island in the River Moy,	343
Hy-Eathach Muaidhe, extent of, 51, 165, 226, 227, 228, 229		Inisgreabhainn, the chief seat of O'Cao- mhain,	175
_____, families of,	165	Inishcoe. <i>See</i> Inis Cua.	
Hy-Eunda Cruim, descent of,	9	Inishcrone castle. <i>See</i> Eiscir abhann, 122	
Hy-Fiachrach Aidhne,	3	Inis Mochua, one of the seats of the chiefs of Hy-Fiachrach, . . .	173, 280, 281
_____, descent of,	33, 35	Inishowen, sea-fight off the coast of, . .	352
Hy-Fiachrach of Cuil Fabhair, descent of, .	33	Inis Raithin, situation of,	303
Hy-Fiachrach Finn, descent of,	9	Inis Sgreabhainn,	169, 175
Hy-Fiachrach, list of chiefs of,	299	_____, the seat of Donnchadh Ultach O'Dubhda,	307
_____, chief seats of, 173, 280, 281, 309		Inis tuathras, off the coast of Carbury, .	353
Hy-Fiachrach Muaidhe, genealogy of, . .	3, 97	Insi Gall, situation of,	303
Hy-Fiachrach Muirsci,	350	Insi Modh, situation of,	303, 402
Hy-Fiachrach, list of Connaught kings of, .	91	Iochtar Ratha,	169, 175, 282, 283
Hy-Fiachrach, northern, extent of, . . .	143	Iomaire,	157
Hy-Fiachrach, north and south,	183	Iorris Iarthair,	73
Hy-Fiachrach, hereditary proprietors of, .	149	Irrua, families of,	163, 215, 216, 217
Hy-Mac Uais,	311	Isl of Mann,	352
Hy-Many, Dubhthach, King of,	11		
Hy-Muireadhaigh of Tirawley, blest by St. Cormac,	7		
Hynes, John, of the New Quay, Esq., his descent,	406		
I.		J.	
Iasgach River, 169, 171, 254, 255, 256, 257		Joyces of Connaught, of Welsh descent, .	352

K.	Page.	Page.
Keary. <i>See</i> Mag Fhiaichra.		
Keating, Dr., his account of the reign of Dathi, the last pagan monarch of Ireland,	22, 23	
—, his account of the inauguration of the prince of Tirconnell, 426, 427		
—, his account of the inauguration of Irish chieftains,	428-434	
Kells. <i>See</i> Cenannus.		
Kenelconil, prince of, account of the inauguration of, as written by Giraldus Cambrensis,	426	
Keogh, Rev. John, his account of the divisions of land in Ireland,	453, 454	
Kilcummin, in Tirawley,	10	
Kilcommon. <i>See</i> Cill Comain.		
Kilgarvan. <i>See</i> Cill na n-garbhan.		
Kilglasse, David O'Dowde of,	362	
Kilkelly, or Killikelly. <i>See</i> Mac Giolla Cheallaigh.		
Kilkenny placed in Munster,	73	
Kilkenny, derivation of the name,	88, 89	
Killaghy, battle of,	403	
Killala, William O'Dubhda, Bishop of,	305	
Killaladh, now Killala,	466, 467	
Killarduff,	222, 223	
Killaraght, derivation of the name,	41	
Killyoveragh, O'Heyne's country, extent of,	4	
Kill Fhorclann,	467	
—, situation of,	464, 465	
Kill Mor Uachtair Muaidhe,	467	
Kill Rodain,	471	
Kilmacrenan, O'Donnell inaugurated at, by O'Freel,	432	
Kilroe mor church, situation of,	470	
Kings of Connaught, of the Hy-Fiachrach race, list of,	91, 92, 309-319	
Kirwan family, of Irish origin,	49	
Knockroe, or Red Hill of Skreen, cairn on, described,		417
L.		
Lady Ellenor Ghest, the mother of David O'Dowde,		361
Laeghaire, son of Niall, his body interred in a standing position,		473
Lagan, a district of Tirawley,		6
—, chief of,	165, 222, 223	
Laighdiagan, now Lydican, O'Heyne of,		65
Larissy. <i>See</i> O'Learghusa.		
Lathrach,	171, 266, 267	
Law, civil and canon,		75
Law, professors of, among the Irish,		ib.
Lawless family of Welsh origin,		325
—, Sir William, his estate in Tirawley,		333
Laws, various, in use in Ireland,		75, 76
Leaba an eich bhuidhe,		123
Leabhar Balbh, or Dumb Book of James Mac Firbis, referred to, 11, 141, 170, 171		
Leabhar Buidhe of Armagh,		319
Leabhar Gearr, or Short Book of Monasterboice,		319
Leabhar na h-Uidhri quoted,		20, 21
Leacan, O'h-Iomhair of,		167, 250, 251
Leacan, or Lacken Castle, by whom built,		167, 169
Leac Bailbene,		468
Leac Chuimin, at Kilcummin,		10
Leac fionnbhaile,		467
Leac Mhic Eochadha, the lord of Hy-Kinsellagh inaugurated at,		434
Leamhach,	173, 268, 269	
—, fort near,		286, 287
Leatha, where,		18, 19, 411, 412
Lecan, or Lacken Castle, by whom built,		167, 168, 407

	<i>Page.</i>		<i>Page.</i>
Lecan, Book of, when compiled, . . .	359	Longphort Ui Dhubhda, . . .	123
Lecan, John O'Clery of, in 1458, . .	125	———, the seat of Brian	
Leitir Maolain, in Thomond, Maccon		Og O'Dubhda, . . .	307
O'Clery died at, . . .	395	Luacharnach, O'Heyne of, his pedigree, 69	
Leyny, O'Hara, lord of, . . .	351	Luach leasa, meaning of, . . .	143
Lia Con, . . .	169, 254, 255	Luffertane, . . .	402
Lia Fail, inaugurating stone at Tara, .	425	Lughbortan, district of, . . .	153
Lia na manach, situation of, . . .	468	Lundunn, battle of, . . .	23
Liathmhuine, the seat of Maolruanaidh		Lydican, or Lydigane Castle, situation of, 65	
O'Dubhda, . . .	306, 360	———, O'Heyne of, 405	
———, river of, anciently called		Lynch, Dr. John, <i>alias</i> Gratianus Lucius,	
Gleoir, . . .	109	his translation of Torna's poem on the	
Liatruim, an ancient name of Tara, . .	29	royal cemetery of Rathcroghan, . 31, 32	
Lionan Cinn mara, . . .	401	———, his	
Lios Beanchair, Mac Carthy More in-		account of the inauguration of Irish	
augurated at, . . .	433	chieftains, . . .	435-437
Lios Cuimin, on the Moy, . . .	11	———, his	
Lios Ladhghuill, . . .	173, 274, 275	refutation of Giraldus's account of	
Lios Leitreach, situation of, . . .	7	the mode of inauguration of the prince	
Lios na Draighnighe, . . .	175	of Tirconnell, . . .	ib.
Lios na reamhar, . . .	173, 272, 273	Lynott brings the Burkes into Tirawley	
Lis ard mor, now Lissardmore, or Lis-		to subdue the Barretts, . . .	337
sermore, . . .	421	Lynotts, with whom they came to Ireland, 335	
Lis Callain, church of, . . .	415	Lynotts of Tirawley subdued by the Bar-	
Lis Cuimin, . . .	234, 235	retts, . . .	337
Loch Buadhaigh, a regal seat in Ceara, 155,			
204, 205			
Loch Con, Joseph of, Abbot of Clonmac-			
noise, . . .	351		
Loch Deala, one of the seats of the Kings			
of Hy-Fiachrach, . . .	280, 281, 467		
Loch Gile, cemetery at, Eoghan Beul,			
King of Connaught, interred in, . .	472		
Loch Glinne, O'Flannghaile of, 165, 240, 241			
Loch Muighe Broin, . . .	165		
Loftus, Adam, Lord Chancellor of Ire-			
land, his decision in favour of Donell			
O'Donovan in 1952, . . .	444-448		
Loftus. <i>See</i> O'Lachtain.			
Longford. <i>See</i> Longphort Ui Dhubhda.			

M.

Mac an Bhainbh, estate of, . . .	153, 190
Mac Andrew of Bac, of Welsh descent, 327	
Mac Bhailseacha, of Welsh descent, . 325	
Mac Bhaitin Barrett of Tirawley, of	
Welsh descent, . . .	ib.
Mac Brody, O'Brien's historian, . . .	433
Mac Cailleachain of Carn, . . 167, 248, 249	
Mac Carraoin of Sgrin, . . .	173
Mac Carthy More inaugurated at Lis-	
banagher, . . .	433
Mac Carthy, Sir Owen, chief of Carbery, 445,	
446, 447	

	<i>Page.</i>		<i>Page.</i>
Mac Coinin, descent of, . . .	5, 165, 216, 217	fallen state of the Hy-Fiachrach race, 317	
Mac Conboirne of Irrus, . . .	216, 217	Mac Firis, Giolla Iosa, his book re-	
Mac Concathrach of Sgrin, . . .	171, 268, 269	ferred to,	153
Mac Congamhna of Cinel Fechin, descent		———, Giolla Iosa Mor, his long	
of,	33	poem on the families and territories of	
Mac Conghaola, descent of,	63	Hy-Fiachrach	177-299
Mac Conlena of Cill Mor Muaidhe, 165, 234,		———, James, his Dumb Book re-	
235		ferred to,	153, 170, 171, 173
Mac Conleithreach, descent of,	7	———, James, son of Diarmaid, his	
———, his estate,	165, 220,	testimony as to the descent of Clann	
221		Robert,	333
Mac Conluain of Cuil Cille Bricin, 173, 272,		———, or Forbes, John, of Lacken,	
273		in the county of Mayo, his memorial	
Mac Cuinn of Coolcarney,	246, 247	to the Royal Irish Academy,	408
Mac Curtin, O'Brien's historian, . . .	433	Mac Fhlannchadha, or Clancy, O'Brien's	
Mac Dermot, Tomaltach Mor,	212	Brehon,	433
———, became chief		Mac Gilla Chais,	260, 261
of Clann Cuain,	163	Mac Gilla Fhaelain of Regles,	155, 195
Mac Egan, Mac Carthy More's Brehon, 433		Mac Giolla na n-each of Corcacha, . . .	17
Mac Eochadha, or Makeogh, Mac Mur-		Mac Gilli bhuidhi, now Kilboy, . . .	202, 203
rough's poet,	434	Mac Giolla bhain of Lios na reamhar, 173,	
———, inaugurated		272, 273	
O'Byrne at Dun Caillighe Beirre, . . .	434	Mac Giolla Bricin of Ard na n-glas, 173, 270,	
Mac Eoghain of Dun Becin,	171, 260, 261	271	
Mac Finn Ui Dubhda,	139	Mac Giolla bhuidhe, estate of,	159
Mac Firis, descent of,	11, 33	Mac Giolla Ceallaigh, subdued and dis-	
Mac Firis of Lecan, pedigree, &c., of, 101,		possessed O'Maghna,	63
107, 167, 407		———, his pedigree,	69
———, privileges of,	143, 145	Mac Giolla Finn of Leamhach, 173, 268, 269	
——— seated one time at Ros Serce, 165,		Mac Giolla duibh of Corcach, descent of, 107,	
236, 237		171	
———, a branch of, seated near the		Mac Giolla Fhaolain, estate of, in Ceara, 155,	
strand of Traigh Eothuille,	173	195	
——— held the rod over O'Dubhda		Mac Giolla mhir of Fionnabhair, 173, 270,	
at his inauguration,	440	271	
———, Duaid, his pedigree,	101	Mac Giolla na n-each, descent of, . . .	107
———, his curious remarks		Mac Giolla riabhach, descent of, . . .	107
on the extinction of some families in		Mac Giolla riabhach of Cricchan, 173, 270,	
Tireragh,	175	271	
———, his reflections on the		Mac Ilrea. See Mac Giolla riabhach.	

	<i>Page.</i>		<i>Page.</i>
Mac Murrrough Kavanagh inaugurated		Magh Muaidhe,	5, 292, 293
at Cnoc an Bhogha,	434	Magh Mucroimhe, near Athenry, . . .	344
Mac Namara inaugurated O'Brien, King		Magh Muirisci,	4
of Thomond,	432	Magh na bethigh district, extent of, 153, 190	
Mac Neill, descent of,	17	Magh na Cnocaighe,	155
———, Giolla an Ghoill, last King		Magh Roisen,	ib.
of Ceara of the Irish race,	159	Magilin, inheritance of,	153
Mac Philbin, descent of,	333	Mag Mailin, Mael Isa, a bishop,	159
Mac Quillins of the Rout, of Welsh de-		Magh Muireadhaigh, where,	179
scend,	325	Mag Lannagan of Clann Cuain,	206, 207
Mac Scellig, commander of a Scotch		Mag Odhrain of Dunfeeny, descent of, 7, 165,	
fleet in 1154,	352		220, 221
Mac William De Burgo, the Lower, his		Magrath, O'Brien's poet,	433
tributes in Tirawley,	455, 456	Mag Rodain of Sgrin,	171, 268, 269
———, com-		Maguire inaugurated at Sgiath Gabhra,	
pacts between him and the Barretts of		now Lisnaskea,	404
Belleek,	458, 459, 460, 461	Maicnia's plain, a name for Ireland, 288, 289	
Maenmagh, situation of,	286	Maighin, now Moyne, in Tirawley, bat-	
Mag Fhionnain of Irrus, 6, 165, 216, 217, 222,		tle of,	329
	223	———, William Fionn Barrett of, 325, 329	
Mag Flannagans of Oga Beathra, . . .	63	Maiteog,	189
Magh Adhair, in Thomond, the place		Maiteog Achaidh Gabhair, one of the	
where O'Brien was inaugurated King		boundaries of Ceara,	149
of Thomond,	432	Makeighry. <i>See</i> Mag Fhiachra,	63
Magh Ailbhe, where situated,	18	Manulla,	192, 193
———, battle of,	19	Markham. <i>See</i> O'Marcachain.	
Magh Broin, in Tirawley,	100	Meadhbh, fort of,	288, 289, 294, 295
———, situation of,	236	———, Queen of Connaught, buried	
———, families of,	236, 237	at Rath-Croghan,	28
Magh Circaín, battle of,	19	Meeny. <i>See</i> O'Maonaigh.	
Magh Eleog, where situated,	113	Meirgeadha, meaning of,	471
Magh Ene plain, extent of,	80	Midh, meaning of the word,	216
Mag Fhiachra, chief of Oga Beathra, . .	63	Mileac an locha, situation of,	330
Magh Fhiondalbha, extent of,	155	Minahan. <i>See</i> O'Muimhneachain.	
Magh Fuara, O'Leathchaile of,	165	Miosgan Meidhbhe, on Knocknarea,	
Magh gamhnach, O'Connagain of, . . .	167	some conjectures concerning,	443
———, situation of,	230, 231	Miscal, battle of,	23
Magh h-Eleag, situation of,	165, 238	Moda, the River Moy, so called by	
Magh h-Indalbh, now Manulla,	192, 193	Adamnan,	3
Magh Luirg, extent of,	77	Moile, battle of,	23

	<i>Page.</i>
Monasterboice, Book of, referred to,	319
Moneyconnilane, the ancient name of Bunnyconnellan, <i>q. v.</i>	
Moy River, course of,	3
Moynes Abbey,	360
Moynes, Abbey of, burial place of the O'Dowds,	308
Muaidh River, now the Moy, situation of,	3
———, called Sal Srotha derg,	34
———, the outlet of the waters of Lough Conn,	219
———, the Moda of Adamnan,	409
Mucna, St., of Dombnach Mor,	466
Mudhubh, O'Floinn of,	167, 250, 251
Muilenn Tiormain, one of the boundaries of Ros laogh,	157
Muine, townland, situation of,	153
Muine Chonallain, the two quarters of, situation of,	420
Muine dhiadh,	171
Muine Fede,	173
Muine, in Partry,	190
Muine na fede, 270, 271. <i>See</i> Bun fede.	
Muine na bh-fiadh,	171
Muintir Ailgheanain, descent of,	41
Muintir Culachan, descent of,	13
Muintir Duincuan, descent of,	ib.
Muintir Fothaigh, descent of,	ib.
Muintir Muiren, descent of,	43
Muintir Murchadha,	181
Muintir Tomaltaigh, descent of,	13
Muintir Ubain, descent of,	ib.
Muireasg, daughter of King Hugony Mor, buried at Rathcroghan,	28
Muiesch-aigle, situation of,	471
Muir n-Icht, sea, situation of,	18
Muirisg,	173
Muirisci, in Tireragh, 171, 256, 257, 262, 263	
Mullach Ratha,	96, 167, 250, 251
Murachs, or Moores, invade Tirawley,	329

	<i>Page.</i>
Murbhach, in Arann,	288, 289
Murbhach, in Tirconnell,	296, 297
Murray. <i>See</i> O'Muireadhaigh.	
Musgrave, Sir Richard, his character of Captain O'Dowda,	370
N.	
Nepotes Neill,	178
Newbrook. <i>See</i> Ath na lub.	
Niall, race of, who,	178, 179
Nuachongbhail, church of,	352
O.	
O'Airmeadhaigh, of Loch Muighe Broin, 165, 236, 237	
———, Magh Broin, 236, 237	
O'Banain, estate of,	153, 189
O'Baothghaile, of Cluain Ui Chosgraigh, 173, 268, 269	
O'Bearga of Dun Fine,	7, 165
———, descent of,	7
O'Beollain of Dun Ulltain,	171, 258, 259
O'Berga of Dun Fine,	220, 221
O'Birn of Ceara, his estate,	159, 200, 201
O'Bligh of Dunfeeny, descent of, 7, 165, 220, 221	
O'Breslen of Cill Faindle,	167, 252, 253
O'Breslen, O'Neill's Brehon,	432
O'Brien inaugurated at Magh Adhair,	432
O'Brien, Mor Pheacach, the wife of Sir Dermot O'Shaughnessy,	376
O'Broduibh, of Hy-Eathach Muaidhe, 165, 228, 229	
———, de- scent of,	35
O'Brogain, estate of in Ceara,	157
O'Brogan of Breachmhagh,	244, 245
O'Brogan of Ceara,	196, 197
O'Brogain of Breachmhagh,	167
O'Broin, or O'Byrne inaugurated at Dun Caillighe Beirre,	434

<i>Page.</i>	<i>Page.</i>
O'Byrne. <i>See</i> O'Broin.	O'Clery, John of Lackan, his deposition in favour of Hugh O'Dowde of Stalinge, 125
O'Caemhagain of Oga Beathra, . . . 63	——, Lughaidh, pedigree of, . . . 83
O'Caithniadh, chief of Iorrus, 163, 214, 215	——, his lands in Tirconnell, . . . 83
O'Caithniadh, chief of Irrus, descent of, 5	——, Michael the friar, . . . 87
O'Callaghan of Erris, descent of, . . . 5	O'Clerys of Breifny O'Reilly, pedigree of, . . . 89
O'Caomhain, pedigree of, . . . 109, 110, 111	—— of Kilkenny, pedigree of, . . . ib.
——, said to be senior to O'Dowd, 109	—— of Tirawley, pedigree of, . . . ib.
——, extent of his territory, 109, 167, 248, 249, 350	O'Coigligh, now Quigly, estate of, 155, 195
——, privileges ceded to, by	O'Coinmin of Irrus, . . . 216, 217
O'Dubhda, . . . 139, 140, 143	O'Coitil of Baile Ui Choitil, 167, 248, 249
——, his estates in Ceara, 157, 198, 199	O'Colmain of Grainseach Mor, 171, 262, 263
——, chief seat of, . . . 169, 175	O'Comhaltain, descent of, . . . 69
——, first pronounced the name	O'Comhdhain of Dun Fine, . . . 165
of the O'Dubhda on his inauguration, 440	——, descent of, . . . 7
O'Caomhain an Chuirrigh, . . . 171	O'Comhghan of Dun Fine, . . . 220, 221
O'Cathail of Cineal Aodha, pedigree of, 57, 374	O'Conbhuidhe, ancient estate of, . . . 171
O'Cathan, chief of Cineal Ianna, . . . 63	——, his chief seat, . . . 175
O'Cathasaigh of Cill Achaidh duibh, de- scend of, . . . 9	——, of Baile Mec Giollachais, 171, 256, 257, 260, 261
——, of Cill Ardubh, 165, 222, 223	O'Conboirne, descent of, . . . 6
O'Cathmogha, descent of, . . . 69	——, of Iorrus, . . . 165
O'Ceallachain or O'Callaghan of Erris, . . . 5, 163, 216, 217	O'Conghaile of Cill Ardubh, 165, 222, 223
O'Ceallaigh of Ard O'g-Ceallaigh, 171, 264, 265	——, descent of, . . . 9
O'Cearnaigh, estate of, in Ceara, 155, 157	O'Connachtain of Cabrach, . . . 169, 252, 253
——, of Manulla, . . . 193	O'Connagain of Magh gamhnach, . . . 167
——, of the termon of Balla, . . . 199	O'Connell, Connor, Bishop of Killala, slain by Maghnus O'Dubhda, . . . 359
Ocha, battle of, . . . 311	O'Conor, Cathal Croibhdhearg, King of Connaught, . . . 303
O'Ciaragain, estate of, . . . 155, 194	——, Charles of Belanagare, his no- tice of David O'Dowda, . . . 368
O'Ciardha of Cairbre, . . . 276, 277	——, Domhnall Iorruis, . . . 333
O'Cinnechnamha, estate of, . . . 151, 189	O'Creachain, descent of, . . . 35
O'Clery, pedigree of, . . . 71-91	—— of Hy-Eathach Muaidhe, 228, 229
——, pedigree of, as compiled by the Editor, . . . 391-398	O'Criaidhchen of Hy-Eathach Muaidhe, 165, 228, 229
—— Cormac settles in Tirconnell and marries the daughter of O'Sgingin, 75, 77	

<i>Page.</i>	<i>Page.</i>
O'Criadhchens, descent of, 51	hill, his pedigree as given by Duald Mac Firis, 445
O'Cuachain, estate of, in Ceara, . . . 157	O'Donovan, Diarmaid, son of Donell, hanged by the celebrated Donell O'Sullivan Beare, 447
O'Cuain of Dun Ui Chobhthaigh, 171, 262, 263	———, Donell, made chief of Clancahill in 1584, his pedigree, as given by Duald Mac Firis, 445
O'Cuanain of Dun Becin, 171	———, decree of Chancery in favour of, in the year 1592, . 444, 448
O'Cuimin of Lios Cuimin, 11, 45, 234, 235	——— law suit between him and his brother Teige in 1592, 444, 448
O'Cuinn or O'Quin of Cinel Laeghaire, 244, 245	———, Donell na g-Croiceann, account of inauguration of, by John Collins of Myross, 448
——— of Clann Cuain, . 161, 206, 207	———, General Richard, of Bawnlahan, 381
——— of Coolcarney, 167, 423	O'Doran, Mac Murrough's Brehon, . . 434
——— of Dunfeeny, . 7, 165, 220, 221	O'Dorchaidhe, or Darcy, chief of Partry, pedigree of, 46, 47, 153, 189
O'Cuinn, Domhnall, separated Clann Cuain from Hy-Fiachrach, 163	———, of Galway, pedigree of, 47, 48, 49
———, murders O'Dubhda, 206, 207	O'Dorchaidhe, chief of Partraighe, . 153
O'Culachain, of Ceara, 159	O'Dowd, various modes of spelling the name, 111, 112
O'Curnins, books of, referred to, . . . 316	O'Dowd, or O'Dubhda, inaugurated on Carn Amhalgaidh, 434
O'Daly, Mac Carthy More's poet, . . . 433	———, Taithleach, slain by Adam Cusack, 355
O'Deirg of Magh gamhnach, . . . 230, 231	———, Tuathal and Taichleach fight with the English at Ardrahin, . . . 400
O'Derig of Caille Conaile, 9, 167	O'Dowda, armorial bearings of, . . . 37
O'Discin of Baile Ui Dhisicin, 171, 260, 261	———, form of inauguration of, as published in the Rainbow or Western Magazine, 441, 442
O'Donnchadha, descent of, 107	———, pedigree of, as compiled by the Editor, 343-372
O'Donnell, daughter of, married to Teige O'Dowd in 1417, 296, 297	———, transplanted to Bunnyconnellan by the Commissioners sitting at Loughreagh in Aug. 1656, 365
O'Donnelly, O'Neill's marshal, . . . 432	
O'Donoghoe More, 433	
O'Donovan family, list of chiefs of, as laid before Adam Loftus, Lord Chancellor of Ireland in 1592, 445, 446	
———, Amlaff More, chief of Carbery, slain at Kineigh in 1200, . . . 450	
———, Daniel, chief of Clancahill, married to Gylles, daughter of Sir Roger O'Shaughnessy, 380	
———, his sons, living in 1655, 381	
———, ode addressed to, by Muldowny O'Morrison, 380	
———, Diarmaid, chief of Clanc-	

	<i>Page.</i>		<i>Page.</i>
O'Dowda, David, Junior, his marriage articles,	363	bhar, descendants of,	135
———, Dominic, his will,	367	O'Dubhda, Ruaidhri, son of Conchobhar, his descendants,	133
———, Captain James, his improvements in Coolcarney,	369	———, Ruaidhri Mear, murdered by O'Cuinn of Clann Cuain, 63, 207, 208, 209, 210, 211	
———, Dr. James Vippler,	372	———, Sen Bhrian, drove the English out of Tireragh,	175
———, Thaddæus, chief of his name, 372		———, fought in the battle of Athenry,	356
O'Dowde, Hughe of Stalinge,	124	———, Teige, address to, by Mac Firbis in 1417,	284-299
———, his hereditary possessions in Tireragh in 1458,	125	———, William, Bishop of Killala, 117, 355	
O'Dowds of Dublin, pedigree of,	127	O'Dubhscuile of Dun Maoilduibh, 107, 258, 259	
O'Driscol, his ancient territory,	450	O'Duibhghiolla, descent of,	55, 61
O'Duanmaighe of Dun Fine, 7, 165, 220, 221		O'Duibhghiolla, chief of Cineal Cinn-gamhna in South Hy-Fiachrach,	63
O'Dubhagain of the Bacs,	10, 11	O'Duibhlearga of Dun Fine, 7, 165, 218, 219	
——— of Cill Mor Muaidhe,	235	O'Duinchinn of Doire na nath, 173, 272, 273	
——— of Loch Muighe Broin,	165	O'Duinin, now Dinneen, Mac Carthy More's historian,	483
——— of Oga Beathra,	63	O'Dunchadha, his estate in Tireragh, 173, 274, 275	
O'Dubhda, or O'Dowda, pedigree of, as given by Duald Mac Firbis,	111-145	———, of Dun Ui Chobhthaigh, 262, 263	
———, extent of his country,	278, 279	O'Dunghaile of Dun Ui Chobhthaigh,	171
———, form of the inauguration of, according to the Book of Lecan, 440, 441, 442		O'Dwyre of Kilnamanagh,	432
O'Dubhda, or O'Dowda family, list of chieftains of,	299-309	Oenadharc, fons,	467
———, Cathal Dubh, pays a tribute to the Lower Mac William,	455	O'Faghartaigh of Ceara, 17, 157, 196, 197	
———, Conchubhar na Cetherne,	418	O'Feinneadhra of Finghid,	169, 256, 257
———, Cosnamhach, descendants of, 137		O'Finaghty, senior to O'Conor of Con-naught,	108
———, Cosnamhach, commander of the Connacian fleet,	352	O'Finain of Coolcarney, 167, 246, 247, 423	
———, Dathi, slain by one of the Queen's soldiers in one of his own castles in Tireragh,	361	O'Fionnagain of Fionnchalamh,	7, 165
———, Dathi Og, living in 1666, pedigree of, according to Duald Mac Firbis,	131	O'Firghil, or O'Freel, of Kilmacrenan, 432	
———, Domhnall, prior of Aughris, pedigree of,	139	O'Flainn of Calraighe Muighe h-Eleag, descent of,	13, 165
———, John Glas, son of Concho-		O'Flaitile of Hy-Eathach Muaidhe, 51, 228, 229	

	<i>Page.</i>		<i>Page.</i>
O'Flannghaile of Corcachs,	171	O'h-Aodha, estate of, in Ceara, . . .	155
_____ of Eachros,	171	_____, of Ard O'n-Aodha, 9, 167, 224,	225
_____ of Finghid, . . . 169, 256, 257		_____ of Baile na Craoibhe, . . .	191
_____ of Loch Glinne, 165, 240, 241		_____ of Toin rego, . . . 173, 272, 273	
O'Flannabhra, of Caeilli Conaill, 9, 167, 226,	227	O'h-Arain of Ardgabhail,	167
O'Floinn of Beartrach, . . . 167, 250, 251		O'h-Eana of Imleach loisge,	167
_____ of Magh h-Eleag, . . . 238, 239		O'h-Eidhneachain, estate of, in Ceara, .	155
_____ of Oireamh Locha Con, now		_____, of Fidh Cruaichi, . . .	194
Errew,	165	O'h-Eighnigh, his estate,	242, 243
O'Fuala of Grainseach Bheag, 171, 262, 263		O'h-Eimeachain, descent of,	9
O'Fualairg of Rath Beorchain, . . . 169, 252		O'h-Eineachain,	165, 234, 235
O'Fuathmharsain of Cacál,	191	O'h-Enda of Imleach loisce, . . .	242, 243
Oga Beathra, tribe of, in Aidhne, . . .	53	O'Heyne, in Irish O'h-Eidhin, pedigree	
O'Gadan of Magh gamhnach, . . . 230, 231		of,	65
O'Gaibhtheachain of Calry, 13, 165, 238, 239		_____, pedigree of, as compiled by the	
O'Gaibhtheachainslew Domhnall O'Dubh-		Editor,	398-406
da at Bearna Domhnaill,	113	_____, his estates in the 30th year of	
O'Gallagher, O'Donnell's marshal, . . .	432	Elizabeth,	404
O'Gara, Farrell of Moy O'Gara, . . .	362	_____, different persons of the name	
O'Gealagain of Cill Iochtari, 167, 242, 243		in the barony of Kiltartan in 1641, .	405
O'Gearadhain of Iorrus, . . . 6, 165, 218, 219		_____, herenach of Kilmacduagh, his	
O'Gibelan, Maurice, professor of laws, .	75	pedigree,	67
O'Gilin of Breadach, . . . 11, 165, 230, 231		_____, of Lydican, pedigree of, . . .	65
O'Gilin of Muine,	191	_____, Eoghan, assists the English, .	400
O'Glaimin of Breudach, descent of, . . .	11	_____, Hugh Boy, Queen Elizabeth's	
O'Gloinin of Rath na n-Goirmghiall, .	165,	grant to,	404
_____ 230, 231		_____, Owen Mantagh, order of the	
_____, slew the celebrated warrior		Council of Connaught in favour of, .	404
Cosnamhach Mor O'Dubhda, at Inis-		_____, Maolruanaidh na paidre, slain	
Cua,	115	at the battle of Clontarf,	398
O'Goirmghiolla, estate of, in Ceara, 159, 201,	203	O'h-Iarnain of Coolcarney, . . .	246, 247, 423
O'Goirmiallaigh of Patraighe, . . . 47, 153		O'h-Iomhair of Leacan, . . . 167, 150, 251	
O'Gorman, or Mac Gorman, O'Brien's		O'h-Iornain of Cuil Cearnadha, . . .	167
marshal,	432	O'h-Oilmhec of Sgrin, . . . 171, 268, 269	
O'Gormghail of Ceara,	187	O'h-Oilmhec. See O'h-Ailmhec.	
O'Gormog of Ceara,	149	O'h-Oireachtaigh of Cineal Ianna in	
O'h-Ailmhec, descent of,	107	South Hy-Fiachrach,	69
O'h-Aodha, descent of,	ib.	O'h-Uada, now Swift, ancient estate of,	
		in the territory of Ceara, . . .	151, 183

	<i>Page.</i>		<i>Page.</i>
O'h-Uadach, descent of,	17	O'Mailraite,	196, 197
O'h-Uathmharain, descent of,	16, 17	O'Malleys, descent of,	181
———, estate of,	155	O'Malley's country, extent of,	43
Oileach, in Erris, one of the seats of the chiefs of Hy-Fiachrach,	280, 281	O'Maoilaichen, descent of,	35
Oileach, in Coolcarney, now Ellagh,	421	O'Maoilaithghen of Hy-Eathach Mu- aidhe,	165
Oilen Edghair,	415	O'Maoilbhreuninn of Hy-Eathach Mu- aidhe,	35, 165, 228, 229
Oireadh or Oireamh Locha Con, situa- tion of,	12, 165	O'Maoilcana of Criathrach,	159, 202, 203
Oireamh in Ceara, now Errew, 157, 196, 197		O'Maoilchonaire of Caille Conaill, de- scend of,	9
Oirghiall, people of,	181	O'Maoilduin, descent of,	107
O'Lachtna, now O'Lachtain, descent of, 10, 11		O'Maoilduin,	169, 173, 254, 255
———, chief of the two Bacs, 165, 232,	233	O'Maoilduin of Imleach iséal,	169, 256, 257
O'Laechaille of Magh Fuara,	234, 235	O'Mailfaghmhair, or O'Maoilfoghmhair of Killala,	51, 165, 228, 227, 354
O'Laitile of Hy-Eathach Muaidhe,	165	O'Maoilfhiona of Calraighe Muighe h-Eleag, descent of,	13, 165
Oldbridge, Bhailiseach of,	127	O'Maoilfhiona of Clann Cuain,	161
O'Leanain,	51, 165, 226, 227	O'Maoilruaidh of Ardachadh,	165
O'Learghusa, estate of, in Ceara,	155	——— descent of,	11
O'Learghusa of West Connaught, de- scend of,	11	O'Maoilruain,	234, 235
O'Leary of Carrignacurra, in the west of the county of Cork,	469	O'Maoilchonaire of Caille Conaill,	167
O'Lerghusa of Cill n-Aindi,	192, 193	O'Maoilraite, estate of, in Ceara,	157
O'Liathain of Muine-Fede,	173, 270, 271	O'Maonaigh,	107, 171, 173, 272, 273
Ollamh, meaning of the word,	77	O'Marcachain of Cineal Ianna,	63
O'Loingseachain of Mullach Ratha, 167, 250,	251	O'Mochain of Cill Athracht, descent of, 41,	42, 43
O'Loinsigh,	171, 264, 265	——— of Cineal Ianna,	63
O'Luachaibh of Breadach, descent of,	11	——— of Hy-Eathach Muaidhe, 165, 228,	229
O'Luachain, or O'Luachduibh, of Brea- dach,	165, 231	———, Gregory, Archbishop of Tuam, pedigree of,	42, 43
O'Luachain of Ros laogh,	169, 258, 259	O'Mochaine of Baile Ui Mochaine, 167, 248,	249
O'Maghna, chief of Cineal Guaire,	63	O'Mongan of Breachmbagh,	244, 245
O'Mailaithghin of Hy-Eathach Mu- aidhe,	228, 229	O'Moran seated at Ardnarea, 167, 244, 245	
O'Mailchonaire of Caeilli Conaill,	226, 227	——— of Cinel Laeghaire,	244, 245
O'Mailcluithi of Cairbre,	274, 275	O'Morrisson, Muldowny, his Odeto O'Do- novan,	380
O'Mailfhina, chief of Calry,	238, 239		
O'Mailina of Clann Cuain,	206, 207		

<i>Page.</i>	<i>Page.</i>
O'Muimhneachain of Iorrus, 5, 6, 165, 216, 217	O'Shaughnessys, of Clare and Limerick, descent of, 386, 387
O'Muireadhaigh of the Lagan, descent of, 6	O'Shaughnessy, Bartholomew of Galway, his pedigree, as compiled by Captain Tyrrell of Kinvara, 388-391
O'Muireadhaigh of Ceara, 6, 149, 165, 187, 222, 223	———, Charles, the second son of Sir Dermot III. 383
O'Muirgeasa, 107, 173, 265, 272, 273, 274, 275	———, Dr. Colman, titular Bishop of Ossory, 384
O'Murchadha of Tireragh, his chief seat, 169, 175, 262, 263, 264, 265	———, Dermot, knighted by Henry VIII. 375
Onchu, meaning of the word, 471	———, Sir Dermot, letters patent to, in 1543, ib.
O'Nuadhan of Calraighe Laithim, 276, 277	———, Dermot Reagh, Queen Elizabeth's letter in favour of, . . . 377
O'Nuallain, inaugurated Mac Murrrough at Cnoc an Bhogha, 434	———, Sir Dermot II. 379
O'Quin. <i>See</i> O'Cuinn.	———, Sir Dermot III., his will in 1671, 382
O'Quin of Meath, 127	———, Gealbhuide, slain in the battle of Athenry, 374
O'Rabhartaigh of Sgrin, 171, 268, 269	———, Gylles, wife of O'Donovan, 380, 381
O'Radubhain of Baile an ghleanna, 7, 165, 220, 221	———, Joseph, the last claimant of the Gort estate, 384, 385, 386
Ormond, extent of, 73	———, Roebuck, 385
O'Ronain of Magh Broin, 236, 237	———, Roger, Esq., forfeited Gort, 383
O'Rothlain of Cluain na g-cliabhadh, 171, 258, 259	———, Sir Roger I., called Giolla dubh by the Irish, 376
——— of Cuil Cearnadha, 167, 423	———, depositions concerning him and his family, . 378, 379
O'Rourke, Sen Fergal, King of Connaught, defeated by O'Clery, chief of Aidhne, 392	———, armorial bearings of, 381, 390, 391
O'Rourke, or Mag Rourke, of Kerry, Mac Carthy More's marshal, 433	———, his letter to his daughter, the wife of O'Donovan, 381
O'Ruadhrach of Lia Con, 169, 254, 255	———, portrait of, preserved in Ormond Castle, . . . ib.
O'Ruaidhin of Ceara, 159, 198, 199	———, Colonel William, died in France in 1744, 383
O'Scannail of Cairbre, 274, 275	
O'Scannlain, pedigree of, 59	
O'Seaghsa of Caeilli Conaill, 167	
O'Seghdha of Caeilli Conaill, 226, 227	
O'Sgingin, historian to O'Donnell, . . . 77	
O'Shaughnessys, pedigree of, 57	
———, pedigree of, as compiled by the Editor, 372-391	
———, not descended from Guaire Aidhne, King of Connaught, 55, 58	

	<i>Page.</i>
O'Sionna of Lathrach, . . .	171, 266, 267
O'Sneadharna of Sgrin, . . .	171, 268, 269
O'Spealain of Coillin, . . .	169, 250, 251
O'Suanaigh, three saints of the name, their pedigree,	35, 36, 37, 45
O'Suidhlearga,	171, 262, 263
O'Sullevan Beare, Philip, his account of the ceremony of inaugurating the Irish chieftains,	439
O'Sullivan More,	433
O'Tarpaigh of Sgrin,	173
O'Tegha of Caelli Conaill,	9
O'Tighearnaigh, descent of, 16, 17, 149, 189	
O'Toghdha, chief of Breadach, 11, 165, 228, 229	229
O'Tuathalain,	167

P.

Parmenius, or Formenius, King of Thrace, a hermit in the Alps, . . .	19
Partraighe, O'Dorchaidhe of, . . .	47
——— territory, extent of . . .	152, 153
———, chiefs of,	189
Patrick, St., his acts in Tirawley, as ex- tracted from his Tripartite Life, . . .	461
Patrick's city, meaning of, . . .	227, 292, 293
Petits invade Tirawley,	329
Powell, Major, succeeded to the property of General Richard O'Donovan, . . .	381

Q.

Quigly. *See* O'Coiglidh.

R.

Rae Roain,	465
Raithleann, in Ceara,	159
Ran Tornaidhe,	155

Page.

Rathain, the northern boundary of Ceara, 149, 200, 201	200, 201
Rathain Ui Shuanaigh, situation of, . . .	36, 37
Rath Bearchain,	169, 252, 253
Rath Branduibh, one of the chief seats of the Kings of Hy-Fiachrach, 173, 280, 281	281
Rath Branduibh, now Rafran, 210, 211, 224, 225	225
Rath Cruachan, battle of,	19
Rath Cuanain, from whom called, . . .	171
Rath Durlais,	278, 279
Rath Laeghaire, at Tara,	473
Rath na n-goirmghiall,	165
Rath O'bh-Fiachrach,	472
Rath Raodain, situation of,	430
Red Earl,	335
Regles,	195
Releg na riogh, at Croghan, cemetery of the Irish kings,	25
Rheims, sacred cruet of, used in the anointing of the Kings of France, . . .	452
Righnach, the mother of St. Colman Mac Duach, her descent,	63
Rithlearg, meaning of the word,	26
Rodhba River, now the Robe, 143, 159, 200, 201, 276, 277	201, 276, 277
———, the southern boundary of Ceara,	149
———, the southern boundary of O'Dowd's country,	301, 303
Roibin beag, in Ceara,	159, 200, 201
Roscam, Brian, ancestor of O'Conor of Connaught, interred at,	344
Ros laogh, extent of district of, 157, 169, 258, 259	157, 169, 258, 259
Ros mac Caithni,	469
Ros seirce, now Rosserk, on the Moy, 226, 227	226, 227
Ros serce, Mac Firisib of,	165
———, derivation of name,	51

	<i>Page.</i>
Rossleagh, William Chapman of, . . .	361
Rowley. <i>See</i> O'Rothlain.	
Rusgach, in Coolcarney,	421
Ryder. <i>See</i> O'Marcachain.	

S.

Saidhin Uisge tar abhainn,	169
Sais Sgrebhainn, 254, 255. <i>See</i> Inis Sgreabhainn.	
Sal Srotha derg,	34, 35
Sarnait, St.	55
Sciath bachlach,	469
Screaptra Ui Chuirnin,	319
Scrin, families of, 266, 267. <i>See</i> Sgrin.	
Seanbhothach, situation of,	36
Searc, St., of Rosserk,	51
Sechnall, St.	4
Sgiath Gabhra, now Lisnaskea, Maguire inaugurated at,	434
Sgrin, now Skreen, in Tireragh, families of,	171
——, pillars of,	171, 173
Sighin Ciarain,	159, 200, 201
Sil Muireadhaigh, who,	212
——, twelve coarbs and twelve chieftains of,	426
Sith Budha,	6, 410, 411
Sith Truim, where,	28
Siuir, a river of, in Clann Cuain, . . .	161
Skreen parish. <i>See</i> Scrin and Sgrin.	
Sliabh Ealpa, the Alps,	19
Sliabh Oighidh an righ, situation of, .	344
Sligeach, now Sligo, battle of, . . .	313
Sligeach River,	470
Sliocht Lochlainn O'Dubhda of Bun Finne,	121
Sodhan, territory of,	266, 267
Soighen Uisge tar abhainn, the chief seat of O'Caomhain,	175

Page.

Srath, battle of,	19
Sruthair, battle of,	123
Staunton of Ceara,	335

T.

Taverners-street, Dublin,	124
Teagusc Righ, or Royal Precepts, 430, 440	
Teamhair, or Tara, Pagan Irish monarchs inaugurated at,	431
Templeshanbo, near Mount Leinster, ancient name of,	36
Tighearnan, St., of Errew, descent of, 13, 103,	239
Tinnsra, meaning of,	77
Tiprad Phadruic, at Tara,	462
Tir Amhalgaidh, from whom named, 73, 311 ———, St. Patrick's travels and acts in,	461
Tirawley, ancient proprietors of, 167, 173 ———, first settlement of the Burkes in,	337
——, townlands in, yielding tribute to the Lower Mac William De Burgo, 455, 456, 457	
Tirechan's Annotations on the Life of St. Patrick quoted,	462, 463, 473
Tir Fiachrach, now Tireragh, from whom named,	99
Tir Tuathail, situation of,	117
Tobar. <i>See</i> Baile an tobair,	191
Tobur Enadhurc. <i>See</i> Oenadharc, fons, 467	
Tobar Lughna, in Ceara,	159, 200, 201
Tobar na Sgornaighe, where,	337
Toin re go,	173, 272, 273
Tor Cathrach, meaning of the term, . .	19
Torna Eigeas, his poem on the Pagan cemetery of Cruachan,	26-31
Tradraighe, in Thomond,	53
Tradraighe, tribe of, in Aidhne, descent of,	ib.

	<i>Page.</i>		<i>Page.</i>
Traigh ceall, situation of, . . .	8, 9, 224, 225	Turloch, church of,	415
———, anciently Traigh Mur-		U.	
bhaigh,	167	Uachtar Charthuinn,	465
Traigh Eothuille strand,	173, 424	Ui. <i>See</i> Hy.	
———, situation of,	8, 9, 335	Ui Amhalgaidh on the Muaidh,	4
———, battle of,	117	Ui Aonghusa, descent of,	99
Traigh Murbhaigh, one of the bounda-		Ui Cuilen of Ath Fen, descent of, . . .	100
ries of Caille Conaill,	167, 333	Ui Faolchon, descent of,	33
Triocha cheud, meaning of,	149	Ui Fiachrach. <i>See</i> Hy-Fiachrach.	
Tuaim dha bhodhar, situation of, . . .	109, 167, 242, 243, 245	Ui Ronain, descent of,	101
Tuaim da Odhar,	167	Uluidh Caolainn, one of the boundaries	
Tuaim, Cosnamhach O'Dubhda, Arch-		of the district of Magh na bethighe, . .	153
deacon of,	115	Uluidh, meaning of the word,	45
Tuath Aitheachda, now Touaghty, . .	157	Umhall, O'Malley's territory, extent of, .	43, 302
Tuath Ruisen, in Ceara, an ancient		V.	
name of Ros laogh,	159, 198, 199	Vippler, Baron, residing in Silesia, the	
Tulach, in Ceara,	196, 197	uncle of Captain James O'Dowda, his	
Tulach Domhnann,	95	letter,	370, 371
Tulach na n-Druadh,	465	W.	
Tulach na Maoile, an ancient name of		Welsh tribes of Tyrawley,	324-339
Knockroe, near Skreen,	97	White Knight,	325
Tulach na molt, now Knockroe, . . .	96	William the Conqueror, William Fitz	
Tulach Og, now Tullaghoge, O'Neill		Adelm De Burgo, so called,	71, 335
inaugurated at, by O'Hagan and		William Fitz Adelm De Burgo, his cha-	
O'Kane,	431	racter,	71, 72
Tulach Spealain,	157		
Tulcha Domhnaill,	344		
Tullyvea, Mac Mahon inaugurated chief			
of Oriel at,	434		

F I N I S .

IRISH

ARCHÆOLOGICAL SOCIETY.

At a General Meeting of the IRISH ARCHÆOLOGICAL SOCIETY, held in the Board Room of the Royal Irish Academy, on Wednesday, the 10th day of July, 1844,

THOMAS HUTTON, ESQ., in the Chair,

The Secretary read the following REPORT from the Council:

“The time for holding the Fourth Anniversary Meeting of the Society having arrived, it becomes the duty of the Council to submit to the Members an account of their own proceedings and a statement of the prospects of the Society.

“Since the last annual Meeting, held on the 27th of June, 1843, the following sixty Members have been elected; those with a star prefixed to their names are life Members.

- | | |
|---|---|
| <ul style="list-style-type: none"> • The Marquis of Drogheda, Moore Abbey, Monastereven. The Earl of Bective, Headfort House, Kells. The Earl of Fingal. The Earl of Orkney, Taplow Court, Maidenhead. • Lord Clonbrock, Clonbrock, Ahascragh. Sir John P. Boileau, Bart., London. James Benjamin Ball, Esq., Dublin. Thomas Brodigan, Esq., Piltown House, Drogheda. • William Eaton Caldbeck, Esq., Kilmastioige. James Stratherne Close, Esq., Dublin. | <ul style="list-style-type: none"> J. G. Cochrane, Esq., for the London Library, Pall Mall, London. Sir Charles Coote, Bart., Ballyfin House, Mountrath. William Coppinger, Esq., Barry's Court, Cork. Michael Creagh, Esq., Dublin. T. Crofton Croker, Esq., M. R. I. A., Rosamond's Bower, Fulham. Rev. William Moore Crosthwaite, Durrus, Bantry. Charles Gavan Duffy, Esq., Dublin. John Edward Errington, Esq., Greenock. James Eyre, Esq., London. |
|---|---|

• Edward Fitzgerald, Esq., Carrigoran.
 William Seymour Fitzgerald, Esq., London.
 Rev. Matthew Flanagan, Dublin.
 John French, Esq., Stockwell-place, Surrey.
 R. French, Esq., Dublin.
 John Graham, Esq., Barlead, Glasgow.
 James Hamilton, Esq., Fintra House, Killybegs.
 William Henry Holbrook, Esq., Dublin.
 • Sir Francis Hopkins, Bart., Rochfort, Mullingar.
 James S. Hamilton Humphreys, Esq., London.
 Thomas Kippax King, Esq., London.
 • Walter Laurence, Jun., Esq., Lawrencetown.
 Robert Leeson, Esq., Florence.
 • Frederick Lindesay, Esq., Dublin.
 • William Horton Lloyd, Esq., London.
 James Allan Maconochie, Esq., Orkney.
 • D. Mac Carthy, Esq., Florence.
 Robert Ogilby Moore, Esq., London.
 William George Morris, Esq., London, for the Oxford and Cambridge Club.
 James Lyster O'Beirne, Esq., Dublin.
 The Very Rev. Dominick O'Brien, Waterford.

Francis O'Brien, Esq., Thurles.
 John C. O'Callaghan, Esq., Dublin.
 The O'Dowda, Bonnicconlan.
 • Joseph M. O'Ferrall, Esq., Dublin.
 The O'Grady, Kilballyowen, Bruff.
 John Patten, Esq., for the Royal Dublin Society.
 Thomas M. Ray, Esq., Dublin.
 Thomas N. Redington, Esq., Kilcornan, Oranmore.
 Rev. William Reeves, Ballymena.
 Lewis Reford, Esq., Beechmount, Belfast.
 George Salmon, Esq., F. T. C., Dublin.
 Robert Sharpe, Esq., Coleraine.
 Rev. Robert C. Singleton, A. M., Stackallan, for the College of St. Columba.
 John Vandeleur Stewart, Esq., Rockhill, Lettorkenny.
 • Edward King Tenison, Castle Tenison, Keadue, Carrick-on-Shannon.
 James Ruddell Todd, Esq., London.
 William B. C. C. Turnbull, Esq., F. S. A., Edinburgh.
 • Henry Tyler, Esq., Newtown-limavady.
 Edward Cripps Villiers, Esq., Kilpeacon.
 James Whiteside, Esq., Dublin.

“The Society has lost by death, during the past year, the following Members:

Robert Bateson, Esq., M. P.
 Thomas Coulter, Esq., M. D.
 Matthew O'Connor, Esq.

“The names on the books of the Society now amount to 385, including forty-eight Life Members ; fourteen have been taken off the books for non-payment of their entrance fees and subscriptions, and although the full complement of 500 (as fixed by a rule of the Society) has not been attained, the Council hope that when the objects of the Society are more generally known, it will meet with that support so essential to its welfare, and be enabled hereafter to prosecute the design, on a scale far greater than the limited funds up to the present time have permitted.

“It

"It should be recollected that difficulties of no ordinary kind were to be overcome in the attempt to establish this Society. There are very few Irish scholars competent to undertake the task of translating and editing the ancient MSS. relating to this country, many of which are now dispersed, and in a great measure inaccessible; and the funds at the disposal of the Council have not permitted them to avail themselves (to any considerable extent) of the rich stores preserved in England and elsewhere. They have been compelled, therefore, to restrict their attention to such manuscripts as are in Ireland, the value of many of which would be greatly increased by collation with manuscripts not at present within the reach of the Society.

"The Council regret that the issue of the volumes for the present year has been so long unavoidably delayed.

"The Account of the Tribes and Customs of the District of Hy-Fiachrach, in the counties of Sligo and Mayo, edited, with a translation and copious notes, by Mr. O'Donovan, and illustrated with a map of the district, is nearly ready. This is a larger volume than any of the previous publications of the Society, and required more time to complete it, than the Council anticipated.

"The Registry of the Church of All-Hallows, which occupied the site where Trinity College now stands, is printed. The Editor has been induced to hold back the publication of this volume, for the purpose of collecting, in an Appendix, such documents as bear relation to the history of this ancient monastic establishment. It is gratifying to be able to state, that many original unpublished documents have been discovered, and as every available source of information has been investigated, the Editor is preparing notes and an index to complete the volume, which will be issued within the current year, as announced in the last Report.

"The Council take this opportunity of returning their sincere thanks to his Grace the Archbishop of Dublin, the Dean and Chapter of Christ Church, the Provost and Senior Fellows of Trinity College, Sir William Betham, the Corporation of the City of Dublin, and William Ford, Esq., Town Clerk, for the use of several valuable manuscripts.

"The Book of Obits and Martyrology of Christ Church Cathedral, which has been announced as one of the publications for the year 1843, will shortly be ready. Mr. Crosthwaite has edited the text, but in consequence of his removal to London, the Secretary, Dr. Todd, has undertaken to complete the work, which

is now in such a state of forwardness, that the Council feel assured it will be delivered to the Members in the course of a few weeks.

"The following works are in the Press, and will be issued as soon as the funds of the Society will permit:

"I. A Description of West or H-Iar Connaught, by Roderic O'Flaherty, author of the *Ogygia*, written A.D. 1684. Edited, with copious notes and an appendix, by James Hardiman, Esq., M.R.I.A., from a manuscript in Trinity College Library, Dublin.

"The Council feel great pleasure in announcing so interesting a publication, and congratulate the Society that this valuable tract is to be edited by a gentleman so competent to the task.

"II. The Annals of Ireland, by John Clyn of Kilkenny. Edited, with notes, by the Rev. Richard Butler, A.B., M.R.I.A. These valuable annals, though frequently quoted by historians, have never been printed. They come down to 1349, in which year the author died, as is supposed, of that great and universal pestilence, known in history as the **BLACK DEATH** of the middle ages, and of which he has left an interesting account, containing many particulars not mentioned by any other annalist of this country.

"III. The Annals of Ireland, by Thady Dowling, Chancellor of Leighlin. Edited, with notes, by Aquilla Smith, Esq., M.D., M.R.I.A. These annals terminate at A.D. 1600, and along with Grace's (already published by the Society) and Clyn's, comprise the greater portion of the annals of Ireland written in Latin which have been preserved.

"IV. The MISCELLANY OF THE IRISH ARCHÆOLOGICAL SOCIETY is also in the Press. The nature of this publication has been explained in the Report of last year. Six sheets of the work are printed, and several articles are prepared, but the progress of the work has been temporarily suspended, from a desire, on the part of the Council, to complete its engagements to the Members for the years 1843 and 1844. The printing of this volume will shortly be resumed, and the Council venture to assert, that it will not be the least interesting publication of the Society. In connexion with this work there is a circumstance which the Council allude to with regret. In the Report for last year the Members of the Society were earnestly invited to contribute from their family records, documents illustrative of the history of this country, or of their illustrious ancestors. This appeal has not been responded to ; but while the

the Council deplore this apathy on the part of the public, they cherish the hope that a renewal of the appeal may be attended with some degree of success.

"V. Cormac's Glossary is now ready to be put into the printer's hands. The Council availed themselves of Mr. O'Donovan's recent visit to London to have the MSS. in the British Museum examined by him, and they also employed him to visit Oxford, for the purpose of collating the imperfect but ancient MS. of Cormac's Glossary which is there preserved. This collation being now finished, there remains no further reason why the publication should be delayed.

"Considerable progress has been made in preparing some of the works mentioned in the last Report as suggested for publication.

"Mr. Kelly has completed the translation of 'Macariæ Excidium,' and Mr. O'Callaghan has made considerable progress in preparing the notes.

"Captain Larcom is ready to put to press Sir William Petty's Narrative of his Proceedings in the Survey of Ireland.

"The Irish version of Nennius, with a translation and notes, by Dr. Todd, is in a very forward state.

"Dr. Todd has also undertaken, with the assistance of Mr. O'Donovan, to edit, with a translation and notes, the Annals of Ulster from the MS. in the Library of Trinity College; this MS. is much older and in many respects more authentic than that in the Bodleian Library, a part of which has been printed by Dr. O'Connor in the *Rerum Hibernicarum Scriptores*.

"The Annals of Henry of Marlborough have been suggested for republication; these annals have been long in print, but as there is reason to believe that a better text in MS. is in existence, the Council have taken steps to procure a copy, the publication of which will be determined on hereafter.

"Other works, besides those just mentioned, have been undertaken by Members of the Society, whose engagements prevent them pledging themselves to complete their task within a limited time, but which will be announced as soon as they are ready for the printer.

"Having now laid before the Society the actual state of the publications, and the measures that have been taken to carry out the objects of its foundation, the Council have only to express their hope that the future progress of the Society will be promoted by more extended patronage than it has yet received from the nobility and gentry of Ireland."

The

The Report having been read, the following Resolutions were adopted unanimously:

" 1. That the Report now read be received and printed, and that the thanks of the Society be given to the Council for their services."

" 2. That Dr. A. Smith and George Smith, Esq., be appointed Auditors of the Society for the ensuing year, and that their statement of the accounts of the Society be printed with the Report."

" 3. That his Grace the DUKE of LEINSTER be elected President of the Society, and the following Noblemen and Gentlemen the Council for the ensuing year :

THE MOST NOBLE THE MARQUIS OF KILDARE.	JAMES HARDIMAN, Esq.
THE RIGHT HON. THE EARL OF LEI- TRIM.	THOMAS A. LARCOM, Esq., CAPT. R.E.
THE RIGHT HON. THE VISCOUNT ADARE, M. P.	JAMES MAC CULLAGH, Esq., LL. D.
REV. RICHARD BUTLER.	GEORGE PETRIE, Esq., R. H. A.
JOHN SMITH FURLONG, Esq., Q. C.	AQUILLA SMITH, Esq., M. D.
	JOSEPH H. SMITH, Esq., A. M.
	REV. J. H. TODD, D. D., V. P. R. I. A.

" 4. That the President and Council now elected be empowered to continue in office until December, 1845, and that the annual Meeting of the Society be held in future in that month ; the day to be fixed by the Council."

" 5. That the thanks of the Society be given to the President and Council of the Royal Irish Academy for their kindness in granting the use of their room for this Meeting."

Mr. Furlong having been requested to take the Chair, it was unanimously resolved,

" That the thanks of the Society be given to Mr. Hutton for his conduct in the Chair at this Meeting."

And the Society then adjourned.

AN ABSTRACT OF THE RECEIPTS AND EXPENDITURE OF THE SOCIETY,

FROM THE 12TH DAY OF JULY, 1943, TO THE 22ND DAY OF JULY, 1944.

Dr.	£	s.	d.	Cr.	£	s.	d.
1843, Sep. 15. To Mr. Mullen, for binding Hy-	28	19	8				
Many, paper for envelopes, portorage, &c.,							
Oct. 6. To Messrs.	192	0	0				
ing and paper of							
Nov. 2. To Mr. Mu	15	12	6				
of Tracts relating							
Grace's Annals, &c.,	30	0	0				
Dec. 1. To Mr. Curry, half year's salary, to	50	0	0				
Dec. 1.	50	0	0				
Dec. 16. To Mr. O'Keefe, for transcribing	50	0	0				
"Liber Hymnorum,"							
Dec. 18. To Mr. O'Donovan, half year's sa-	50	0	0				
lary, to Jan. 1, 1844,							
1844, Jan. 15. To Messrs. Pettigrew and Oulton,							
for printing the list of Members in their Di-	5	0	0				
rectory,							
Jan. 27. To Messrs. Hodges and Smith, on ac-	150	0	0				
count, for printing and paper of the Book of							
Obits	20	0	0				
May 21.	30	0	0				
assistant							
June 4. To Messrs. Hodges and Smith, on ac-	200	0	0				
count, for printing and paper of Hy-Fiach-							
June 1.	50	0	0				
June 24. To Messrs. Hodges and Smith, on	15	0	0				
account, for printing and paper of Hy-Fiach-							
June 5. To Mr. O'Donovan, half year's salary,	6	15	6				
to July 1.	10	0	0				
To Mr. O'Donovan, expenses to Oxford,	26	15	6				
To Secretary, for account books, postage, car-	0	5	0				
riage of parcels, &c.,	120	0	0				
To Mr. T. C. Smith of London, commission,	95	10	8				
To do. do. advertisements,							
portage, postage, &c.,							
To Mr. Plunket, for two drawings of ancient							
seals,							
To life compositions of 12 Members, invested							
in 3½ per cent. stock,							
To balance to credit of Society,							
	£1099	18	10		£1099	18	10

(Signed)

**AQUILA SMITH, } Auditors.
GEORGE SMITH, }**

IRISH ARCHÆOLOGICAL SOCIETY.

1844.

Patron :

HIS ROYAL HIGHNESS THE PRINCE ALBERT.

President :

HIS GRACE THE DUKE OF LEINSTER.

Council :

THE MOST NOBLE THE MARQUIS OF KILDARE, M. R. I. A.

THE RIGHT HON. THE EARL OF LEITRIM, M. R. I. A.

THE RIGHT HON. THE VISCOUNT ADARE, M. P., M. R. I. A.

REV. RICHARD BUTLER, M. R. I. A.

JOHN SMITH FURLONG, Esq., Q. C., *Treasurer.*

JAMES HARDIMAN, Esq., M. R. I. A.

CAPTAIN LARCOM, R. E., M. R. I. A.

JAMES MAC CULLAGH, Esq., LL. D., M. R. I. A.

GEORGE PETRIE, Esq., R. H. A., M. R. I. A.

AQUILLA SMITH, M. D., M. R. I. A.

JOS. H. SMITH, Esq., A. M., M. R. I. A.

REV. J. H. TODD, D. D., V. P. R. I. A., *Secretary.*

Members of the Society.

[*Life Members are marked thus *.*]

* His Royal Highness THE PRINCE ALBERT.

* His Excellency EARL DE GREY, LORD LIEUTENANT OF IRELAND.

His Grace the ARCHBISHOP of CANTERBURY.

His Grace the LORD PRIMATE of IRELAND.

* His Grace the DUKE of BUCKINGHAM and CHANDOS.

* His Grace the DUKE of LEINSTER.

His Grace the DUKE of NORTHUMBERLAND.

THE MARQUIS CONYNGHAM.

THE MARQUIS of DOWNSHIRE.

* THE MARQUIS of DROGHEDA.

THE MARQUIS of ELY.

* THE MARQUIS of KILDARE, M. R. I. A.

* THE MARQUIS of LANSDOWNE.

THE MARQUIS of ORMONDE.

* THE MARQUIS of WATERFORD.

THE EARL of BANDON.

THE EARL of BECTIVE.

THE EARL of CARLISLE.

THE EARL of CAWDOR.

THE EARL of CHARLEMONT, M. R. I. A.

THE EARL of CLANCARTY.

THE EARL of DONOUGHMORE.

THE EARL of DUNRAVEN, M. R. I. A.

THE EARL of ENNISKILLEN.

THE EARL of FINGAL.

THE EARL of FIFE.

The EARL FITZWILLIAM.
 The EARL FORTESCUE.
 The EARL of LEITRIM, M. R. I. A.
 The EARL of MEATH.
 The EARL of ORKNEY.
 The EARL of POWIS.
 The EARL of ROSSE, M. R. I. A.
 The VISCOUNT ACHESON, M. P.
 The VISCOUNT ADARE, M. P., M. R. I. A.
 The VISCOUNT COURTENAY, M. P.
 The VISCOUNT DE VESCI.
 LORD ELIOT, M. P.
 The VISCOUNT JOCELYN, M. P.
 The VISCOUNT LISMORE.
 The VISCOUNT LORTON.
 The VISCOUNT MASSAREENE.
 The VISCOUNT MORPETH.
 The VISCOUNT O'NEILL.
 * The VISCOUNT PALMERSTON.
 The VISCOUNT POWERSCOURT.
 The VISCOUNT TEMPLETOWN.

LORD CARBERRY.
 * LORD CLONBROCK.
 LORD ALBERT CONTINGHAM.
 LORD CREMORNE.
 LORD FARNHAM.
 LORD GEORGE HILL, M. R. I. A.
 LORD ROSSMORE, M. R. I. A.
 The LORD BISHOP of CASHEL, EMLY, WATERFORD, and LISMORE.
 The LORD BISHOP of CHICHESTER.
 The HON. THE LORD BISHOP of CLOGHER.
 The LORD BISHOP of CORK, CLOYNE, and ROSS.
 The HON. THE LORD BISHOP of DERRY and RAFFOE.
 The LORD BISHOP of DOWN and CONNOR, and DROMORE.
 The Rt. Hon. the LORD BISHOP of KILDARE.
 The LORD BISHOP of KILMORE, ELPHIN, and ARDAGH.

Abraham Abell, Esq., M. R. I. A., Cork.
 Miss M. J. Alexander, Dublin.
 William Antisell, Esq., Ballyowen Cottage, Philipstown.
 Rev. John H. Armstrong, A. B., Fitzwilliam-square, Dublin.
 George Atkinson, Esq., A. M., M. B., Upper Temple-street, Dublin.
 Rev. James Kennedy Bailie, D.D., M. R. I. A., Ardrea House, Stewartstown.
 James B. Ball, Esq., Merriion-square, East, Dublin.
 Matthew Barrington, Esq., M. R. I. A., St. Stephen's-green, Dublin.
 Hugh Barton, jun., Esq., Regent-street, London.
 Miss Beaufort, Hatch-street, Dublin.
 Sir Michael Dillon Bellew, Bart., Mount Dillon, Galway.

Colonel Robert H. Birch, Leeson-st., Dublin.
 John Blachford, Esq., Moorgate-st., London.
 The Right Hon. Anthony Richard Blake, Merriion-square, Dublin.
 Loftus H. Bland, Esq., Pembroke-st., Dublin.
 Bindon Blood, Esq., M. R. I. A., F. R. S. E., Ennis.
 Sir John P. Boileau, Bart., London.
 Walter W. Bond, Esq., The Argory, Moy.
 * Beriah Botfield, Esq., M. P., M. R. I. A., London.
 Right Hon. Maziere Brady, Lord Chief Baron of the Exchequer, M. R. I. A.
 Thomas Brodigan, Esq., Pilton House, Drogheda.
 William Brooke, Esq., Q. C., Leeson-street, Dublin.
 Haliday Bruce, Esq., M. R. I. A., Dublin.
 John Bruce, Esq., F. S. A., Chelsea.

Rev.

Rev. William Bruce, for the Belfast Library.
 Rev. Dr. Brunton, for the University Library,
 Edinburgh.
 Samuel Bryson, Esq., Belfast.
 The Chevalier Bunsen, London.
 John Ynyr Burges, Esq., Parkanaur, Dun-
 gannon.
 John Burrowes, Esq., Herbert-street, Dublin.
 Robert Burrowes, Esq., Merrion-sq., Dublin.
 Rev. Samuel Butcher, A.M., M.R.I.A., Fel-
 low of Trinity College, Dublin.
 Rev. Richard Butler, A.B., M.R.I.A., Trim.
 * William E. Caldbeck, Esq., Kilmastogue.
 Robert Callwell, Esq., M. R. I. A., Herbert-
 place, Dublin.
 Edward Cane, Esq., M. R. I. A., Dawson-st.,
 Dublin.
 George Carr, Esq., M. R. I. A., Mountjoy-
 square, Dublin.
 * Rev. Joseph Carson, A.M., M. R. I. A., Fel-
 low of Trinity College, Dublin.
 Rev. William Carus, A.M., Fellow of Trinity
 College, Cambridge.
 Thomas Cather, Esq., Blessington-st., Dublin.
 Sir Montagu L. Chapman, Bart., M.R.I.A.,
 Killua Castle, Clonmellon.
 Edward Wilmot Chetwode, Esq., M. R. I. A.,
 Woodbrook, Portarlinton.
 Rev. William Cleaver, A.M., Delgany.
 James Stratherne Close, Esq., Dublin.
 J. G. Cochrane, Esq., for the London Library.
 Rev. Thomas De Vere Coneys, A.M., Pro-
 fessor of Irish in the University of Dublin.
 Frederick W. Conway, Esq., M.R.I.A., Ter-
 race Lodge, Rathmines-road, Dublin.
 Adolphus Cooke, Esq., Cookesborough, Mul-
 lingar.
 James R. Cooke, Esq., Blessington-st., Dublin.
 Philip Davies Cooke, Esq., Ouston, Doncaster.
 The Rev. Peter Cooper, Marlborough-street,
 Dublin.

Sir Charles Coote, Bart., Ballyfinn House,
 Mountrath.
 William Coppinger, Esq., Barryscourt, Cork.
 * Rev. George E. Corrie, B.D., Fellow of St.
 Catherine's Hall, Cambridge.
 Very Rev. Henry Cotton, D.C.L., Dean of
 Lismore.
 Rev. George Edmund Cotter, Glenview, Mid-
 dleton.
 James T. Gibson Craig, Esq., Edinburgh.
 Michael Creagh, Esq., Upper Gloucester-st.,
 Dublin.
 T. Crofton Croker, Esq., Rosamond's Bower,
 Fulham.
 Rev. Charles Crosthwaite, A.M., Monastere-
 van.
 Rev. John C. Crosthwaite, A.M., Rectory,
 St. Mary's at Hill, London.
 Rev. William M. Crosthwaite, A.M., Dur-
 rus, Bantry.
 Rev. Edward Cupples, LL.B., V.G. of Down
 and Connor, Lisburn.
 Miss J. M. Richardson Currer, Eshton Hall,
 Yorkshire.
 * Eugene Curry, Esq., Dublin.
 William Curry, Jun., Esq., Dublin.
 * James W. Cusack, Esq., M.D., M. R. I. A.,
 Kildare-street, Dublin.
 Quentin Dick, Esq., M.P., London.
 C. Wentworth Dilke, Esq., London.
 Rev. Robert Vickers Dixon, A.M., M.R.I.A.,
 Fellow of Trinity College, Dublin.
 Thomas Dobbin, Esq., Armagh.
 Joseph Dobbs, Esq., Dublin.
 William C. Dobbs, Esq., Fitzwilliam-pl.,
 Dublin.
 William V. Drury, Esq., M.D., M. R. I. A.,
 Lower Merrion-street, Dublin.
 Charles Gavan Duffy, Esq., Holme Ville, Rath-
 mines, Dublin.
 Major Francis Dunne, Brittas, Clonaslee.

Rev. Charles R. Elrington, D.D., M.R.I.A.,
Regius Professor of Divinity, Dublin.
John Edward Errington, Esq., Greenock.
Robert Ewing, Esq., Greenock.
James Eyre, Esq., London.
• J. Walter K. Eyton, Esq., Elgin Villa,
Leamington.
Samuel Graeme Fenton, Esq., Belfast.
Sir Robert Ferguson, Bart., M. P., London-
derry.
Clement Ferguson, Esq., Lower Ormond-
quay, Dublin.
John Ferguson, Esq., Castle Forward, Derry.
• Edward Fitzgerald, Esq., Carrigoran.
W. Seymour Fitzgerald, Esq., London.
Patrick Vincent Fitzpatrick, Esq., Eccles-
street, Dublin.
Rev. Matthew Flanagan, Francis-st., Dublin.
Thomas Fortescue, Esq., M. R. I. A., Ravens-
dale Park, Flurrybridge.
Rev. Smyth W. Fox, Richview, Rathmines,
Dublin.
William D. Freeman, Esq., Q. C., Upper
Mount-street, Dublin.
John French, Esq., Stockwell-place, Surrey.
Robert French, Esq., Fitzwilliam-sq., East,
Dublin.
Alfred Furlong, Esq., Newcastle, County of
Limerick.
John S. Furlong, Esq., Q. C., Leeson-street,
Dublin.
Rev. Robert Gage, A. M., Rathlin Island,
Ballycastle.
Bryan Geraghty, Esq., Anglesea-st., Dublin.
Edmund Getty, Esq., Victoria-place, Belfast.
Rev. Richard Gibbings, A. M., Myragh Glebe,
Dunfanaghy.
Michael Henry Gill, Esq., Great Brunswick-
street, Dublin.
Rev. William S. Gilly, D. D., Norham Vi-
carage, Berwick-on-Tweed.

The Knight of Glin, Glin Castle, Glin.
• Rev. Thomas Goff, M. R. I. A., Carriglea.
Thomas Goold, Esq., Master in Chancery,
Dublin.
John Graham, Esq., Craigallian.
George B. Grant, Esq., Grafton-st., Dublin.
• Rev. Charles Graves, A. M., M. R. I. A.,
Fellow of Trinity College, Dublin.
Robert Graves, Esq., M. D., M. R. I. A., Dublin.
Rev. James Graves, Borris-in-Ossory.
John Gray, Esq., Greenock.
Rev. John Greham, LL. D., Portora House,
Enniskillen.
Right Hon. Thomas Grenville, Cleveland-
square, London.
• Richard Griffith, Esq., M. R. I. A., Fitzwil-
liam-place, Dublin.
Rev. Charles Grogan, Harcourt-st., Dublin.
John Gumley, Esq., LL. D., St. Stephen's-
green, Dublin.
James Haire, Esq., Summer-hill, Dublin.
Sir Benjamin Hall, Bart., M. P., Portman-
square, London.
George Alexander Hamilton, Esq., M. P.,
Hampton Hall, Balbriggan.
James Hamilton, Esq., Fintra House, Killy-
begs.
Sir William R. Hamilton, LL. D., President
R. I. A., Observatory, Dunsink.
James Hardiman, Esq., M. R. I. A., Galway.
Andrew Searle Hart, Esq., LL. D., M. R. I. A.,
Fellow of Trinity College, Dublin.
Leonard S. Hartley, Esq., Middleton Lodge,
Richmond, Yorkshire.
Hon. Algernon Herbert, Ickleton, Saffron
Walden.
John E. Herrick, Esq., Belmont, Crookstown.
Thomas Hewitt, Esq., Spencer's Library,
London.
William Henry Holbrook, Esq., Leeson-
street, Dublin.

Sir

Sir W. Jackson Homan, Bart., Drumroe, Cappoquin.

• A. J. B. Hope, Esq., Lamberhurst.

• Sir Francis Hopkins, Bart., Rochfort, Mullingar.

The Very Rev. Edward Gustavus Hudson, Dean of Armagh, Glenville, Watergrass-hill.

William E. Hudson, Esq., M. R. I. A., Upper Fitzwilliam-street, Dublin.

J. S. Hamilton Humphreys, Esq., London.

Thomas Hutton, Esq., M. R. I. A., Dublin.

Sir Robert H. Inglis, Bart., M. P., London.

• Rev. James Ingram, D. D., President of Trinity College, Oxford.

David Irving, Esq., LL. D., for Advocates' Library, Edinburgh.

John H. Jellett, Esq., A. M., M. R. I. A., Fellow of Trinity College, Dublin.

• Robert Jones, Esq., M. R. I. A., Fortland, Dromore West.

Mrs. Margaret Jones, Kilwaughter Castle, County Antrim.

• W. Bence Jones, Esq., Athenæum, London.

Robert Kane, Esq., M. D., M. R. I. A., Upper Gloucester-street, Dublin.

Thomas Kane, Esq., M. D., for the Limerick Institution.

William Kane, Esq., Gloucester-st., Dublin.

Denis H. Kelly, Esq., M. R. I. A., Castle Kelly, Mount Talbot.

Rev. Matthew Kelly, Maynooth College.

Henry Kemmis, Esq., Q. C., Merrion-square, Dublin.

The Right Honourable the Knight of Kerry, M. R. I. A., Listowell.

Thomas Kippax King, Esq., London.

Rev. Henry Barry Knox, M. R. I. A., Monks-Eleigh, Bilderstone, Suffolk.

George J. Knox, Esq., M. R. I. A., Maddox-street, London.

David Laing, Esq., Signet Library, Edinburgh.

Alexander C. Lambert Esq., Ballinrobe.

Henry Lanauze, Esq., College-green, Dublin.

• Capt. Thomas A. Larcom, R. E., M. R. I. A., Dublin.

• Walter Laurence, Jun., Esq., 41st Welch Regt., Lisreaghane, Lawrencetown, Co. Galway.

Rev. William Lee, A. M., M. R. I. A., Fellow of Trinity College, Dublin.

Robert Leeson, Esq., Florence.

The Right Hon. Baron Lefroy, Leeson-street, Dublin.

Charles Lever, Esq., Templeogue.

• Frederick Lindesay, Esq., Mountjoy-square, West, Dublin.

John Lindsay, Esq., Maryville, Blackrock, Cork.

Rev. John Lingard, D. D., Hornby, Lancaster.

Rev. Humphrey Lloyd, D. D., M. R. I. A., Senior Fellow of Trinity College, Dublin.

• William Horton Lloyd, Esq., Park-square, Regent's Park, London.

Rev. Richard H. Low, Lowville, Ahascragh.

Joseph Lowell, Esq., London.

Very Rev. J. P. Lyons, Lyons Port, Belmullet.

• D. Mac Carthy, Esq., Florence.

James Allan Maconochie, Esq., Sheriff of Orkney.

Rev. Charles M'Crossan, Derry.

• James Mac Cullagh, Esq., LL. D., M. R. I. A., Fellow of Trinity College, Dublin.

William Torrens M'Cullagh, Esq., M. R. I. A., Upper Gloucester-street, Dublin.

Alexander M'Donnell, Esq., Dublin.

Charles P. Mac Donnell, Esq., Bonabrougha House, Wicklow.

Edmund Mac Donnell, Esq., Glenarm Castle, County Antrim.

Rev.

- Rev. Richard Mac Donnell, D.D., M.R.I.A.,
Senior Fellow of Trinity College, Dublin.
- George M'Dowell, Esq., A.M., M.R.I.A.,
Fellow of Trinity College, Dublin.
- M'Gillicuddy of the Reeks.
- James M'Glashan, Esq., Dublin.
- Most Reverend John Mac Hale, D.D., St.
Jarlath's, Tuam.
- Rev. John M'Hugh, Baldoyle.
- John W. M'Kenzie, Esq., Edinburgh.
- Rev. Thomas M'Neece, A.M., M.R.I.A.,
Archbishop King's Divinity Lecturer in the
University of Dublin.
- Sir Frederick Madden, Hon. M.R.I.A., Bri-
tish Museum.
- James Magee, Esq., Leeson-street, Dublin.
- Edward Magrath, Esq., for the Athenæum
Library, London.
- John Mahon, Jun., Esq., Somer's Place, West,
London.
- Pierce Mahony, Esq., M.R.I.A., William-
street, Dublin.
- Rev. Samuel R. Maitland, F.R.S., F.A.S.,
Palace, Lambeth.
- Andrew J. Maley, Esq., Merrion-sq., Dublin.
- Henry Martley, Esq., Q.C., Harcourt-street,
Dublin.
- Henry J. Monck Mason, Esq., M.R.I.A.,
for King's Inns' Library, Dublin.
- George Mathews, Esq., Spring Vale, Belfast.
- Rev. George Maxwell, Askeaton.
- Honourable General Meade, Bryanston-sq.,
London.
- Andrew Milliken, Esq., Grafton-st., Dublin.
- Daniel Molloy, Esq., York-street, Dublin.
- Richard Monck, Esq., Banagher.
- Rev. Charles H. Monsell, A.M., Prebendary
of Donoghmore, Limerick.
- William Monsell, Esq., M.R.I.A., Tervoe,
Limerick.
- Rev. Philip Moore, Rosbercon.
- Robert Ogilby Moore, Esq., London.
- Thomas Moore, Esq., Sloper-ton, Devizes.
- John Shank More, Esq., Great King-street,
Edinburgh.
- William G. Morris, Esq., for the Oxford and
Cambridge Club, London.
- Sinclair Kilbourne Mulholland, Esq., Belfast.
- Joseph William Murphy, Esq., Belfast.
- Joseph Neeld, Esq., M.P., Grosvenor-sq.,
London.
- Joseph Nelson, Esq., Q.C., M.R.I.A., Gar-
diner's-place, Dublin.
- The Very Rev. Dean Nowlan, P.P., Gowran.
- William Nugent, Esq., Killester Abbey, Ra-
heny.
- James L. O'Beirne, Esq., Lower Gardiner-
street, Dublin.
- Cornelius O'Brien, Esq., M.P., Ennistimon.
- Francis O'Brien, Esq., Thurles.
- Sir Lucius O'Brien, Bart., Dromoland.
- Augustus Stafford O'Brien, Esq., M.P., Bla-
therwycke, Northamptonshire.
- William Smith O'Brien, Esq., M.P., Carmoy
Hill, Limerick.
- The Very Rev. Dominick O'Brien, Water-
ford.
- John Cornelius O'Callaghan, Esq., Russell-
place, Dublin.
- Daniel O'Connell, Esq., M.P., Merrion-sq.,
Dublin.
- O'Connor Don, M.P.
- John O'Donoghue, Esq., Kilkenny.
- The O'Donovan, Montpelier, Douglas, Cork.
- John O'Donovan, Esq., Dublin.
- The O'Dowda, Bonniclan House, Ballina.
- Joseph Michael O'Ferrall, Esq., Rutland-
square, West, Dublin.
- William Ogilby, Esq., London.
- The O'Grady, Kilballyowen, Bruff.
- Thomas O'Hagan, Esq., Great Charles street,
Dublin.

Major

Major O'Hara, Annamoe, Collooney.
 Sir Colman M. O'Loughlen, Bart., Dublin.
 Rev. Mortimer O'Sullivan, D.D., Killyman.
 George Panton, Esq., Heriot's Hospital, Edinburgh.
 John Patten, Esq., for the Library of the Royal Dublin Society.
 Rt. Hon. Sir Robert Peel, Bart., M.P., London.
 Louis Hayes Petit, Esq., F.R.S., London.
 George Petrie, Esq., R.H.A., V.P.R.I.A., Great Charles-street, Dublin.
 • Sir Thomas Phillipps, Bart., Middlehill, Broadway, Worcestershire.
 John Edward Pigott, Esq., for the Irish Historical Society, Merrion-square, Dublin.
 Robert Pitcairn, Esq., Queen-st., Edinburgh.
 • Rev. Charles Porter, Ballibay.
 Rev. Classon Porter, Larne.
 Colonel Henry Edward Porter.
 William Potts, Esq., Dame-street, Dublin.
 Hon. Edward Preston, Gormanstown Castle, Balbriggan.
 Colonel J. Dawson Rawdon, M.P., Coldstream Guards, Stanhope-street, London.
 Thomas M. Ray, Esq., Dublin.
 Thomas N. Redington, Esq., Kilcornan.
 Rev. William Reeves, M.B., Ballymena.
 Lewis Reford, Esq., Beechmount, Belfast.
 Rev. L. F. Renahan, College, Maynooth.
 E. William Robertson, Esq., Breadsall Priory, Derby.
 Rev. Thomas R. Robinson, D.D., M.R.I.A., Observatory, Armagh.
 George Roe, Esq., Nutley, Dublin.
 Richard Rothwell, Esq., Rockfield, Kells.
 Rev. Franc Sadleir, D.D., M.R.I.A., Provost of Trinity College, Dublin.
 George Salmon, Esq., A.M., F.T.C.D.
 Rev. Francis A. Sanders, A.B., Dublin.
 Robert Sharpe, Esq., Coleraine.

Right Hon. Frederick Shaw, M.P., Recorder of Dublin.
 Remmy H. Sheehan, Esq., Mespil House, Dublin.
 Evelyn John Shirley, Esq., M.P., Carrickmacross.
 Evelyn Philip Shirley, Esq., M.P., Eatington Park, Shipton-on-Stour.
 Rev. Joseph H. Singer, D.D., M.R.I.A., Senior Fellow of Trinity College, Dublin.
 Rev. Robert C. Singleton, for the College of St. Columba, Stackallan, Navan.
 W. F. Skene, Esq., Edinburgh.
 Aquilla Smith, Esq., M.D., M.R.I.A., Dublin.
 • Rev. John Campbell Smith, Glasgow.
 Joseph Huband Smith, Esq., A.M., M.R.I.A., Dublin.
 William Smith, Esq., Carbeth, Guthrie, Glasgow.
 John Smith, Esq., LL.D., Secretary to the Maitland Club, Glasgow.
 • George Smith, Esq., Lower Baggot-street, Dublin.
 John G. Smyly, Esq., Merrion-street, Dublin.
 George Lewis Smyth, Esq., Bridge-street, London.
 Sir William Meredith Somerville, Bart., M.P.
 Rev. Thomas Stack, A.M., M.R.I.A., Fellow of Trinity College, Dublin.
 John Vandeleur Stewart, Esq., Rockhill, Letterkenny.
 Colonel William Stuart, Killymoon, Cookstown.
 Hon. Andrew Godfrey Stuart, Aughnacloy.
 William Stokes, Esq., M.D., M.R.I.A., Regius Professor of Physic, Dublin.
 Andrew Storie, Esq., for the Signet Library, Edinburgh.

William

William Villiers Stuart, Esq., M. P. Dromana, Cappoquin.
 Rev. George Studdert, A. B., Dundalk.
 Walter Sweetman, Esq., for the St. Stephen's-green Club, Dublin.
 Bartholomew M. Tabuteau, Esq., Fitzwilliam-place, Dublin.
 • Edward King Tenison, Esq., Castle Tenison, Keadue, Carrick-on-Shannon.
 • Robert J. Tennent, Esq., Belfast.
 James Thompson, Esq., Belfast.
 Richard Thompson, Esq., for the London Institution, Finsbury Circus.
 Rev. M. A. Tierney, F. R. S., Arundel.
 Robert Tighe, Esq., M. R. I. A., Fitzwilliam-square, Dublin.
 • Wm. F. Tighe, Esq., Woodstock, Inistiogue.
 • Rev. James H. Todd, D.D., V. P. R. I. A., Fellow of Trinity College, Dublin.
 James Ruddell Todd, Esq., London.
 Rev. Robert Trail, D.D., M. R. I. A., F. R. S. E., Schull, Skibbereen.
 Rev. John M. Traherne, Coedriglan, Cardiff.
 George Trundle, Esq., for the Irish Office, London.
 William B. C. C. Turnbull, Esq., Advocate, F. S. A., Edinburgh.
 Travers Twiss, Esq., F. S. A., University College, Oxford.
 • Henry Tyler, Esq., Newtown-limavaddy.
 Crofton Moore Vandeleur, Esq., Rutland-square, Dublin.
 Sir Aubrey de Vere, Bart., Currah Chase, Adare.

Edward Crips Villiers, Esq., Kilpeacon.
 John Walker, Esq., Cornhill House, Coldstream, W. B.
 Rev. Charles Wm. Wall, D.D., V. P. R. I. A., Senior Fellow of Trinity College, Dublin.
 James A. Wall, Esq., Baggot-street, Dublin.
 Samuel Hibbert Ware, Esq., M.D., F. R. S. E., Edinburgh.
 Charles T. Webber, Esq., M. R. I. A., Upper Gloucester-street, Dublin.
 Rev. William Whewell, B. D., Vice-Chancellor of Cambridge.
 Rev. ——— Whitely, for the "Portico," Manchester.
 James Whiteside, Esq., Q. C., M. R. I. A., Mountjoy-square, Dublin.
 The Venerable Archdeacon Williams, Edinburgh.
 Richard Williams, Esq., Jun., M. R. I. A., Drumcondra Castle, Dublin.
 William Williams, Esq., Aberpergwm, Neath.
 Lestock P. Wilson, Esq., North Audley-street, London.
 Rev. John Wilson, B. D., Fellow of Trinity College, Oxford.
 Rev. James Wilson, D. D., M. R. I. A., Precentor of St. Patrick's Cathedral, Dublin.
 John Windele, Esq., Sunday's Well, Cork.
 Edward Wright, Esq., Leeson-street, Dublin.
 • John Wynne, Esq., M. R. I. A., Hazlewood, Sligo.
 Rev. Walter Young, Enniskillen.

FUNDAMENTAL LAWS OF THE SOCIETY.

- I. The number of Members shall be limited to 500.
- II. The affairs of the Society shall be managed by a President and Council of twelve Members, to be elected annually by the Society.
- III. Those Noblemen and Gentlemen who have been admitted Members prior to the first day of May, 1841, shall be deemed the *original Members* of the Society, and all future Members shall be elected by the Council.
- IV. Each Member shall pay four pounds on the first year of his election, and one pound every subsequent year. These payments to be made in advance, on or before the first day of January, annually.
- V. Such Members as desire it, may become Life Members, on payment of the sum of thirteen pounds, or ten pounds (if they have already paid their entrance fee) in lieu of the annual subscription.
- VI. Every Member whose subscription is not in arrear shall be entitled to receive one copy of each publication of the Society issued subsequently to his admission ; and the books printed by the Society shall not be sold to the public.
- VII. No Member who is three months in arrear of his subscription shall be entitled to vote, or to any other privileges of a Member ; and any Member who shall be one year in arrear shall be considered as having resigned.
- VIII. Any Member who shall gratuitously edit any book, approved of by the Council, shall be entitled to twenty copies of such book, when printed, for his own use : and the Council shall at all times be ready to receive suggestions from Members, relative to such rare books or manuscripts as they may be acquainted with, and which they may deem worthy of being printed by the Society.
- IX. The Council shall have power to appoint officers ; and to make by-laws not inconsistent with the fundamental laws of the Society.

Noblemen and Gentlemen desirous of becoming Members of the Irish Archaeological Society are requested to forward their names and addresses to the Secretary, Rev. Dr. Todd, Trinity College, Dublin. Literary Societies and public libraries may procure the Society's publications, by causing their Librarian, or any other officer, to become a Member of the Irish Archaeological Society in their name.

Subscriptions will be received in DUBLIN by Messrs. Hodges and Smith, the Society's Booksellers, 21, *College-green*.

In LONDON, by Mr. T. Clerc Smith, 13, *Henrietta-street, Covent Garden.*

In BELFAST, by Edmund Getty, Esq., *Victoria-place.*

In CORK, by John Lindsay, Esq., *Maryville, Blackrock.*

In EDINBURGH, by Mr. Stevenson, 87, *Princes-street.*

In GLASGOW, by John Smith, Esq., LL.D., 70, *St. Vincent-street.*

Those Members who may find it inconvenient to pay their subscriptions to these gentlemen, will have the goodness to procure a Post-Office order made payable to the Secretary, Rev. J. H. Todd, D.D., Trinity College, Dublin; or to the Treasurer, John Smith Furlong, Esq., Q. C., 146, Leeson-street, Dublin.

PUBLICATIONS FOR THE YEAR 1841.

I. Tracts relating to Ireland, vol. I. containing:

1. The Circuit of Ireland; by Muircheartach Mac Neill, Prince of Aileach; a Poem written in the year 942 by Cormacan Eigeas, Chief Poet of the North of Ireland. Edited, with a Translation and Notes, by JOHN O'DONOVAN.
2. "A Brife Description of Ireland: Made in this year 1589, by Robert Payne unto xxv. of his partners for whom he is vndertaker there." Reprinted from the second edition, London, 1590, with a Preface and Notes, by AQUILLA SMITH, M.D., M.R.I.A.

II. The Annals of Ireland; by James Grace of Kilkenny. Edited from the MS. in the Library of Trinity College, Dublin, in the original Latin, with a Translation and Notes, by the REV. RICHARD BUTLER, M. R. I. A.

PUBLICATIONS FOR THE YEAR 1842.

I. *Cath Muiğhi Rach.* The Battle of Moira, from an ancient MS. in the Library of Trinity College, Dublin. Edited in the original Irish, with a Translation and Notes, by JOHN O'DONOVAN.

II. Tracts relating to Ireland, vol. II. containing:

1. "A Treatise of Ireland; by John Dymmok." Edited from a MS. in the British Museum, with Notes, by the REV. RICHARD BUTLER, M. R. I. A.
2. The Annals of Multifernam; from the original MS. in the Library of Trinity College, Dublin. Edited by AQUILLA SMITH, M. D., M. R. I. A.
3. A Statute passed at a Parliament held at Kilkenny, A. D. 1367; from a MS. in the British Museum. Edited, with a Translation and Notes, by JAMES HARDIMAN, Esq., M. R. I. A.

PUBLICATIONS

PUBLICATIONS FOR THE YEAR 1843.

I. An Account of the Tribes and Customs of the District of Hy-Many, commonly called O'Kelly's Country, in the Counties of Galway and Roscommon. Edited from the Book of Lecan in the Library of the Royal Irish Academy; in the original Irish, with a Translation and Notes, by JOHN O'DONOVAN.

II. The Book of Obits and Martyrology of the Cathedral of the Holy Trinity, commonly called Christ Church, Dublin. Edited from the original MS. in the Library of Trinity College, Dublin, by the REV. JOHN CLARKE CROSTHWAITE, A. M., late Dean's Vicar of Christ Church Cathedral, &c. With an Introduction by JAMES HENTHORN TODD, D. D., V. P. R. I. A., Fellow of Trinity College, &c. *Nearly ready.*

PUBLICATIONS FOR THE YEAR 1844.

I. An Account of the Tribes and Customs of the District of Hy-Fiachrach, in the Counties of Sligo and Mayo. Edited from the Book of Lecan, in the Library of the Royal Irish Academy, and from the M'Firbis MS. in the possession of the Earl of Roden. By JOHN O'DONOVAN.

II. "Registrum Ecclesie Omnium Sanctorum juxta Dublin;" from the original MS. in the Library of Trinity College. Edited by the REV. RICHARD BUTLER, M. R. I. A. *Nearly ready.*

PUBLICATIONS FOR THE YEAR 1845.

I. Cormac's Glossary; in the original Irish. Edited, with a Translation and Notes, by JOHN O'DONOVAN. *In the Press.*

II. The Annals of Ireland, by John Clyn of Kilkenny. Edited, with Notes, by the REV. RICHARD BUTLER, M. R. I. A. *In the Press.*

III. The Annals of Ireland, by Thady Dowling, Chancellor of Leighlin. Edited, with Notes, by AQUILLA SMITH, M. D., M. R. I. A. *In the Press.*

IV. A Description of West or H-Iar-Connaught, by Roderic O'Flaherty, Author of the Ogygia, written A. D. 1684. Edited, with copious Notes and an Appendix, by JAMES HARDIMAN, Esq., M. R. I. A., from a MS. in the Library of Trinity College, Dublin. *In the Press.*

PUBLICATIONS SUGGESTED OR IN PROGRESS.

I. The Miscellany of the Irish Archæological Society, vol. i. *In the Press.*

II.

II. The Irish Version of the "Historia Britonum" of Nennius, from the Book of Ballimote, collated with copies in the Book of Lecan, and in the Library of Trinity College, Dublin. With a Translation and Notes, by JAMES HENTHORN TODD, D. D., V. P. R. I. A., Fellow of Trinity College, &c.

III. "Macariæ Excidium. The Destruction of Cyprus;" by Col. Charles O'Kelly. In the original Latin, with a Translation by DENIS HENRY KELLY, Esq., of Castle Kelly; and Notes by JOHN O'CALLAGHAN, Esq.

IV. Sir William Petty's Narrative of his Proceedings in the Survey of Ireland. From a MS. recently purchased by Government, and deposited in the Library of Trin. Coll., Dublin. Edited, with Notes, by THOS. A. LARCOM, Esq., Capt. R. E., M. R. I. A.

V. Articles of Capitulation and Surrender of Cities, Towns, Castles, Forts, &c., in Ireland, to the Parliamentary Forces, from A. D. 1649 to 1654. Edited, with Historical Notices, by JAMES HARDIMAN, Esq., M. R. I. A.

VI. The Progresses of the Lords Lieutenant in Ireland; from MSS. in the Library of Trinity College, Dublin. Edited by JOSEPH HUBAND SMITH, Esq., M. A., M. R. I. A.

VII. *Ópama*. The Origin and History of the Boromean Tribute. Edited from a MS. in the Library of Trinity College, Dublin, with a Translation and Notes, by EUGENE CURRY.

VIII. *Cae Carn Chonaill*. The battle of Carn Chonaill, between Guaire, King of Aidhne, and Dermot, King of Ireland, A. D. 648. From the *Leabhar na-h Uidhre*, a very ancient MS. in the Collection of Messrs. Hodges and Smith, with a Translation and Notes, by EUGENE CURRY.

IX. The Annals of Ulster. With a Translation and Notes; Edited from a MS. in the Library of Trinity College, Dublin, collated with the Translation made for Sir James Ware by Dudley M'Firbis, a MS. in the British Museum, by JAMES HENTHORN TODD, D. D., V. P. R. I. A., and JOHN O'DONOVAN.

X. An Account of the Firbolgs and Danes of Ireland, by Duald Mac Firbis. Edited, with a Translation and Notes, from MSS. in the Library of the Royal Irish Academy, by JOHN O'DONOVAN.

Rebid S. H. 200



